

LilyPond

The music typesetter

Notation Reference

The LilyPond development team

This manual provides a reference for all notation that can be produced with LilyPond version 2.27.3. It assumes that the reader is familiar with the material in the *Learning Manual*.

For more information about how this manual fits with the other documentation, or to read this manual in other formats, see Section “Manuals” in *General Information*.

If you are missing any manuals, the complete documentation can be found at <https://lilypond.org/>.

Copyright © 1998–2026 by the authors.

Permission is granted to copy, distribute and/or modify this document under the terms of the GNU Free Documentation License, Version 1.1 or any later version published by the Free Software Foundation; with no Invariant Sections. A copy of the license is included in the section entitled “GNU Free Documentation License”.

For LilyPond version 2.27.3

Table of Contents

Musical notation

1	Pitches	3
1.1	Writing pitches	3
1.1.1	Absolute octave entry	3
1.1.2	Relative octave entry	4
1.1.3	Accidentals	8
1.1.4	Approximate pitches	10
1.1.5	Note names in other languages	10
1.2	Changing multiple pitches	12
1.2.1	Octave checks	12
1.2.2	Transpose	13
1.2.3	Inversion	16
1.2.4	Retrograde	17
1.2.5	Modal transformations	17
1.3	Displaying pitches	19
1.3.1	Clef	19
1.3.2	Key signature	24
1.3.3	Ottava brackets	26
1.3.4	Instrument transpositions	30
1.3.5	Automatic accidentals	31
1.3.6	Alternate accidental glyphs	39
1.3.7	Ambitus	40
1.4	Note heads	43
1.4.1	Special note heads	43
1.4.2	Easy notation note heads	45
1.4.3	Shape note heads	46
1.4.4	Improvisation	50
2	Rhythms	52
2.1	Writing rhythms	52
2.1.1	Durations	52
2.1.2	Tuplets	55
2.1.3	Scaling durations	61
2.1.4	Ties	63
2.2	Writing rests	67
2.2.1	Rests	67
2.2.2	Invisible rests	69
2.2.3	Full measure rests	71
2.2.4	Caesuras	76
2.3	Displaying rhythms	78
2.3.1	Measures	78
2.3.2	Time signature	79
2.3.3	Metronome marks	86
2.3.4	Upbeats	90
2.3.5	Unmetered music	91
2.3.6	Polymetric notation	93
2.3.7	Automatic note splitting	97

2.3.8	Showing melody rhythms	98
2.4	Beams.....	101
2.4.1	Automatic beams.....	101
2.4.2	Setting automatic beam behavior	104
2.4.3	Manual beams.....	114
2.4.4	Feathered beams.....	118
2.4.5	Slashed beams.....	119
2.5	Bars.....	120
2.5.1	Bar lines	120
2.5.2	Automatic bar lines.....	130
2.5.3	Bar numbers.....	132
2.5.4	Bar and bar number checks	140
2.5.5	Rehearsal marks.....	141
2.5.6	Measure counts	143
2.5.7	Section divisions.....	146
2.6	Special rhythmic concerns	147
2.6.1	Grace notes.....	147
2.6.2	Aligning to cadenzas.....	152
3	Expressive marks.....	155
3.1	Expressive marks attached to notes	155
3.1.1	Articulations and ornamentations.....	155
3.1.2	Dynamics.....	159
3.1.3	New dynamic marks	167
3.2	Expressive marks as curves	170
3.2.1	Slurs	170
3.2.2	Phrasing slurs	173
3.2.3	Breath marks.....	175
3.2.4	Falls and doits.....	176
3.3	Expressive marks as lines	176
3.3.1	Glissando.....	176
3.3.2	Arpeggio	181
3.3.3	Trills	185
4	Repeats	188
4.1	Long repeats	188
4.1.1	Written-out repeats.....	188
4.1.2	Simple repeats.....	189
4.1.3	Alternative endings	190
4.1.4	Other variation in repeated sections.....	192
4.1.5	Al-fine repeats.....	194
4.1.6	Segno repeat structure.....	195
4.1.7	Segno repeat appearance.....	198
4.1.8	Manual repeat marks	204
4.2	Short repeats.....	208
4.2.1	Percent repeats	208
4.2.2	Tremolo repeats	211

5	Simultaneous notes	215
5.1	Single voice	215
5.1.1	Chorded notes	215
5.1.2	Chord repetition	217
5.1.3	Simultaneous expressions	219
5.1.4	Clusters	220
5.2	Multiple voices	221
5.2.1	Single-staff polyphony	221
5.2.2	Voice styles	226
5.2.3	Collision resolution	226
5.2.4	Merging rests	231
5.2.5	Automatic part combining	232
5.2.6	Writing music in parallel	237
6	Staff notation	241
6.1	Displaying staves	241
6.1.1	Instantiating new staves	241
6.1.2	Grouping staves	243
6.1.3	Nested staff groups	247
6.1.4	Separating systems	248
6.2	Modifying single staves	249
6.2.1	Staff symbol	249
6.2.2	Ossia staves	253
6.2.3	Hiding staves	256
6.3	Writing parts	261
6.3.1	Instrument names	261
6.3.2	Quoting other voices	265
6.3.3	Formatting cue notes	268
6.3.4	Compressing empty measures	273
7	Editorial annotations	277
7.1	Inside the staff	277
7.1.1	Selecting notation font size	277
7.1.2	Fingering instructions	281
7.1.3	Gliding fingers	284
7.1.4	Hidden notes	288
7.1.5	Coloring objects	288
7.1.6	Staff highlights	291
7.1.7	Brackets for optional material	294
7.1.8	Parentheses	295
7.1.9	Stems	296
7.2	Outside the staff	297
7.2.1	Note names	297
7.2.2	Balloon help	299
7.2.3	Grid lines	301
7.2.4	Analysis brackets	303
8	Text	307
8.1	Writing text	307
8.1.1	Text objects overview	307

8.1.2	Text scripts.....	309
8.1.3	Text spanners	311
8.1.4	Section labels.....	312
8.1.5	Text marks	313
8.1.6	Separate text	317
8.2	Formatting text	319
8.2.1	Text markup introduction	319
8.2.2	Selecting font and font size.....	323
8.2.3	Text alignment	326
8.2.4	Graphic notation inside markup.....	331
8.2.5	Music notation inside markup.....	334
8.3	Fonts.....	336
8.3.1	Unsupported font formats.....	336
8.3.2	Finding fonts	337
8.3.3	Font families.....	337
8.3.4	Font features	339
8.3.5	Changing fonts	340

Specialist notation

9	Vocal music	345
9.1	Common notation for vocal music.....	345
9.1.1	References for vocal music	345
9.1.2	Entering lyrics	346
9.1.3	Aligning lyrics to a melody	347
9.1.4	Automatic syllable durations.....	349
9.1.5	Manual syllable durations.....	352
9.1.6	Multiple syllables to one note	353
9.1.7	Multiple notes to one syllable	354
9.1.8	Extenders and hyphens	357
9.1.9	Gradual changes of vowel	357
9.2	Techniques specific to lyrics.....	358
9.2.1	Working with lyrics and variables	358
9.2.2	Placing lyrics vertically	360
9.2.3	Placing syllables horizontally.....	363
9.2.4	Lyrics and repeats	366
9.2.5	Divisi lyrics.....	374
9.2.6	Polyphony with shared lyrics.....	376
9.3	Stanzas.....	377
9.3.1	Adding stanza numbers.....	377
9.3.2	Stanza reminders	378
9.3.3	Adding dynamics marks to stanzas.....	381
9.3.4	Adding singers' names to stanzas	382
9.3.5	Stanzas with different rhythms.....	382
9.3.6	Printing stanzas at the end	385
9.3.7	Printing stanzas at the end in multiple columns	386
9.4	Songs	388
9.4.1	References for songs	388
9.4.2	Lead sheets.....	389
9.5	Choral	389

9.5.1	References for choral	389
9.5.2	Score layouts for choral	390
9.6	Opera and stage musicals	392
9.6.1	References for opera and stage musicals	393
9.6.2	Character names	393
9.6.3	Musical cues	395
9.6.4	Spoken music	399
9.6.5	Dialogue over music	399
9.7	Chants psalms and hymns	400
9.7.1	References for chants and psalms	400
9.7.2	Setting a chant	400
9.7.3	Pointing a psalm	406
9.7.4	Phrase bar lines in hymn tunes	409
9.7.5	Partial measures in hymn tunes	410
9.8	Ancient vocal music	412
10	Keyboard and other multi-staff instruments	413
10.1	Common notation for keyboards	413
10.1.1	References for keyboards	414
10.1.2	Changing staff manually	414
10.1.3	Changing staff automatically	416
10.1.4	Staff-change lines	418
10.2	Piano	421
10.2.1	Piano pedals	421
10.3	Organ	423
10.3.1	Organ pedal marks	423
10.4	Accordion	424
10.4.1	Discant symbols	424
10.5	Harp	425
10.5.1	References for harps	425
10.5.2	Harp pedals	425
11	Unfretted string instruments	427
11.1	Common notation for unfretted strings	427
11.1.1	References for unfretted strings	427
11.1.2	Bowing indications	428
11.1.3	Harmonics	428
11.1.4	Snap (Bartók) pizzicato	429
12	Fretted string instruments	431
12.1	Common notation for fretted strings	431
12.1.1	References for fretted strings	431
12.1.2	String number indications	432
12.1.3	Default tablatures	433
12.1.4	Custom tablatures	452
12.1.5	Fret diagram markups	455
12.1.6	Predefined fret diagrams	466
12.1.7	Automatic fret diagrams	477
12.1.8	Right-hand fingerings	479
12.2	Guitar	481

12.2.1	Indicating position and barring	481
12.2.2	Indicating harmonics and dampened notes	482
12.2.3	Indicating power chords	483
12.3	Banjo	484
12.3.1	Banjo tablatures	484
12.4	Lute	485
12.4.1	Lute tablatures	485
13	Percussion	487
13.1	Common notation for percussion	487
13.1.1	References for percussion	487
13.1.2	Basic percussion notation	487
13.1.3	Drum rolls	488
13.1.4	Pitched percussion	488
13.1.5	Percussion staves	489
13.1.6	Custom percussion staves	491
13.1.7	Ghost notes	494
14	Wind instruments	495
14.1	Common notation for wind instruments	495
14.1.1	References for wind instruments	495
14.1.2	Fingerings	496
14.2	Bagpipes	498
14.2.1	Bagpipe definitions	498
14.2.2	Bagpipe example	498
14.3	Woodwinds	500
14.3.1	Woodwind diagrams	500
15	Chord notation	507
15.1	Chord mode	507
15.1.1	Chord mode overview	507
15.1.2	Common chords	508
15.1.3	Extended and altered chords	509
15.1.4	Chord inversions and specific voicings	512
15.2	Displaying chords	512
15.2.1	Printing chord names	512
15.2.2	Customizing chord names	515
15.2.3	Chord grids	521
15.3	Figured bass	525
15.3.1	Introduction to figured bass	525
15.3.2	Entering figured bass	526
15.3.3	Displaying figured bass	530
16	Contemporary music	534
16.1	Pitch and harmony in contemporary music	534
16.1.1	References for pitch and harmony in contemporary music	534
16.1.2	Microtonal notation	534
16.1.3	Contemporary key signatures and harmony	534
16.2	Contemporary approaches to rhythm	534
16.2.1	References for contemporary approaches to rhythm	534

16.2.2	Tuplets in contemporary music	534
16.2.3	Contemporary time signatures	534
16.2.4	Extended polymetric notation	534
16.2.5	Beams in contemporary music	534
16.2.6	Bar lines in contemporary music	534
16.3	Graphical notation	534
16.4	Contemporary scoring techniques	536
16.5	New instrumental techniques	536
16.6	Further reading and scores of interest	536
16.6.1	Books and articles on contemporary musical notation	536
16.6.2	Scores and musical examples	536
17	Ancient notation	537
17.1	Overview of the supported styles	538
17.2	Ancient notation – common features	539
17.2.1	Predefined contexts	539
17.2.2	Ligatures	539
17.2.3	Custodes	540
17.3	Typesetting mensural music	541
17.3.1	Mensural contexts	541
17.3.2	Mensural clefs	542
17.3.3	Mensural time signatures	543
17.3.4	Mensural note heads	543
17.3.5	Mensural flags	544
17.3.6	Mensural rests	545
17.3.7	Mensural accidentals and key signatures	545
17.3.8	Annotational accidentals (<i>musica ficta</i>)	546
17.3.9	Historical overview of ligatures	546
17.3.10	White mensural ligatures	548
17.3.11	Reading white mensural ligatures	550
17.4	Typesetting Gregorian chant	553
17.4.1	Gregorian chant contexts	554
17.4.2	Gregorian clefs	554
17.4.3	Gregorian accidentals and key signatures	555
17.4.4	Divisiones	555
17.4.5	Gregorian articulation signs	556
17.4.6	Augmentum dots (<i>morae</i>)	557
17.4.7	Gregorian square neume ligatures	557
17.5	Typesetting Kievan square notation	563
17.5.1	Kievan contexts	563
17.5.2	Kievan clefs	564
17.5.3	Kievan notes	564
17.5.4	Kievan accidentals	564
17.5.5	Kievan bar lines	565
17.5.6	Kievan melismata	565
17.6	Working with ancient music – scenarios and solutions	566
17.6.1	Incipits	566
17.6.2	Mensurstriche layout	567
17.6.3	Transcribing Gregorian chant	568
17.6.4	Ancient and modern from one source	571

18	World music	574
18.1	Common notation for non-Western music	574
18.1.1	Extending notation and tuning systems	574
18.2	Arabic music	574
18.2.1	References for Arabic music	574
18.2.2	Arabic note names	575
18.2.3	Arabic key signatures	576
18.2.4	Arabic time signatures	578
18.2.5	Arabic music example	579
18.2.6	Further reading for Arabic music	580
18.3	Turkish classical music	580
18.3.1	References for Turkish classical music	580
18.3.2	Turkish note names	580
18.3.3	Turkish key signatures	581
18.3.4	Further reading for Turkish music	582
18.4	Persian classical music	582
18.4.1	Persian music notation	582
18.4.2	Persian tunings	583
18.4.3	Persian key signatures	583
18.4.4	Further reading on Persian music	584

General input and output

19	Input modes	587
20	Input structure	590
20.1	Structure of a score	590
20.2	Multiple scores in a book	591
20.3	Multiple output files from one input file	593
20.4	Output file names	593
20.5	File structure	594
21	Titles and headers	597
21.1	Creating titles, headers, and footers	597
21.1.1	Titles explained	597
21.1.2	Default layout of bookpart and score titles	600
21.1.3	Default layout of headers and footers	604
21.2	Custom titles, headers, and footers	605
21.2.1	Custom text formatting for titles	605
21.2.2	Custom layout for titles	605
21.2.3	Custom layout for headers and footers	608
21.3	Creating output file metadata	609
21.4	Creating footnotes	610
21.4.1	Footnotes in music expressions	610
21.4.2	Footnotes in stand-alone text	616
21.5	Creating in-notes	619
21.6	Reference to page numbers	620
21.7	Table of contents	622

22	Working with input files	625
22.1	Including LilyPond files	625
22.2	Different editions from one source	626
22.2.1	Using variables	626
22.2.2	Using tags	628
22.2.3	Using global settings	638
22.3	Using music functions	638
22.3.1	Substitution function syntax	639
22.3.2	Substitution function examples	639
22.3.3	How to prevent sharing of music expressions	641
22.3.4	Substitution functions and relative octave entry	643
22.4	Special characters	644
22.4.1	Text encoding	644
22.4.2	Unicode	645
22.4.3	ASCII aliases	645
23	Controlling output	647
23.1	Extracting fragments of music	647
23.2	Skipping corrected music	647
23.3	Alternative output formats	648
23.3.1	SVG Output	648
23.4	Embedding files in PDF output	649
23.5	Replacing the notation font	649
24	Creating MIDI output	651
24.1	Supported notation for MIDI	651
24.2	Unsupported notation for MIDI	652
24.3	The MIDI block	652
24.4	Controlling MIDI dynamics	653
24.4.1	Dynamic marks in MIDI	653
24.4.2	Setting MIDI volume	654
24.4.3	Setting MIDI block properties	656
24.5	Using MIDI instruments	657
24.6	Using repeats with MIDI	658
24.7	MIDI channel mapping	658
24.8	Context properties for MIDI effects	661
24.9	Enhancing MIDI output	662
24.9.1	The articulate script	662
24.9.2	The swing script	662
25	Extracting musical information	664
25.1	Displaying LilyPond notation	664
25.2	Displaying Scheme music expressions	664
25.3	Saving music events to a file	664

Spacing issues

26	Page layout	669
26.1	The <code>\paper</code> block	669
26.2	Paper size and automatic scaling	670
26.2.1	Setting the paper size	670
26.2.2	Automatic scaling to paper size	671
26.3	Fixed vertical spacing <code>\paper</code> variables	671
26.4	Flexible vertical spacing <code>\paper</code> variables	672
26.4.1	Structure of flexible vertical spacing <code>alist</code> s	672
26.4.2	List of flexible vertical spacing <code>\paper</code> variables	673
26.5	Horizontal spacing <code>\paper</code> variables	674
26.5.1	<code>\paper</code> variables for widths and margins	674
26.5.2	<code>\paper</code> variables for two-sided mode	676
26.5.3	<code>\paper</code> variables for shifts and indents	676
26.6	Other <code>\paper</code> variables	677
26.6.1	<code>\paper</code> variables for line breaking	677
26.6.2	<code>\paper</code> variables for page breaking	677
26.6.3	<code>\paper</code> variables for page numbering	678
26.6.4	<code>\paper</code> variables concerning headers and markups	679
26.6.5	<code>\paper</code> variables for debugging	680
27	Score layout	681
27.1	The <code>\layout</code> block	681
27.2	Setting the staff size	683
28	Breaks	687
28.1	Line breaking	687
28.2	Page breaking	691
28.2.1	Manual page breaking	691
28.2.2	Optimal page breaking	692
28.2.3	Minimal page breaking	692
28.2.4	One-page page breaking	692
28.2.5	One-line page breaking	693
28.2.6	One-line-auto-height page breaking	693
28.2.7	Optimal page turning	693
29	Vertical spacing	695
29.1	Flexible vertical spacing within systems	695
29.1.1	Within-system spacing properties	695
29.1.2	Spacing of ungrouped staves	698
29.1.3	Spacing of grouped staves	699
29.1.4	Spacing of non-staff lines	700
29.2	Explicit staff and system positioning	702
29.3	Vertical collision avoidance	708

30	Horizontal spacing	711
30.1	Horizontal spacing overview	711
30.2	New spacing section	712
30.3	Changing horizontal spacing globally	713
30.3.1	Uniform stretching of tuplets	714
30.3.2	Strict note spacing	715
30.4	Adjusting horizontal spacing for specific layout objects	715
30.4.1	Overview of object-specific horizontal spacing tweaks	715
30.4.2	Spacing between adjacent non-musical items	716
30.4.3	Spacing between adjacent columns	718
30.5	Line width	720
30.6	Proportional notation	720
31	Fitting music onto fewer pages	727
31.1	Displaying spacing	727
31.2	Changing spacing	728
 Changing defaults		
32	Tuning output	733
33	Interpretation contexts	734
33.1	Contexts explained	734
33.1.1	Output definitions – blueprints for contexts	734
33.1.2	Score – the master of all contexts	734
33.1.3	Top-level contexts – staff containers	735
33.1.4	Intermediate-level contexts – staves	735
33.1.5	Bottom-level contexts – voices	736
33.2	Creating and referencing contexts	737
33.3	Keeping contexts alive	740
33.4	Modifying context plug-ins	743
33.5	Changing context default settings	744
33.5.1	Changing all contexts of the same type	744
33.5.2	Changing just one specific context	747
33.5.3	Order of precedence	749
33.6	Defining new contexts	749
33.7	Context layout order	753
34	Explaining the Internals Reference	755
34.1	Navigating the program reference	755
34.2	Layout interfaces	755
34.3	Determining the grob property	757

35	Modifying properties	758
35.1	Overview of modifying properties	758
35.2	<code>\set</code> and <code>\unset</code>	758
35.3	<code>\override</code> and <code>\revert</code>	760
35.4	The <code>\once</code> command	761
35.5	<code>\set</code> versus <code>\override</code>	762
35.6	<code>\tweak</code> and <code>\single</code>	762
35.7	The <code>\offset</code> command	764
35.8	Modifying alists	769
36	Useful concepts and properties	772
36.1	Direction and placement	772
36.1.1	Articulation direction indicators	772
36.1.2	The direction property	773
36.2	Distances and measurements	773
36.3	Dimensions	774
36.4	Spanners	774
36.4.1	Modifying broken spanners	774
36.4.2	Setting minimum lengths for spanners	776
36.4.3	Controlling spanner end points	779
36.5	Line styles	780
36.6	Line spanners	780
36.7	Visibility of objects	782
36.7.1	Removing the stencil	783
36.7.2	Making objects transparent	783
36.7.3	Painting objects white	783
36.7.4	Using break-visibility	784
36.7.5	Special considerations	786
36.8	Rotating objects	789
36.8.1	Rotating layout objects	789
36.8.2	Rotating markup	789
36.9	Aligning objects	789
36.9.1	Setting X-offset and Y-offset directly	791
36.9.2	Using the side-position-interface	791
36.9.3	Using the self-alignment-interface	792
36.9.4	Using the break-alignable-interface	795
36.10	Modifying stencils	798
36.11	Modifying shapes	799
36.11.1	Modifying ties and slurs	799

Appendices

A	Markup commands	807
A.1	Text markup commands	807
A.1.1	Font markup	807
A.1.2	Markup for text alignment	820
A.1.3	Graphical markup	838
A.1.4	Markup for music and musical symbols	849
A.1.5	Conditional markup	862

A.1.6 Instrument-specific markup.....	862
A.1.7 Accordion registers.....	867
A.1.8 Other markup commands.....	872
A.2 Text markup list commands.....	884

B Notation manual tables 888

B.1 Chord name chart.....	888
B.2 Common chord modifiers.....	888
B.3 Predefined string tunings.....	891
B.4 Predefined fretboard diagrams.....	892
B.4.1 Diagrams for Guitar.....	892
B.4.2 Diagrams for Ukulele.....	894
B.4.3 Diagrams for Mandolin.....	895
B.5 Predefined paper sizes.....	897
B.6 MIDI instruments.....	899
B.7 List of colors.....	900
B.8 The Emmentaler font.....	905
B.8.1 Modern glyph charts.....	905
B.8.2 Ancient glyph charts.....	914
B.9 Note head styles.....	920
B.10 Accidental glyph sets.....	920
B.11 Clef styles.....	921
B.11.1 Standard clefs.....	921
B.11.2 Percussion staff clef.....	922
B.11.3 Tab staff clefs.....	922
B.11.4 Ancient music clefs.....	923
B.12 List of special characters.....	925
B.13 List of articulations.....	927
B.13.1 Articulation scripts.....	927
B.13.2 Ornament scripts.....	927
B.13.3 Fermata scripts.....	928
B.13.4 Instrument-specific scripts.....	928
B.13.5 Repeat sign scripts.....	929
B.13.6 Ancient scripts.....	929
B.14 List of breath marks.....	929
B.15 Percussion notes.....	930
B.16 List of bar lines.....	932
B.17 Default values for outside-staff-priority.....	936
B.18 Default values for script-priority.....	937
B.19 Grobs and their break-align symbols.....	938
B.20 Technical glossary.....	939
B.21 Available music functions.....	942
B.22 Context modification identifiers.....	962
B.23 Paper variables.....	963
B.24 Naming conventions.....	972
B.25 Predefined type predicates.....	972
B.25.1 R5RS primary predicates.....	972
B.25.2 R5RS secondary predicates.....	973
B.25.3 Guile predicates.....	973
B.25.4 LilyPond scheme predicates.....	973
B.25.5 LilyPond exported predicates.....	974

C	Cheat sheet	976
D	GNU Free Documentation License.....	979
E	Index	986

Musical notation

1 Pitches

34 *dolce e molto legato*
p
cresc.
sf
 Red. * Red. * Red. *

38
p
 Red. *

This section discusses how to specify the pitch of notes. There are three steps to this process: input, modification, and output.

1.1 Writing pitches

This section discusses how to input pitches. There are two different ways to place notes in octaves: absolute and relative mode. In most cases, relative mode will be more convenient.

1.1.1 Absolute octave entry

A pitch name is specified using lowercase letters a through g. The note names c to b are engraved in the octave below middle C.

```
{
  \clef bass
  c4 d e f
  g4 a b c
  d4 e f g
}
```

Other octaves may be specified with a single quote (') or comma (,) character. Each ' raises the pitch by one octave; each , lowers the pitch by an octave.

```
{
  \clef treble
  c'4 e' g' c''
  c'4 g b c'
  \clef bass
  c,4 e, g, c
  c,4 g,, b,, c,
}
```



Common octave marks can be entered just once on a reference pitch after `\fixed` placed before the music. Pitches inside `\fixed` only need ' or , marks when they are above or below the octave of the reference pitch.

```
{
  \fixed c' {
    \clef treble
    c4 e g c'
    c4 g, b, c
  }
  \clef bass
  \fixed c, {
    c4 e g c'
    c4 g, b, c
  }
}
```



Pitches in the music expression following `\fixed` are unaffected by any enclosing `\relative`, discussed next.

See also

Music Glossary: Section “Pitch names” in *Music Glossary*.

Snippets: Section “Pitches” in *Snippets*.

1.1.2 Relative octave entry

Absolute octave entry requires specifying the octave for every single note. Relative octave entry, in contrast, specifies each octave in relation to the last note: changing one note’s octave will affect all of the following notes.

Relative note mode has to be entered explicitly using the `\relative` command:

```
\relative startpitch musicexpr
```

In relative mode, each note is assumed to be as close to the previous note as possible. This means that the octave of each pitch inside *musicexpr* is calculated as follows:

- If no octave changing mark is used on a pitch, its octave is calculated so that the interval with the previous note is less than a fifth. This interval is determined without considering accidentals.

- An octave changing mark ' or , can be added to respectively raise or lower a pitch by an extra octave, relative to the pitch calculated without an octave mark.
- Multiple octave changing marks can be used. For example, '' and ,, will alter the pitch by two octaves.
- The pitch of the first note is relative to *startpitch*. *startpitch* is specified in absolute octave mode. Which choices are meaningful?

an octave of c

Identifying middle C with c' is quite basic, so finding octaves of c tends to be straightforward. If your music starts with gis above c'', you'd write something like `\relative c'' { gis' ... }`

an octave of the first note inside

Writing `\relative gis'' { gis ... }` makes it easy to determine the absolute pitch of the first note inside.

no explicit starting pitch

The form `\relative { gis'' ... }` serves as a compact version of the previous option: the first note inside is written in absolute pitch itself. (This happens to be equivalent to choosing f as the reference pitch.)

The documentation will usually employ the last option.

Here is the relative mode shown in action:

```
\relative {
  \clef bass
  c d e f
  g a b c
  d e f g
}
```



Octave changing marks are used for intervals greater than a fourth:

```
\relative {
  c'' g c f,
  c' a, e'' c
}
```



A note sequence without a single octave mark can nevertheless span large intervals:

```
\relative {
  c f b e
  a d g c
}
```



When `\relative` blocks are nested, the innermost `\relative` block starts with its own reference pitch independently of the outer `\relative`.

```
\relative {
  c' d e f
  \relative {
    c'' d e f
  }
}
```




To use absolute mode inside of `\relative`, put the absolute music inside `\fixed c { ... }` and the absolute pitches will not affect the octaves of the relative music:

```
\relative {
  c'4 \fixed c { f'' g'' } c |
  c4 \fixed c'' { f g } c
}
```



`\relative` is not allowed inside of `\chordmode` blocks. `\chordmode` blocks inside a `\relative` block remain unchanged.

```
\new Staff {
  \relative c''' {
    \chordmode { c1 }
  }
  \chordmode { c1 }
}
```



Music inside a `\transpose` block is absolute unless a `\relative` is included.

```
\relative {
  d' e
  \transpose f g {
    d e
    \relative {
      d' e
    }
  }
}
```



If the preceding item is a chord, the first note of the chord is used as the reference point for the octave placement of a following note or chord. Inside chords, the next note is always relative to the preceding one. Examine the next example carefully, paying attention to the c notes.

```
\relative {
  c'
  <c e g>
  <c' e g'>
  <c, e, g''>
}
```




As explained above, the octave of pitches is calculated only with the note names, regardless of any alterations. Therefore, an E-double-sharp following a B will be placed higher, while an F-double-flat will be placed lower. In other words, a double-augmented fourth is considered a smaller interval than a double-diminished fifth, regardless of the number of semitones that each interval contains.

```
\relative {
  c''2 fis
  c2 ges
  b2 eisis
  b2 feses
}
```



In complex situations, it is sometimes useful to get back to a certain pitch regardless of what happened before. This can be done using `\resetRelativeOctave`:

```
\relative {
  <<
    { c''2 d }
  \\\
    { e,,2 f }
  >>
  \resetRelativeOctave c''
  c2
}
```



See also

Music Glossary: Section “fifth” in *Music Glossary*, Section “interval” in *Music Glossary*, Section “Pitch names” in *Music Glossary*.

Notation Reference: Section 1.2.1 [Octave checks], page 12.

Snippets: Section “Pitches” in *Snippets*.

Internals Reference: Section “RelativeOctaveMusic” in *Internals Reference*.

1.1.3 Accidentals

Note: New users are sometimes confused about accidentals and key signatures. In LilyPond, note names specify pitches; key signatures and clefs determine how these pitches are displayed. An unaltered note like `c` means ‘C natural’, regardless of the key signature or clef. For more information, see Section “Pitches and key signatures” in *Learning Manual*.

A *sharp* pitch is made by adding `is` to the note name, and a *flat* pitch by adding `es`. As you might expect, a *double sharp* or *double flat* is made by adding `isis` or `eses`. This syntax is derived from Dutch note naming conventions. To use other names for accidentals, see Section 1.1.5 [Note names in other languages], page 10.

```
\relative c'' { ais1 aes aisis aeses }
```



A natural pitch is entered as a simple note name; no suffix is required. A natural sign will be printed when needed to cancel the effect of an earlier accidental or key signature.

```
\relative c'' { a4 aes a2 }
```



Quarter tones may be added; the following is a series of Cs with increasing pitches:

```
\relative c'' { ceseh1 ces ceh c cih cis cisih }
```



Normally accidentals are printed automatically, but you may also print them manually. A reminder accidental can be forced by adding an exclamation mark `!` after the pitch. A cautionary accidental (i.e., an accidental within parentheses) can be obtained by adding the question mark `?` after the pitch.

```
\relative c'' { cis cis cis! cis? c c c! c? }
```



Accidentals on tied notes are only printed at the beginning of a new system:

```
\relative c'' {
  cis1~ 1~
  \break
  cis
}
```



Selected snippets

Hiding accidentals on tied notes at the start of a new system

This shows how to hide accidentals on tied notes at the start of a new system.

```
\relative c'' {
  \override Accidental.hide-tied-accidental-after-break = ##t
  cis1~ cis~
  \break
  cis
}
```



Preventing extra naturals from being automatically added

In accordance with traditional typesetting rules, a natural sign is printed before a sharp or flat if a previous double sharp or flat on the same note is canceled. To change this behavior to contemporary practice, set the `extraNatural` property to `#f` in the `Staff` context.

```
\relative c'' {
  aeses4 aes ais a
  \set Staff.extraNatural = ##f
  aeses4 aes ais a
}
```



See also

Music Glossary: Section “sharp” in *Music Glossary*, Section “flat” in *Music Glossary*, Section “double sharp” in *Music Glossary*, Section “double flat” in *Music Glossary*, Section “Pitch names” in *Music Glossary*, Section “quarter tone” in *Music Glossary*.

Learning Manual: Section “Pitches and key signatures” in *Learning Manual*.

Notation Reference: Section 1.3.5 [Automatic accidentals], page 31, Section 17.3.8 [Annotational accidentals (*musica ficta*)], page 546, Section 1.1.5 [Note names in other languages], page 10.

Snippets: Section “Pitches” in *Snippets*.

Internals Reference: Section “Accidental_engraver” in *Internals Reference*, Section “Accidental” in *Internals Reference*, Section “AccidentalCautionary” in *Internals Reference*, Section “accidental-interface” in *Internals Reference*.

Known issues and warnings

There are no generally accepted standards for denoting quarter tone accidentals, so LilyPond’s symbols do not conform to any standard.

1.1.4 Approximate pitches

To write a note when the pitch is not known exactly, such as the highest note a singer can sing, use the `\approximatePitch` command with a pitch that communicates the rough expectation. LilyPond prints the note at the given pitch with a triangular head and no ledger lines.

```
\relative c' ' {
  e4 f g \approximatePitch c
}
```



See also

Internals Reference: Section “ApproximatePitchNoteHead” in *Internals Reference*, Section “Note_heads_engraver” in *Internals Reference*.

1.1.5 Note names in other languages

There are predefined sets of note and accidental names for various other languages. Selecting the note name language is usually done at the beginning of the file; the following example is written using Italian note names:

```
\language "italiano"
```

```
\relative {
  do' re mi sib
}
```



The available languages and the note names they define are:

Language	Note Names
nederlands	c d e f g a bes b
català or catalan	do re mi fa sol la sib si
deutsch	c d e f g a b h
english	c d e f g a bf/b-flat b
español or espanol	do re mi fa sol la sib si

français	do ré/re mi fa sol la sib si
italiano	do re mi fa sol la sib si
norsk	c d e f g a b h
português or portugues	do re mi fa sol la sib si
suomi	c d e f g a b h
svenska	c d e f g a b h
vlaams	do re mi fa sol la sib si

In addition to note names, accidental suffixes may also vary depending on the language:

Language	sharp	flat	double sharp	double flat
nederlands	is	es	isis	eses
català or catalan	d/s	b	dd/ss	bb
deutsch	is	es	isis	eses
english	s/-sharp	f/-flat	ss/x/-sharpsharp	ff/-flatflat
español or español	s	b	ss/x	bb
français	d	b	dd/x	bb
italiano	d	b	dd	bb
norsk	iss/is	ess/es	ississ/isis	essess/eses
português or portugues	s	b	ss	bb
suomi	is	es	isis	eses
svenska	iss	ess	ississ	essess
vlaams	k	b	kk	bb

In Dutch, German, Norwegian, and Finnish, aes is contracted to as; in Dutch and Norwegian, however, both forms are accepted by LilyPond. Exactly the same holds for es and ees, aeses and ases, and finally eeses and eses.

In German and Finnish, LilyPond additionally provides the more frequent form asas for ases.

```
\relative c'' { a2 as e es a ases e eses }
```



Some music uses microtones whose alterations are fractions of a ‘normal’ sharp or flat. The following table lists note name suffixes for quarter tone accidentals; here the prefixes *semi-* and *sesqui-* respectively mean ‘half’ and ‘one and a half’.

Language	semi-sharp	semi-flat	sesqui-sharp	sesqui-flat
nederlands	ih	eh	isih	eseh
català or catalan	qd/qs	qb	tqd/tqs	tqb
deutsch	ih	eh	isih	eseh
english	qs	qf	tqs	tqf
español or español	cs	cb	tcs	tcb
français	sd	sb	dsd	bsb
italiano	sd	sb	dsd	bsb
norsk	ih	eh	issih/isih	esseh/eseh

português or portugues	sqt	bqt	stqt	btqt
suomi	ih	eh	isih	eseh
svenska	ih	eh	issih	esseh
vlaams	hk	hb	khk	bhb

In German, there are similar name contractions for microtones as with normal pitches described above.

```
\language "deutsch"
```

```
\relative c'' { asah2 eh aih eisih }
```



Most languages presented here are commonly associated with Western classical music, also referred to as *Common Practice Period*. However, alternate pitches and tuning systems are also supported: see Section 18.1 [Common notation for non-Western music], page 574.

See also

Music Glossary: Section “Pitch names” in *Music Glossary*, Section “Common Practice Period” in *Music Glossary*.

Notation Reference: Section 18.1 [Common notation for non-Western music], page 574.

Installed Files: `scm/define-note-names.scm`.

Snippets: Section “Pitches” in *Snippets*.

1.2 Changing multiple pitches

This section discusses how to modify pitches.

1.2.1 Octave checks

In relative mode, it is easy to forget an octave changing mark. Octave checks make such errors easier to find by displaying a warning and correcting the octave if a note is found in an unexpected octave.

To check the octave of a note, specify the absolute octave after the = symbol. This example will generate a warning (and change the pitch) because the second note is the absolute octave d'' instead of d' as indicated by the octave correction.

```
\relative {
  c''2 d='
  e2 f
}
```



The octave of notes may also be checked with the `\octaveCheck controlpitch` command. `controlpitch` is specified in absolute mode. This checks that the interval between the previous note and the `controlpitch` is within a fourth (i.e., the normal calculation of relative mode). If this check fails, a warning is printed. While the previous note itself is not changed, future notes are relative to the corrected value.

```
\relative {
  c''2 d
  \octaveCheck c'
  e2 f
}
```



Compare the two bars below. The first and third `\octaveCheck` checks fail, but the second one does not fail.

```
\relative {
  c''4 f g f

  c4
  \octaveCheck c'
  f
  \octaveCheck c'
  g
  \octaveCheck c'
  f
}
```



See also

Snippets: Section “Pitches” in *Snippets*.

Internals Reference: Section “RelativeOctaveCheck” in *Internals Reference*.

1.2.2 Transpose

A music expression can be transposed with `\transpose`. The syntax is

```
\transpose frompitch topitch musicexpr
```

This means that *musicexpr* is transposed by the interval between the pitches *frompitch* and *topitch*: any note with pitch *frompitch* is changed to *topitch* and any other note is transposed by the same interval. Both pitches are entered in absolute mode.

Note: Music inside a `\transpose` block is absolute unless a `\relative` is included in the block.

Consider a piece written in the key of D-major. It can be transposed up to E-major; note that the key signature is automatically transposed as well.

```
\transpose d e {
  \relative {
    \key d \major
    d'4 fis a d
  }
}
```



If a part written in C (normal *concert pitch*) is to be played on the A clarinet (for which an A is notated as a C and thus sounds a minor third lower than notated), the appropriate part will be produced with:

```
\transpose a c' {
  \relative {
    \key c \major
    c'4 d e g
  }
}
```



Note that we specify `\key c \major` explicitly. If we do not specify a key signature, the notes will be transposed but no key signature will be printed.

`\transpose` distinguishes between enharmonic pitches: both `\transpose c cis` or `\transpose c des` will transpose up a semitone. The first version will print sharps and the notes will remain on the same scale step, the second version will print flats on the scale step above.

```
music = \relative { c' d e f }
\new Staff {
  \transpose c cis { \music }
  \transpose c des { \music }
}
```



`\transpose` may also be used in a different way, to input written notes for a transposing instrument. The previous examples show how to enter pitches in C (or *concert pitch*) and typeset them for a transposing instrument, but the opposite is also possible if you for example have a set of instrumental parts and want to print a conductor's score. For example, when entering music for a B-flat trumpet that begins on a notated E (concert D), one would write:

```
musicInBflat = { e4 ... }
\transpose c bes, \musicInBflat
```

To print this music in F (e.g., rearranging to a French horn) you could wrap the existing music with another `\transpose`:

```
musicInBflat = { e4 ... }
\transpose f c' { \transpose c bes, \musicInBflat }
```

For more information about transposing instruments, see Section 1.3.4 [Instrument transpositions], page 30.

Selected snippets

Transposing pitches with minimum accidentals (“smart” transpose)

This example uses some Scheme code to enforce enharmonic modifications for notes in order to have the minimum number of accidentals. In this case, the following rules apply:

- double accidentals should be removed
- b sharp $\rightarrow$ c
- e sharp $\rightarrow$ f
- c flat $\rightarrow$ b
- f flat $\rightarrow$ e

In this manner, the most natural enharmonic notes are chosen.

```
#(define (naturalize-pitch p)
  (let ((o (ly:pitch-octave p))
        ;; `ly:pitch-alteration` returns quarter tone steps.
        (a (* 4 (ly:pitch-alteration p)))
        (n (ly:pitch-notename p)))
    (cond
      ((and (> a 1)
            (or (eqv? n 6) (eqv? n 2)))
       (set! a (- a 2))
       (set! n (+ n 1)))
      ((and (< a -1)
            (or (eqv? n 0) (eqv? n 3)))
       (set! a (+ a 2))
       (set! n (- n 1)))
      ((> a 2)
       (set! a (- a 4))
       (set! n (+ n 1)))
      ((< a -2)
       (set! a (+ a 4))
       (set! n (- n 1)))
      (when (< n 0)
        (set! o (- o 1))
        (set! n (+ n 7)))
      (when (> n 6)
        (set! o (+ o 1))
        (set! n (- n 7)))
      (ly:make-pitch o n (/ a 4))))

#(define (naturalize music)
  (let ((es (ly:music-property music 'elements))
        (e (ly:music-property music 'element))
        (p (ly:music-property music 'pitch)))
    (when (pair? es)
      (ly:music-set-property! music 'elements
                              (map naturalize es)))
    (when (ly:music? e)
      (ly:music-set-property! music 'element
                              (naturalize e))))
```


Note: Motifs to be inverted should be expressed in absolute form or be first converted to absolute form by enclosing them in a `\relative` block.

See also

Notation Reference: Section 1.2.5 [Modal transformations], page 17, Section 1.2.4 [Retrograde], page 17, Section 1.2.2 [Transpose], page 13.

1.2.4 Retrograde

A music expression can be reversed to produce its retrograde:

```
music = \relative { c'8. ees16( fis8. a16 b8.) gis16 f8. d16 }

\new Staff {
  \music
  \retrograde \music
}
```



Known issues and warnings

`\retrograde` is a rather simple tool. Since many events are ‘mirrored’ rather than exchanged, tweaks and directional modifiers for opening spanners need to be added at the matching closing spanners: `^(` needs to be ended by `^)`, every `\<` or `\cresc` needs to be ended by `\!` or `\endcr`, every `\>` or `\decr` needs to be ended by `\enddecr`. Property-changing commands/overrides with a lasting effect will likely cause surprises.

See also

Notation Reference: Section 1.2.3 [Inversion], page 16, Section 1.2.5 [Modal transformations], page 17, Section 1.2.2 [Transpose], page 13.

1.2.5 Modal transformations

In a musical composition that is based on a scale, a motif is frequently transformed in various ways. It may be *transposed* to start at different places in the scale or it may be *inverted* around a pivot point in the scale. It may also be reversed to produce its *retrograde*, see Section 1.2.4 [Retrograde], page 17.

Note: Any note that does not lie within the given scale will be left untransformed.

Modal transposition

A motif can be transposed within a given scale with:

```
\modalTranspose from-pitch to-pitch scale motif
```

The notes of *motif* are shifted within the *scale* by the number of scale degrees given by the interval between *to-pitch* and *from-pitch*:


```
diatonicScale = \relative { c' d e f g a b }
motif = \relative { c'8 d e f g a b c }
```

```
\new Staff {
  \motif
  \modalTranspose c f \diatonicScale \motif
  \modalTranspose c b, \diatonicScale \motif
}
```



An ascending scale of any length and with any intervals may be specified:

```
pentatonicScale = \relative { ges aes bes des ees }
motif = \relative { ees'8 des ges,4 <ges' bes,> <ges bes,> }
```

```
\new Staff {
  \motif
  \modalTranspose ges ees' \pentatonicScale \motif
}
```



When used with a chromatic scale `\modalTranspose` has a similar effect to `\transpose`, but with the ability to specify the names of the notes to be used:

```
chromaticScale = \relative { c' cis d dis e f fis g gis a ais b }
motif = \relative { c'8 d e f g a b c }
```

```
\new Staff {
  \motif
  \transpose c f \motif
  \modalTranspose c f \chromaticScale \motif
}
```



Modal inversion

A motif can be inverted within a given scale around a given pivot note and transposed in a single operation with:

```
\modalInversion around-pitch to-pitch scale motif
```

The notes of *motif* are placed the same number of scale degrees from the *around-pitch* note within the *scale*, but in the opposite direction, and the result is then shifted within the *scale* by the number of scale degrees given by the interval between *to-pitch* and *around-pitch*.

So to simply invert around a note in the scale use the same value for *around-pitch* and *to-pitch*:

```

octatonicScale = \relative { ees' f fis gis a b c d }
motif = \relative { c'8. ees16 fis8. a16 b8. gis16 f8. d16 }

\new Staff {
  \motif
  \modalInversion fis' fis' \octatonicScale \motif
}

```



To invert around a pivot between two notes in the scale, invert around one of the notes and then transpose by one scale degree. The two notes specified can be interpreted as bracketing the pivot point:

```

scale = \relative { c' g' }
motive = \relative { c' c g' c, }

\new Staff {
  \motive
  \modalInversion c' g' \scale \motive
}

```



The combined operation of inversion and retrograde produce the retrograde inversion:

```

octatonicScale = \relative { ees' f fis gis a b c d }
motif = \relative { c'8. ees16 fis8. a16 b8. gis16 f8. d16 }

\new Staff {
  \motif
  \retrograde \modalInversion c' c' \octatonicScale \motif
}

```



See also

Notation Reference: Section 1.2.3 [Inversion], page 16, Section 1.2.4 [Retrograde], page 17, Section 1.2.2 [Transpose], page 13.

1.3 Displaying pitches

This section discusses how to alter the output of pitches.

1.3.1 Clef


Without any explicit command, the default clef for LilyPond is the treble (or *G*) clef.

```
c'2 c'
```



However, the clef can be changed by using the `\clef` command and an appropriate clef name. *Middle C* is shown in each of the following examples.

```
\clef treble
c'2 c'
\clef alto
c'2 c'
\clef tenor
c'2 c'
\clef bass
c'2 c'
```



For the full range of possible clef names see Section B.11 [Clef styles], page 921.

Specialized clefs, such as those used in *Ancient* music, are described in Section 17.3.2 [Mensural clefs], page 542, and Section 17.4.2 [Gregorian clefs], page 554. Music that requires tablature clefs is discussed in Section 12.1.3 [Default tablatures], page 433, and Section 12.1.4 [Custom tablatures], page 452.

For mixing clefs when using cue notes, see the `\cueClef` and `\cueDuringWithClef` commands in Section 6.3.3 [Formatting cue notes], page 268.

By adding `_8` or `^8` to the clef name, the clef is transposed one octave down or up respectively, and `_15` and `^15` transpose by two octaves. Other integers can be used if required. Clef names containing non-alphabetic characters must be enclosed in quotes

```
\clef treble
c'2 c'
\clef "treble_8"
c'2 c'
\clef "bass^15"
c'2 c'
\clef "alto_2"
c'2 c'
\clef "G_8"
c'2 c'
\clef "F^5"
c'2 c'
```



Optional octavation can be obtained by enclosing the numeric argument in parentheses or brackets:


```
\clef "treble_(8)"
c'2 c'
\clef "bass^[15]"
c'2 c'
```



The pitches are displayed as if the numeric argument were given without parentheses/brackets.

By default, a clef change taking place at a line break causes the new clef symbol to be printed at the end of the previous line, as a ‘warning clef’, as well as at the beginning of the next. This warning clef can be suppressed.

```
\clef treble c'2 c' \break
\clef bass c'2 c' \break
\set Staff.explicitClefVisibility = #end-of-line-invisible
\clef alto c'2 c' \break
\unset Staff.explicitClefVisibility
\clef bass c'2 c'
```



By default, a clef that has previously been printed will not be reprinted if the same `\clef` command is issued again and will be ignored. The command `\set Staff.forceClef = ##t` changes this behavior.

```
\clef treble
c'1
\clef treble
c'1
\set Staff.forceClef = ##t
c'1
\clef treble
c'1
```



To be more precise, it is not the `\clef` command itself that prints a clef. Instead, it sets or changes a property of the `Clef_engraver`, which then decides by its own whether to display a

clef or not in the current staff. The `forceClef` property overrides this decision locally to reprint a clef once.

When there is a manual clef change, the glyph of the changed clef will be smaller than normal. This behavior can be overridden.

```
\clef "treble"
c'1
\clef "bass"
c'1
\clef "treble"
c'1
\override Staff.Clef.full-size-change = ##t
\clef "bass"
c'1
\clef "treble"
c'1
\revert Staff.Clef.full-size-change
\clef "bass"
c'1
\clef "treble"
c'1
```



Selected snippets

Tweaking clef properties

Changing the clef glyph, its position, or the ottavation does not change the position of subsequent notes on the staff. To get key signatures on their correct staff lines, `middleCClefPosition` must also be specified, with positive or negative values moving “middle C” up or down respectively, relative to the staff’s center line.

For example, `\clef "treble_8"` is equivalent to setting the context properties `clefGlyph`, `clefPosition` (the vertical position of the clef itself on the staff), `middleCPosition`, and `clefTransposition`. Note that when any of these properties (except `middleCPosition`) are changed a new clef symbol is printed.

The following examples show the possibilities when setting these properties manually. On the first line, the manual changes preserve the standard relative positioning of clefs and notes, whereas on the second line, they do not.

```
{
  % The default treble clef.
  \key f \major
  c'1
  % The standard bass clef
  \set Staff.clefGlyph = "clefs.F"
  \set Staff.clefPosition = 2
  \set Staff.middleCPosition = 6
  \set Staff.middleCClefPosition = 6
  \key g \major
  c'1
  % The baritone clef.
```

The image displays a musical score for the song "The Rose Tree". It consists of two systems of music. The first system is a single melodic line in treble clef, starting with a common time signature (C) and a key signature of one flat (B-flat). The melody is written on a five-line staff. The second system is a single melodic line in bass clef, starting with a common time signature (C) and a key signature of one flat (B-flat). The melody is written on a five-line staff. The score is presented in a clean, black-and-white format with standard musical notation, including notes, rests, and clefs.

See also

Notation Reference: Section 17.3.2 [Mensural clefs], page 542, Section 17.4.2 [Gregorian clefs], page 554, Section 12.1.3 [Default tablatures], page 433, Section 12.1.4 [Custom tablatures], page 452, Section 6.3.3 [Formatting cue notes], page 268.

Installed Files: `scm/parser-clef.scm`.

Snippets: Section “Pitches” in *Snippets*.

Internals Reference: Section “Clef-engraver” in *Internals Reference*, Section “Clef” in *Internals Reference*, Section “ClefModifier” in *Internals Reference*, Section “clef-interface” in *Internals Reference*.

Known issues and warnings

Ottavation numbers attached to clefs are treated as separate grobs. So any `\override` done to the *Clef* will also need to be applied, as a separate `\override`, to the *ClefModifier* grob.

```
\new Staff \with {
  \override Clef.color = #(universal-color 'blue)
  \override ClefModifier.color = #(universal-color 'vermillion)
}

\clef "treble_8" c'4
```



1.3.2 Key signature

Note: New users are sometimes confused about accidentals and key signatures. In LilyPond, note names are the raw input; key signatures and clefs determine how this raw input is displayed. An unaltered note like `c` means ‘C natural’, regardless of the key signature or clef. For more information, see Section “Pitches and key signatures” in *Learning Manual*.

The key signature indicates the tonality in which a piece is played. It is denoted by a set of alterations (flats or sharps) at the start of the staff. The key signature may be altered:

```
\key pitch mode
```

Here, *mode* should be `\major` or `\minor` to get a key signature of *pitch-major* or *pitch-minor*, respectively. You may also use the standard mode names, also called *church modes*: `\ionian`, `\dorian`, `\phrygian`, `\lydian`, `\mixolydian`, `\aeolian`, and `\locrian`.

```
\relative {
  \key g \major
  fis''1
  f
  fis
}
```



Additional modes can be defined, by listing the alterations for each scale step when the mode starts on C.

```

freygish = #`((0 . ,NATURAL) (1 . ,FLAT) (2 . ,NATURAL)
              (3 . ,NATURAL) (4 . ,NATURAL) (5 . ,FLAT) (6 . ,FLAT))

\relative {
  \key c \freygish c'4 des e f
  \bar "||" \key d \freygish d es fis g
}

```



Accidentals in the key signature may be printed in octaves other than their traditional positions, or in multiple octaves, by using the flat-positions and sharp-positions properties of KeySignature. Entries in these properties specify the range of staff positions where accidentals will be printed. If a single position is specified in an entry, the accidentals are placed within the octave ending at that staff position.

```

\override Staff.KeySignature.flat-positions = #'((-5 . 5))
\override Staff.KeyCancellation.flat-positions = #'((-5 . 5))
\clef bass \key es \major es g bes d'
\clef treble \bar "||" \key es \major es' g' bes' d''

\override Staff.KeySignature.sharp-positions = #'(2)
\bar "||" \key b \major b' fis' b'2

```



Selected snippets

Preventing natural signs from being printed when the key signature changes

When the key signature changes, natural signs are automatically printed to cancel any accidentals from previous key signatures. This may be prevented by setting the printKeyCancellation property to #f in the Staff context.

```

\relative c' {
  \key d \major
  a4 b cis d
  \key g \minor
  a4 bes c d
  \set Staff.printKeyCancellation = #f
  \key d \major
  a4 b cis d
  \key g \minor
  a4 bes c d
}

```




Non-traditional key signatures

The commonly used `\key` command sets the `keyAlterations` property, in the `Staff` context.

To create non-standard key signatures, set this property directly. The format of this command is a list:

```
\set Staff.keyAlterations =
  #`(((octave . step) . alter) ((octave . step) . alter) ...)
```

where, for each element in the list, *octave* specifies the octave (0 being the octave from middle C to the B above), *step* specifies the note within the octave (0 means C and 6 means B), and *alter* is one of SHARP, FLAT, DOUBLE-SHARP, etc., preceded by a comma.

Alternatively, you can use the more concise format (*step . alter*) for each item in the list if the same alterations are used in all octaves.

For microtonal scales where a “sharp” is not 100 cents, *alter* refers to the alteration as a proportion of a 200-cent whole tone.

```
\include "arabic.ly"
```

```
\relative do' {
  \set Staff.keyAlterations = #`((0 . ,SEMI-FLAT)
                                (1 . ,SEMI-FLAT)
                                (2 . ,FLAT)
                                (5 . ,FLAT)
                                (6 . ,SEMI-FLAT))

  % \set Staff.extraNatural = ##f
  re reb \down reb resd
  dod dob dosd \down dob |
  dobsb dodsd do do |
}
```



See also

Music Glossary: Section “church mode” in *Music Glossary*, Section “scordatura” in *Music Glossary*.

Learning Manual: Section “Pitches and key signatures” in *Learning Manual*.

Snippets: Section “Pitches” in *Snippets*.

Internals Reference: Section “KeyChangeEvent” in *Internals Reference*, Section “Key_engraver” in *Internals Reference*, Section “Key_performer” in *Internals Reference*, Section “KeyCancellation” in *Internals Reference*, Section “KeySignature” in *Internals Reference*, Section “key-signature-interface” in *Internals Reference*.


1.3.3 Ottava brackets

Ottava brackets raise or lower displayed notes by one or more octaves, leaving the sounding pitch unchanged. The purpose of the octavation is to reduce the use of ledger lines, especially when wide intervals occur in short passages. The `\ottava` takes a positive integer to indicate

playing higher than printed, or a negative to play lower. The effect of the ottava brackets lasts to the next entry of a different octavation, and can be ended by using `\ottava 0`.

In the following example, all notes sound at the same pitch:

```
\relative c' ' {
  a2 b
  \ottava -2
  a2 b
  \ottava -1
  a2 b
  \ottava 0
  a2 b
  \ottava 1
  a2 b
  \ottava 2
  a2 b
}
```



By default, only a number is printed at the start of the bracket. That setting may be changed to include an abbreviated ordinal, either in superscript or in normal letters; the initial bold font weight of these characters may also be altered, as explained in Section 8.2.2 [Selecting font and font size], page 323.

The following example demonstrates various options, as well as how to go back to the current default behavior:

```
\relative c' ' {
  \ottava 1
  a'2 b
  \ottava 2
  a'2 b
  \bar "||"
  \set Staff.ottavationMarkups = #ottavation-ordinals
  \ottava 1
  a,2 b
  \ottava 2
  a'2 b
  \bar "||"
  \override Staff.OttavaBracket.font-series = #'normal
  \set Staff.ottavationMarkups = #ottavation-simple-ordinals
  \ottava 1
  a,2 b
  \ottava 2
  a'2 b
  \bar "||"
  \revert Staff.OttavaBracket.font-series
  \set Staff.ottavationMarkups = #ottavation-numbers
  \ottava 1
```

```

a,2 b
\ottava 2
a'2 b
}

```



Selected snippets

Changing ottava text

Internally, `\ottava` sets the properties `ottavation` (for example, to `8va` or `8vb`) and `middleCPosition`. To override the text of the bracket, set `ottavation` after invoking `\ottava`.

Short text is especially useful when a brief ottava is used.

```

{
  c'2
  \ottava 1
  \set Staff.ottavation = "8"
  c''2
  \ottava 0
  c'1
  \ottava 1
  \set Staff.ottavation = "Text"
  c''1
}

```



Adding an ottava marking to a single voice

If you have more than one voice on the staff, setting `ottavation` in one voice transposes the position of notes in all voices for the duration of the `ottava` bracket. If the `ottavation` is only intended to apply to one voice, the `Ottava_spanner_engraver` should be moved to `Voice` context.

```

\layout {
  \context {
    \Staff
    \remove Ottava_spanner_engraver
  }
  \context {
    \Voice
    \consists Ottava_spanner_engraver
  }
}


{
  \clef bass
  << { <g d'>1~ q2 <c' e'> }
}

```

```

\\
{
  r2.
  \ottava -1
  <b,,, b,,,>4 ~ |
  q2
  \ottava 0
  <c e>2
}
>>
}

```




Modifying the ottava spanner slope

It is possible to change the slope of the ottava spanner.

```

\relative c'' {
  \override Staff.OttavaBracket.stencil = #ly:line-spanner::print
  \override Staff.OttavaBracket.bound-details =
    #`((left . ((Y . 0)
      (attach-dir . ,LEFT)
      (padding . 0)
      (stencil-align-dir-y . ,CENTER)))
    (right . ((Y . 5.0) ; Change the number here
      (padding . 0)
      (attach-dir . ,RIGHT)
      (text . ,(make-draw-dashed-line-markup
        (cons 0 -1.2))))))
  \override Staff.OttavaBracket.left-bound-info =
    #ly:horizontal-line-spanner::calc-left-bound-info-and-text
  \override Staff.OttavaBracket.right-bound-info =
    #ly:horizontal-line-spanner::calc-right-bound-info
  \ottava 1
  c1
  c'''1
}

```



See also

Music Glossary: Section “octavation” in *Music Glossary*.

Notation Reference: Section 8.2.2 [Selecting font and font size], page 323.

Snippets: Section “Pitches” in *Snippets*.

Internals Reference: Section “Ottava_spanner_engraver” in *Internals Reference*, Section “OttavaBracket” in *Internals Reference*, Section “ottava-bracket-interface” in *Internals Reference*.

1.3.4 Instrument transpositions

When typesetting scores that involve transposing instruments, some parts can be typeset in a different pitch than the *concert pitch*. In these cases, the key of the *transposing instrument* should be specified; otherwise the MIDI output and cues in other parts will produce incorrect pitches. For more information about quotations, see Section 6.3.2 [Quoting other voices], page 265.

`\transposition pitch`

The pitch to use for `\transposition` should correspond to the real sound heard when a `c'` written on the staff is played by the transposing instrument. This pitch is entered in absolute mode, so an instrument that produces a real sound which is one tone higher than the printed music should use `\transposition d'`. `\transposition` should *only* be used if the pitches are *not* being entered in concert pitch.

Here are a few notes for violin and B-flat clarinet where the parts have been entered using the notes and key as they appear in each part of the conductor’s score. The two instruments are playing in unison.

```
\new GrandStaff <<
  \new Staff = "violin" \with {
    instrumentName = "Vln"
    midiInstrument = "violin"
  }
  \relative c'' {
    % not strictly necessary, but a good reminder
    \transposition c'
    \key c \major
    g4( c8) r c r c4
  }
  \new Staff = "clarinet" \with {
    instrumentName = \markup { Cl (B\flat) }
    midiInstrument = "clarinet"
  }
  \relative c'' {
    \transposition bes
    \key d \major
    a4( d8) r d r d4
  }
}>>
```



The `\transposition` may be changed during a piece. For example, a clarinetist may be required to switch from an A clarinet to a B-flat clarinet.

```

flute = \relative c'' {
  \key f \major
  \cueDuring "clarinet" #DOWN {
    R1 _\markup\tiny "clarinet"
    c4 f e d
    R1 _\markup\tiny "clarinet"
  }
}
clarinet = \relative c'' {
  \key aes \major
  \transposition a
  aes4 bes c des
  R1^\markup { muta in B\flat }
  \key g \major
  \transposition bes
  d2 g,
}
\addQuote "clarinet" \clarinet
<<
  \new Staff \with { instrumentName = "Flute" }
  \flute
  \new Staff \with { instrumentName = "Cl (A)" }
  \clarinet
>>

```

See also

Music Glossary: Section “concert pitch” in *Music Glossary*, Section “transposing instrument” in *Music Glossary*.

Notation Reference: Section 6.3.2 [Quoting other voices], page 265, Section 1.2.2 [Transpose], page 13.

Snippets: Section “Pitches” in *Snippets*.

1.3.5 Automatic accidentals

There are many different conventions on how to typeset accidentals. LilyPond provides a function to specify which accidental style to use. This function is called as follows:

```

\new Staff <<
  \accidentalStyle voice
  { ... }
>>

```

The accidental style normally applies to the current Staff (with the exception of the styles choral, piano and piano-cautionary, which are explained below). Optionally, the function can take a second argument that determines in which scope the style should be changed. For example, to use the same style in all staves of the current StaffGroup, use:

```

\accidentalStyle StaffGroup.voice


```

The following accidental styles are supported. To demonstrate each style, we use the following example:

```
musicA = {
  <<
    \relative {
      cis''8 fis, bes4 <a cis>8 f bis4 |
      cis2. <c, g'>4 |
    }
  \\\
    \relative {
      ais'2 cis, |
      fis8 b a4 cis2 |
    }
  >>
}
```

```
musicB = {
  \clef bass
  \new Voice {
    \voiceTwo \relative {
      <fis a cis>8[ <fis a cis>
      \change Staff = up
      cis' cis
      \change Staff = down
      <fis, a> <fis a>]
      \showStaffSwitch
      \change Staff = up
      dis'4 |
      \change Staff = down
      <fis, a cis>4 gis <f a d>2 |
    }
  }
}
```

```
\new PianoStaff {
  <<
    \new Staff = "up" {
      \accidentalStyle default
      \musicA
    }
    \new Staff = "down" {
      \accidentalStyle default
      \musicB
    }
  >>
}
```



Note that the last lines of this example can be replaced by the following, as long as the same accidental style should be used in both staves.

```
\new PianoStaff {
  <<
    \new Staff = "up" {
      %% change the next line as desired:
      \accidentalStyle Score.default
      \musicA
    }
    \new Staff = "down" {
      \musicB
    }
  >>
}
```

default

This is the default typesetting behavior. It corresponds to eighteenth-century common practice: accidentals are remembered to the end of the measure in which they occur and only in their own octave. Thus, in the example below, no natural signs are printed before the b in the second measure or the last c :



voice


The normal behavior is to remember the accidentals at Staff-level. In this style, however, accidentals are typeset individually for each voice. Apart from that, the rule is similar to default.

As a result, accidentals from one voice do not get canceled in other voices, which is often an unwanted result: in the following example, it is hard to determine whether the second a should be played natural or sharp. The voice option should therefore be used only if the voices are to be read solely by individual musicians. If the staff is to be used by one musician (e.g., a conductor or in a piano score) then modern or modern-cautionary should be used instead.




modern

This rule corresponds to the common practice in the twentieth century. It omits some extra natural signs, which were traditionally prefixed to a sharp following a double sharp, or a flat following a double flat. The modern rule prints the same accidentals as default, with two additions that serve to avoid ambiguity: after temporary accidentals, cancellation marks are printed also in the following measure (for notes in the same octave) and, in the same measure, for notes in other octaves. Hence the naturals before the b and the c in the second measure of the upper staff:



modern-cautionary

This rule is similar to modern, but the ‘extra’ accidentals are printed as cautionary accidentals (with parentheses). They can also be printed at a different size by overriding `AccidentalCautionary’s` font-size property.



modern-voice

This rule is used for multi-voice accidentals to be read both by musicians playing one voice and musicians playing all voices. Accidentals are typeset for each voice, but they *are* canceled across voices in the same Staff. Hence, the a in the last measure is canceled because the previous cancellation was in a different voice, and the d in the lower staff is canceled because of the accidental in a different voice in the previous measure:



modern-voice-cautionary

This rule is the same as modern-voice, but with the extra accidentals (the ones not typeset by voice) typeset as cautionaries. Even though all accidentals typeset by default *are* typeset with this rule, some of them are typeset as cautionaries.



piano

This rule reflects twentieth-century practice for piano notation. Its behavior is very similar to modern style, but here accidentals also get canceled across the staves in the same GrandStaff or PianoStaff, hence all the cancellations of the final notes. This accidental style applies to the current GrandStaff or PianoStaff unless qualified with a second argument.




piano-cautionary

This is the same as piano but with the extra accidentals typeset as cautionaries.




choral

This rule is a combination of the modern-voice and the piano style. It shows all accidentals required for singers that only follow their own voice, as well as additional accidentals for readers that follow all voices of an entire ChoirStaff simultaneously. This accidental style applies to the current ChoirStaff unless qualified with a second argument.




choral-cautionary

This is the same as choral but with the extra accidentals typeset as cautionaries.



neo-modern

This rule reproduces a common practice in contemporary music: accidentals are printed like with modern, but they are printed again if the same note appears later in the same measure – except if the note is immediately repeated.



neo-modern-cautionary

This rule is similar to neo-modern, but the ‘extra’ accidentals are printed as cautionary accidentals (with parentheses). They can also be printed at a different size by overriding `AccidentalCautionary’s` font-size property.



neo-modern-voice

This rule is used for multi-voice accidentals to be read both by musicians playing one voice and musicians playing all voices. Accidentals are typeset for each voice as with neo-modern, but they are canceled across voices in the same Staff.



neo-modern-voice-cautionary

This rule is similar to neo-modern-voice, but the extra accidentals are printed as cautionary accidentals.



dodecaphonic

This rule reflects a practice introduced by composers at the beginning of the 20th century, in an attempt to abolish the hierarchy between natural and non-natural notes. With this style, *every* note gets an accidental sign, including natural signs.




dodecaphonic-no-repeat

Like with the dodecaphonic accidental style *every* note gets an accidental sign by default, but accidentals are suppressed for pitches immediately repeated within the same staff.



dodecaphonic-first

Similar to the dodecaphonic accidental style *every* pitch gets an accidental sign, but only the first time it is encountered in a measure. Accidentals are only remembered for the actual octave but throughout voices.



teaching

This rule is intended for students, and makes it easy to create scale sheets with automatically created cautionary accidentals. Accidentals are printed like with modern, but cautionary accidentals are added for all sharp or flat tones specified by the key signature, except if the note is immediately repeated.




no-reset

This is the same as default but with accidentals lasting 'forever' and not only within the same measure:



forget

This is the opposite of no-reset: Accidentals are not remembered at all – and hence all accidentals are typeset relative to the key signature, regardless of what came before in the music.



See also

Snippets: Section “Pitches” in *Snippets*.

Internals Reference: Section “Accidental” in *Internals Reference*, Section “Accidental-engraver” in *Internals Reference*, Section “GrandStaff” in *Internals Reference*, Section “PianoStaff” in *Internals Reference*, Section “Staff” in *Internals Reference*, Section “AccidentalSuggestion” in *Internals Reference*, Section “AccidentalPlacement” in *Internals Reference*, Section “accidental-suggestion-interface” in *Internals Reference*.

Known issues and warnings

Simultaneous notes are not considered in the automatic determination of accidentals; only previous notes and the key signature are taken into account. Forcing accidentals with ‘!’ or ‘?’ may be required when the same note name occurs simultaneously with different alterations, as in <f! fis!>.

```
\relative c' <<
  { fis8 g } \\  
  { f! f }  
>>
```



A more sophisticated solution is given in a LilyPond Wiki snippet (https://wiki.lilypond.community/wiki/Accidental_adjustments_for_single-voice_polyphony).

In alternative endings, cautionary cancellation should be based on the previous *played* measure, but it is based on the previous *printed* measure. In the following example, the natural c in the second alternative does not need a natural sign:




The following workaround can be used: define a function that locally changes the accidental style to forget:

```
forget = #(define-music-function (music) (ly:music?) #{  
  \accidentalStyle forget  
  #music  
  \accidentalStyle modern  
  #})  
{  
  \accidentalStyle modern  
  \time 2/4  
  \repeat volta 2 {  
    c'2
```

```

}
\alternative {
  \volta 1 { cis' }
  \volta 2 { \forget c' }
}
}

```



1.3.6 Alternate accidental glyphs

Non-Western and ancient notation systems have their own accidentals. The glyphs are controlled through the `alterationGlyphs` property of the `Staff` context and similar context types. The predefined values for this property are listed in Section B.10 [Accidental glyph sets], page 920.

```

\layout {
  \context {
    \Staff
    alterationGlyphs = #alteration-vaticana-glyph-name-alist
  }
}

{ ces' c' cis' }

```



The property may also be set to a custom associative list mapping alterations to glyph names. Alterations are given as fractions in tones. Glyphs are listed at [Accidental glyphs], page 907.

```

\layout {
  \context {
    \Staff
    alterationGlyphs =
      #'((-1/2 . "accidentals.flat.arrowdown")
        (0 . "accidentals.natural.arrowup")
        (1/2 . "accidentals.sharp.arrowup"))
  }
}

{ ces' c' cis' }

```




The `padding-pairs` property of `KeySignature` and `KeyCancellation` objects is an associative list mapping pairs of glyphs to the padding that should be added between these glyphs in key signatures.

```

\layout {
  \context {
    \Staff
    alterationGlyphs =
      #'((-1/2 . "accidentals.flat.arrowdown")
        (0 . "accidentals.natural.arrowup")
        (1/2 . "accidentals.sharp.arrowup"))
    \override KeySignature.padding-pairs =
      #'(((("accidentals.sharp.arrowup" . "accidentals.sharp.arrowup")
          . 0.25)
        (("accidentals.flat.arrowdown" . "accidentals.flat.arrowdown")
          . 0.3))
    \override KeyCancellation.padding-pairs =
      #'(((("accidentals.natural.arrowup" . "accidentals.natural.arrowup")
          . 0.7))
  }
}

{
  \key cis \major
  ces' c'
  \key ces \major
  cis'
}

```



See also

Notation Reference: Section B.10 [Accidental glyph sets], page 920, [Accidental glyphs], page 907.

Internals Reference: Section “accidental-switch-interface” in *Internals Reference*, Section “Alteration_glyph_engraver” in *Internals Reference*, Section “key-signature-interface” in *Internals Reference*.

1.3.7 Ambitus

The term *ambitus* (pl. *ambitus*) denotes a range of pitches for a given voice in a part of music. It may also denote the pitch range that a musical instrument is capable of playing. Ambitus are printed on vocal parts so that performers can easily determine if it matches their capabilities.

Ambitus are denoted at the beginning of a piece near the initial clef. The range is graphically specified by two note heads that represent the lowest and highest pitches. Accidentals are only printed if they are not part of the key signature.

```

\layout {
  \context {
    \Voice
    \consists Ambitus_engraver
  }
}

```

```
\relative {
  aes' c e2
  cis,1
}
```



Selected snippets

Adding ambitus per voice

Ambitus can be added per voice. In this case, the ambitus must be moved manually to prevent collisions.

```
\new Staff <<
  \new Voice \with {
    \consists "Ambitus_engraver"
  } \relative c'' {
    \override Ambitus.X-offset = 2.0
    \voiceOne
    c4 a d e
    f1
  }
  \new Voice \with {
    \consists "Ambitus_engraver"
  } \relative c' {
    \voiceTwo
    es4 f g as
    b1
  }
}>>
```



Ambitus with multiple voices

Adding the `Ambitus_engraver` to the `Staff` context creates a single ambitus per staff, even in the case of staves with multiple voices.

```
\new Staff \with {
  \consists "Ambitus_engraver"
}
<<
  \new Voice \relative c'' {
    \voiceOne
    c4 a d e
    f1
  }
  \new Voice \relative c' {
    \voiceTwo
```



```

es4 f g as
b1
}
>>

```



Changing the ambitus gap

It is possible to change the default gap between the ambitus noteheads and the line joining them.

```

\layout {
  \context {
    \Voice
    \consists "Ambitus_engraver"
  }
}

\new Staff {
  \time 2/4
  % Default setting
  c'4 g' '
}


\new Staff {
  \time 2/4
  \override AmbitusLine.gap = 0
  c'4 g' '
}

\new Staff {
  \time 2/4
  \override AmbitusLine.gap = 1
  c'4 g' '
}

\new Staff {
  \time 2/4
  \override AmbitusLine.gap = 1.5
  c'4 g' '
}

```





Ambitus after key signature

By default, ambitus are positioned at the left of the clef. The `\ambitusAfter` function allows for changing this placement. Syntax is `\ambitusAfter grob-interface`; see Graphical Object Interfaces (<https://lilypond.org/doc/v2.24/Documentation/internals/graphical-object-interfaces>) for a list of possible values for *grob-interface*.

A common use case is printing the ambitus between key signature and time signature.

```
\new Staff \with {
  \consists Ambitus_engraver
} \relative {
  \ambitusAfter key-signature
  \key d \major
  es'8 g bes cis d2
}
```



See also

Music Glossary: Section “ambitus” in *Music Glossary*.

Snippets: Section “Pitches” in *Snippets*.

Internals Reference: Section “Ambitus_engraver” in *Internals Reference*, Section “Voice” in *Internals Reference*, Section “Staff” in *Internals Reference*, Section “Ambitus” in *Internals Reference*, Section “AmbitusAccidental” in *Internals Reference*, Section “AmbitusLine” in *Internals Reference*, Section “AmbitusNoteHead” in *Internals Reference*, Section “ambitus-interface” in *Internals Reference*.

Known issues and warnings

There is no collision handling in the case of multiple per-voice ambitus.

1.4 Note heads

This section suggests ways of altering note heads.

1.4.1 Special note heads

The appearance of note heads may be altered:

```
\relative c' ' {
  c4 b
  \override NoteHead.style = #'cross
  c4 b
  \revert NoteHead.style
  a b
  \override NoteHead.style = #'harmonic
```

```

a b
\revert NoteHead.style
c4 d e f
}

```




To see all note head styles, see Section B.9 [Note head styles], page 920.

The cross style is used to represent a variety of musical intentions. The following generic predefined commands modify the note head in both staff and tablature contexts and can be used to represent any musical meaning:

```

\relative {
  c' '4 b
  \xNotesOn
  a b c4 b
  \xNotesOff
  c4 d
}

```




The music function form of this predefined command may be used inside and outside chords to generate crossed note heads in both staff and tablature contexts:

```

\relative {
  c' '4 b
  \xNote { e f }
  c b < g \xNote c f > b
}

```



As synonyms for `\xNote`, `\xNotesOn` and `\xNotesOff`, `\deadNote`, `\deadNotesOn` and `\deadNotesOff` can be used. The term *dead note* is commonly used by guitarists.

There is also a similar shorthand for diamond shapes:

```

\relative c' ' {
  <c f\harmonic>2 <d a'\harmonic>4 <c g'\harmonic> f\harmonic
}

```



Predefined commands

`\harmonic`, `\xNotesOn`, `\xNotesOff`, `\xNote`.

See also

Snippets: Section “Pitches” in *Snippets*.


Notation Reference: Section B.9 [Note head styles], page 920, Section 5.1.1 [Chorded notes], page 215, Section 12.2.2 [Indicating harmonics and dampened notes], page 482.

Internals Reference: Section “note-event” in *Internals Reference*, Section “Note_heads_engraver” in *Internals Reference*, Section “Ledger_line_engraver” in *Internals Reference*, Section “NoteHead” in *Internals Reference*, Section “LedgerLineSpanner” in *Internals Reference*, Section “note-head-interface” in *Internals Reference*, Section “ledger-line-spanner-interface” in *Internals Reference*.

1.4.2 Easy notation note heads

The ‘easy play’ note head includes a note name inside the head. It is used in music for beginners. To make the letters readable, it should be printed in a large font size. To print with a larger font, see Section 27.2 [Setting the staff size], page 683.

```
#(set-global-staff-size 26)
\relative c' {
  \easyHeadsOn
  c2 e4 f
  g1
  \easyHeadsOff
  c,1
}
```



Predefined commands

`\easyHeadsOn`, `\easyHeadsOff`.

Selected snippets

Numbers as easy note heads

Easy notation note heads use the `note-names` property of the `NoteHead` object to determine what appears inside the note head. By overriding this property, it is possible to print numbers representing the scale-degree.

A simple engraver can be created to do this for every note head object it sees.

```
#(define Ez_numbers_engraver
  (make-engraver
    (acknowledgers
      ((note-head-interface engraver grob source-engraver)
        (let* ((context (ly:translator-context engraver))
              (tonic-pitch (ly:context-property context 'tonic))
              (tonic-name (ly:pitch-notename tonic-pitch))
              (grob-pitch
                (ly:event-property (event-cause grob) 'pitch))
              (grob-name (ly:pitch-notename grob-pitch))
              (delta (modulo (- grob-name tonic-name) 7)))
          (note-names
            (make-vector 7 (number->string (1+ delta)))))))
```

```

(ly:grob-set-property! grob 'note-names note-names))))))

#(set-global-staff-size 30)


\layout {
  ragged-right = ##t
  \context {
    \Voice
    \consists \Ez_numbers_engraver
  }
}

\relative c' {
  \easyHeadsOn
  c4 d e f
  g4 a b c \break

  \key a \major
  a,4 b cis d
  e4 fis gis a \break

  \key d \dorian
  d,4 e f g
  a4 b c d
}

```



See also

Notation Reference: Section 27.2 [Setting the staff size], page 683.

Snippets: Section “Pitches” in *Snippets*.

Internals Reference: Section “note-event” in *Internals Reference*, Section “Note_heads_engraver” in *Internals Reference*, Section “NoteHead” in *Internals Reference*, Section “note-head-interface” in *Internals Reference*.

1.4.3 Shape note heads

In shape note head notation, the shape of the note head corresponds to the harmonic function of a note in the scale. This notation was popular in nineteenth-century American song books.

Shape note heads can be produced in Sacred Harp, Southern Harmony, Funk (Harmonia Sacra), Walker, and Aiken (Christian Harmony) styles:

```
\relative c'' {
  \aikenHeads
  c, d e f g2 a b1 c \break
  \aikenThinHeads
  c,4 d e f g2 a b1 c \break
  \sacredHarpHeads
  c,4 d e f g2 a b1 c \break
  \southernHarmonyHeads
  c,4 d e f g2 a b1 c \break
  \funkHeads
  c,4 d e f g2 a b1 c \break
  \walkerHeads
  c,4 d e f g2 a b1 c \break
}
```



Shapes are typeset according to the step in the scale, where the base of the scale is determined by the `\key` command. When writing in a minor key, the scale step can be determined from the relative major:

```
\relative c'' {
  \key a \minor
  \aikenHeads
  a b c d e2 f g1 a \break
  \aikenHeadsMinor
  a,4 b c d e2 f g1 a \break
  \aikenThinHeadsMinor
  a,4 b c d e2 f g1 a \break
  \sacredHarpHeadsMinor
  a,4 b c d e2 f g1 a \break
}
```

```

a,2 b c d \break
\southernHarmonyHeadsMinor
a2 b c d \break
\funkHeadsMinor
a2 b c d \break
\walkerHeadsMinor
a2 b c d \break
}

```

Predefined commands

\aikenHeads, \aikenHeadsMinor, \aikenThinHeads, \aikenThinHeadsMinor, \funkHeads, \funkHeadsMinor, \sacredHarpHeads, \sacredHarpHeadsMinor, \southernHarmonyHeads, \southernHarmonyHeadsMinor, \walkerHeads, \walkerHeadsMinor.

Selected snippets

Aiken head thin variant noteheads

Aiken head white notes get harder to read at smaller staff sizes, especially with ledger lines. Losing interior white space makes them appear as quarter notes.

```

\score {
  {
    \aikenHeads
    c''2 a' c' a

    % Switch to thin-variant noteheads
    \set shapeNoteStyles = ##(doThin reThin miThin
                             faThin sol laThin tiThin)

    c'' a' c' a
  }
}

```



Direction of merged ‘fa’ shape note heads

Using property `NoteCollision.fa-merge-direction`, the direction of “fa” shape note heads (“fa”, “faThin”, etc.) can be controlled independently of the stem direction if two voices with the same pitch and different stem directions are merged. If this property is not set, the “down” glyph variant is used.

```

{
  \clef bass

  << { \aikenHeads
      f2
      \override Staff.NoteCollision.fa-merge-direction = #UP
      f2 }
  \\ { \aikenHeads
      f2
      f2 }
  >>
}

```



Applying note head styles depending on the step of the scale

The `shapeNoteStyles` property can be used to define various note head styles for each step of the scale (as set by the key signature or the tonic property).

This property requires a set of symbols, which can be purely arbitrary (geometrical expressions such as `triangle`, `cross`, and `xcircle` are allowed) or based on old American engraving tradition (some latin note names are also allowed).

That said, to imitate old American song books, there are several predefined note head styles available through shortcut commands such as `\aikenHeads` or `\sacredHarpHeads`.

This example shows different ways to obtain shape note heads, and demonstrates the ability to transpose a melody without losing the correspondence between harmonic functions and note head styles.


```

fragment = {
  \key c \major
  c2 d
  e2 f
  g2 a
  b2 c
}

\new Staff {
  \transpose c d
  \relative c' {
    \set shapeNoteStyles = ##(do re mi fa
                          #f la ti)


    \fragment
  }

  \break

  \relative c' {
    \set shapeNoteStyles = ##(cross triangle fa #f
                          mensural xcircle diamond)

    \fragment
  }
}

```



To see all note head styles, see Section B.9 [Note head styles], page 920.

See also

Snippets: Section “Pitches” in *Snippets*.

Notation Reference: Section B.9 [Note head styles], page 920.

Internals Reference: Section “note-event” in *Internals Reference*, Section “Note_heads_engraver” in *Internals Reference*, Section “NoteHead” in *Internals Reference*, Section “note-head-interface” in *Internals Reference*.

1.4.4 Improvisation

Improvisation is sometimes denoted with slashed note heads, where the performer may choose any pitch but should play the specified rhythm. Such note heads can be created:

```

\new Voice \with {
  \consists Pitch_squash_engraver
} \relative {
  e' '8 e g a a16( bes) a8 g
  \improvisationOn
  e8 ~
  2 ~ 8 f4 f8 ~

```

```

2
\improvisationOff
a16( bes) a8 g e
}

```



Predefined commands

`\improvisationOn`, `\improvisationOff`.

See also

Snippets: Section “Pitches” in *Snippets*.

Internals Reference: Section “Pitch_squash_engraver” in *Internals Reference*, Section “Voice” in *Internals Reference*, Section “RhythmicStaff” in *Internals Reference*.

2 Rhythms

The musical score consists of four systems of piano notation, measures 31 through 34. The key signature has two flats (B-flat major or D-flat minor), and the time signature is 2/4. The right hand (treble clef) plays a melody with various note values, including quarter, eighth, and sixteenth notes, often beamed together. The left hand (bass clef) provides a steady accompaniment of eighth notes. Measure 31 is marked *a tempo*. Measure 32 has a *cresc.* marking. Measure 33 is marked *p* (piano). Measure 34 also has a *cresc.* marking.

This section discusses rhythms, rests, durations, beaming and bars.

2.1 Writing rhythms

2.1.1 Durations

The durations of notes are entered using numbers and dots. The number entered is based on the reciprocal value of the length of the note. For example, a quarter note is designated using the numerical value of 4 as it is a 1/4 note, a half note using 2, an eighth using 8 and so on. Durations as short as 1024 notes can be entered but shorter values, while possible, can only be entered as beamed notes. Also see Section 2.4 [Beams], page 101.

For notes longer than a whole use the `\longa` – double breve – and `\breve` commands. A note with the duration of a quadruple breve is possible using the `\maxima` command but is only supported within ancient music notation. See Chapter 17 [Ancient notation], page 537.

```
\relative {
  \time 8/1
  c''\longa c\breve c1 c2
  c4 c8 c16 c32 c64 c128 c128
}
```



Here are the same durations with automatic beaming turned off.

```
\relative {
  \time 8/1
  \autoBeamOff
  c''\longa c\breve c1 c2
  c4 c8 c16 c32 c64 c128 c128
}
```



Isolated durations – durations without a pitch – that occur within a music sequence will take their pitch from the preceding note or chord.

```
\relative {
  \time 8/1
  c'' \longa \breve 1 2
  4 8 16 32 64 128 128
}
```



Isolated pitches – pitches without a duration – that occur within a music sequence will take their duration from the preceding note or chord. If there is no preceding duration, then default for the note is always 4, a quarter note.

```
\relative { a' a a2 a a4 a a1 a }
```



Place a dot (.) after the duration to obtain ‘dotted’ note lengths. Double-dotted notes are specified by appending two dots, and so on.

```
\relative { a'4 b c4. b8 a4. b4.. c8. }
```



To avoid clashing with staff lines, dots on notes are normally moved up. In polyphonic situations however, they can be placed, manually, above or below the staff as required. See Section 36.1 [Direction and placement], page 772.

Some note durations cannot be represented using just numbers and dots but only by tying two or more notes together. See Section 2.1.4 [Ties], page 63.

To specify durations that align the syllables of lyrics and notes together see Chapter 9 [Vocal music], page 345.

Notes can also be spaced proportionately to their duration, see Section 30.6 [Proportional notation], page 720.

Predefined commands

`\autoBeamOn`, `\autoBeamOff`, `\dotsUp`, `\dotsDown`, `\dotsNeutral`.

Selected snippets

Alternative breve notes

Breve notes are also available with two vertical lines on each side of the notehead instead of one line and in baroque style.

```
\relative c' {
  \time 4/2
  c\breve |
  \override Staff.NoteHead.style = #'altdefault
  b\breve
  \override Staff.NoteHead.style = #'baroque
  b\breve
  \revert Staff.NoteHead.style
  a\breve
}
```



Changing the number of augmentation dots per note

The number of augmentation dots on a single note can be overridden by setting the dot-count property of the Dots grob.

```
\relative c' {
  c4.. a16 r2 |
  \override Dots.dot-count = 4
  c4.. a16 r2 |
  \override Dots.dot-count = 0
  c4.. a16 r2 |
  \revert Dots.dot-count
  c4.. a16 r2 |
}
```



See also

Music Glossary: Section “breve” in *Music Glossary*, Section “longa” in *Music Glossary*, Section “maxima” in *Music Glossary*, Section “note value” in *Music Glossary*, Section “Duration names notes and rests” in *Music Glossary*.

Notation Reference: Section 2.4 [Beams], page 101, Section 2.1.4 [Ties], page 63, Section 7.1.9 [Stems], page 296, Section 2.1 [Writing rhythms], page 52, Section 2.2 [Writing rests], page 67, Chapter 9 [Vocal music], page 345, Chapter 17 [Ancient notation], page 537, Section 30.6 [Proportional notation], page 720.

Snippets: Section “Rhythms” in *Snippets*.

Internals Reference: Section “Dots” in *Internals Reference*, Section “DotColumn” in *Internals Reference*.

Known issues and warnings

While there is no fundamental limit to rest durations (longest or shortest), there is a limit to the number of glyphs possible so only rests between 1024 and \maxima may be printed.

2.1.2 Tuplets

Tuplets are made from a music expression with the `\tuplet` command, multiplying the speed of the music expression by a fraction:

```
\tuplet fraction { music }
```

The fraction’s numerator will be printed over or under the notes, optionally with a bracket. The most common tuplets are triplets (3 notes played within the duration normally allowed for 2).

```
\relative {
  a'2 \tuplet 3/2 { b4 4 4 }
  c4 c \tuplet 3/2 { b4 a g }
}
```



When entering long passages of tuplets, having to write a separate `\tuplet` command for each group is inconvenient. It is possible to specify the duration of one tuplet group directly before the music in order to have the tuplets grouped automatically:

```
\relative {
  g'2 r8 \tuplet 3/2 8 { cis16 d e e f g g f e }
}
```



Tuplet brackets may be manually placed above or below the staff:

```
\relative {
  \tupletUp \tuplet 3/2 { c'8 d e }
  \tupletNeutral \tuplet 3/2 { c8 d e }
  \tupletDown \tuplet 3/2 { f,8 g a }
  \tupletNeutral \tuplet 3/2 { f8 g a }
}
```



Tuplets may be nested:


```
\relative {
  \autoBeamOff
  c'4 \tuplet 5/4 { f8 e f \tuplet 3/2 { e[ f g] } } f4
}
```



Modifying nested tuplets which begin at the same musical moment must be done with `\tweak`; see Section 35.6 [`\tweak` and `\single`], page 762.

Tuplet brackets may be replaced with slurs, as is preferred in many older editions:

```
\relative {
  \tuplet 3/2 4 {
    \override TupletBracket.tuplet-slur = ##t
    c'4 e8 d4 f8
    \override TupletBracket.bracket-visibility = ##t
    e f g f e d
  } c1
}
```



By default, a bracket is only printed if all of the notes it spans are not beamed together; in some cases (for example with slurs, as in the example above) it may be preferable to change that behavior, through the `bracket-visibility` property as detailed in one of the following snippets.

More generally, either or both the `TupletBracket` and `TupletNumber` objects may be hidden or shown as explained in Section 36.7 [Visibility of objects], page 782; however, a more flexible way of modifying the duration of notes without printing a tuplet bracket is also introduced in Section 2.1.3 [Scaling durations], page 61.

Predefined commands

`\tupletUp`, `\tupletDown`, `\tupletNeutral`.


Selected snippets

Entering several tuplets using only one `\tuplet` command

The property `tupletSpannerDuration` sets how long each of the tuplets contained within the brackets after `\tuplet` should last. Many consecutive tuplets can then be placed within a single `\tuplet` expression, thus saving typing.

There are ways to set `tupletSpannerDuration` besides using a `\set` command. The command `\tupletSpan` sets it to a given duration, or clears it when instead of a duration `\default` is specified. Another way is to use an optional argument with `\tuplet`.

```
\relative c' {
  \time 2/4
  \tupletSpan 4
  \tuplet 3/2 { c8^"\tupletSpan 4" c c c c c }
  \tupletSpan \default
  \tuplet 3/2 { c8^"\tupletSpan \default" c c c c c }
  \tuplet 3/2 4 { c8^"\tuplet 3/2 4 {...}" c c c c c }
}
```



Changing the tuplet number

By default, only the numerator of the tuplet number is printed over the tuplet bracket, i.e., the numerator of the argument to the `\tuplet` command.

Alternatively, *num:den* of the tuplet number may be printed, or the tuplet number may be suppressed altogether.

```
\relative c' {
  \tuplet 3/2 { c8 c c }
  \tuplet 3/2 { c8 c c }
  \override TupletNumber.text = #tuplet-number::calc-fraction-text
  \tuplet 3/2 { c8 c c }
  \omit TupletNumber
  \tuplet 3/2 { c8 c c }
}
```




Non-default tuplet numbers

LilyPond also provides formatting functions to print tuplet numbers different than the actual fraction, as well as to append a note value to the tuplet number or tuplet fraction.


```

\relative c' {
  \once \override TupletNumber.text =
    #(tuplet-number::non-default-tuplet-denominator-text 7)
  \tuplet 3/2 { c4. c4. c4. c4. }
  \once \override TupletNumber.text =
    #(tuplet-number::non-default-tuplet-fraction-text 12 7)
  \tuplet 3/2 { c4. c4. c4. c4. }
  \once \override TupletNumber.text =
    #(tuplet-number::append-note-wrapper
      (tuplet-number::non-default-tuplet-fraction-text 12 7)
      (ly:make-duration 3 0))
  \tuplet 3/2 { c4. c4. c4. c4. }
  \once \override TupletNumber.text =
    #(tuplet-number::append-note-wrapper
      tuplet-number::calc-denominator-text
      (ly:make-duration 2 0))
  \tuplet 3/2 { c8 c8 c8 c8 c8 c8 }
  \once \override TupletNumber.text =
    #(tuplet-number::append-note-wrapper
      tuplet-number::calc-fraction-text
      (ly:make-duration 2 0))
  \tuplet 3/2 { c8 c8 c8 c8 c8 c8 }
  \once \override TupletNumber.text =
    #(tuplet-number::fraction-with-notes
      (ly:make-duration 2 1) (ly:make-duration 3 0))
  \tuplet 3/2 { c4. c4. c4. c4. }
  \once \override TupletNumber.text =
    #(tuplet-number::non-default-fraction-with-notes 12
      (ly:make-duration 3 0) 4 (ly:make-duration 2 0))
  \tuplet 3/2 { c4. c4. c4. c4. }
}

```



Controlling tuplet bracket visibility

The default behavior of tuplet-bracket visibility is to print a bracket unless there is a beam of the same length as the tuplet.

To control the visibility of tuplet brackets, set the property `bracket-visibility` to either `#t` (always print a bracket), `if-no-beam` (only print a bracket if there is no beam) or `#f` (never print a bracket). The latter is in fact equivalent to omitting the `TupletBracket` object altogether from the printed output.

```

music = \relative c' {
  \tuplet 3/2 { c16[ d e ] f8]
  \tuplet 3/2 { c8 d e }
  \tuplet 3/2 { c4 d e }
}

\new Voice {
  \relative c' {
    \override Score.TextMark.non-musical = ##f
    \textMark "default" \music
    \override TupletBracket.bracket-visibility = #'if-no-beam
    \textMark \markup \typewriter "'if-no-beam" \music
    \override TupletBracket.bracket-visibility = ##t
    \textMark \markup \typewriter "#t" \music
    \override TupletBracket.bracket-visibility = ##f
    \textMark \markup \typewriter "#f" \music
    \omit TupletBracket
    \textMark \markup \typewriter "omit" \music
  }
}

```

The image displays five musical staves, each illustrating a different configuration for the visibility of tuplet brackets. All staves are in treble clef and common time (C). Each staff contains a sequence of notes with tuplet brackets. The configurations are as follows:

- Staff 1 (labeled 'default'):** Shows standard notation with tuplet brackets visible on the stem side of the notes.
- Staff 2 (labeled 'if-no-beam'):** Shows the same notation, but the tuplet brackets are hidden when the notes are beamed together.
- Staff 3 (labeled '#t'):** Shows the same notation, but the tuplet brackets are always visible, regardless of whether the notes are beamed.
- Staff 4 (labeled '#f'):** Shows the same notation, but the tuplet brackets are always hidden, regardless of whether the notes are beamed.
- Staff 5 (labeled 'omit'):** Shows the same notation, but the tuplet brackets are completely omitted.

Printing tuplet brackets on the note head side

Whichever option you choose for controlling the tuplet bracket visibility, it will show or hide the tuplet bracket irrespectively of tuplet bracket placement (stem side or note head side). However, when placing the tuplet bracket on the note head side some authors recommend always printing the tuplet bracket. The option `visible-over-note-heads` can be used to achieve this.


```

music = \relative c'' {
  \tupletNeutral \tuplet 3/2 { c16[ d e ] f8]
  \tupletUp \tuplet 3/2 { c8 d e }
}

\new Voice {
  \relative c' {
    \override TextScript.staff-padding = #2.5

    \time 2/4
    \override TupletBracket.visible-over-note-heads = ##t
    \override Score.TextMark.non-musical = ##f
    <>^\markup "default" \music
    \override TupletBracket.bracket-visibility = #'if-no-beam
    <>^\markup \typewriter "if-no-beam" \music
  }
}

```



Permitting line breaks within beamed triplets

These artificial examples show how both manual and automatic line breaks may be permitted within beamed triplets that can't be rhythmically split in an exact way.

This feature only works with manually beamed triplets.

```

\layout {
  \context {
    \Voice
    % Permit automatic line breaks within triplets.
    \remove "Forbid_line_break_engraver"
    % Allow beams to be broken at line breaks.
    \override Beam.breakable = ##t
  }
}

\relative c'' {
  <>^\markup "manually forced line break"
  a8
  \*5 { \tuplet 3/2 { c8[ b g16 a] } }
  \tuplet 3/2 { c8[ b \break g16 a] }
  \*5 { \tuplet 3/2 { c8[ b g16 a] } }
  c8 \bar "||"
}

\relative c'' {
  <>^\markup "automatic line break"
  \*28 a16
  \tuplet 11/8 { a16[ b c d e f e d c b a] }
  \*28 a16 \bar "||"
}

```

}

manually forced line break

automatic line break

See also

Music Glossary: Section “triplet” in *Music Glossary*, Section “tuplet” in *Music Glossary*, Section “polymetric” in *Music Glossary*.

Learning Manual: Section “Tweaking methods” in *Learning Manual*.

Notation Reference: Section 36.1 [Direction and placement], page 772, Section 36.7 [Visibility of objects], page 782, Section 2.3.1 [Measures], page 78, Section 2.1.3 [Scaling durations], page 61, Section 35.6 [`\tweak` and `\single`], page 762, Section 2.3.6 [Polymetric notation], page 93.

Snippets: Section “Rhythms” in *Snippets*.

Internals Reference: Section “TupletBracket” in *Internals Reference*, Section “Tuplet-Number” in *Internals Reference*, Section “TimeScaledMusic” in *Internals Reference*.

2.1.3 Scaling durations

The duration of single notes, rests or chords may be multiplied by a fraction N/M by appending $*N/M$ (or $*N$ if M is 1) to the duration. Factors may also be added by using Scheme expressions evaluating to a number or musical length like `*#(ly:music-length music)`. This is convenient for scaling a duration of ‘1’ to let a note or multi-measure rest stretch to a length derived from a music variable.

Adding a factor will not affect the appearance of the notes or rests produced, but the altered duration will be used in calculating the position within the measure and setting the duration in the MIDI output. Multiplying factors may be combined like $*L*M/N$. Factors are part of the duration: if a duration is not specified for subsequent notes, the default duration taken from the preceding note will include any scaling factor.

In the following example, the first three notes take up exactly two beats, but no triplet bracket is printed.

```

\relative {
  \time 2/4
  % Alter durations to triplets
  a'4*2/3 gis a
  % Normal durations
  a4 a
  % Double the duration of chord
  <a d>4*2
  % Duration of quarter, appears like sixteenth
  b16*4 c4
}

```



The duration of spacer rests may also be modified by a multiplier. This is useful for skipping many measures, e.g., `s1*23`.

Longer stretches of music may be compressed by a fraction in the same way, as if every note, chord or rest had the fraction as a multiplier. This leaves the appearance of the music unchanged but the internal duration of the notes will be multiplied by the given scale factor, usually *num/den*. Here is an example showing how music can be compressed and expanded:

```

\relative {
  \time 2/4
  % Normal durations
  <c' a>4 c8 a
  % Scale music by *2/3
  \scaleDurations 2/3 {
    <c a f>4. c8 a f
  }
  % Scale music by *2
  \scaleDurations 2 {
    <c' a>4 c8 b
  }
}

```



One application of this command is in polymetric notation, see Section 2.3.6 [Polymetric notation], page 93.

See also

Notation Reference: Section 2.1.2 [Tuplets], page 55, Section 2.2.2 [Invisible rests], page 69, Section 2.3.6 [Polymetric notation], page 93.

Snippets: Section “Rhythms” in *Snippets*.

Known issues and warnings

The calculation of the position within a measure must take into account all the scaling factors applied to the notes within that measure and any fractional carry-out from earlier measures. This calculation is carried out using rational numbers. If an intermediate numerator or denominator

in that calculation exceeds 2^{30} the execution and typesetting will stop at that point without indicating an error.

2.1.4 Ties

A tie connects two adjacent note heads of the same pitch. The tie in effect extends the duration of a note.

Ties that connect notes to nothing are called *laissez vibrer* articulation; see [Laissez vibrer], page 64, for the `\laissezVibrer` command. Ties that connect nothing to notes (as needed in *seconda volta* sections, for example), can be entered with the `\repeatTie` command; see [Repeat tie], page 64.

Note: Ties should not be confused with *slurs*, which indicate articulation, or *phrasing slurs*, which indicate musical phrasing. A tie is just a way of extending a note duration, similar to the augmentation dot.

A tie is entered by appending a tilde symbol ('~') to the first of each pair of notes being tied. This indicates that the note should be tied to the following note, which must be at the same pitch. Note that ties make use of the 'last explicit pitch' interpretation of isolated durations:

```
{ a'2~ 4~ 16 r r8 }
```



LilyPond also supports ties between notes that are enharmonically equivalent.

```
{ gis'1~ | as'1 }
```



Ties are used either when the note crosses a bar line, or when dots cannot be used to denote the rhythm. Ties should also be used when note values cross larger subdivisions of the measure:


```
\relative {
  r8 c'4.~ 4 r4 |
  r8^"not" c2~ 8 r4
}
```



If you need to tie many notes across bar lines, it may be easier to use automatic note splitting, see Section 2.3.7 [Automatic note splitting], page 97. This mechanism automatically splits long notes, and ties them across bar lines.


When a tie is applied to a chord, all note heads whose pitches match are connected. When no note heads match, no ties will be created. Chords may be partially tied by placing the ties inside the chord.

```
\relative c' {
  <c e g>2~ 2 |
  <c e g>4~ <c e g c>
    <c~ e g~ b> <c e g b> |
}
```




When a tie continues into alternative endings, you have to specify the repeated tie as follows:

```
\relative {
  \repeat volta 2 { c' g <c e>2~ }
  \alternative {
    % the following note is tied normally
    \volta 1 { <c e>2. r4 }
    % the following note has a repeated tie
    \volta 2 { <c e>2\repeatTie d4 c }
  }
}
```



L.v. ties (*laissez vibrer*) indicate that notes must not be damped at the end. It is used in notation for piano, harp and other string and percussion instruments. They can be entered as follows:

```
<c' f' g'>1\laissezVibrer
```



Ties may be made to curve up or down manually; see Section 36.1 [Direction and placement], page 772.

Ties may be made dashed, dotted, or a combination of solid and dashed.

```
\relative c' {
  \tieDotted
  c2~ 2
  \tieDashed
  c2~ 2
  \tieHalfDashed
  c2~ 2
  \tieHalfSolid
  c2~ 2
  \tieSolid
  c2~ 2
}
```



Custom dash patterns can be specified:

```
\relative c' {
  \tieDashPattern 0.3 0.75
  c2~ 2
  \tieDashPattern 0.7 1.5
  c2~ 2
  \tieSolid
  c2~ 2
}
```



Dash pattern definitions for ties have the same structure as dash pattern definitions for slurs. For more information about complex dash patterns, see Section 3.2.1 [Slurs], page 170.

Override *whiteout* and *layer* layout properties of objects that should cause a gap in ties.

```
\relative {
  \override Tie.layer = -2
  \override Staff.TimeSignature.layer = -1
  \override Staff.KeySignature.layer = -1
  \override Staff.TimeSignature.whiteout = ##t
  \override Staff.KeySignature.whiteout = ##t
  b'2 b~
  \time 3/4
  \key a \major
  b r4
}
```



Predefined commands

`\tieUp`, `\tieDown`, `\tieNeutral`, `\tieDotted`, `\tieDashed`, `\tieDashPattern`,
`\tieHalfDashed`, `\tieHalfSolid`, `\tieSolid`.

Selected snippets

Using ties with arpeggios

Ties are sometimes used to write out arpeggios. In this case, two tied notes need not be consecutive. This can be achieved by setting the `tieWaitForNote` property to `#t`. The same feature is also useful, for example, to tie a tremolo to a chord, but in principle, it can also be used for ordinary consecutive notes.


```
\relative c' {
  \set tieWaitForNote = ##t
  \grace { c16[ ~ e ~ g] ~ } <c, e g>2
  \repeat tremolo 8 { c32 ~ c' ~ } <c c,>1
  e8 ~ c ~ a ~ f ~ <e' c a f>2
  \tieUp
  c8 ~ a
}
```



```

\tieDown
\tieDotted
g8 ~ c g2
}

```



Engraving ties manually

A single tie may be engraved manually by changing the `staff-position` property (an offset) of the `Tie` grob; if there are multiple ties at the same musical moment, they can be adjusted manually by changing the `tie-configuration` property (a list of offset/direction pairs) of the `TieColumn` object.

The offset indicates the distance from the center of the staff in half-staff spaces, the direction can be either 1 (up) or -1 (down).

Note that LilyPond makes a distinction between exact and inexact values for the offset. If using an exact value (i.e., either an integer or a fraction like $(/ 4 5)$), the value serves as a rough vertical position that gets further tuned by LilyPond to make the tie avoid staff lines. If using an inexact value like a floating point number, it is taken as the precise vertical position without further adjustments.

```

\relative c' {
  <>^"default"
  g'1 ^~ g

  <>^"0"
  \once \override Tie.staff-position = 0
  g1 ^~ g

  <>^"0.0"
  \once \override Tie.staff-position = 0.0
  g1 ^~ g

  <>^"reset"
  \revert Tie.staff-position
  g1 ^~ g
}

\relative c' {
  \override TextScript.outside-staff-priority = ##f
  \override TextScript.padding = 0

  <>^"default"
  <c e g>1~ <c e g>

  <>^"0, -2, -4"
  \override TieColumn.tie-configuration =
    #'((0 . 1) (-2 . 1) (-4 . 1))
  <c e g>1~ <c e g>

  <>^"0.0, -2.0, -4.0"

```

```

\override TieColumn.tie-configuration =
  #'((0.0 . 1) (-2.0 . 1) (-4.0 . 1))
<c e g>1~ <c e g>

<>^"reset"
\override TieColumn.tie-configuration = ##f
<c e g>1~ <c e g>
}

```



See also

Music Glossary: Section “tie” in *Music Glossary*, Section “laissez vibrer” in *Music Glossary*.

Notation Reference: Section 3.2.1 [Slurs], page 170, Section 2.3.7 [Automatic note splitting], page 97.

Snippets: Section “Expressive marks” in *Snippets*, Section “Rhythms” in *Snippets*.

Internals Reference: Section “LaissezVibrerTie” in *Internals Reference*, Section “Laissez-VibrerTieColumn” in *Internals Reference*, Section “TieColumn” in *Internals Reference*, Section “Tie” in *Internals Reference*.

Known issues and warnings

Switching staves when a tie is active will not produce a slanted tie.

Changing clefs or ottavations during a tie is not really well-defined. In these cases, a slur may be preferable.

2.2 Writing rests

Rests are entered as part of the music in music expressions.


2.2.1 Rests

Rests are entered like notes with the note name `r`. Durations longer than a whole rest use the following predefined commands:

```

\new Staff {
  % These two lines are just to prettify this example
  \time 16/1
  \omit Staff.TimeSignature
  % Print a maxima rest, equal to four breves
  r\maxima
  % Print a longa rest, equal to two breves
  r\longa
  % Print a breve rest
  r\breve
  r1 r2 r4 r8 r16 r32 r64 r128
}

```



Whole measure rests, centered in the middle of the measure, must be entered as multi-measure rests. They can be used for a single measure as well as many measures and are discussed in Section 2.2.3 [Full measure rests], page 71.

To explicitly specify a rest's vertical position, write a note followed by `\rest`. A rest of the duration of the note will be placed at the staff position where the note would appear. This allows for precise manual formatting of polyphonic music, since the automatic rest collision formatter will not move these rests.

```
\relative { a'4\rest d4\rest }
```



Selected snippets

Rest styles

Rests may be used in various styles.

```
restsA = {
  r\maxima r\longa r\breve r1 r2 r4 r8 r16 s32
  s64 s128 s256 s512 s1024 s1024
}
restsB = {
  r\maxima r\longa r\breve r1 r2 r4 r8 r16 r32
  r64 r128 r256 r512 r1024 s1024
}

\new Staff \relative c {
  \omit Score.TimeSignature
  \cadenzaOn


  \override Staff.Rest.style = #'mensural
  <>\markup \typewriter { mensural } \restsA \bar "" \break

  \override Staff.Rest.style = #'neomensural
  <>\markup \typewriter { neomensural } \restsA \bar "" \break

  \override Staff.Rest.style = #'classical
  <>\markup \typewriter { classical } \restsB \bar "" \break

  \override Staff.Rest.style = #'z
  <>\markup \typewriter { z-style } \restsB \bar "" \break

  \override Staff.Rest.style = #'default
  <>\markup \typewriter { default } \restsB \bar "" \break
}
```



See also

Music Glossary: Section “breve” in *Music Glossary*, Section “longa” in *Music Glossary*, Section “maxima” in *Music Glossary*.

Notation Reference: Section 2.2.3 [Full measure rests], page 71.

Snippets: Section “Rhythms” in *Snippets*.

Internals Reference: Section “Rest” in *Internals Reference*.

Known issues and warnings

There is no fundamental limit to rest durations (both in terms of longest and shortest), but the number of glyphs is limited: there are rests from 1024th to maxima (8× whole).

2.2.2 Invisible rests

There are two forms of invisible rests: the *spacer rest* named ‘s’, and the `\skip` command. The spacer rest is a note that does not produce output. Like any other note or rest, its duration sets the default duration of following notes.

```
\relative c' ' {
  c4 c s c |
  s2 c |
}
```



Also like other notes and rests, it implicitly causes Staff and Voice contexts to be created if none exist.


```
{ s1 s s }
```



```
<<
{
    a'2 \skip2 a'2 a'2
}
\new Lyrics {
    \lyricmode {
        foo2 \skip 1 bla2
    }
}
>>
```



```
<<
{
  \*12 a'4
}
{
  a'4 \skip 2 a' |
  a'4 \skip { a'8 a' a' a' } a' a' |
  s2 a'
}
>>
```



```
MyCadenza = \fixed c' {
  \repeat volta 2 {
    d8 e f g g4 f4
  }
}
```

```
music = <<
```

```

\new Staff {
  \MyCadenza
  c'1
}
\new Staff {
  #(skip-of-length MyCadenza)
  c'1
}
\new Staff {
  \skip \MyCadenza
  c'1
}
>>

\unfoldRepeats \music

```



The `\skip` command simply skips musical time; it creates no output of any kind.

```

% This is valid input, but does nothing
{ \skip 1 \skip1 \skip 1 }

```

See also

Learning Manual: Section “Visibility and color of objects” in *Learning Manual*.

Notation Reference: Section 7.1.4 [Hidden notes], page 288, Section 36.7 [Visibility of objects], page 782.

Snippets: Section “Rhythms” in *Snippets*.

Internals Reference: Section “SkipMusic” in *Internals Reference*.


Known issues and warnings

Because duration and music arguments to the `\skip` command affect the duration of subsequent music differently, it is good practice to provide an explicit duration for the music immediately following the command.

2.2.3 Full measure rests

Rests for one or more full measures are entered like notes with the note name uppercase ‘R’. Their duration is entered identically to the duration notation used for notes, including the ability to use duration multipliers, as explained in Section 2.1.3 [Scaling durations], page 61:


```
% Rest measures contracted to single measure
\compressMMRests {
  R1*4
  R1*24
  R1*4
  b'2^"Tutti" b'4 a'4
}
```



The example above also demonstrates how to compress multiple empty measures, as explained in Section 6.3.4 [Compressing empty measures], page 273.

The duration of a multi-measure rest must always be equal to the length of one or several measures. Therefore, some time signatures require the use of augmentation dots or fractions:

```
\compressMMRests {
  \time 2/4
  R1 | R2 |
  \time 3/4
  R2. | R2.*2 |
  \time 13/8
  R1*13/8 | R1*13/8*12 |
  \time 10/8
  R4*5*4 |
}
```



A full-measure rest is printed as either a whole or breve rest, centered in the measure, depending on the time signature.

```
\time 4/4
R1 |
\time 6/4
R1*3/2 |
\time 8/4
R1*2 |
```



Markups can be added to multi-measure rests.


```
\compressMMRests {
  \time 3/4
  R2.*10^\markup { \italic "ad lib." }
}
```



Note: Markups and articulations attached to multi-measure rests are `MultiMeasureRestText` and `MultiMeasureRestScript` types, not `TextScript` and `Script`. Overrides must be directed to the correct object, or they will be ignored. See the following example:

```
% This fails, as the wrong object name is specified
\override TextScript.padding = 5
\override Script.color = #blue
R1~"wrong"
R1\fermata

% This is the correct object name to be specified
\override MultiMeasureRestText.padding = 5
\override MultiMeasureRestScript.color = #blue
R1~"right"
R1\fermata
```



When a multi-measure rest immediately follows a `\partial` setting, resulting bar-check warnings may not be displayed.

Predefined commands

`\textLengthOn`, `\textLengthOff`, `\compressMMRests`.

Selected snippets

Multi-measure rest length control

Multi-measure rests have a length according to their total duration, which is under the control of the space-increment property of the `MultiMeasureRest` grob; its default value is 2.

```
\relative c' {
  \omit Staff.TimeSignature
  \compressEmptyMeasures

  R1*2 R1*4 R1*64 R1*16 \break
  \override MultiMeasureRest.space-increment = 4
  R1*2 R1*4 R1*64 R1*16
}
```



```
\layout {
  ragged-right = ##t
}
```

Positioning multi-measure rests

Unlike ordinary rests, there is no predefined command to change the staff position of a multi-measure rest symbol of either form by attaching it to a note. However, multi-measure rests in odd-numbered and even-numbered voices are vertically separated in polyphonic music.


This snippet shows how positioning of multi-measure rests can be controlled.

```
\relative c' {
  % Multi-measure rests by default are set under the fourth line.
  R1
  % They can be moved using an override or tweak.
  \tweak staff-position -2 R1
  \tweak staff-position 0 R1
  \tweak staff-position 2 R1
  \override MultiMeasureRest.staff-position = 3 R1
  \override MultiMeasureRest.staff-position = 6 R1
  \revert MultiMeasureRest.staff-position
  \break

  % Odd-numbered voices are under the top line.
  << { R1 } \\\ { a1 } >>
  % Even-numbered voices are under the bottom line.
  << { a1 } \\\ { R1 } >>
  % Multi-measure rests in both voices remain separate.
  << { R1 } \\\ { R1 } >>

  % Separating multi-measure rests in more than two voices
  % requires an override or tweak.
  << { R1 } \\\ { R1 } \\\ { \tweak staff-position -2 R1 } >>


  % Using compressed bars in multiple voices requires another override
  % in all voices to avoid multiple instances being printed.
  \compressMMRests
  <<
    \revert MultiMeasureRest.direction
    { R1*3 } \\\
    \revert MultiMeasureRest.direction
    { R1*3 }
  >>
```



Multi-measure rest markup

Markups attached to a multi-measure rest will be centered above or below it. Long markups attached to multi-measure rests do not cause the measure to expand. To expand a multi-measure rest to fit the markup, use an empty chord with an attached markup before the multi-measure rest. Text attached to a spacer rest in this way is left-aligned to the position where the note would be placed in the measure, but if the measure length is determined by the length of the text, the text will appear to be centered.

```
\relative c' {
  \compressMMRests {
    \textLengthOn
    <>^\markup { [MAJOR GENERAL] }
    R1*19
    <>_\markup { \italic { Cue: ... it is yours } }
    <>^\markup { A }
    R1*30^\markup { [MABEL] }
    \textLengthOff
    c4^\markup { CHORUS } d f c
  }
}
```



See also

Music Glossary: Section “multi-measure rest” in *Music Glossary*.

Notation Reference: Section 2.1.1 [Durations], page 52, Section 2.1.3 [Scaling durations], page 61, Section 6.3.4 [Compressing empty measures], page 273, Chapter 8 [Text], page 307, Section 8.2 [Formatting text], page 319, Section 8.1.2 [Text scripts], page 309.

Snippets: Section “Rhythms” in *Snippets*.

Internals Reference: Section “MultiMeasureRest” in *Internals Reference*, Section “MultiMeasureRestNumber” in *Internals Reference*, Section “MultiMeasureRestScript” in *Internals Reference*, Section “MultiMeasureRestText” in *Internals Reference*.

Known issues and warnings

Fingerings over multi-measure rests (e.g., R1*10-4) may result in the fingering numeral colliding with the bar counter numeral.

There is no way to automatically condense multiple ordinary rests into a single multi-measure rest.

Multi-measure rests do not take part in rest collisions.

2.2.4 Caesuras

The `\caesura` command calls for unmeasured silence: typically, a short break in sound that does not shorten the previous note.

```
\fixed c' { c2. \caesura d4 }
```



In chants and hymns, `\caesura` can serve more generally as a phrase division; for more information, see the references at the end of this section. For a break in sound that shortens the previous note, see Section 3.2.3 [Breath marks], page 175.

Articulations may follow `\caesura` to indicate the relative duration or significance of the break; these create `CaesuraScript` grobs.

```
\fixed c' { c2. \caesura \fermata d4 }
```



By default, `\caesura` creates a `BreathingSign` grob. The `breath` element of the `caesuraType` context property controls which of several predefined signs `\caesura` creates. See Section B.14 [List of breath marks], page 929.

```
\fixed c' {
  \set Score.caesuraType = #'((breath . curvedcaesura))
  c2. \caesura d4
}
```



To designate one or more `CaesuraScript` grobs to be created as a normal part of an unarticulated caesura, set the `scripts` element of the `caesuraType` context property. (Additional scripts can still be attached as articulations.) In conjunction with the `breath` element, the scripts listed in the `script` element attach to the `BreathingSign`; otherwise, if a `BarLine` is present, they attach to it.

The `caesuraTypeTransform` context property can be set to a Scheme function to enable a degree of automatic adaptation. The `at-bar-line-substitute-caesura-type` function generator supports styles where the notation differs at a bar line.

```
\fixed c' {
  \set Score.caesuraType =
    #'((breath . spacer)
      (scripts . (outsidecomma)))
  \set Score.caesuraTypeTransform =
    #((at-bar-line-substitute-caesura-type
      '((scripts . (fermata))))
  c'2. \caesura d'4
  b1 \caesura
  a1
}
```



Predefined commands

`\caesura.`

Selected snippets


Positioning opposing fermatas on a bar line

This snippet demonstrates a command that prints fermatas both above and below a bar line. If there would not otherwise be a bar line, it adds a double bar line. Semantically, the command codes a longer-than-normal caesura, which might be considered misuse depending on the situation.

```
twoWayFermata = {
  \once \set Staff.caesuraType = #'((underlying-bar-line . "||"))
  \once \set Staff.caesuraTypeTransform = ##f
  \caesura ^\fermata _\fermata
}

music = {
  f'1 \twoWayFermata
  R1
  f'2 \twoWayFermata f'2
  R1
  b'1 \twoWayFermata \fine
}

\new GrandStaff <<
  \new Staff \music
  \new Staff \music
>>
```



See also

Music Glossary: Section “caesura” in *Music Glossary*.

Notation Reference: Section 3.2.3 [Breath marks], page 175, Section 17.4.4 [Divisiones], page 555, Section 17.5.5 [Kievan bar lines], page 565, Section 9.7.4 [Phrase bar lines in hymn tunes], page 409.

Snippets: Section “Expressive marks” in *Snippets*.

Internals Reference: Section “BreathingSign” in *Internals Reference*, Section “Caesura_engraver” in *Internals Reference*, Section “CaesuraEvent” in *Internals Reference*, Section “CaesuraScript” in *Internals Reference*, Section “Tunable context properties” in *Internals Reference*.

2.3 Displaying rhythms

2.3.1 Measures

Dividing music into numbered measures and tracking time within measures are duties of the `Timing_translator`. This translator is not directly responsible for any engraving, but it sets context properties that guide engravers and performers.

The context in which the `Timing_translator` is placed, which is `Score` by default, is assigned the alias `Timing`. If you add `Timing_translator` to another context (such as `Voice` or `Staff`), you may need to instantiate that context explicitly before using the `Timing` alias to address properties.

The `Timing_translator` uses the following properties of the `Timing` context to keep track of time and describe it to engravers and performers.

`currentBarNumber`

The current measure number. For an example showing the use of this property see Section 2.5.3 [Bar numbers], page 132.

`measureLength`

The length of the measures in the current time signature. For example, `\time 4/4` sets this to 1, and `\time 6/8` sets it to $3/4$. This property may be set manually to create a shorter or longer measure than usual, but it cannot reasonably be set less than or equal to `measurePosition`, since the opportunity to start a new measure at the correct time is past.

`measurePosition`

This internal property is the current point in the current measure. When it reaches `measureLength`, it is reset to zero and `currentBarNumber` is incremented. `measurePosition` should not be set explicitly, but may be changed with the `\partial` command.

`timing`

When set to `#t`, `measurePosition` is updated at every note, rest, or skip. When set to `#f`, `measurePosition` keeps its current value indefinitely.

Timing can be changed by setting any of these variables. In the next example, the default 4/4 time signature is printed, but `measureLength` is set to $5/4$. At 4/8 through the third measure, the `\partial` command advances the measure position to leave only 5/8 remaining, which shortens that bar by 1/8. The next bar line then falls at 9/8 rather than 5/4.

```
\fixed c' {
  \override Score.BarNumber.break-visibility = #all-visible
  \set Timing.measureLength = #5/4
  c1 c4
  c1 c4
  c4 c \partial 8*5 b4 b b8
  c4 c1
}
```



See also

Notation Reference: Section 2.5.3 [Bar numbers], page 132, Section 2.3.5 [Unmetered music], page 91.

Snippets: Section “Rhythms” in *Snippets*.

Internals Reference: Section “Timing-translator” in *Internals Reference*, Section “Score” in *Internals Reference*.

2.3.2 Time signature

To set a basic time signature, use the `\time` command with the fraction as argument.

```
\time 2/4
c''2
```

```
\time 3/4
c''2.
```



Fractional time signatures and denominators longer than a whole note require Scheme syntax.

```
\time #'(5/2 . 4)
c''2 r8
```

```
\override Timing.TimeSignature.denominator-style = #'note
\time #'(2 . 1/2)
f''\breve c''
```



Other unusual denominators may be used to add augmentation dots in the number-over-note style; however, to benefit the most from features covered elsewhere, using a conventional fraction for `\time` and overriding `TimeSignature.time-signature` is recommended in such cases.

```
\override Timing.TimeSignature.denominator-style = #'note
\once \override Timing.TimeSignature.time-signature = #'(2 . 8/3)
\time 6/8
c''8 8 8 8 8 8
```



Mid-measure time signature changes are covered in Section 2.3.4 [Upbeats], page 90.

Time signatures are printed at the beginning of a piece and whenever the time signature changes. If a change takes place at the end of a line a warning time signature sign is printed there. This default behavior may be changed, see Section 36.7 [Visibility of objects], page 782.

```
\relative c'' {
  \time 2/4
  c2 c
  \break
  c c
  \break
  \time 4/4
  c c c c
```

}



The time signature symbol that is used in 2/2 and 4/4 time can be changed to a numeric style:

```
\relative c' {
  % Default style
  \time 4/4 c1
  \time 2/2 c1
  % Change to numeric style
  \numericTimeSignature
  \time 4/4 c1
  \time 2/2 c1
  % Revert to default style
  \defaultTimeSignature
  \time 4/4 c1
  \time 2/2 c1
}
```



Mensural time signatures are covered in Section 17.3.3 [Mensural time signatures], page 543.

Complex time signatures

The `\time` function supports a variety of complex time signatures represented as Scheme expressions. Fractions are represented as pairs, (*numerator* . *denominator*), where the denominator is always a number. The numerator is one number or a list of two or more numbers. A list represents concatenation.

```
\fixed c' {
  \time #'((2 2 2) . 8)
  \*6 c8
  \*12 c16
}
```



Meters that alternate strictly through multiple fractions can be constructed by grouping the fractions into a list. Automatic beaming settings will be adjusted depending on the values. Submeasure bar lines can be enabled to help clarify complex rhythms.

```
\fixed c' {
  \time #'((1 . 4) (3 . 8))
  \*5 c8
  \*10 c16
}
```



```
\fixed c' {
  \time #'(((1 2 3) . 8) (3 . 4))
  \*12 c8
  \submeasureBarsOn
  \*12 c8
}
```



By default, strictly alternating meters consisting of 4/4 and 2/2 are printed in a historic style using multiple C or cut-C symbols. It is not necessary to use this interpretation of these time signatures for the underlying meter: it is also possible to override `TimeSignature.time-signature` to print these symbols while setting a different meter with `\time`.

```
\fixed c' {
  \time #'((4 . 4) (4 . 4))
  \*4 c2
  \once \override Timing.TimeSignature.time-signature
    = #'((2 . 2) (2 . 2))
  \time 4/2
  \*4 c2
}
```



Metric properties

In addition to setting the printed time signature, the `\time` command also sets the values of the context properties `beatBase`, `beatStructure`, `submeasureStructure`, and `beamExceptions`.

The default values of these properties are derived formulaically from the time signature, with various exceptions defined in `scm/time-signature-settings.scm`. Setting aside the exceptions,

- `beatBase` is one over the denominator of the time signature. For example, in 3/2 time, `beatBase` is 1/2.
- `beatStructure` divides the measure
 - according to a structured numerator (a), or
 - into beats of $3 \times \text{beatBase}$ when the numerator is 6, 9, 12, ... (b), or
 - into beats of $1 \times \text{beatBase}$.
- `submeasureStructure` divides the measure between strictly alternating time signatures (c).



The default value of `beatStructure` can be overridden in the `\time` command itself by supplying it as the optional first argument:

```
\score {
  \new Staff {
    \relative {
      \time 2,2,3 7/8
      \*7 c'8 |
      \time 3,2,2 7/8
      \*7 c8 |
    }
  }
}
```



Alternatively, the default values of these metric properties can be set as a group for a given time signature. The new values take effect at a subsequent `\time` command with that time signature:

```
\score {
  \new Staff {
    \relative c' {
      \overrideTimeSignatureSettings
        8/4          % timeSignature
        #1/4         % beatBase
        #'((2 2) (3 1)) % beatStructure, submeasureStructure
        #'()          % beamExceptions
      \time 8/4
      \submeasureBarsOn
      \*16 c8 |
    }
  }
}
```



`\overrideTimeSignatureSettings` takes four arguments:

1. *timeSignature*, a fraction describing the time signature to which these values apply.
2. *beatBase*, the musical length corresponding to one unit of *beatStructure*.
3. *structure*, a Scheme list describing the length of each beat in the measure in units of *beatBase* (i.e., *beatStructure*), optionally grouped with inner lists describing larger subdivisions of the measure (i.e., *submeasureStructure*).
4. *beamExceptions*, an alist containing any beaming rules for the time signature that go beyond ending at every beat, as described in Section 2.4.2 [Setting automatic beam behavior], page 104.


Changed values of default time signature properties can be restored to the original values:

```
\score {
  \relative {
    \*8 c'8 |
    \overrideTimeSignatureSettings
      4/4      % timeSignature
      #1/4     % beatBase
      3,1      % beatStructure
      #'()     % beamExceptions
    \time 4/4
    \*8 c8 |
    \revertTimeSignatureSettings 4/4
    \time 4/4
    \*8 c8 |
  }
}
```



Different values of default time signature properties can be established for different staves by enabling polymetric notation (see Section 2.3.6 [Polymetric notation], page 93).

```
\score {
  \new StaffGroup <<
    \new Staff {
      \overrideTimeSignatureSettings
        4/4      % timeSignature
        #1/4     % beatBase
        3,1      % beatStructure
        #'()     % beamExceptions
      \time 4/4
      \*8 c''8
    }
    \new Staff {
      \overrideTimeSignatureSettings
        4/4      % timeSignature
        #1/4     % beatBase
        1,3      % beatStructure
        #'()     % beamExceptions
      \time 4/4
      \*8 c''8
    }
  >>
  \layout {
    \enablePerStaffTiming
  }
}
```



A further method of changing these metric properties, which avoids reprinting the time signature at the time of the change, is shown in Section 2.4.2 [Setting automatic beam behavior], page 104.

Predefined commands

`\numericTimeSignature`, `\defaultTimeSignature`.

Selected snippets

Time signature printing only the numerator as a number (instead of the fraction)

Sometimes, a time signature should not print the whole fraction (for example, 7/4), but only the numerator (digit 7 in this case). This can be easily done by using `\override Staff.TimeSignature.style = #'single-number` to change the style permanently. By using `\revert Staff.TimeSignature.style`, this setting can be reversed. To apply the single-number style to only one time signature, use `\tweak`.

```
\relative c'' {
  \time 3/4
  c4 c c
  % Change the style permanently
  \override Staff.TimeSignature.style = #'single-number
  \time 2/4
  c4 c
  \time 3/4
  c4 c c
  % Revert to default style:
  \revert Staff.TimeSignature.style
  \time 2/4
  c4 c
  % single-number style only for the next time signature
  \tweak style #'single-number \time 5/4
  c4 c c c c
  \time 2/4
  c4 c
}
```



See also

Music Glossary: Section “time signature” in *Music Glossary*

Notation Reference: Section 2.3.1 [Measures], page 78, Section 17.3.3 [Mensural time signatures], page 543, Section 2.3.6 [Polymetric notation], page 93, Section 2.4.2 [Setting automatic beam behavior], page 104.

Installed Files: scm/time-signature-settings.scm.

Snippets: Section “Rhythms” in *Snippets*.

Internals Reference: Section “TimeSignature” in *Internals Reference*, Section “Timing-translator” in *Internals Reference*.

Known issues and warnings

`\numericTimeSignature` and `\defaultTimeSignature` have no effect when used in a `MensuralStaff`. To use these modern time signatures in a `MensuralStaff`, either select them already when creating the context:

```
\new MensuralStaff \with { \numericTimeSignature } {
  c'1
}
```



or use an explicit `\override`:

```
\new MensuralStaff {
  \time 2/2
  c'1
  \override MensuralStaff.TimeSignature.style = #'numbered
  \time 2/2
  c'
  \override MensuralStaff.TimeSignature.style = #'default
  \time 2/2
  c'
}
```



If there is more than a single staff, and a time signature starts a prima volta but not the seconda volta, it is necessary to help LilyPond synchronize this situation by adding an explicit but invisible time signature in the seconda volta.

```
music = {
  \repeat volta 2 {
    \time 2/4 c'2 |
    \alternative {
      \volta 1 {
        \time 3/8 d'4. |
        \time 2/4 c'2 | }
      \volta 2 {
        \once \omit Staff.TimeSignature
        \time 2/4 c'2 |
      }
    }
  }
  \time 3/8 c'4. |
}
```

<<

```
\new Staff \music
\new Staff \music
>>
```



2.3.3 Metronome marks

A basic metronome mark is simple to write:

```
\relative {
  \tempo 4 = 120
  c'2 d
  e4. d8 c2
}
```



The stated rate does not have to be an integer, but it must be an exact number. The default formatter rounds to the nearest 0.25; the context property `tempoCountPrecision` controls this.

```
tempoI = 100
\fixed c' {
  \tempo 4 = #(* tempoI 2/3) % 66.66...
  e2 e4 d
  \once \set Timing.tempoCountPrecision = #1/1000000
  \tempo 4 = #(* tempoI 8/11) % 72.72...
  c2 g2
  g4 e2 f4
}
```



Metronome marks may also be printed as a range of two numbers:

```
\relative {
  \tempo 4 = 40 - 46
  c'4. e8 a4 g
  b,2 d4 r
}
```



Tempo indications with text can be used instead:

```
\relative {
  \tempo "Allegretto"
  c' '4 e d c
  b4. a16 b c4 r4
}
```



Combining a metronome mark and text will automatically place the metronome mark within parentheses:

```
\relative {
  \tempo "Allegro" 4 = 160
  g'4 c d e
  d4 b g2
}
```



In general, the text can be any markup object:

```
\relative {
  \tempo \markup { \italic Faster } 4 = 132
  a'8-. r8 b-. r gis-. r a-. r
}
```



A particularly useful markup command is `\rhythm`, which prints a rhythmic pattern. See Section A.1.4 [Markup for music and musical symbols], page 849.

```
\relative {
  \tempo \markup {
    Swing
    \hspace #0.4
    \rhythm { 8[ 8] } = \rhythm { \tuplet 3/2 { 4 8 } }
  }
  b8 g' c, d ees d16 ees d c r8
}
```



A parenthesized metronome mark with no textual indication may be written by including an empty string in the input:

```
\relative {
  \tempo "" 8 = 96
  d' '4 g e c
}
```



In a part for an instrument with long periods of rests (see Section 2.2.3 [Full measure rests], page 71) it happens quite frequently that tempo indications, rehearsal marks, and text marks sometimes follow each other closely. The command `\markLengthOn` provides extra horizontal (and vertical) space to prevent such marks from horizontal overlapping, often causing unwanted vertical stacking. Use `\markLengthOff` to restore the default behavior of ignoring these marks for the horizontal spacing algorithm.

```
\compressMMRests {
  \markLengthOn
  \tempo "Molto vivace"
  R1*12
  \mark \default \tempo "Allegretto ma non troppo"
  R1*16
  \mark \default \tempo "Tranquillo"
  R1*2
  \markLengthOff
  \mark \default \tempo "Tempo I"
  R1 R1 \break

  \markLengthOff
  \tempo "Molto vivace"
  R1*12
  \mark \default \tempo "Allegretto ma non troppo"
  R1*16
  \mark \default \tempo "Tranquillo"
  R1*2
  \mark \default \tempo "Tempo I"
  R1 R1
}
```

A musical staff in treble clef with a key signature of one sharp (F#). The staff contains five measures, each with a whole note. Above the staff, the following markings are present: **33** (measure 1), **Molto vivace** (measure 2), **12** (measure 3), **Allegretto ma non troppo** (measure 4), **16** (measure 5), **E** (measure 6), **2** (measure 7), **Tranquillo** (measure 8), **F** (measure 9), and **Tempo I** (measure 10). The staff is divided into five measures by vertical bar lines.

Selected snippets

Printing metronome and rehearsal marks below the staff

By default, metronome and rehearsal marks are printed above the staff. To place them below the staff simply set the direction property of `MetronomeMark` or `RehearsalMark` appropriately.

```
\layout {
  ragged-right = ##f
}

{
  % Metronome marks below the staff
  \override Score.MetronomeMark.direction = #DOWN
  \tempo 8. = 120
  c' '1

  % Rehearsal marks below the staff
  \override Score.RehearsalMark.direction = #DOWN
  \mark \default
  c' '1
}
```

A musical staff in treble clef with a key signature of one sharp (F#). The staff contains two measures, each with a whole note. Below the staff, the following markings are present: **♩. = 120** (measure 1) and **A** (measure 2). The staff is divided into two measures by a vertical bar line.

Changing the tempo without a metronome mark

To change the tempo in MIDI output without printing anything, make the metronome mark invisible.

```
\score {
  \new Staff \relative c' {
    \tempo 4 = 160
    c4 e g b
    c4 b d c
    \set Score.tempoHideNote = ##t
    \tempo 4 = 96
    d,4 fis a cis
    d4 cis e d
  }
  \layout { }
  \midi { }
}
```




Creating metronome marks in markup mode

New metronome marks can be created in markup mode, but they will not change the tempo in MIDI output.

```
\relative c' {
  \tempo \markup {
    \concat {
      (
        \smaller \general-align #Y #DOWN \note { 16. } #UP
        " = "
        \smaller \general-align #Y #DOWN \note { 8 } #UP
      )
    }
  }
  c1
  c4 c' c,2
}
```



For more details, see Section 8.2 [Formatting text], page 319.

See also

Music Glossary: Section “metronome” in *Music Glossary*, Section “metronomic indication” in *Music Glossary*, Section “tempo indication” in *Music Glossary*, Section “metronome mark” in *Music Glossary*.

Notation Reference: Section 8.2 [Formatting text], page 319, Chapter 24 [Creating MIDI output], page 651, Section 2.2.3 [Full measure rests], page 71.

Snippets: Section “Staff notation” in *Snippets*.

Internals Reference: Section “MetronomeMark” in *Internals Reference*.

2.3.4 Upbeats

Partial or pickup measures, such as an *anacrusis* or an *upbeat*, are entered using the `\partial` command:

```
\partial duration
```

When `\partial` is used at the beginning of a score, *duration* is the length of the music preceding the first bar.

```
\relative {
  \verboseBarNumbers
  \time 3/4
  \partial 4.
  r4 e'8 | a4 c8 b c4 |
}
```



When `\partial` is used after the beginning of a score, *duration* is the *remaining* length of the current measure. It does not create a new numbered bar.

```
\relative {
  \verboseBarNumbers
  \time 9/8
  d'4.~ 4 d8 d( c) b | c4.~ 4. \bar "||"
  \time 12/8
  \partial 4.
  c8( d) e | f2.~ 4 f8 a,( c) f |
}
```



The `\partial` command is *required* when the time signature changes in mid measure, but it may also be used alone.

```
\relative {
  \verboseBarNumbers
  \time 6/8
  \partial 8
  e'8 | a4 c8 b[ c b] |
  \partial 4
  r8 e,8 | a4 \bar "||"
  \partial 4
  r8 e8 | a4
  c8 b[ c b] |
}
```



For technical reasons, the argument to `\partial` cannot be a zero-length duration (like `\partial 4*0`).

See also

Music Glossary: Section “anacrusis” in *Music Glossary*.

Notation Reference: Section 2.6.1 [Grace notes], page 147.

Snippets: Section “Rhythms” in *Snippets*.

Internal Reference: Section “Timing_translator” in *Internals Reference*.

2.3.5 Unmetered music

In music such as cadenzas, it may be desirable to disable automatic measure demarcation and all that it entails: numbering bars, resetting accidentals, etc. Music between `\cadenzaOn` and `\cadenzaOff` does not count toward the length of a measure.

```

\relative c'' {
  % Show all bar numbers
  \override Score.BarNumber.break-visibility = #all-visible
  c4 d e d
  \cadenzaOn
  c4 cis d8[ d d] f4 g4.
  \cadenzaOff
  d4 e d c
}

```



To divide an unmeasured passage into irregular measures, temporarily re-enable timing and use `\partial` to create a tiny measure. The `\bar` command alone does not start a new measure.

```

cadenzaMeasure = {
  \cadenzaOff
  \partial 1024 s1024
  \cadenzaOn
}

\relative c'' {
  % Show all bar numbers
  \override Score.BarNumber.break-visibility = #all-visible
  c4 d e d
  \cadenzaOn
  c4 cis \bar {"!"} d8[ d d] \cadenzaMeasure f4 g4.
  \cadenzaMeasure
  \cadenzaOff
  d4 e d c
}

```



Automatic beaming is disabled by `\cadenzaOn`. Therefore, all beaming in cadenzas must be entered manually. See Section 2.4.3 [Manual beams], page 114.

```

\relative {
  \*8 c''8
  \cadenzaOn
  cis8 c c c c
  \bar{"|"}
  c8 c c
  \cadenzaOff
  \*8 c8
}

```



These predefined commands affect all staves in the score, even when placed in just one Voice context. To change this, move the `Timing_translator` from the `Score` context to the `Staff` context. See Section 2.3.6 [Polymetric notation], page 93.

Within a cadenza section, automatic breaks are disabled: since there is no metric, it is not possible to determine automatically where they would be appropriate. Therefore, in a long cadenza passage, you must insert possible break points at appropriate places using the `\allowBreak` command or other solutions in Section 28.1 [Line breaking], page 687.

```
\relative {
  c'4 f g c, d f g c
  \cadenzaOn
  c4 cis8
  \allowBreak
  d[ cis c cis]
  \allowBreak
  d[ f g a]
  \allowBreak
  ais[ g f g]
  \allowBreak
  d4 f8
  \allowBreak
  d[ cis] c4
  \allowBreak
  a8[ c] g4
}
```



Predefined commands

`\cadenzaOn`, `\cadenzaOff`.

See also

Music Glossary: Section “cadenza” in *Music Glossary*.

Notation Reference: Section 36.7 [Visibility of objects], page 782, Section 2.3.6 [Polymetric notation], page 93, Section 2.4.3 [Manual beams], page 114, Section 1.1.3 [Accidentals], page 8.

Snippets: Section “Rhythms” in *Snippets*.

2.3.6 Polymetric notation

Polymetric notation is supported explicitly or by manually modifying the visible time signature symbol and/or scaling note durations.


Different time signatures with equal-length measures

Use `\polymetric \time` to set a local time signature and `\scaleDurations` to make its measure length match `Timing.measureLength`. This sets the same set of properties as the `\time` command, except for `measureLength`.

To unset the local properties and resume using the values from the Timing context, use `\polymetric \default`.

In the following example, staves with time signatures 3/4, 9/8, and 10/8 are used in parallel, with 3/4 chosen as the reference measure length. The music in the first staff is spaced normally. In the second staff, the notated durations are multiplied by 2/3 (because $2/3 * 9/8 = 3/4$) and in the third staff, the notated durations are multiplied by 3/5 (because $3/5 * 10/8 = 3/4$).

```
\relative <<
  \new Staff {
    \time 3/4
    c'4 c c |
    c4 c c |
  }
  \new Staff {
    \scaleDurations 2/3 {
      \context Staff \polymetric \time 9/8
      \*3 { c8 c c }
      \*3 { c4 c8 }
    }
  }
  \new Staff {
    \scaleDurations 3/5 {
      \context Staff \polymetric \time 3,3,2,2 10/8
      \*2 { c8 c c }
      \*2 { c8 c } |
      c4. c \tuplet 3/2 { c8 c c } c4
    }
  }
>>
```



Different time signatures with unequal-length measures

Each staff can be given its own independent time signature as soon as `\enablePerStaffTiming` is placed in the `\layout` block.

```
\layout {
  \enablePerStaffTiming
}
```


% Now each staff has its own time signature.

```
\relative <<
  \new Staff {
    \time 3/4
```

```

      c'4 c c |
      c4 c c |
    }
    \new Staff {
      \time 2/4
      c4 c |
      c4 c |
      c4 c |
    }
    \new Staff {
      \time 3/8
      c4. |
      c8 c c |
      c4. |
      c8 c c |
    }
  >>

```



To have just one polymetric score, include `\enablePerStaffTiming` in a `\layout` block inside the `\score` block.

```

\score {
  <<
    \new Staff { c''1 1 }
    \new Staff { c'2 d' g'2~ 2 }
  >>
}

\score {
  \layout {
    \enablePerStaffTiming
  }
  <<
    \new Staff { \time 4/4 c''1 1 }
    \new Staff { \time 2/4 c'2 d' g'2~ 2 }
  >>
}

```



When using polymeter, all staves should include a `\time` command if their meter is not the default 4/4. This is true even for special staves without actual staff lines, such as Dynamics contexts, since the placement of certain spanners like hairpins is synchronized with bar lines.

In order to use this feature with MIDI output, also include `\enablePerStaffTiming` in a `\midi` block.

```

\layout {

```

```

\enablePerStaffTiming
}

\midi {
  \enablePerStaffTiming
}

```

See also

Music Glossary: Section “polymetric” in *Music Glossary*, Section “polymetric time signature” in *Music Glossary*, Section “meter” in *Music Glossary*.

Notation Reference: Section 2.4.1 [Automatic beams], page 101, Section 2.4.3 [Manual beams], page 114, Section 2.3.2 [Time signature], page 79, Section 2.1.3 [Scaling durations], page 61.

Snippets: Section “Rhythms” in *Snippets*.

Internals Reference: Section “TimeSignature” in *Internals Reference*, Section “Timing_translator” in *Internals Reference*, Section “Staff” in *Internals Reference*.

Known issues and warnings

Although notes that occur at the same moment in each of the different staves will be placed at the same horizontal location, bar lines (in each staff) may cause inconsistent spacing within each of the different time signatures.

2.3.7 Automatic note splitting

Long notes which overrun bar lines can be converted automatically to tied notes. This is done by replacing the `Note_heads_engraver` with the `Completion_heads_engraver`. Similarly, long rests which overrun bar lines are split automatically by replacing the `Rest_engraver` with the `Completion_rest_engraver`. In the following example, notes and rests crossing the bar lines are split, notes are also tied.

```

\new Voice \with {
  \remove Note_heads_engraver
  \consists Completion_heads_engraver
  \remove Rest_engraver
  \consists Completion_rest_engraver
}
\relative {
  c'2. c8 d4 e f g a b c8 c2 b4 a g16 f4 e d c8. c2 r1*2
}

```



These engravers split all running notes and rests at the bar line, and inserts ties for notes. One of its uses is to debug complex scores: if the measures are not entirely filled, then the ties show exactly how much each measure is off.

The property `completionUnit` sets a preferred duration for the split notes.


```

\new Voice \with {
  \remove Note_heads_engraver
  \consists Completion_heads_engraver
} \relative {
  \time 9/8 g\breve. d''4. \bar "||"
  \set completionUnit = #3/8
  g\breve. d4.
}

```



These engravers split notes with scaled duration, such as those in tuplets, into notes with the same scale factor as in the input note.

```

\new Voice \with {
  \remove Note_heads_engraver
  \consists Completion_heads_engraver
} \relative {
  \time 2/4 r4
  \tuplet 3/2 {g'4 a b}
  \scale Durations 2/3 {g a b}
  g4*2/3 a b
  \tuplet 3/2 {g4 a b}
  r4
}

```



See also

Music Glossary: Section “tie” in *Music Glossary*

Learning Manual: Section “Engravers explained” in *Learning Manual*, Section “Adding and removing engravers” in *Learning Manual*.

Snippets: Section “Rhythms” in *Snippets*.

Internals Reference: Section “Note_heads_engraver” in *Internals Reference*, Section “Completion_heads_engraver” in *Internals Reference*, Section “Rest_engraver” in *Internals Reference*, Section “Completion_rest_engraver” in *Internals Reference*, Section “Forbid_line_break_engraver” in *Internals Reference*.

Known issues and warnings

For consistency with previous behavior, notes and rests with duration longer than a measure, such as $c1*2$, are split into notes without any scale factor, $\{c1\ c1\}$. The property `completionFactor` controls this behavior, and setting it to `#f` cause split notes and rests to have the scale factor of the input durations.


2.3.8 Showing melody rhythms

Sometimes you might want to show only the rhythm of a melody. This can be done with the rhythmic staff. All pitches of notes on such a staff are squashed, and the staff itself has a single line

```
<<
\new RhythmicStaff {
  \new Voice = "myRhythm" \relative {
    \time 4/4
    c'4 e8 f g2
    r4 g g f
    g1
  }
}

\new Lyrics {
  \lyricsto "myRhythm" {
    This is my song
    I like to sing
  }
}

>>
```



Guitar chord charts often show the strumming rhythms. This can be done with the `Pitch_squash_engraver` and `\improvisationOn`.

```
<<
\new ChordNames {
  \chordmode {
    c1 f g c
  }
}
\new Voice \with {
  \consists Pitch_squash_engraver
} \relative c' {
  \improvisationOn
  c4 c8 c c4 c8 c
  f4 f8 f f4 f8 f
  g4 g8 g g4 g8 g
  c4 c8 c c4 c8 c
}
>>
```




Music containing chords can also be used as input to `RhythmicStaff` and for use with the `Pitch_squash_engraver` if the chords are first reduced to single notes with the `\reduceChords` music function:

```

\new RhythmicStaff {
  \time 4/4
  \reduceChords {
    <c>2
    <e>2
    <c e g>2
    <c e g>4
    <c e g>4
  }
}

```



Predefined commands

`\improvisationOn`, `\improvisationOff`, `\reduceChords`.

Selected snippets

Guitar strum rhythms

For guitar music it is possible to show strum rhythms, along with melody notes, chord names, and fret diagrams.

```

\include "predefined-guitar-fretboards.ly"

<<
\new ChordNames \chordmode {
  c1 | f | g | c
}
\new FretBoards \chordmode {
  c1 | f | g | c
}
\new Voice \with {
  \consists "Pitch_squash_engraver"
} \relative c'' {
  \improvisationOn
  c4 c8 c c4 c8 c
  f4 f8 f f4 f8 f
  g4 g8 g g4 g8 g
  c4 c8 c c4 c8 c
}
\new Voice = "melody" \relative c'' {
  c2 e4 e4
  f2. r4
  g2. a4
  e4 c2.
}
\new Lyrics \lyricsto "melody" {
  This is my song.
  I like to sing.
}
>>

```

The image shows a musical score for the lyrics "This is my song. I like to sing." in 2/4 time. The score is written on two staves. The first staff contains the melody, and the second staff contains the lyrics. Above the first staff, there are three guitar chord diagrams: C (x 3 2 1), F (1 3 4 2 1 1), and G (2 1 3). Above the second staff, there is a guitar chord diagram: C (x 3 2 1). The lyrics are: "This is my song. I like to sing."

See also

Snippets: Section “Rhythms” in *Snippets*.

Internals Reference: Section “RhythmicStaff” in *Internals Reference*, Section “Pitch_squash_engraver” in *Internals Reference*.

2.4 Beams

LilyPond provides two different possibilities for entering beams: automatic and manual input, which can be also mixed.

2.4.1 Automatic beams

By default, beams are inserted automatically:

```
\relative c'' {
  \time 2/4 c8 c c c
  \time 6/8 c8 c c c8. c16 c8
}
```

The image shows a musical score for the automatic beaming example. It consists of two measures. The first measure is in 2/4 time and contains four eighth notes (c8 c c c) beamed together. The second measure is in 6/8 time and contains a sequence of eighth notes (c8 c c c8. c16 c8) beamed together.

If these automatic decisions are not satisfactory, beaming can be entered explicitly; see Section 2.4.3 [Manual beams], page 114. Beams *must* be entered manually if beams are to be extended over rests.

If automatic beaming is not required, it may be turned off with `\autoBeamOff` and on with `\autoBeamOn`:

```

\relative c' {
  c4 c8 c8. c16 c8. c16 c8
  \autoBeamOff
  c4 c8 c8. c16 c8.
  \autoBeamOn
  c16 c8
}

```



Note: If beams are used to indicate melismata in songs, then automatic beaming should be switched off with `\autoBeamOff` and the beams indicated manually. Using `\partCombine` with `\autoBeamOff` can produce unintended results. See the snippets for more information.

Beaming patterns that differ from the automatic defaults can be created; see Section 2.4.2 [Setting automatic beam behavior], page 104.

Predefined commands

`\autoBeamOff`, `\autoBeamOn`.

Selected snippets

Beams across line breaks

Normally, LilyPond refuses to automatically break a line at places where a beam crosses a bar line. This behavior can be changed by setting the `Beam.breakable` property to `#t`.

This property does not affect manual breaks inserted with commands like `\break`.

```

music = {
  \*8 c8
  c8 \*7 { c[ c] } c
  \*8 c8
}

\relative c'' {
  <>^\markup { \typewriter Beam.breakable set to \typewriter "#t" }
  \override Beam.breakable = ##t
  \music
}

\relative c'' {
  <>^\markup { \typewriter Beam.breakable not set }
  \music
}

\paper {
  line-width = 100\mm
}

```

Beam.breakable set to #t

3

Beam.breakable not set

2

4

Changing beam knee gap

Kneaded beams are inserted automatically when a large gap is detected between the note heads. This behavior can be tuned through the `auto-knee-gap` property. A kneaded beam is drawn if the gap is larger than the value of `auto-knee-gap` plus the width of the beam object (which depends on the duration of the notes and the slope of the beam). By default, `auto-knee-gap` is set to 5.5 staff spaces.

```
{
  f8 f''8 f8 f''8
  \override Beam.auto-knee-gap = #6
  f8 f''8 f8 f''8
}
```

Partcombine and \autoBeamOff

The function of `\autoBeamOff` when used with `\partCombine` can be difficult to understand. It may be preferable to use

```
\set Staff.autoBeaming = ##f
```

instead to ensure that auto-beaming is turned off for the entire staff. Use this at a spot in your score where no beam generated by the auto-beamer is still active.

Internally, `\partCombine` works with four voices – up-stem single, down-stem single, combined, and solo. In order to use `\autoBeamOff` to stop all auto-beaming when used with `\partCombine`, it is necessary to use *four* calls to `\autoBeamOff`.

```

{
  % \set Staff.autoBeaming = ##f % turns off all auto-beaming

  \partCombine {
    \autoBeamOff % applies to split up-stems
    \*4 a'16
    % \autoBeamOff % applies to combined stems
    \*4 a'8
    \*4 a'16
    % \autoBeamOff % applies to solo
    \*4 a'16
    r4
  } {
    % \autoBeamOff % applies to split down-stems
    \*4 f'8
    \*8 f'16 |
    r4
    \*4 a'16
  }
}

```



See also

Notation Reference: Section 2.4.3 [Manual beams], page 114, Section 2.4.2 [Setting automatic beam behavior], page 104.

Installed Files: scm/auto-beam.scm.

Snippets: Section “Rhythms” in *Snippets*.

Internals Reference: Section “Auto_beam_engraver” in *Internals Reference*, Section “Beam_engraver” in *Internals Reference*, Section “Beam” in *Internals Reference*, Section “BeamEvent” in *Internals Reference*, Section “BeamForbidEvent” in *Internals Reference*, Section “beam-interface” in *Internals Reference*, Section “unbreakable-spanner-interface” in *Internals Reference*.

Known issues and warnings

The properties of a beam are determined at the *start* of its construction and any additional beam property changes that occur before the beam has been completed will not take effect until the *next*, new beam starts.

2.4.2 Setting automatic beam behavior

When automatic beaming is enabled, the placement of automatic beams is determined by three context properties: `beatBase`, `beatStructure`, and `beamExceptions`. Any of these may be overridden until the next `\time` command as described below; alternatively, their default values per time signature may be changed persistently as explained in Section 2.3.2 [Time signature], page 79.

When `beamExceptions` contains an applicable rule, it takes precedence over `beatBase` and `beatStructure`.

Beaming based on `beatBase` and `beatStructure`

Built-in `beamExceptions` rules are defined for many common time signatures. They must be disabled if automatic beaming is to be based strictly on `beatBase` and `beatStructure`. The `beamExceptions` rules are disabled by

```
\set Timing.beamExceptions = #'()
```

When `beamExceptions` is set to `#'()`, either due to an explicit setting or because no built-in `beamExceptions` rules are defined for the time signature in force, beams end on beats specified by the context properties `beatBase` and `beatStructure`.

The `\time` command resets `beatBase`, `beatStructure`, and `beamExceptions`, so desired modifications must be placed after the `\time` command, not before it.

```
\relative c'' {
  \time 5/16
  c16^"default" c c c c |
  % beamExceptions are unlikely to be defined for 5/16 time,
  % but let's disable them anyway to be sure
  \set Timing.beamExceptions = #'()
  \set Timing.beatStructure = 2,3
  c16^(2+3) c c c c |
  \set Timing.beatStructure = 3,2
  c16^(3+2) c c c c |
}
```



```
\relative {
  \time 4/4
  a'8^"default" a a a a a a a
  % Disable beamExceptions because they are definitely
  % defined for 4/4 time
  \set Timing.beamExceptions = #'()
  \set Timing.beatBase = #1/4
  \set Timing.beatStructure = 1,1,1,1
  a8^"changed" a a a a a a a
}
```



Beam setting changes can be limited to specific contexts. If no setting is included in a lower-level context, the setting of the enclosing context will apply.

```
\new Staff {
  \time 7/8
  % No need to disable beamExceptions
  % as they are not defined for 7/8 time
  \set Staff.beatStructure = 2,3,2
  <<
  \new Voice = one {
    \relative {
```



```

        a'8 a a a a a a
    }
}
\new Voice = two {
  \relative {
    \voiceTwo
    \set Voice.beatStructure = 1,3,3
    f'8 f f f f f f
  }
}
>>
}

```



When multiple voices are used the Staff context must be specified if the beaming is to be applied to all voices in the staff:

```

\time 7/8
% rhythm 3-1-1-2
% Change applied to Voice by default -- does not work correctly
% Because of auto-generated voices, all beaming will
% be at beatBase #1/8
\set beatStructure = 3,1,1,2
<< \relative {a'8 a a a16 a a a a8 a} \\\relative {f'4. f8 f f f} >>

% Works correctly with context Staff specified
\set Staff.beatStructure = 3,1,1,2
<< \relative {a'8 a a a16 a a a a8 a} \\\relative {f'4. f8 f f f} >>

```



The value of beatBase can be adjusted to change the beaming behavior, if desired. When this is done, the value of beatStructure must be set to be compatible with the new value of beatBase.

```

\time 5/8
% No need to disable beamExceptions
% as they are not defined for 5/8 time
\set Timing.beatBase = #1/16
\set Timing.beatStructure = 7,3
\*10 a'16

```



Beaming based on beamExceptions

Special auto-beaming rules (other than ending a beam on a beat) are defined in the beamExceptions property.

The value for `beamExceptions`, a somewhat complex Scheme data structure, is easiest generated with the `\beamExceptions` function. This function is given one or more manually beamed measure-long rhythmic patterns (measures have to be separated by a bar check `|` since the function has no other way to discern the measure length). Here is a simple example:

```
\relative c' {
  \time 3/16
  \set Timing.beatStructure = 2,1
  \set Timing.beamExceptions =
    \beamExceptions { 32[ 32] 32[ 32] 32[ 32] }
  c16 c c |
  \*6 c32 |
}
```



Note: A `beamExceptions` value must be *complete* exceptions list. That is, every exception that should be applied must be included in the setting. It is not possible to add, remove, or change only one of the exceptions. While this may seem cumbersome, it means that the current beaming settings need not be known in order to specify a new beaming pattern.

When the time signature is changed, default values of `Timing.beatBase`, `Timing.beatStructure`, and `Timing.beamExceptions` are set. Setting the time signature will reset the automatic beaming settings for the `Timing` context to the default behavior.

```
\relative a' {
  \time 6/8
  \*6 a8
  % group (4 + 2)
  \set Timing.beatStructure = 4,2
  \*6 a8
  % go back to default behavior
  \time 6/8
  \*6 a8
}
```



The default automatic beaming settings for a time signature are determined in `scm/time-signature-settings.scm`. Changing the default automatic beaming settings for a time signature is described in Section 2.3.2 [Time signature], page 79.

Many automatic beaming settings for a time signature contain an entry for `beamExceptions`. For example, 4/4 time tries to beam the measure in two if there are only eighth notes. The `beamExceptions` rule can override the `beatStructure` setting if `beamExceptions` is not reset.

```

\time 4/4
\set Timing.beatBase = #1/8
\set Timing.beatStructure = 3,3,2
% This won't beam (3 3 2) because of beamExceptions
\*8 c''8 |
% This will beam (3 3 2) because we clear beamExceptions
\set Timing.beamExceptions = #'()
\*8 c''8

```



In a similar fashion, eighth notes in 3/4 time are beamed as a full measure by default. To beam eighth notes in 3/4 time on the beat, reset `beamExceptions`.

```

\time 3/4
% by default we beam in (6) due to beamExceptions
\*6 a'8 |
% This will beam (1 1 1) due to default beatBase and beatStructure
\set Timing.beamExceptions = #'()
\*6 a'8

```



In engraving from the romantic and classical periods, beams often begin midway through the measure in 3/4 time, but modern practice is to avoid the false impression of 6/8 time (see Gould, p. 153). Similar situations arise in 3/8 time. This behavior is controlled by the context property `beamHalfMeasure`, which has effect only in time signatures with 3 in the numerator:

```

\relative a' {
  \time 3/4
  r4. a8 a a |
  \set Timing.beamHalfMeasure = ##f
  r4. a8 a a |
}

```



How automatic beaming works

When automatic beaming is enabled, the placement of automatic beams is determined by the context properties `beatBase`, `beatStructure`, and `beamExceptions`.

The following rules, in order of priority, apply when determining the appearance of beams:

- If a manual beam is specified with [...] set the beam as specified, otherwise
- if a beam ending rule is defined in `beamExceptions` for the beam type, use it to determine the valid places where beams may end, otherwise
- if a beam ending rule is defined in `beamExceptions` for a longer beam type, use it to determine the valid places where beams may end, otherwise
- use the values of `beatBase` and `beatStructure` to determine the ends of the beats in the measure, and end beams at the end of beats.

In the rules above, the *beam type* is the duration of the shortest note in the beamed group. The default beaming rules can be found in `scm/time-signature-settings.scm`.

Selected snippets

Subdividing beams

The beams of consecutive 16th (or shorter) notes are, by default, not subdivided. That is, the beams of more than two stems stretch over the entire group of notes without a break. This behavior can be modified to subdivide the beams into sub-groups by setting the property `subdivideBeams` to `#t`. When set, beams are subdivided at (rhythmic) intervals to match the metric value of the subdivision.

Using the properties `beamMinimumSubdivision` and `beamMaximumSubdivision` it is possible to configure the limits of automatic beam subdivision, namely the minimum and maximum rhythmic lengths at which beamlets are removed. The default values are 0 for the former and `+inf.0` for the latter, making LilyPond subdivide beams as much as possible.

There are two special cases to consider.

- If the numerator of `beamMaximumSubdivision` is not a power of 2, the rhythmic lengths considered for subdivision are `beamMaximumSubdivision` divided by powers of 2 that stay greater than or equal to `beamMinimumSubdivision`.
- If `beamMaximumSubdivision` is smaller than `beamMinimumSubdivision`, the depth of beam subdivisions is limited by `beamMaximumSubdivision`, but not the frequency and rhythmic intervals, therefore possibly deviating from the correct, expected metric value.

If `respectIncompleteBeams` is set to `#t`, incomplete subdivisions with more than two stems are treated as an ‘extension’ of the previous subdivision group, i.e., the length of the previous subdivision group gets extended to also cover the incomplete subdivision. If set to `#f` (which is the default), a new subdivision group gets started instead.

```
\relative c' {
  \time 1/4

  <>^"default"
  c32 c c c c c c c

  <>^"with subdivision"
  \set subdivideBeams = #t
  c32 c c c c c c c

  <>^"min 1/8"
  \once \set beamMinimumSubdivision = #1/8
  c32 c c c c c c c

  <>^"max 1/16"
  \once \set beamMaximumSubdivision = #1/16
  c32 c c c c c c c

  <>^"max 3/8"
  \once \set beamMaximumSubdivision = #3/8
  \*16 c64

  <>^"min 1/32, max 1/64"
  % Set maximum beam subdivision interval to 1/64 to limit
```

```

% subdivision depth, despite not being metrically correct.
\once \set beamMinimumSubdivision = #1/32
\once \set beamMaximumSubdivision = #1/64
\*32 c128
\break

<>^"beams with incomplete subdivisions"
c32 c c c c c c r32
c32 c c c c r16.

<>^\markup { "the same with"
              \typewriter { "respectIncomplete=#t" } }
\set respectIncompleteBeams = ##t
% The incomplete subgroup extends the completed subgroup.
c32 c c c c c c r32
% No visual change since we have only two stems in the
% incomplete subgroup.
c32 c c c c r16.
}

```

default with subdivision min 1/8

4 max 1/16 max 3/8

6 min 1/32, max 1/64

7 beams with incomplete subdivisions

9 the same with respectIncomplete=#t

Strict beat beaming

Beamlets can be set to point in the direction of the beat to which they belong. The first beam avoids sticking out flags (the default); the second beam strictly follows the beat.

```

\relative c'' {
  \time 6/8
  a8. a16 a a
  \set strictBeatBeaming = ##t
  a8. a16 a a
}

```


Conducting signs, measure grouping signs

Context properties control the grouping of beats within a measure: `beatStructure` lists the length of each beat in units of `beatBase`. Default values are established in `scm/time-signature-settings.scm`. These properties may be changed particularly with `\set`.

Alternatively, `\time` optionally accepts a beat structure to use instead of the default. `\time` applies to the Timing context, so it does not reset values of properties that are set in lower-level contexts such as Voice.

If the `Measure_grouping_engraver` is included in one of the display contexts, measure grouping signs will be created. Such signs ease reading rhythmically complex modern music. In the example, the 9/8 measure is grouped in two different patterns using the two different methods, while the 5/8 measure is grouped according to the default setting in `scm/time-signature-settings.scm`. For the 4/4 measure you have to explicitly set `beatBase` to eighths so that the bar's irregular pattern gets displayed.

```
\score {
  \new Voice \relative c'' {
    \time 9/8
    g8 g d d g g a( bes g) |
    \set Timing.beatStructure = 2,2,2,3
    g8 g d d g g a( bes g) |
    \time 4,5 9/8
    g8 g d d g g a( bes g) |
    \time 5/8
    a4. g4 |
    \time 3,3,2 4/4
    \set Timing.beatBase = #1/8
    f4 d8 f4 d8 g4
  }
  \layout {
    \context {
      \Staff
      \consists "Measure_grouping_engraver"
    }
  }
}
```



Beam endings in Score context

Beam-ending rules specified in the Score context apply to all staves, but can be modified at both Staff and Voice levels:

```

\relative c'' {
  \time 5/4
  % Set default beaming for all staves
  \set Score.beatBase = #1/8
  \set Score.beatStructure = 3,4,3
  <<
    \new Staff {
      c8 c c c c c c c c c
    }
    \new Staff {
      % Modify beaming for just this staff
      \set Staff.beatStructure = 6,4
      c8 c c c c c c c c c
    }
    \new Staff {
      % Inherit beaming from Score context
      <<
        {
          \voiceOne
          c8 c c c c c c c c c
        }
        % Modify beaming for this voice only
        \new Voice {
          \voiceTwo
          \set Voice.beatStructure = 6,4
          a8 a a a a a a a a a
        }
      >>
    }
  >>
}

```



See also

Notation Reference: Section 2.3.2 [Time signature], page 79.

Installed Files: `scm/time-signature-settings.scm`.

Snippets: Section “Rhythms” in *Snippets*.


Internals Reference: Section “Auto_beam_engraver” in *Internals Reference*, Section “Beam” in *Internals Reference*, Section “BeamForbidEvent” in *Internals Reference*, Section “beam-interface” in *Internals Reference*.

Known issues and warnings

If a score ends while an automatic beam has not been ended and is still accepting notes, this last beam will not be typeset at all. The same holds for polyphonic voices, entered with `<< ... \\ ... >>`. If a polyphonic voice ends while an automatic beam is still accepting notes, it is not typeset. The workaround for these problems is to manually beam the last beam in the voice or score.


By default, the Timing translator is aliased to the Score context. This means that setting the time signature in one staff will affect the beaming of the other staves as well. Thus, a time signature setting in a later staff will reset custom beaming that was set in an earlier staff. One way to avoid this problem is to set the time signature in only one staff.

```
<<
  \new Staff {
    \time 3/4
    \set Timing.beatBase = #1/8
    \set Timing.beatStructure = 1,5
    \set Timing.beamExceptions = #'()
    \*6 a'8
  }
  \new Staff {
    \*6 a'8
  }
>>
```



The default beam settings for the time signature can also be changed, so that the desired beaming will always be used. Changes in automatic beaming settings for a time signature are described in Section 2.3.2 [Time signature], page 79.

```
<<
  \new Staff {
    \overrideTimeSignatureSettings
      3/4           % timeSignature
      #1/8         % beatBase
      1,5          % beatStructure
      #'()         % beamExceptions
    \time 3/4
    \*6 a'8
  }
  \new Staff {
    \time 3/4
    \*6 a'8
  }
>>
```

2.4.3 Manual beams


In some cases it may be necessary to override the automatic beaming algorithm. For example, the auto-beamer will not put beams over rests or bar lines, and in choral scores the beaming is often set to follow the meter of the lyrics rather than the notes. For complete manual control, beams can be specified by marking the begin and end point with `[` and `]`, respectively:

```
\relative { r4 r8[ g' a r] r g[ | a] r }
```



Beaming direction can then be set manually using direction indicators:

```
\relative { c''8^[ d e] c,_[ d e f g] }
```



Instead of taking full manual control over the beams, it often suffices to give the automatic beaming algorithm some hints. With `\beamBreak`, you demand that an automatically created beam be interrupted. With `\noBeamBreak`, on the contrary, you force two adjoining notes to get connected by a beam. This may even cause a completely new beam to be created:

```
{
  c''8 8 8 8 8 8 8 8 |
  c''8 8 8 8 \noBeamBreak 8 8 8 8 |
  8 8 8 8 8 8 \beamBreak 8 8 \noBeamBreak |
  \time 3/8 |
  8 4 |
  4 8 \noBeamBreak |
  8 4 |
}
```



Also, individual notes may be marked with `\noBeam` to completely prevent them from being beamed:

```
\relative {
  \time 2/4
  c' '8 c \noBeam c c
}
```



Grace note beams and normal note beams can occur simultaneously. Unbeamed grace notes are not put into normal note beams.

```
\relative {
  c' '4 d8[
  \grace { e32 d c d }
  e8] e[ e
  \grace { f16 }
  e8 e]
}
```



Even more strict manual control with the beams can be achieved by setting the properties `stemLeftBeamCount` and `stemRightBeamCount`. They specify the number of beams to draw on the left and right side, respectively, of the next note. If either property is set, its value will be used only once, and then it is erased. In this example, the last `f` is printed with only one beam on the left side, i.e., the eighth-note beam of the group as a whole.

```
\relative a' {
  a8[ r16 f g a]
  a8[ r16
  \set stemLeftBeamCount = 2
  \set stemRightBeamCount = 1
  f16
  \set stemLeftBeamCount = 1
  g16 a]
}
```



Predefined commands

`\noBeam`.

Selected snippets

Beam nibs

Beam nibs at the start and end of beams together with beams attached to solitary notes that look like flat flags are possible with a combination of `stemLeftBeamCount`, `stemRightBeamCount`, and paired `[]` beam indicators.


For imitating right-pointing flat flags on lone notes, use paired `[]` beam indicators and set `stemLeftBeamCount` to zero. For imitating left-pointing flat flags on lone notes, set `stemRightBeamCount` to zero instead (line one).

For right-pointing nibs at the end of a run of beamed notes, set `stemRightBeamCount` to a positive value. For left-pointing nibs at the start of a run of beamed notes, set `stemLeftBeamCount` instead (line two).

Sometimes it may make sense for a lone note surrounded by rests to carry both a left- and right-pointing nib. Do this with paired `[]` beam indicators alone (line three).

Note that `\set stemLeftBeamCount` is always equivalent to `\once \set`. In other words, the beam count settings are not “sticky”, so the pair of nibs attached to the lone 16th note in the last example has nothing to do with the `\set` command for the beam before.

```
\score {
  <<
    \new RhythmicStaff {
      \set stemLeftBeamCount = 0
      c16[] r8.
      r8.
      \set stemRightBeamCount = 0
      16[]
    }
    \new RhythmicStaff {
      16 16
      \set stemRightBeamCount = 2
      16 r r
      \set stemLeftBeamCount = 2
      16 16 16
    }
    \new RhythmicStaff {
      16 16
      \set stemRightBeamCount = 2
      16 r16
      16[] r16
      \set stemLeftBeamCount = 2
      16 16
    }
  >>
}
```



Using alternative flag styles

Alternative shapes for flags on eighth and shorter notes can be displayed by overriding the `stencil` property of `Flag`. LilyPond provides the following functions: `modern-straight-flag`, `old-straight-flag`, and `flat-flag`. Use `\revert` to restore the default shape.

To get stacked (i.e., vertically more compact) flags, call the command `\flagStyleStacked`, which can be reset with `\flagStyleDefault`.

Overriding the `Flag` stencil does not change how flag elements are positioned vertically. This is especially noticeable for flat flags: LilyPond doesn't dynamically adjust the vertical gaps between flag elements in the same way as it does for beams. A possible solution to harmonize the appearance is to replace flat flags with half beams, as shown in the second staff; however, this can't be done automatically. In the code of this snippet, such half beams are entered with `@` as a prefix, for example `@c8`.

Be aware that half beams are *not* `Flag` grobs. This means in particular that modifying `Flag` properties won't have any effect on them (you have to use `Beam` properties instead), and properties for their associated `Stem` grob will also behave beam-like.

"@" =

```
#(define-music-function (music) (ly:music?)
  #{ \set stemLeftBeamCount = 0 $music [] #})

testnotes = {
  \autoBeamOff
  c8 d16 e''32 f64 \acciaccatura { g,,,8 } a128 b
}

\relative c' {
  \override TextScript.staff-padding = 6
  \time 1/4
  <>^"default" \testnotes
  \override Flag.stencil = #modern-straight-flag
  <>_"modern straight" \testnotes
  \override Flag.stencil = #old-straight-flag
  <>^"old straight" \testnotes
  \override Flag.stencil = #flat-flag
  <>_"flat" \testnotes
  \revert Flag.stencil

  \flagStyleStacked
  <>^"stacked" \testnotes
  \flagStyleDefault
  <>_"default" \testnotes
}
```


```

\relative c' {
  \time 3/4
  \override Flag.stencil = #flat-flag

  <>^"flat" c8 c[ c] d16 d[ d] e''32 e[ e] f64 f[ f]
  \acciaccatura { g,,,8 } a128 a[ a a a a]
  <>^"beam-like" @c8 c[ c] @d16 d[ d] @e''32 e[ e] @f64 f[ f]
  \acciaccatura { g,,,8 } @a128 a[ a a a a]
}

\layout {
  indent = 0
  \context {
    \Score
    \override NonMusicalPaperColumn.line-break-permission = ##f
  }
}

```



See also

Notation Reference: Section 36.1 [Direction and placement], page 772, Section 2.6.1 [Grace notes], page 147.

Snippets: Section “Rhythms” in *Snippets*.

Internals Reference: Section “Beam” in *Internals Reference*, Section “BeamEvent” in *Internals Reference*, Section “Beam_engraver” in *Internals Reference*, Section “beam-interface” in *Internals Reference*, Section “Stem_engraver” in *Internals Reference*.

2.4.4 Feathered beams

Feathered beams are used to indicate that a small group of notes should be played at an increasing (or decreasing) tempo, without changing the overall tempo of the piece. The extent of the feathered beam must be indicated manually using [and], and the beam feathering is turned on by specifying a direction to the Beam property grow-direction.

If the placement of the notes and the sound in the MIDI output is to reflect the *ritardando* or *accelerando* indicated by the feathered beam the notes must be grouped as a music expression delimited by braces and preceded by a `\featherDurations` command which specifies the ratio between the durations of the first and last notes in the group.

The square brackets show the extent of the beam and the braces show which notes are to have their durations modified. Normally these would delimit the same group of notes, but this is not required: the two commands are independent.

In the following example the eight 16th notes occupy exactly the same time as a half note, but the first note is one half as long as the last one, with the intermediate notes gradually lengthening. The first four 32nd notes gradually speed up, while the last four 32nd notes are at a constant tempo.

```
\relative c' {
  \override Beam.grow-direction = #LEFT
  \featherDurations 2/1
  { c16[ c c c c c c c c] }
  \override Beam.grow-direction = #RIGHT
  \featherDurations 2/3
  { c32[ d e f] }
  % revert to non-feathered beams
  \override Beam.grow-direction = #'()
  { g32[ a b c] }
}
```



The spacing in the printed output represents the note durations only approximately, but the MIDI output is exact.

Predefined commands

`\featherDurations`.

See also

Snippets: Section “Rhythms” in *Snippets*.

Known issues and warnings

The `\featherDurations` command only works with very short music snippets, and when numbers in the fraction are small.

2.4.5 Slashed beams

Slashed beams are printed by using the special stencil procedure `beam::slashed-stencil`. The slash may be printed at the left or right side of the beam and is further customizable by overrides of the details subproperties `over-beam-height`, `slash-slope`, `slash-side`, `slash-stem-fraction`, `slash-thickness`, and `slash-X-positions`. Note that those subproperties negotiate with each other to get a pleasing output, i.e., changing one of them may have impact on others.

```
mus = \*4 a16

{
  \override TextScript.rotation = #'(15 1 0)
  \override Beam.stencil = #beam::slashed-stencil
  \mus
  <>^"slash-side" %% default: LEFT
  \once \override Beam.details.slash-side = #RIGHT
  \mus
  <>^"over-beam-height" %% default: 0.75
  \once \override Beam.details.over-beam-height = #1.5
}
```

```

\mus
<>^"slash-slope" %% default: 2
\once \override Beam.details.slash-slope = #1.0
\mus
<>^"slash-stem-fraction" %% default: 0.3
\once \override Beam.details.slash-stem-fraction = #0.6
\mus
<>^"slash-thickness" %% default: 0.1
\once \override Beam.details.slash-thickness = #0.2
\mus
<>^"slash-X-positions" %% default: (-0.5 . 1)
\once \override Beam.details.slash-X-positions = #'(-1 . 2)
\mus
}

```



2.5 Bars

2.5.1 Bar lines

Bar lines are used to delimit measures and sections, and to indicate repetition. Normally, simple bar lines are automatically inserted into the printed output at places according to the current time signature. Various commands insert other kinds of bar lines automatically as part of their effect (see Section 2.5.2 [Automatic bar lines], page 130).

A bar line inserted automatically can be changed to another type with the `\bar` command:

```
\relative { e'4 d c2 \bar "!" }
```



The final note of a measure is not required to end on the automatically inserted bar line: the note is assumed to carry over into the next measure. But if a long sequence of such carry-over measures appears, the music can appear compressed or even flowing off the page. This is because automatic line breaks happen only at the end of complete measures, i.e., where all notes end before the end of a measure.

Note: An incorrect duration can inhibit line breaks, leading to a line of highly compressed music or music that flows off the page.


Line breaks are also permitted at manually inserted bar lines even within incomplete measures. To allow a line break without printing a bar line, use `\allowBreak`; see Section 28.1 [Line breaking], page 687.

This and other special bar lines may be inserted manually at any point. When they coincide with the end of a measure they replace the simple bar line which would have been inserted there automatically. When they do not coincide with the end of a measure the specified bar line is inserted at that point in the printed output.

Manual bar lines are purely visual. They do not affect any of the properties that a normal bar line would affect, such as measure numbers and accidentals. They do not affect the calculation and placement of subsequent automatic bar lines. When a manual bar line is placed where a normal bar line already exists, the effects of the original bar line are not altered.


Various single and double bar lines are available for manual insertion:

```
\relative {
  f'1 \bar "|"
  f1 \bar "."
  g1 \bar "||"      % see \section
  a1 \bar ".|"
  b1 \bar ".."
  c1 \bar "|.|"
  d1 \bar "|."      % see \fine
  e1
}
```




together with dotted and dashed bar lines:

```
\relative {
  f'1 \bar ";;"
  g1 \bar "!"
  a1
}
```




and various repeat bar lines:

```
\relative {
  f'1 \bar ".|:"
  g1 \bar ":\.:"
  a1 \bar ":\.|\.:"
  b1 \bar ":\.|\.:"
  c1 \bar ":\.|\.:"
  d1 \bar "[|:"
  e1 \bar ":\]|[:]"
  f1 \bar ":\]|]"
  g1 \bar ":\.|"
  a1
}
```




Ticks and short bar lines are also available; however, in the context of Gregorian chant, using `\divisioMinima` and `\divisioMaior` is preferable (see Section 17.4.4 [Divisiones], page 555).


```
f'1 \bar ""
g1 \bar ", "
a1
```



LilyPond supports Kievan notation and provides a special Kievan bar line:

```
f'1 \bar "k"
```




Further details of this notation are explained in Section 17.5 [Typesetting Kievan square notation], page 563.

There are various in-staff segno signs which differ in their behavior at line breaks:

```
\fixed c' {
  c4 4 4 4
  \bar "S"
  d4 4 4 4 \break
  \bar "S"
  e4 4 4 4
  \bar "S-|"
  f4 4 4 4 \break
  \bar "S-|"
  g4 4 4 4
  \bar "S-||"
  a4 4 4 4 \break
  \bar "S-||"
  b4 4 4 4
  \bar "S-S"
  c'4 4 4 4 \break
  \bar "S-S"
  d'1
}
```





Although the bar line types signifying repeats may be inserted manually they do not in themselves cause LilyPond to recognize a repeated section. Such repeated sections are better entered using the various repeat commands (see Chapter 4 [Repeats], page 188), which automatically print the appropriate bar lines, which can be customized (see Section 2.5.2 [Automatic bar lines], page 130).

In addition, you can specify ".|:-||", which is equivalent to ".|:" except at line breaks, where it gives a double bar line at the end of the line and a start repeat at the beginning of the next line.

```
\fixed c' {
  c4 4 4 4
  \bar ".|:"
  d4 4 4 4 \break
  \bar ".|:"
  e4 4 4 4
  \bar ".|:-|"
  f4 4 4 4 \break
  \bar ".|:-|"
  g4 4 4 4
  \bar ".|:-||"
  a4 4 4 4 \break
  \bar ".|:-||"
  b4 4 4 4
  \bar ".|:-|."
  c'4 4 4 4 \break
  \bar ".|:-|."
  d'4 4 4 4
}
```




There are various combinations of repeats with the segno sign:

```

\fixed c' {
  g,4 4 4 4
  \bar ":|.S"
  a,4 4 4 4 \break
  \bar ":|.S"
  b,4 4 4 4
  \bar ":|.S-S"
  c4 4 4 4 \break
  \bar ":|.S-S"
  d4 4 4 4
  \bar "S.|:-S"
  e4 4 4 4 \break
  \bar "S.|:-S"
  f4 4 4 4
  \bar "S.|:"
  g4 4 4 4 \break
  \bar "S.|:"
  a4 4 4 4
  \bar "S.|:-|"
  b4 4 4 4 \break
  \bar "S.|:-|"
  c'4 4 4 4
  \bar "S.|:-||"
  d'4 4 4 4 \break
  \bar "S.|:-||"
  e'4 4 4 4
  \bar ":|.S.|:"
  f'4 4 4 4 \break
  \bar ":|.S.|:"
  g'4 4 4 4
  \bar ":|.S.|:-S"
  a'4 4 4 4 \break
  \bar ":|.S.|:-S"
  b'1
}

```





Many of the repeat and segno bar lines above can be inserted automatically by `\repeat` commands (see Chapter 4 [Repeats], page 188).


New bar line types can be defined with `\defineBarLine`:

```
\defineBarLine bar-type #'(eol-bar bol-bar span-bar)
```

Briefly, the *bar-type* argument specifies the bar line glyph to use in the middle of a staff line, and also serves as the name by which this bar line type is referenced. The other arguments specify the bar line glyph to use at the end or beginning of a line, or in the span between multiple staves. Setting any of *eol-bar*, *bol-bar*, or *span-bar* to `#t` means to use the same bar line type specified by *bar-type* for the corresponding position. Setting them to `#f` means to print no bar line in the corresponding position.

In more detail, the *bar-type* argument is a string that serves a dual purpose: It specifies the bar line glyph to be printed when it occurs in the middle of a staff line; and it identifies the bar line object that can be invoked with `\bar bar-type`. It must have the form *midglyph* or *midglyph-annotation* (with a literal hyphen), where *annotation* is an arbitrary string, and *midglyph* is a string each of whose characters is the name of one of the predefined bar line elements listed below. The resulting bar line glyph to be used in the middle of a line is the concatenation of these elements. For example, a *bar-type* of either `" ; | "` or `" ; | -other "` specifies a compound bar line consisting of a dotted line (‘;’) paired with a solid line (‘|’):


```
\defineBarLine " ; | " #'(#t #t #t)
\defineBarLine " ; | -other " #'(#f #f #f)
\fixed c' {
  \bar " ; | " a1 \bar " ; | " b1 \bar " ; | -other " c'1 \bar " ; | -other "
}
```



The *annotation* (‘other’ in the second example above) is used to distinguish this bar type from others with the same *midglyph* but different line break or multi-staff behavior. (By convention, the string specified in *eol-bar* is often used as the annotation, so we might have named the second example `" ; | -f "`.)

The arguments *eol-bar* and *bol-bar* specify the bar line to be printed at the end of the line and beginning of the next line, when `\bar bar-type` occurs at a line break. *bol-bar* also applies when `\bar bar-type` is used at the beginning of a score. The format of these arguments is the same as that of *bar-type*. The string of bar line elements specifies the bar line glyph to print at the corresponding line position. In addition, either of these arguments can be `#t` as a shorthand for copying the value of *bar-type*; or `#f` to print no bar line. For example, all of the bar line types in this example print a dotted-solid line pair in the middle of a staff line, but have different behavior at ends or beginnings of lines:

```
% dotted-solid everywhere
\defineBarLine ";"| " #'( #t #t #t)
% solid-bold at EOL, solid-solid at BOL
\defineBarLine ";|-A" #'( "|" "." "||" #f )
% dotted-solid at EOL, nothing at BOL
\defineBarLine ";|-B" #'( #t #f #f )
% nothing at EOL, dotted-solid at BOL
\defineBarLine ";|-C" #'( #f #t #f )
\relative c'' {
  \bar ";"| " \textMark "\";|\"
  a1 \bar ";|-A"
  a1 \bar ";|-A" \textEndMark "\";|-A\" \break
  b1 \bar ";|-B" b \bar ";|-B" \textEndMark "\";|-B\" \break
  c1 \bar ";|-C" c \bar ";|-C" \textEndMark "\";|-C\" \break
  d1 \bar ";"| " \textEndMark "\";|\"
}
```




Note: The *eol-bar* or *bol-bar* strings may be names of previously defined bar line types. In a single staff context, it does not matter: the bar line elements in the given string are used regardless of any features of the defined bar line named by the string. In particular, any annotation is ignored in this context. However, in a multi-staff system it is important that *eol-bar* and *bol-bar* refer to previously defined bar line types (including *bar-type* itself), or be `#t` or `#f`. This is explained in more detail below.

The argument *span-bar* has an effect only in multi-staff systems (see Section 6.1.2 [Grouping staves], page 243), where it specifies what to print between grouped staves. This argument should be a string of bar line elements, of the same length as *bar-type* or shorter. (Extra elements are ignored.) Each element will be printed in line with the corresponding element of

bar-type. A space character (‘ ’) can be used to omit a bar line element but leave space for it. Setting *span-bar* to #t makes it the same as the mid-line glyph. Setting it to #f omits the span bar, and setting it to "" (an empty string) makes a zero-width span bar. Here are some examples:


```
\defineBarLine ";|!-A" #'(#t #t "!"")
\defineBarLine ";|!-B" #'(#t #t " !"")
\defineBarLine ";|!-C" #'(#t #t #t)
\defineBarLine ";|!-D" #'(#t #t #f)
\fixed c' {
  \new StaffGroup <<
    \new Staff {
      a1 \bar ";|!-A"
      b  \bar ";|!-B"
      c' \bar ";|!-C"
      d' \bar ";|!-D"
      e'
    }
    \new Staff {
      a1 b c' d' e'
    }
  >>
}
```



At line breaks, instead of using *span-bar*, the bar line types referenced by *eol-bar* and *bol-bar* are used to determine the span bar to print. In the context of a staff group, if *eol-bar* and *bol-bar* do not refer to defined bar line types, LilyPond issues a warning, and no span bar is printed at line breaks. It is allowed for *eol-bar* or *bol-bar* to be #f, in which case no span bar is printed at the corresponding line position. These arguments can also be #t, or equivalently, equal to *bar-type*, in which case the current *span-bar* does determine the span bar to print at the corresponding line position:

```
\defineBarLine "!"-t" #'(#t #t #t)
\defineBarLine "!"-t" #'(#t #t #t)
\defineBarLine ";|!-bad" #'("!" "!" #t) % fails at line breaks
\defineBarLine ";|!-good" #'("!"-t" "!"-t" #t)
\relative c'' {
  \new StaffGroup <<
    \new Staff {
      \bar ";|!-good"
      a1 \bar ";|!-good"
      % \bar ";|!-bad" % "WARNING: No span bar glyph defined..."
      b1 \bar ";|!-good"
    }
    \new Staff {
      a1 b1
    }
  >>
}
```

```
>>
}
```




Note: If *span-bar* is a string, it should contain *only* bar line elements, or space (' '), and not an annotation such as allowed in the other arguments. If *span-bar* contains an annotation, LilyPond issues a warning. The one exception is that it may be equal to *bar-type*, in which case no warning is issued even if *bar-type* includes an annotation.

All the available bar line elements are shown below. Most also have predefined bar types (for arguments to `\bar`) that reference them individually. Some elements are primarily intended to be combined with others and so do not have predefined individual bar types.

```
\defineBarLine ":" #'(#f #t #f)
\defineBarLine "=" #'(#t #f #t)
\defineBarLine "[" #'(#f #t #f)
\defineBarLine "]" #'(#t #f #f)
```

```
\new Staff {
  s1 \bar ""
  s1 \bar ", "
  s1 \bar "| "
  s1 \bar ". "
  s1 \bar "! "
  s1 \bar "; "
  s1 \bar ": "
  s1 \bar "k"
  s1 \bar "S"
  s1 \bar "="
  s1 \bar "["
  s1 \bar "]"
  s1 \bar ""
}
```



The "=" bar line provides a double span bar line for use in combination with the segno sign. Using it as a stand-alone double thin bar line is not recommended; `\bar "| |"` is preferred.

If additional elements are needed, LilyPond provides a simple way to define them. For more information on modifying or adding bar lines, see file `scm/bar-line.scm`.

In scores with many staves, a `\bar` command in one staff is automatically applied to all staves. The resulting bar lines are connected between different staves of a `StaffGroup`, `PianoStaff`, or `GrandStaff`.

```

<<
  \new StaffGroup <<
    \new Staff \relative {
      e'4 d
      \bar "||"
      f4 e
    }
    \new Staff \relative { \clef bass c'4 g e g }
  >>
  \new Staff \relative { \clef bass c'2 c2 }
>>

```



The bar type used for automatically inserted measure bar lines is `"|"`. This may be changed at any time with `\set Timing.measureBarType = bartype`.

It is also possible to set different types of bar lines in a score with multiple staves, using one of the possible commands or properties explained below (see Section 2.5.2 [Automatic bar lines], page 130). Of course this may lead to a mismatch of bar lines and span bars, due to their different width.

Usually bar lines are left-aligned (disregarding colon signs as in repeat bar lines). To get them right-aligned the command


```
[\once] \override Context.BarLine.right-justified = ##t
```

needs to be applied, where *Context* is a context suitable for multiple staves, like *Score*, *StaffGroup*, *Grandstaff*, etc.

```

\new StaffGroup
<<
  \new Staff = "a" {
    b1 b b
    <<
      { \textMark "BarLines right-justified" b b }
      \new Staff \with { alignAboveContext = "b" }
      {
        \override StaffGroup.BarLine.right-justified = ##t
        b
        \section
      }
    >>
  }
  \new Staff = "b" { b \section }
  \new Staff = "c" { b b \section b b b \section }
>>

```

After a line-break bar lines are never right-aligned. For mid-line and right-aligned bar lines the anchor-point (used to align `BarNumber`, `RehearsalMark`, etc.) moves accordingly.

See also

Notation Reference: Section 28.1 [Line breaking], page 687, Chapter 4 [Repeats], page 188, Section 6.1.2 [Grouping staves], page 243.

Installed Files: `scm/bar-line.scm`.

Snippets: Section “Rhythms” in *Snippets*.

Internals Reference: Section “BarLine” in *Internals Reference* (created at Staff level), Section “SpanBar” in *Internals Reference* (across staves), Section “Timing_translator” in *Internals Reference* (for Timing properties).

2.5.2 Automatic bar lines

Various commands other than `\bar` can also create bar lines as part of their effect. The bar lines created in these cases can be changed by setting context properties. If a property is set to `'()` or is unset, it is ignored; otherwise, the value must be a predefined bar type or one previously defined with the `\defineBarLine` command (see Section 2.5.1 [Bar lines], page 120).

Multiple reasons for creating different automatic bar lines may apply at the same time. Conflicts are resolved in part by providing properties for predetermined combinations and in part by a priority scheme. The table below presents the available properties in order of increasing priority.

`underlyingRepeatBarType`

Used at points of repetition or departure where no bar line would otherwise appear. This is expected when repeated sections are not aligned to measures. Several commands employ this bar type: `\codaMark`, `\inStaffSegno`, `\repeat segno`, `\repeat volta`, and `\segnoMark`.

`caesuraType` `underlying-bar-line`

Used at `\caesura`; see Section 9.7.4 [Phrase bar lines in hymn tunes], page 409.

`submeasureBarType`

Used at submeasure boundaries specified by `submeasureStructure`, when `\submeasureBarsOn` allows; see Section 2.3.2 [Time signature], page 79.

`measureBarType`

Used at a measure boundary.

`caesuraType bar-line`

Used at `\caesura`; see Section 9.7.4 [Phrase bar lines in hymn tunes], page 409.

`sectionBarType`

Used at a section break created by `\section`.

`fineBarType`

Used at `\fine`.

`doubleRepeatBarType`

`doubleRepeatSegnoBarType`

`endRepeatBarType`

`endRepeatSegnoBarType`

`fineSegnoBarType`

`fineStartRepeatSegnoBarType`

`segnoBarType`

`startRepeatBarType`

`startRepeatSegnoBarType`

Only one of these bar types is used at a time; which one is used depends on the structure of the piece.


Properties with `startRepeat` or `endRepeat` in the name are used at the start or end of a repeated section created by `\repeat volta`, and properties with `doubleRepeat` in the name are used where the end of one repeated section and the start of another coincide.

Properties with `segno` in the name are used at an in-staff segno, which can be created by `\repeat segno` or `\segnoMark` when the `segnoStyle` property is set to `bar-line`, or created by `\inStaffSegno`.

Properties with `fine` in the name are used at `\fine`.

Priority applies independently to beginning-, middle-, and end-of-line bar lines, allowing a lower-priority bar line to appear where higher-priority bar types have no glyphs defined (see Section 2.5.1 [Bar lines], page 120).

```
\fixed c' {
  c1 \section \break
  \repeat volta 2 d1
}
```




Selected snippets

Setting the double repeat default for volte

There are different double repeat styles for volte that can be selected using the context property `doubleRepeatBarType`.

```
\relative c' {
  \repeat volta 2 { c1 }
  \set Score.doubleRepeatBarType = "...:"
  \repeat volta 2 { c1 }
  \set Score.doubleRepeatBarType = ":\.|\.:"
  \repeat volta 2 { c1 }
  \set Score.doubleRepeatBarType = ":\.|\.:"
  \repeat volta 2 { c1 }
}
```



See also

Notation Reference: Section 2.5.1 [Bar lines], page 120, Chapter 4 [Repeats], page 188.


Snippets: Section “Rhythms” in *Snippets*.

Internals Reference: Section “Repeat_acknowledge_engraver” in *Internals Reference*.

2.5.3 Bar numbers

Bar numbers are typeset by default at the start of every line except the first line. The number itself is stored in the `currentBarNumber` property, which is normally updated automatically for every measure. It may also be set manually:

```
\relative c' {
  c1 c c c
  \break
  \set Score.currentBarNumber = 50
  c1 c c c
}
```




The default behavior of only printing bar numbers at the start of every line can be changed through the `break-visibility` property of `BarNumber`. This takes three values which may be set to `#t` or `#f` to specify whether the corresponding bar number is visible or not. The order of the three values is end of line visible, middle of line visible, beginning of line visible. In the following example bar numbers are printed at all possible places:

```

\relative c' {
  \override Score.BarNumber.break-visibility = ##(#t #t #t)
  \set Score.currentBarNumber = 11
  c1 | c | c | c |
  \break
  c1 | c | c | c |
}

```



Selected snippets

Printing the bar number for the first measure


By default, the first bar number in a score is suppressed if it is less than or equal to 1. This can be changed by setting the `barNumberVisibility` context property to value `all-bar-numbers-visible`.

```

\paper {
  line-width = 50\mm
}

\relative c' {
  \set Score.barNumberVisibility = #all-bar-numbers-visible
  c1 | d | e | f \break
  g1 | e | d | c
}

```




Printing bar numbers at regular intervals

By setting the `barNumberVisibility` property, bar numbers can be printed at regular intervals. Here the bar numbers are printed every two measures except at the end of the line.

```

\relative c' {
  \override Score.BarNumber.break-visibility = #end-of-line-invisible
  \set Score.currentBarNumber = 11
  % Print a bar number every second measure
  \set Score.barNumberVisibility = #(every-nth-bar-number-visible 2)
  c1 | c | c | c | c
  \break
  c1 | c | c | c | c
}

```




Printing bar numbers with changing regular intervals

Using the `set-bar-number-visibility` context function, bar number intervals can be changed.

```

\relative c' {
  \override Score.BarNumber.break-visibility = #end-of-line-invisible
  \context Score \applyContext #(set-bar-number-visibility 4)
  \*10 c'1
  \context Score \applyContext #(set-bar-number-visibility 2)
  \*10 c
}

```



Printing bar numbers for broken measures

By default, a bar number of a broken measure is not repeated at the beginning of the new line. Use `first-bar-number-invisible-save-broken-bars` for `barNumberVisibility` to get a parenthesized BarNumber there.

```


\layout {
  \context {
    \Score
    barNumberVisibility = #first-bar-number-invisible-save-broken-bars
    \override BarNumber.break-visibility = ##(#f #t #t)
  }
}

```

```

\relative c' {
  c1 | d | e | f2 \break
  fis2 | g1 | e2 \break
  <>^"reenabled default"
  % back to default -
  % \unset Score.barNumberVisibility would do so as well
  \set Score.barNumberVisibility =
    #first-bar-number-invisible-and-no-parenthesized-bar-numbers
  es2 | d1 | c
}

```



Printing bar numbers using modulo-bar-number-visible

If the remainder of the division of the current bar number by the first argument of `modulo-bar-number-visible` equals its second argument, print a bar number.

This is useful to print the bar number at certain distances. Some examples:

- `(modulo-bar-number-visible 3 2)` → prints 2, 5, 8, ...
- `(modulo-bar-number-visible 4 2)` → prints 2, 6, 10, ...
- `(modulo-bar-number-visible 2 1)` → prints 3, 5, 7, ...
- `(modulo-bar-number-visible 5 0)` → prints 5, 10, 15, ...

```


\layout {
  \context {
    \Score
    \override BarNumber.break-visibility = ##(#f #t #t)
    barNumberVisibility = #(modulo-bar-number-visible 5 0)
  }
}

```

```

\relative c' {
  c1 | d | e | f \break
  g1 | e | d | c
}

```



Printing bar numbers inside boxes or circles

Bar numbers can also be printed inside boxes or circles.

```
\relative c' {
  % Center bar numbers except at the beginning of a staff.
  \override Score.BarNumber.self-alignment-X =
    #(break-alignment-list CENTER CENTER 0.3)


  % Prevent bar numbers at the end of a line and permit them elsewhere.
  \override Score.BarNumber.break-visibility = #end-of-line-invisible

  \set Score.barNumberVisibility = #(every-nth-bar-number-visible 4)

  % Increase the size of the bar number by 2.
  \override Score.BarNumber.font-size = 2

  % Draw a circle round the following bar number(s).
  \override Score.BarNumber.stencil
    = #(make-stencil-circler 0.1 0.25 ly:text-interface::print)
  \*7 c1 \break

  % Draw a box round the following bar number(s).
  \override Score.BarNumber.stencil
    = #(make-stencil-boxer 0.1 0.25 ly:text-interface::print)
  \*7 c1 \bar "|."
}
```



Alternative bar numbering

Setting the `alternativeNumberingStyle` context property, two additional methods are available for enumerating bar numbers in repeats.

```
music = \relative c' {
  \repeat volta 3 {
    c4 d e f |
    \alternative {
      \volta 1 { c4 d e f | c2 d \break }
      \volta 2 { f4 g a b | f4 g a b | f2 a | \break }
      \volta 3 { c4 d e f | c2 d } } }
  c1 \bar "|."
}

{
  \textMark \markup \large "default"
  \music
}
```

```

}

{
  \textMark \markup \large \typewriter "numbers"
  \set Score.alternativeNumberingStyle = #'numbers
  \music
}

{
  \textMark \markup \large \typewriter "numbers-with-letters"
  \set Score.alternativeNumberingStyle = #'numbers-with-letters
  \music
}

\layout {
  \context {
    \Score
    \override TextMark.Y-offset = #5
  }
}

```

default

4

7

numbers

2

2

numbers-with-letters

1.



Aligning bar numbers


The default alignment of bar numbers depends on its position: at the beginning of a staff, bar numbers are right-aligned; at all other positions, they are left-aligned. Using Scheme function `break-alignment-list`, this can be changed; the three arguments of this function are the alignment for end-of-line, middle-of-line, and start-of-line position (in this order).

```
\relative c' {
  \set Score.currentBarNumber = 111
  \override Score.BarNumber.break-visibility = #all-visible
  % Increase the size of the bar number by 2
  \override Score.BarNumber.font-size = 2
  % Print a bar number every second measure
  \set Score.barNumberVisibility = #(every-nth-bar-number-visible 2)

  c1 | c1 | c1 | \break
  c1 | c1 | c1 | \break

  \override Score.BarNumber.self-alignment-X =
    #(break-alignment-list CENTER RIGHT CENTER)
  c1 | c1 | c1 | \break
  c1 | c1 | c1 |
}

\paper {
  line-width = 70\mm
}
```



Removing bar numbers from a score

Bar numbers can be removed entirely by removing the `Bar_number_engraver` from the `Score` context.

```
\layout {
  \context {
    \Score
    \omit BarNumber
    % or:
    % \remove "Bar_number_engraver"
  }
}

\relative c' {
  c4 c c c \break
  c4 c c c
}
```



Measure-centered bar numbers

For film scores, a common convention is to center bar numbers within their measure. This is achieved through setting the `centerBarNumbers` context property to `#t`. When this is used, the type of the bar number grobs is `CenteredBarNumber` rather than `BarNumber`.

This example demonstrates a number of settings: the centered bar numbers are boxed and placed below the staves.

```
\layout {
  \context {
    \Score
    centerBarNumbers = ##t
    barNumberVisibility = #all-bar-numbers-visible
    \override CenteredBarNumber.stencil
      = #(make-stencil-boxer 0.1 0.25 ly:text-interface::print)
    \override CenteredBarNumberLineSpanner.direction = #DOWN
  }
}

\new StaffGroup <<
  \new Staff \relative c' {
    d4-. f8( e d4) bes'-> |
    d,-. f8( e d4) cis'-> |
    g-. f8( d e4) g-> |
    a,1-> |
  }
  \new Staff \relative c {
    \clef bass
```

```

d4 f8 e d2~ |
4 f8 e d2~ |
4 4 2 |
a1 |
}
>>

```



See also

Snippets: Section “Rhythms” in *Snippets*.

Internals Reference: Section “BarNumber” in *Internals Reference*, Section “Centered-BarNumber” in *Internals Reference*, Section “CenteredBarNumberLineSpanner” in *Internals Reference*, Section “Bar_number-engraver” in *Internals Reference*, Section “Centered_bar_number_align-engraver” in *Internals Reference*.

Known issues and warnings

Bar numbers may collide with the top of the StaffGroup bracket, if there is one. To solve this, the padding property of BarNumber can be used to position the number correctly. See Section “StaffGroup” in *Internals Reference* and Section “BarNumber” in *Internals Reference* for more.

2.5.4 Bar and bar number checks

Bar checks help detect errors in the entered durations. A bar check may be entered using the bar symbol, |, at any place where a bar line is expected to fall. If bar check lines are encountered at other places, a list of warnings is printed in the log file, showing the line numbers and lines in which the bar checks failed. In the next example, the second bar check will signal an error.

```
\time 3/4 c2 e4 | g2 |
```

An incorrect duration can result in a completely garbled score, especially if the score is polyphonic, so a good place to start correcting input is by scanning for failed bar checks and incorrect durations.

If successive bar checks are off by the same musical interval, only the first warning message is displayed. This allows the warning to focus on the source of the timing error.

Bar checks can also be inserted in lyrics:

```

\lyricmode {
  \time 2/4
  Twin -- kle | Twin -- kle |
}

```

Note that bar check marks in lyrics are evaluated at the musical moment when the syllable *following* the check mark is processed. If the lyrics are associated with the notes of a voice which has a rest at the beginning of a bar, then no syllable can be located at the start of that bar and a warning will be issued if a bar check mark is placed in the lyrics at that position.

It is also possible to redefine the action taken when a bar check or pipe symbol, |, is encountered in the input, so that it does something other than a bar check. This is done by assigning

a music expression to "|". In the following example | is set to insert a double bar line wherever it appears in the input, rather than checking for end of bar.

```
"|" = \bar "||"
{
  c'2 c' |
  c'2 c'
  c'2 | c'
  c'2 c'
}
```



When copying large pieces of music, it can be helpful to check that the LilyPond bar number corresponds to the original that you are entering from. This can be checked with `\barNumberCheck`, for example,

```
\barNumberCheck 123
```

will print a warning if the `currentBarNumber` is not 123 when it is processed.


See also

Snippets: Section “Rhythms” in *Snippets*.

2.5.5 Rehearsal marks


To print a rehearsal mark, use the `\mark` command.

```
\relative c'' {
  c1 \mark \default
  c1 \mark \default
  c1 \mark \default
  c1 \mark \default
}
```




The mark is incremented automatically if you use `\mark \default`, but you can also use an integer argument to set the mark manually. The value to use is stored in the property `rehearsalMark`.

```
\relative c'' {
  c1 \mark \default
  c1 \mark \default
  c1 \mark 8
  c1 \mark \default
  c1 \mark \default
}
```




The letter ‘I’ is skipped in accordance with engraving traditions. If you wish to include the letter ‘I’, then use one of the following commands, depending on which style of rehearsal mark you want (letters only, letters in a hollow box, or letters in a hollow circle).

```
\set Score.rehearsalMarkFormatter = #format-mark-alphabet
\set Score.rehearsalMarkFormatter = #format-mark-box-alphabet
\set Score.rehearsalMarkFormatter = #format-mark-circle-alphabet
\relative c'' {
  \set Score.rehearsalMarkFormatter = #format-mark-box-alphabet
  c1 \mark \default
  c1 \mark \default
  c1 \mark 8
  c1 \mark \default
  c1 \mark \default
}
```



The style is defined by the property `rehearsalMarkFormatter`. It is a function taking the current mark (an integer) and the current context as argument. It should return a markup object. In the following example, `rehearsalMarkFormatter` is set to a predefined procedure. After a few measures, it is set to a procedure that produces a boxed number.

```
\relative c'' {
  \set Score.rehearsalMarkFormatter = #format-mark-numbers
  c1 \mark \default
  c1 \mark \default
  \set Score.rehearsalMarkFormatter = #format-mark-box-numbers
  c1 \mark \default
  \set Score.rehearsalMarkFormatter = #format-mark-circle-numbers
  c1 \mark \default
  \set Score.rehearsalMarkFormatter = #format-mark-circle-letters
  c1
}
```



The file `scm/translation-functions.scm` contains the definitions of `format-mark-letters` (the default format), `format-mark-box-letters`, `format-mark-numbers`, and `format-mark-box-numbers`. These can be used as inspiration for other formatting functions.

You may use `format-mark-barnumbers`, `format-mark-box-barnumbers`, and `format-mark-circle-barnumbers` to get bar numbers instead of incremented numbers or letters.

For common tweaks to the positioning of rehearsal marks, see Section 8.2 [Formatting text], page 319. For more precise control, consider `break-alignable-interface` (see Section 36.9 [Aligning objects], page 789).


The file `scm/translation-functions.scm` contains the definitions of `format-mark-numbers` and `format-mark-letters`. They can be used as inspiration for other formatting functions.

Selected snippets

Printing marks on every staff

Although rehearsal and text marks are normally only printed above the topmost staff, they may also be printed on every staff.

```
\score {
  <<
    \new Staff { \mark \default c'1 \textMark "molto" c' }
    \new Staff { \mark \default c'1 \textMark "molto" c' }
  >>
  \layout {
    \context {
      \Score
      \remove Mark_engraver
      \remove Text_mark_engraver
      \remove Staff_collecting_engraver
    }
    \context {
      \Staff
      \consists Mark_engraver
      \consists Text_mark_engraver
      \consists Staff_collecting_engraver
    }
  }
}
```



See also

Notation Reference: Section B.8 [The Emmmentaler font], page 905, Section 8.2 [Formatting text], page 319, Section 36.9 [Aligning objects], page 789, Section 8.2.5 [Music notation inside markup], page 334, Section 2.3.3 [Metronome marks], page 86, Section 8.1.4 [Section labels], page 312.

Installed Files: scm/translation-functions.scm.

Snippets: Section “Rhythms” in *Snippets*.

Internals Reference: Section “AdHocMarkEvent” in *Internals Reference*, Section “RehearsalMark” in *Internals Reference*, Section “RehearsalMarkEvent” in *Internals Reference*.

2.5.6 Measure counts

Measure counts are a way to number consecutive measures, for example as an aid for musicians to count measures in written-out repeats. Using this feature requires adding the `Measure_counter_engraver` to a context type, usually `Staff` or `Score`.

```
\layout {
  \context {
    \Staff
    \consists Measure_counter_engraver
  }
}
```

```
\relative c' {
  \time 6/8
  \key e \minor
  r4 a8 b c dis
  \startMeasureCount
  \*3 {
    e8 b e g8. fis32 e dis8
  }
  \stopMeasureCount
  b'4. r
}
```



Broken measures are numbered in parentheses.

```
\layout {
  \context {
    \Staff
    \consists Measure_counter_engraver
  }
}
```

```
\relative c' {
  \time 6/8
  \key e \minor
  r4 a8 b c dis
  \startMeasureCount
  e8 b e g8. fis32 e dis8
  e8 b e \break g8. fis32 e dis8
  e8 b e g8. fis32 e dis8
  \stopMeasureCount
  b'4. r
}
```





Compressed multi-measure rests receive special treatment: the full measure range is shown.

```
\layout {
  \context {
    \Staff
    \consists Measure_counter_engraver
  }
  \context {
    \Voice
    \override MultiMeasureRestNumber.direction = #DOWN
  }
}

\compressMMRests {
  \key e \minor
  \startMeasureCount
  \new CueVoice {
    b4.( e'8) b8 r e' r
  }
  R1*2
  \stopMeasureCount
  g'2\> fis'2\!
}
```



Measure counters honor alternative numbering styles. If the style is numbers-with-letters, they render best with a textual font.

```
\layout {
  \context {
    \Score
    alternativeNumberingStyle = #'numbers-with-letters
  }
  \context {
    \Staff
    \consists Measure_counter_engraver
    \override MeasureCounter.Y-offset = 6
    \override MeasureCounter.font-encoding = #'latin1
    \override MeasureCounter.font-size = 1
  }
}


\relative c' {
  \startMeasureCount
  \repeat volta 2 {
    c8 d e f c d e f
  }
}
```



```

\alternative {
  { e4 d c b }
  { g'4 g c2 }
}
\bar " | ."
\stopMeasureCount
}

```



Predefined commands

`\startMeasureCount`, `\stopMeasureCount`.

See also

Notation Reference: Section 33.4 [Modifying context plug-ins], page 743, Section 6.3.4 [Compressing empty measures], page 273, Chapter 28 [Breaks], page 687, Section 2.5.3 [Bar numbers], page 132.

Internals Reference: Section “Measure_counter_engraver” in *Internals Reference*, Section “MeasureCounter” in *Internals Reference*, Section “measure-counter-interface” in *Internals Reference*.

2.5.7 Section divisions

The `\section` command marks a point where one section of music ends and another begins. It does not have to be followed by more music: it may also be used to emphasize that the written end of the music is not the end of the piece, such as at a *D.C.* instruction or where one movement continues into the next without a break. `\section` normally creates a double bar line, but its effect can depend on other notation, e.g., repeat bar lines.


The `\fine` command ends the piece, normally with a final bar line. It is not limited to use at the written end of the music: it may also appear inside `\repeat` (see Section 4.1.5 [Al-fine repeats], page 194).

A section can optionally be named with `\sectionLabel` (see Section 8.1.4 [Section labels], page 312).

```

\fixed c' {
  f1
  \section
  \sectionLabel "Refrain"
  g1
  a1
  \fine
}

```



For details on interactions of `\fine` and `\section` bar lines with other types of bar lines, and options for changing their appearance, see Section 2.5.2 [Automatic bar lines], page 130.

See also

Music Glossary: Section “fine” in *Music Glossary*.

Notation Reference: Section 2.5.2 [Automatic bar lines], page 130, Section 17.4.4 [Divisiones], page 555, Section 4.1.5 [Al-fine repeats], page 194, Section 8.1.4 [Section labels], page 312.

Internals Reference: Section “FineEvent” in *Internals Reference*, Section “SectionEvent” in *Internals Reference*.

2.6 Special rhythmic concerns

2.6.1 Grace notes

Grace notes are musical ornaments, printed in a smaller font, that take up no additional logical time in a measure.

```
\relative {
  c' '4 \grace b16 a4(
  \grace { b16 c16 } a2)
}
```



There are three other types of grace notes possible; the *acciaccatura* – an unmeasured grace note indicated by a slurred note with a slashed stem – and the *appoggiatura*, which takes a fixed fraction of the main note it is attached to and prints without the slash. It is also possible to write a grace note with a slashed stem, like the *acciaccatura* but without the slur, so as to place it between notes that are slurred themselves, using the `\slashedGrace` function.

```
\relative {
  \acciaccatura d' '8 c4
  \appoggiatura e8 d4
  \acciaccatura { g16 f } e2
  \slashedGrace a,8 g4
  \slashedGrace b16 a4(
  \slashedGrace b8 a2)
}
```




The placement of grace notes is synchronized between different staves. In the following example, there are two sixteenth grace notes for every eighth grace note

```
<<
  \new Staff \relative { e''2 \grace { c16 d e f } e2 }
  \new Staff \relative { c''2 \grace { g8 b } c2 }
>>
```



If you want to end a note with a grace, use the `\afterGrace` command. It takes two arguments: the main note, and the grace notes following the main note.

```
\relative { c''1 \afterGrace d1 { c16[ d] } c1 }
```



This will place the grace notes *after* the start of the main note. The point of time where the grace notes are placed is a given fraction of the main note's duration. The default setting of

```
afterGraceFraction = 3/4
```

may be redefined at top level. Individual `\afterGrace` commands may have the fraction specified right after the command itself instead.

The following example shows the results from setting with the default space, setting it at 15/16, and finally at 1/2 of the main note.

```
<<
  \new Staff \relative {
    c''1 \afterGrace d1 { c16[ d] } c1
  }
  \new Staff \relative {
    c''1 \afterGrace 15/16 d1 { c16[ d] } c1
  }
  \new Staff \relative {
    c''1 \afterGrace 1/2 d1 { c16[ d] } c1
  }
>>
```



The effect of `\afterGrace` can also be achieved using spacers. The following example places the grace note after a space lasting 7/8 of the main note.

```

\new Voice \relative {
  <<
    { d' '1^\trill_( }
    { s2 s4. \grace { c16 d } }
  >>
  c1)
}

```



A `\grace` music expression will introduce special typesetting settings, for example, to produce smaller type, and set directions. Hence, when introducing layout tweaks to override the special settings, they should be placed inside the grace expression. The overrides should also be reverted inside the grace expression. Here, the grace note's default stem direction is overridden and then reverted.

```

\new Voice \relative {
  \acciaccatura {
    \stemDown
    f' '16->
    \stemNeutral
  }
  g4 e c2
}

```



Selected snippets

Using grace note slashes with normal heads

The slash through the stem found in acciaccaturas can be applied in other situations.

```

\relative c' {
  \override Flag.stroke-style = "grace"
  c8( d2) e8( f4)
}

```



Tweaking grace layout within music

The appearance of grace expressions can be changed by using the functions `add-grace-property` and `remove-grace-property`.

The following example undefines the `direction` property of Stem grobs for this grace so that stems do not always point up, and changes the default note heads to crosses.

```

\relative c'' {
  \new Staff {
    $(remove-grace-property 'Voice 'Stem 'direction)
    $(add-grace-property 'Voice 'NoteHead 'style 'cross)
    \new Voice {
      \acciaccatura { f16 } g4
      \grace { d16 e } f4
      \appoggiatura { f,32 g a } e2
    }
  }
}

```



Redefining grace note global defaults

The global defaults for grace notes are stored in the following identifiers.

```

startGraceMusic
stopGraceMusic
startAcciaccaturaMusic
stopAcciaccaturaMusic
startAppoggiaturaMusic
stopAppoggiaturaMusic

```

They are defined in file `ly/grace-init.ly`. By redefining them other effects may be obtained.

```

startAcciaccaturaMusic = {
  <>(
    \override Flag.stroke-style = "grace"
    \slurDashed
  )
}

```

```

stopAcciaccaturaMusic = {
  \revert Flag.stroke-style
  \slurSolid
  <>
}

```

```

\relative c'' {
  \acciaccatura d8 c1
}

```



Positioning grace notes with floating space

Setting the property `strict-grace-spacing` makes the musical columns for grace notes ‘floating’, i.e., decoupled from the non-grace notes: first the normal notes are spaced, then the (musical columns of the) graces are put left of the musical columns for the main notes.

Due to Issue #6876 (<https://gitlab.com/lilypond/lilypond/-/issues/6876>), however, accidentals are ignored if this property is set. This snippet gives a workaround to circumvent the problem.

Another unfortunate side effect of this property is that LilyPond does not check whether there is enough horizontal space for grace notes (this is tracked as Issue #2630 (<https://gitlab.com/lilypond/lilypond/-/issues/2630>)). You have to make sure that enough space is available, for example, by using `\newSpacingSection` together with a proper value for the `base-shortest-duration` of the `SpacingSpanner` grob.


```

shiftedGrace =
#(define-music-function (offset music) (number? ly:music?)
  #{
    \override NoteHead.X-offset = #(- offset 0.85)
    \override Stem.X-offset = #offset
    \grace { $music }
    \revert NoteHead.X-offset
    \revert Stem.X-offset
  #})

\relative c'' <<
  { g4 \shiftedGrace #-1.3 a32 \shiftedGrace #-0.5 { bes c d } es4 }
  { f,32 e d c f e d c f4 }
>>

\layout {
  \context {
    \Score
    \override SpacingSpanner.strict-grace-spacing = ##t
  }
}

```



See also

Music Glossary: Section “grace notes” in *Music Glossary*, Section “acciaccatura” in *Music Glossary*, Section “appoggiatura” in *Music Glossary*.

Notation Reference: Section 2.1.3 [Scaling durations], page 61, Section 2.4.3 [Manual beams], page 114.

Installed Files: `ly/grace-init.ly`.

Snippets: Section “Rhythms” in *Snippets*.

Internals Reference: Section “GraceMusic” in *Internals Reference*, Section “Grace_beam_engraver” in *Internals Reference*, Section “Grace_auto_beam_engraver” in *Internals Reference*, Section “Grace_engraver” in *Internals Reference*, Section “Grace_spacing_engraver” in *Internals Reference*.

Known issues and warnings

A multi-note beamed *acciaccatura* is printed without a slash, and looks exactly the same as a multi-note beamed *appoggiatura*.

Grace note synchronization can also lead to surprises. Staff notation, such as key signatures, bar lines, etc., are also synchronized. Take care when you mix staves with grace notes and staves without, for example,

```
<<
  \new Staff \relative { e''4 \section \grace c16 d2. }
  \new Staff \relative { c''4 \section d2. }
>>
```



This can be remedied by inserting grace skips of the corresponding durations in the other staves. For the above example

```
<<
  \new Staff \relative { e''4 \section \grace c16 d2. }
  \new Staff \relative { c''4 \section \grace s16 d2. }
>>
```



Please make sure that you use the `\grace` command for the spacer part, even if the visual part uses `\acciaccatura` or `\appoggiatura` because otherwise an ugly slur fragment will be printed, connecting the invisible grace note with the following note.

Grace sections should only be used within sequential music expressions. Nesting or juxtaposing grace sections is not supported, and might produce crashes or other errors.

Each grace note in MIDI output has a length of 1/4 of its actual duration. If the combined length of the grace notes is greater than the length of the preceding note a “Going back in MIDI time” error will be generated. Either make the grace notes shorter in duration, for example:

```
c'8 \acciaccatura { c'8[ d' e' f' g'] }
```

becomes:

```
c'8 \acciaccatura { c'16[ d' e' f' g'] }
```

Or explicitly change the musical duration:

```
c'8 \acciaccatura { \scaleDurations 1/2 { c'8[ d' e' f' g'] } }
```

See Section 2.1.3 [Scaling durations], page 61.

2.6.2 Aligning to cadenzas

In an orchestral context, cadenzas present a special problem: when constructing a score that includes a measured cadenza or other solo passage, all other instruments should skip just as many notes as the length of the cadenza, otherwise they will start too soon or too late.


One solution to this problem is to use the functions `mmrest-of-length` and `skip-of-length`. These Scheme functions take a defined piece of music as an argument and generate a multi-measure rest or `\skip` exactly as long as the piece.

```

MyCadenza = \relative {
  c'4 d8 e f g g4
  f2 g4 g
}

\new GrandStaff <<
  \new Staff {
    \MyCadenza c'1
    \MyCadenza c'1
  }
  \new Staff {
    #(mmrest-of-length MyCadenza)
    c'1
    #(skip-of-length MyCadenza)
    c'1
  }
>>

```



Another solution is to use the `\skip` command.

```

MyCadenza = \fixed c' {
  \repeat volta 2 {
    d8 e f g g4 f4
  }
}

```

```

music = <<
  \new Staff {
    \MyCadenza
    c'1
  }
  \new Staff {
    \skip \MyCadenza
    c'1
  }
>>

```

```

\unfoldRepeats \music

```



See also

Music Glossary: Section “cadenza” in *Music Glossary*.

Snippets: Section “Rhythms” in *Snippets*.

3 Expressive marks

RONDO
Allegro

This section lists various expressive marks that can be created in a score.

3.1 Expressive marks attached to notes

This section explains how to create expressive marks that are attached to notes: articulations, ornamentations, and dynamics. Methods to create new dynamic markings are also discussed.

3.1.1 Articulations and ornamentations

A variety of symbols that denote articulations, ornamentations, and other performance indications can be attached to a note using this syntax:

`note\name`

The possible values for *name* are listed in Section B.13 [List of articulations], page 927. For example:

```
\relative {
  c'4\staccato c\mordent b2\turn
  c1\fermata
}
```

Some of these articulations have shorthands for easier entry. Shorthands are appended to the note name, and their syntax consists of a dash – followed by a symbol signifying the articulation. Predefined shorthands exist for *marcato*, *stopped*, *tenuto*, *staccatissimo*, *accent*, *staccato*, and *portato*. Their corresponding output appears as follows:

```
\relative {
  c'4-^ c-+ c-- c-!
  c4-> c-. c2-_
}
```



The rules for the default placement of articulations are defined in `scm/script.scm`. Articulations and ornamentations may be manually placed above or below the staff; see Section 36.1 [Direction and placement], page 772.


The *bachschleifer* is positioned to the left of the `NoteHead`. This ornament may have ledger lines.

```
{
  \autoBeamOff
  b'8 g' '\bachschleifer
  e' c' '\bachschleifer
}
```



It is also possible to position common articulations and ornamentations to the left or right of a note head by overriding their `side-axis` and, if necessary, the `direction` property. The convenience functions `\atLeft` or `\atRight` take care of this.

```
{
  \set fingeringOrientations = #'(left)
  \set stringNumberOrientations = #'(left down)
  <
  c'-3\5\_rightHandFinger #1 \atLeft \mordent
  g'^\_rightHandFinger #2
  c'-1\2^\_rightHandFinger #3 \atRight \prall
  e' ^\_rightHandFinger #4
  >2^ \tenuto
}
```



Predefined commands

`\atLeft`, `\atRight`.

The type of grob that an articulation creates depends on what it is attached to.

- On notes or ordinary rests, articulations create `Script` objects.
- On multi-measure rests, articulations create `MultiMeasureRestScript` objects.
- On `\caesura`, articulations create `CaesuraScript` objects.

```

\override Score.Script.color = #(universal-color 'vermillion)
\override Score.MultiMeasureRestScript.color = #(universal-color 'blue)
\override Score.CaesuraScript.color = #(universal-color 'orange)
a'2\fermata r\fermata
R1\fermata
g'2 \caesura \fermata f'2

```



In addition to articulations, text and markups can be attached to notes. See Section 8.1.2 [Text scripts], page 309.

For more information about the ordering of Script and TextScript grobs that are attached to notes, see Section “Placement of objects” in *Learning Manual*.

Selected snippets

Modifying default values for articulation shorthand notation

The shorthands are defined in `ly/script-init.ly`, where the variables `dashHat`, `dashPlus`, `dashDash`, `dashBang`, `dashLarger`, `dashDot`, and `dashUnderscore` are assigned default values. The default values for the shorthands can be modified. For example, to associate the `-+` (`dashPlus`) shorthand with the *trill* symbol instead of the default “+” symbol, assign the value `\trill` to the variable `dashPlus`:

```
\relative c' { c1-+ }
```

```
dashPlus = \trill
```

```
\relative c' { c1-+ }
```



Controlling the vertical ordering of scripts

The vertical ordering of scripts is controlled with the `script-priority` property. The lower this number, the closer it will be put to the note. In this example, the TextScript (the *sharp* symbol) first has the lowest priority, so it is put lowest in the first example. In the second, the *prall trill* (the Script) has the lowest, so it is on the inside. When two objects have the same priority, the order in which they are entered determines which one comes first.

Note that for Fingering, StringNumber, and StrokeFinger grobs, if used within a chord, the vertical order is also determined by the vertical position of the associated note head, which is added to (or, depending on the direction, subtracted from) the grob’s `script-priority` value. This ensures that for fingerings above a chord the lower note is associated with the lower fingering (and vice versa for the other direction); it doesn’t matter whether you input the notes in the chord from top to bottom or from bottom to top.

By default, the least technical scripts are positioned closest to the note head; the rough order is articulation, flageolet, fingering, right-hand fingering, string number, fermata, bowing, and text script.


```

\relative c''' {
  \once \override TextScript.script-priority = -100
  a2^\prall^\markup { \sharp }

  \once \override Script.script-priority = -100
  a2^\prall^\markup { \sharp }

  \set fingeringOrientations = #'(up)
  <c-2 a-1>2
  <a-1 c>\tweak script-priority -100 -2>2
}

```



See Section B.18 [Default values for script-priority], page 937.

Creating a delayed turn

Creating a delayed turn, where the lower note of the turn uses the accidental, requires several overrides. The outside-staff-priority property must be set to #f, as otherwise this would take precedence over the avoid-slur property. Changing the first argument of \after (which is a duration) adjusts the horizontal position.

```

\relative c'' {
  \after 2*2/3 \turn c2( d4) r |
  \after 4 \turn c4.( d8)
  \after 4
  {
    \once \set suggestAccidentals = ##t
    \once \override AccidentalSuggestion.outside-staff-priority = ##f
    \once \override AccidentalSuggestion.avoid-slur = #'inside
    \once \override AccidentalSuggestion.font-size = -3
    \once \override AccidentalSuggestion.script-priority = -1
    \once \hideNotes
    cis8\turn \noBeam
  }
  d4.( e8)
}

```



See also

Music Glossary: Section “tenuto” in *Music Glossary*, Section “accent” in *Music Glossary*, Section “staccato” in *Music Glossary*, Section “portato” in *Music Glossary*.

Learning Manual: Section “Placement of objects” in *Learning Manual*.

Notation Reference: Section 8.1.2 [Text scripts], page 309, Section 36.1 [Direction and placement], page 772, Section B.13 [List of articulations], page 927, Section 3.3.3 [Trills], page 185.

Installed Files: scm/script.scm.

Snippets: Section “Expressive marks” in *Snippets*.

Internals Reference: Section “CaesuraScript” in *Internals Reference*, Section “Multi-MeasureRestScript” in *Internals Reference*, Section “Script” in *Internals Reference*, Section “TextScript” in *Internals Reference*.

3.1.2 Dynamics


Absolute dynamic marks are specified using a command after a note, such as `c4\ff`. The available dynamic marks are `\ppppp`, `\pppp`, `\ppp`, `\pp`, `\p`, `\mp`, `\mf`, `\f`, `\ff`, `\fff`, `\ffff`, `\fffff`, `\fp`, `\sf`, `\sff`, `\sp`, `\spp`, `\sfz`, `\rfz`, and `\n`. Dynamic marks may be manually placed above or below the staff; see Section 36.1 [Direction and placement], page 772.

```
\relative c'' {
  c2\ppp c\mp
  c2\rfz c^\mf
  c2_\spp c^\ff
}
```



A *crescendo* mark is started with `\<` and terminated with `\!`, an absolute dynamic, or an additional crescendo or decrescendo mark. A *decrescendo* mark is started with `\>` and is also terminated with `\!`, an absolute dynamic, or another crescendo or decrescendo mark. `\cr` and `\decr` may be used instead of `\<` and `\>`; `\endcr` and `\enddecr` maybe used instead of `\!` to end a crescendo or decrescendo mark, respectively. *Hairpins* are engraved by default using this notation.

```
\relative c'' {
  c2\< c\!
  d2\< d\f
  e2\< e\>
  f2\> f\!
  e2\> e\mp
  d2\> d\>
  c1\!
}
```



A hairpin that is terminated with `\!` will end at the right edge of the note that has the `\!` assigned to it. In the case where it is terminated with the start of another *crescendo* or *decrescendo* mark, it will end at the center of the note that has the next `\<` or `\>` assigned to it. The next hairpin will then start at the right edge of the same note instead of the usual left edge had it been terminated with `\!` before. A hairpin ending on a downbeat will stop at the preceding bar line.

```
\relative {
  c'1\< | c4 a c\< a | c4 a c\! a\< | c4 a c a\!
}
```




Hairpins that are terminated with absolute dynamic marks instead of \! will also be engraved in a similar way. However, the length of the absolute dynamic itself can alter where the preceding hairpin ends.

```
\relative {
  c'1\< | c4 a c\mf a | c1\< | c4 a c\ffff a
}
```




Often, marks like *crescendo* or *decrescendo* should begin or end at some point of time during a sustained note. This can be achieved with \after, which can also be used to create delayed articulations or text scripts:

```
<<
\relative {
  \after 2 \< c'1
  d4\f\> e f g
  \after 2. \pp c,1
  \after 2. \fermata e
  \after 2. ^"Fine." f
}
\relative {
  \*12 c'4
  c c c c\fermata
  c c c c
}
>>
```




Multiple instances of \after can be used to engrave multiple marks on one note. This is particularly useful when adding a crescendo and decrescendo to the same note:

```
\relative {
  c'4\< d\! e\> c\!
  \after 4 \< \after 2\> \after 2. \! f1
  \textLength0n
  \after 4 \> \after 2. ^"hush!" c1
  g4\pp
}
```



If the first in such a sequence of marks on a single note is supposed to coincide with the onset of the note, it is convenient to attach it to an empty chord `<>`. This way, all marks can be entered in their natural visual order:

```
{
  <>\< \after 4 \> \after 2 \! c'1
  % easier to write and read than:
  \after 4 \> \after 2 \! c'1\<
}
```



The `\espressivo` command can also be used to indicate a crescendo and decrescendo on the same note. However, be warned that this is implemented as an articulation, not a dynamic.

```
\relative {
  c'2 b4 a
  g1\espressivo
  \after 2. \espressivo c
}
```



Textual crescendo marks begin with `\cresc.`. Textual decrescendos begin with `\decreasc` or `\dim.`. Extender lines are engraved as required.

```
\relative {
  g'8\cresc a b c b c d e\mf |
  f8\decreasc e d c e\> d c b |
  a1\dim ~ |
  a2. r4\! |
}
```



Textual marks for dynamic changes can also replace hairpins:


```

\relative c'' {
  \crescTextCresc
  c4\< d e f\! |
  \dimTextDecresc
  g4\> e d c\! |
  \dimTextDecr
  e4\> d c b\! |
  \dimTextDim
  d4\> c b a\! |
  \crescHairpin
  \dimHairpin
  c4\< d\! e\> d\! |
}

```



To create new absolute dynamic marks or text that should be aligned with dynamics, see Section 3.1.3 [New dynamic marks], page 167.

Vertical positioning of dynamics is handled by Section “DynamicLineSpanner” in *Internals Reference*.

A Dynamics context is available to engrave dynamics on their own horizontal line. Use spacer rests to indicate timing. (Notes in a Dynamics context will also take up musical time, but will not be engraved.) The Dynamics context can usefully contain some other items such as text scripts, text spanners, and piano pedal marks.

```

<<
\new Staff \relative {
  c'2 d4 e |
  c4 e e,2 |
  g'4 a g a |
  c1 |
}
\new Dynamics {
  s1\< |
  s1\f |
  s2\dim s2-"rit." |
  s1\p |
}
>>

```



Note: Even if there is only a single absolute dynamic mark like `\p` in a score, LilyPond always creates *two* objects for it, a `DynamicText` and a `DynamicLineSpanner` object, and the properties to control the dynamic mark are shared between these two objects. For example, the size can be changed with the `DynamicText.font-size` property, while the vertical position is controlled by `DynamicLineSpanner.Y-offset`.

As a consequence, code like

```
\tweak font-size 5 \p
```

works but

```
\tweak Y-offset 5 \p
```

does not. You have to say

```
\tweak DynamicLineSpanner.Y-offset 5 \p
```

instead.

Predefined commands


`\dynamicUp`, `\dynamicDown`, `\dynamicNeutral`, `\crescTextCresc`, `\dimTextDim`, `\dimTextDecr`, `\dimTextDecresc`, `\crescHairpin`, `\dimHairpin`.

Selected snippets

Setting hairpin behavior at bar lines

If the note which ends a hairpin falls on a downbeat, the hairpin stops at the bar line immediately preceding. This behavior can be controlled by overriding the `to-barline` property.


```
\relative c' {
  e4\< e2.
  e1\!
  \override Hairpin.to-barline = ##f
  e4\< e2.
  e1\!
}
```



Setting the minimum length of hairpins

If hairpins are too short, they can be lengthened by modifying the `minimum-length` property of the `Hairpin` object.

```
<<
{
  \after 4 \< \after 2 \> \after 2. \! f'1
  \override Hairpin.minimum-length = 8
  \after 4 \< \after 2 \> \after 2. \! f'1
}
{
  \*8 c'4
}
>>
```



Aligning the ends of hairpins to NoteColumn directions

The ends of hairpins may be aligned to the LEFT, CENTER, or RIGHT of NoteColumn grobs by overriding the property `endpoint-alignments`, which is a pair of numbers representing the left and right ends of the hairpin. `endpoint-alignments` are expected to be directions (either -1, 0 or 1). Other values will be transformed with a warning. The right end of a hairpin terminating at a rest is not affected, always ending at the left edge of the rest.

```
{
  c'2\< <c' d'\>\! |
  \override Hairpin.endpoint-alignments = #'(1 . -1)
  c'2\< <c' d'\>\! |
  \override Hairpin.endpoint-alignments = #'(,LEFT . ,CENTER)
  c'2\< <c' d'\>\! |
}
```



Moving the ends of hairpins

The ends of hairpins may be offset by setting the `shorten-pair` property of the Hairpin object. Positive values move endpoints to the right, negative to the left. Unlike the `minimum-length` property, this property only affects the appearance of the hairpin; it does not adjust horizontal spacing (including the position of bounding dynamics). This method is thus suitable for fine-tuning a hairpin within its allotted space.

```
{
  c'1~\<
  c'2~ c'\!
  \once \override Hairpin.shorten-pair = #'(2 . 2)
  c'1~\<
  c'2~ c'\!
  \once \override Hairpin.shorten-pair = #'(-2 . -2)
  c'1~\<
  c'2~ c'\!
  c'1~\p-\tweak shorten-pair #'(2 . 0)\<
  c'2~ c'\ffff
}
```



Printing hairpins using *al niente* notation

Hairpin dynamics may be printed with a circled tip (“al niente” notation) by setting the circled-tip property of the Hairpin object to #t.

```
\relative c'' {
  \override Hairpin.circled-tip = ##t
  c2\< c\!
  c4\> c\< c2\!
}
```



Printing hairpins in various styles

Hairpin dynamics may be created in a variety of styles.

```
\relative c'' {
  \override Hairpin.stencil = #flared-hairpin
  a4\< a a a\f
  a4\p\< a a a\ff
  a4\s fz\< a a a\!
  \override Hairpin.stencil = #constante-hairpin
  a4\< a a a\f
  a4\p\< a a a\ff
  a4\s fz\< a a a\!
  \override Hairpin.stencil = #flared-hairpin
  a4\> a a a\f
  a4\p\> a a a\ff
  a4\s fz\> a a a\!
  \override Hairpin.stencil = #constante-hairpin
  a4\> a a a\f
  a4\p\> a a a\ff
  a4\s fz\> a a a\!
}
```



Vertically aligned dynamics and textscripts

For all DynamicLineSpanner objects (i.e., hairpins and dynamic texts), the vertical minimum distance between their reference line and the staff is given by the value in the staff-padding property, unless other notation elements forces them to be farther away. Setting this property to a sufficiently large value aligns the dynamics.

The same idea, together with \textLengthOn, is used to align text scripts along their baseline.

```

music = \relative c' {
  a'2\p b\f
  e4\p f\f> g, b\p
  c2^\markup { \huge gorgeous } c^\markup { \huge fantastic }
}

{
  \music
  \break
  \override DynamicLineSpanner.staff-padding = 3
  \textLengthOn
  \override TextScript.staff-padding = 1
  \music
}

```



Breaking vertical alignment of dynamics and textscripts

By default, LilyPond uses `DynamicLineSpanner` grobs to vertically align successive dynamic objects like hairpins and dynamic text. However, this is not always wanted. By inserting `\breakDynamicSpan`, which ends the alignment spanner prematurely, this vertical alignment can be avoided.


See also snippet “Breaking horizontal alignment of dynamics and textscripts”.

```

{ g1\< |
  e''\f\> |
  c'\p }

{ g1\< |
  e''\breakDynamicSpan\f\> |
  c'\p }


```



Hiding the extender line for text dynamics

Text-style dynamic changes (such as *cresc.* and *dim.*) are printed with a dashed line showing their extent. This line can be suppressed as follows.

```
\relative c' {
  \override DynamicTextSpanner.style = #'none
  \crescTextCresc
  c1\< | d | b | c\!
}
```



Changing text and spanner styles for text dynamics

The text used for *crescendos* and *decrescendos* can be changed by modifying the context properties `crescendoText` and `decrescendoText`.

The style of the spanner line can be changed by modifying the `style` property of `DynamicTextSpanner`. The default value is dashed-line, and other possible values include line, dotted-line, and none.

```
\relative c' {
  \set crescendoText = \markup { \italic { cresc. poco } }
  \set crescendoSpanner = #'text
  \override DynamicTextSpanner.style = #'dotted-line
  a2\< a
  a2 a
  a2 a
  a2 a\mf
}
```



See also

Music Glossary: Section “al niente” in *Music Glossary*, Section “crescendo” in *Music Glossary*, Section “decrescendo” in *Music Glossary*, Section “hairpin” in *Music Glossary*.

Learning Manual: Section “Articulations and dynamics” in *Learning Manual*.

Notation Reference: Section 36.1 [Direction and placement], page 772, Section 3.1.3 [New dynamic marks], page 167, Section 24.9 [Enhancing MIDI output], page 662, Section 24.4 [Controlling MIDI dynamics], page 653.

Snippets: Section “Expressive marks” in *Snippets*.

Internals Reference: Section “DynamicText” in *Internals Reference*, Section “Hairpin” in *Internals Reference*, Section “DynamicLineSpanner” in *Internals Reference*, Section “Dynamics” in *Internals Reference*.

3.1.3 New dynamic marks

The easiest way to create dynamic indications is to use `\markup` objects.

```
moltoF = \markup { molto \dynamic f }
```

```
\relative {
  <d' e>16_\moltoF <d e>
  <d e>2..
}
```



In markup mode, editorial dynamics (within parentheses or square brackets) can be created. The syntax for markup mode is described in Section 8.2 [Formatting text], page 319.

```
roundF = \markup {
  \center-align \concat { \bold { \italic ( }
    \dynamic f \bold { \italic ) } } }
boxF = \markup { \bracket { \dynamic f } }
\relative {
  c'1_\roundF
  c1_\boxF
}
```



Simple, centered dynamic marks are easily created with the make-dynamic-script function.

```
sfzp = #(make-dynamic-script "sfzp")
\relative {
  c'4 c c\sfpz c
}
```



In general, make-dynamic-script takes any markup object as its argument. The dynamic font only contains the characters f, m, p, r, s, z, and n; if a dynamic mark that includes plain text or punctuation symbols is desired, markup commands that reverts font family and font encoding to normal text should be used, for example \normal-text. Using make-dynamic-script instead of an ordinary markup ensures vertical alignment of markup objects and hairpins that are attached to the same note head.

```
roundF = \markup { \center-align \concat {
  \normal-text { \bold { \italic ( } }
  \dynamic f
  \normal-text { \bold { \italic ) } } } }
boxF = \markup { \bracket { \dynamic f } }
mfEspress = \markup { \center-align \line {
  \hspace #3.7 mf \normal-text \italic espress. } }
roundFdynamic = #(make-dynamic-script roundF)
```

```

boxFdynamic = #(make-dynamic-script boxF)
mfEspressDynamic = #(make-dynamic-script mfEspress)
\relative {
  c'4_\roundFdynamic\< d e f
  g,1~_\boxFdynamic\>
  g1
  g'1~\mfEspressDynamic
  g1
}

```




The Scheme form of markup mode may be used instead. Its syntax is explained in Section “Markup construction in Scheme” in *Extending*.

```

moltoF = #(make-dynamic-script
  (markup #:normal-text "molto"
    #:dynamic "f"))
\relative {
  <d' e>16 <d e>
  <d e>2..\moltoF
}

```



To left-align the dynamic text rather than centering it on a note use a `\tweak`:

```

moltoF = \tweak DynamicText.self-alignment-X #LEFT
  #(make-dynamic-script
    (markup #:normal-text "molto"
      #:dynamic "f"))
\relative {
  <d' e>16 <d e>
  <d e>2..\moltoF <d e>1
}

```



Font settings in markup mode are described in Section 8.2.2 [Selecting font and font size], page 323.

See also

Notation Reference: Section 8.2 [Formatting text], page 319, Section 8.2.2 [Selecting font and font size], page 323, Section 24.9 [Enhancing MIDI output], page 662, Section 24.4 [Controlling MIDI dynamics], page 653.

Extending LilyPond: Section “Markup construction in Scheme” in *Extending*.

Snippets: Section “Expressive marks” in *Snippets*.

3.2 Expressive marks as curves

This section explains how to create various expressive marks that are curved: normal slurs, phrasing slurs, breath marks, falls, and doits.

3.2.1 Slurs

Slurs are entered using parentheses:

Note: In polyphonic music, a slur must be terminated in the same voice it began.

```
\relative {
  f' '4( g a) a8 b(
  a4 g2 f4)
  <c e>2( <b d>2)
}
```



Slurs may be manually placed above or below the staff; see Section 36.1 [Direction and placement], page 772.

Simultaneous or overlapping slurs require special attention. Most occurrences of outer slurs actually indicate phrasing, and phrasing slurs may overlap a regular slur, see Section 3.2.2 [Phrasing slurs], page 173. When multiple regular slurs are needed in a single Voice, matching slur starts and ends need to be labeled by preceding them with \= followed by an identifying key (a symbol or non-negative integer).

```
\fixed c' {
  <c~ f\=1( g\=2( >2 <c e\=1) a\=2) >
}
```



Slurs can be solid, dotted, or dashed. Solid is the default slur style:

```
\relative {
  c'4( e g2)
  \slurDashed
  g4( e c2)
  \slurDotted
  c4( e g2)
  \slurSolid
  g4( e c2)
}
```



Slurs can also be made half-dashed (the first half dashed, the second half solid) or half-solid (the first half solid, the second half dashed):


```

((off1 . off2) offsets))
(set! (ly:grob-property grob 'positions)
  (cons (+ y1 off1) (+ y2 off2)))
(ly:slur::calc-control-points grob)))
#})

\relative c' {
  c4("default" c, d2)
  \offsetPositions #'(0 . 1)
  c'4(" (0 . 1)" c, d2)
  \offsetPositions #'(0 . 2)
  c'4(" (0 . 2)" c, d2)
  \bar "||"
  g4("default" a d'2)
  \offsetPositions #'(1 . 0)
  g,,4(" (1 . 0)" a d'2)
  \offsetPositions #'(2 . 0)
  g,,4(" (2 . 0)" a d'2)
}

```



Using double slurs for legato chords

Some composers write two *slurs* when they want legato chords. This can be achieved by setting `doubleSlurs` context property.

```

\relative c' {
  \set doubleSlurs = ##t
  <c e>4( <d f> <c e> <d f>)
}

```



Positioning text markups inside slurs

Text markups need to have the `outside-staff-priority` property set to `#f` in order to be printed inside slurs.

```

\relative c' {
  \override TextScript.avoid-slur = #'inside
  \override TextScript.outside-staff-priority = ##f
  c2(\markup { \halign #-10 \natural } d4.) c8
}

```



Making slurs with complex dash structure

Slurs can be composed of complex dash patterns by setting the `dash-definition` property, which is a list of slur segments, which in turn are lists of parameters setting up the dash behavior of the given segment.

Slur segments are defined in terms of the Bézier parameter t , which ranges from 0 at the left end of the slur to 1 at the right end of the slur. A slur segment has the form $(start-t\ stop-t\ dash-fraction\ dash-period)$. In the segment spanning the range $start-t$ to $stop-t$, the dash pattern is defined by the values of $dash-fraction$ and $dash-period$. $dash-fraction$ specifies how much of a dash period is black; if set to 1 you get a solid slur segment. The unit for $dash-period$ is staff spaces.

```
\relative c' {
  \once \override
    Slur.dash-definition = #'(( 0 0.3 0.1 0.75)
                              (0.3 0.6 1 1 )
                              (0.65 1.0 0.4 0.75))

  c4( d e f)
  \once \override
    Slur.dash-definition = #'((0 0.25 1 1 )
                              (0.3 0.7 0.4 0.75)
                              (0.75 1.0 1 1 ))

  c4( d e f)
}
```



See also

Music Glossary: Section “slur” in *Music Glossary*.

Learning Manual: Section “On the un-nestedness of brackets and ties” in *Learning Manual*.

Notation Reference: Section 36.1 [Direction and placement], page 772, Section 3.2.2 [Phrasing slurs], page 173.

Snippets: Section “Expressive marks” in *Snippets*.

Internals Reference: Section “Slur” in *Internals Reference*.

3.2.2 Phrasing slurs

Phrasing slurs (or phrasing marks) that indicate a musical sentence are written using the commands `\(` and `\)` respectively:

```
\relative {
  c' '4\ ( d( e) f(
  e2) d\ )
}
```



Typographically, a phrasing slur behaves almost exactly like a normal slur. However, they are treated as different objects; a `\slurUp` will have no effect on a phrasing slur. Phrasing

may be manually placed above or below the staff; see Section 36.1 [Direction and placement], page 772.

Simultaneous or overlapping phrasing slurs are entered using `\=` as with regular slurs, see Section 3.2.1 [Slurs], page 170.

Phrasing slurs can be solid, dotted, or dashed. Solid is the default style for phrasing slurs:

```
\relative {
  c'4\ ( e g2\ )
  \phrasingSlurDashed
  g4\ ( e c2\ )
  \phrasingSlurDotted
  c4\ ( e g2\ )
  \phrasingSlurSolid
  g4\ ( e c2\ )
}
```



Phrasing slurs can also be made half-dashed (the first half dashed, the second half solid) or half-solid (the first half solid, the second half dashed):

```
\relative {
  c'4\ ( e g2\ )
  \phrasingSlurHalfDashed
  g4\ ( e c2\ )
  \phrasingSlurHalfSolid
  c4\ ( e g2\ )
  \phrasingSlurSolid
  g4\ ( e c2\ )
}
```



Custom dash patterns for phrasing slurs can be defined:

```
\relative {
  c'4\ ( e g2\ )
  \phrasingSlurDashPattern 0.7 0.75
  g4\ ( e c2\ )
  \phrasingSlurDashPattern 0.5 2.0
  c4\ ( e g2\ )
  \phrasingSlurSolid
  g4\ ( e c2\ )
}
```



Dash pattern definitions for phrasing slurs have the same structure as dash pattern definitions for slurs. For more information about complex dash patterns, see the snippets under Section 3.2.1 [Slurs], page 170.

Predefined commands

`\phrasingSlurUp`, `\phrasingSlurDown`, `\phrasingSlurNeutral`, `\phrasingSlurDashed`,
`\phrasingSlurDotted`, `\phrasingSlurHalfDashed`, `\phrasingSlurHalfSolid`,
`\phrasingSlurDashPattern`, `\phrasingSlurSolid`.

See also

Learning Manual: Section “On the un-nestedness of brackets and ties” in *Learning Manual*.

Notation Reference: Section 36.1 [Direction and placement], page 772, Section 3.2.1 [Slurs], page 170.

Snippets: Section “Expressive marks” in *Snippets*.

Internals Reference: Section “PhrasingSlur” in *Internals Reference*.

3.2.3 Breath marks

The `\breathe` command calls for the performer to shorten the previous note to take a breath.

```
\fixed c' { c2. \breathe d4 }
```



For a short break in sound that is not taken away from the previous note, see Section 2.2.4 [Caesuras], page 76.

Unlike other expressive marks, a breath mark is treated as a separate music event; therefore, any expressive marks pertaining to the preceding note, and any brackets indicating manual beams, slurs, or phrasing slurs, must be placed before `\breathe`. `\breathe` does not accept articulations itself, but see Section 2.2.4 [Caesuras], page 76.

A breath mark ends an automatic beam; to override this, see Section 2.4.3 [Manual beams], page 114.

```
\fixed c' { c8 \breathe d e f g2 }
```



The `breathMarkType` context property controls which of several predefined breath marks the `\breathe` command creates. See Section B.14 [List of breath marks], page 929.

```
\fixed c' {  
  \set breathMarkType = #'tickmark  
  c2. \breathe d4  
}
```



See also

Music Glossary: Section “breath mark” in *Music Glossary*.

Notation Reference: Section 2.2.4 [Caesuras], page 76, Section 17.4.4 [Divisiones], page 555.

Snippets: Section “Expressive marks” in *Snippets*.

Internals Reference: Section “BreathingEvent” in *Internals Reference*, Section “Breathing-Sign” in *Internals Reference*, Section “Breathing-sign-engraver” in *Internals Reference*.

3.2.4 Falls and doits

Falls and *doits* can be added to notes using the `\bendAfter` command. The direction of the fall or doit is indicated with a plus or minus (up or down). The number indicates the pitch interval that the fall or doit will extend *beyond* the main note.

```
\relative c'' {
  c2\bendAfter 4
  c2\bendAfter -4
  c2\bendAfter 6.5
  c2\bendAfter -6.5
  c2\bendAfter 8
  c2\bendAfter -8
}
```



Selected snippets

Adjusting the shape of falls and doits

The shortest-duration-space property may be tweaked to adjust the shape of *falls* and *doits*.

```
\relative c'' {
  \override Score.SpacingSpanner.shortest-duration-space = 4.0
  c2-\bendAfter 5
  c2-\bendAfter -4.75
  c2-\bendAfter 8.5
  c2-\bendAfter -6
}
```



See also

Music Glossary: Section “fall” in *Music Glossary*, Section “doit” in *Music Glossary*.

Snippets: Section “Expressive marks” in *Snippets*.

3.3 Expressive marks as lines

This section explains how to create various expressive marks that follow a linear path: glissandi, arpeggios, and trills.

3.3.1 Glissando


A *glissando* is created by appending `\glissando` to a note:

```
\relative {
  g'2\glissando g'
  c2\glissando c,
  \afterGrace f,1\glissando f'16
}
```



A glissando can connect notes across staves:

```
\new PianoStaff <<
  \new Staff = "right" {
    e'''2\glissando
    \change Staff = "left"
    a,,4\glissando
    \change Staff = "right"
    b''8 r |
  }
  \new Staff = "left" {
    \clef bass
    s1
  }
>>
```



A glissando can connect notes in chords. If anything other than a direct one-to-one pairing of the notes in the two chords is required, the connections between the notes are defined by setting `\glissandoMap` to a Scheme list. The elements are pairs of integers; each pair $(x . y)$ creates a glissando line from the x -th note of the first chord to the y -th note of the second chord. Notes are numbered from zero in the order in which they appear in the input `.ly` file. Not all notes need be part in a glissando.

```
\relative {
  <c' e>2\glissando g'
  <c, e>\glissando <g' b>
  \break
  \set glissandoMap = #'((0 . 1) (1 . 0))
  <c, g'>\glissando <d a'>
  \set glissandoMap = #'((0 . 0) (0 . 1) (0 . 2))
  c\glissando <d f a>
  \set glissandoMap = #'((2 . 2) (0 . 0))
  <f d a'>\glissando <c f c'>
}
```




Different styles of glissandi can be created. For details, see Section 36.5 [Line styles], page 780.

Selected snippets

Contemporary glissando

A contemporary glissando without a final note can be typeset using a hidden note and cadenza timing.

```
\relative c'' {
  \time 3/4
  \override Glissando.style = #'zigzag
  c4 c
  \cadenzaOn
  c4\glissando
  \hideNotes
  c,,4
  \unHideNotes
  \cadenzaOff
  \bar "|"
}
```



Adding timing marks to long glissandi

Skipped beats in very long glissandi are sometimes indicated by timing marks consisting of stems without noteheads. Such stems can also be used to carry intermediate expression markings.

If the stems do not align well with the glissando, they may need to be repositioned slightly.

```
glissandoSkipOn = {
  \override NoteColumn.glissando-skip = ##t
  \hide NoteHead
  \override NoteHead.no-ledgers = ##t
}

glissandoSkipOff = {
  \revert NoteColumn.glissando-skip
  \undo \hide NoteHead
  \revert NoteHead.no-ledgers
}

\relative c'' {
  r8 f8\glissando \glissandoSkipOn f4 g a |
```

```

a8\noBeam \glissandoSkipOff a8
  r8 f8\glissando \glissandoSkipOn g4 a8 \glissandoSkipOff a8 |
r4 f\glissando\< \glissandoSkipOn a4\f\> \glissandoSkipOff b8\! r |
}

```



Making glissandi breakable

Normally, LilyPond refuses to automatically break a line at places where a glissando crosses a bar line. This behavior can be changed by setting the `Glissando.breakable` property to `#t`. Also setting the after-line-breaking property to `#t` makes the glissando line continue after the break.

The breakable property does not affect manual breaks inserted with commands like `\break`.

```

glissandoSkipOn = {
  \override NoteColumn.glissando-skip = ##t
  \hide NoteHead
  \override NoteHead.no-ledgers = ##t
}

music = {
  \*16 f8 |
  f1\glissando |
  a4 r2. |
  \*16 f8 |
  f1\glissando \once\glissandoSkipOn |
  a2 a4 r4 |
  \*16 f8
}

\relative c'' {
  <>\markup { \typewriter Glissando.breakable
    set to \typewriter "#t" }
  \override Glissando.breakable = ##t
  \override Glissando.after-line-breaking = ##t
  \music
}

\relative c'' {
  <>\markup { \typewriter Glissando.breakable not set }
  \music
}

\paper {
  line-width = 100\mm
}

```





Extending glissandi across repeats

A glissando that extends into several `\alternative` blocks can be simulated by adding a hidden grace note with a glissando at the start of each `\alternative` block. The grace note should be at the same pitch as the note which starts the initial glissando. This is implemented here with a music function that takes the pitch of the grace note as its argument.

Note that in polyphonic music the grace note must be matched with corresponding grace notes in all other voices.

```
repeatGliss = #(define-music-function (grace)
  (ly:pitch?)
  #{
    % the next two lines ensure the glissando is long enough
    % to be visible
    \once \override Glissando.springs-and-rods
      = #ly:spanner::set-spacing-rods
    \once \override Glissando.minimum-length = 3.5
    \once \hideNotes
    \grace $grace \glissando
  #})

\score {
  \relative c'' {
    \repeat volta 3 { c4 d e f\glissando }
    \alternative {
      { g2 d }
      { \repeatGliss f g2 e }
      { \repeatGliss f e2 d }
    }
  }
}

music = \relative c' {
  \voiceOne
```

```

\repeat volta 2 {
  g a b c\glissando
}
\alternative {
  { d1 }
  { \repeatGliss c \once \omit StringNumber e1\2 }
}
}

\score {
  \new StaffGroup <<
    \new Staff <<
      \new Voice { \clef "G_8" \music }
    >>
    \new TabStaff <<
      \new TabVoice { \clef "moderntab" \music }
    >>
  >>
}

```

See also

Music Glossary: Section “glissando” in *Music Glossary*.

Notation Reference: Section 36.5 [Line styles], page 780.

Snippets: Section “Expressive marks” in *Snippets*.

Internals Reference: Section “Glissando” in *Internals Reference*.

Known issues and warnings

Printing text over the line (such as *gliss.*) is not supported.

3.3.2 Arpeggio

An *arpeggio* on a chord (also known as a broken chord) is denoted by appending `\arpeggio` to the chord construct:

```

\relative { <c' e g c>1\arpeggio }

```

It is possible to connect arpeggios across voices or staves by setting the property `connectArpeggios` in a staff-grouping context. This connects all arpeggios in that context:

```
\new PianoStaff \fixed c' <<
  \new Staff {
    \once \set PianoStaff.connectArpeggios = ##t
    <e g>2\arpeggio q\arpeggio
  }
  \new Staff {
    \clef "bass"
    <a, c>2\arpeggio q\arpeggio
  }
>>
```



There are commands to specify the performance direction. `\arpeggioNormal` reverts to a normal arpeggio:

```
\relative {
  <c' e g c>2\arpeggio

  \arpeggioArrowUp
  <c e g c>2\arpeggio

  \arpeggioArrowDown
  <c e g c>2\arpeggio

  \arpeggioNormal
  <c e g c>2\arpeggio
}
```



These predefined commands internally modify the `arpeggio-direction` property; see their full definition in the `ly/property-init.ly` file.

The symbol that the `\arpeggio` command creates can be changed:

```
\relative {
  <c' e g c>2

  \arpeggioBracket
  <c e g c>2\arpeggio

  \arpeggioParenthesis
  <c e g c>2\arpeggio


  \arpeggioParenthesisDashed
```

```

<c e g c>2\arpeggio

\arpeggioNormal
<c e g c>2\arpeggio
}

```



These predefined commands internally override the Arpeggio object's stencil property, and may also adapt its X-extent (that is, the horizontal dimension it takes not to collide with other objects).

For a bracket designating a non-arpeggiated chord, it is better to use `\nonArpeggiato` than to use `\arpeggio` and alter the appearance. This creates a ChordBracket object.

```

\new PianoStaff \fixed c' <<
  \new Staff {
    \once \set PianoStaff.connectChordBrackets = ##t
    <e g>2\nonArpeggiato q\nonArpeggiato
  }
  \new Staff {
    \clef "bass"
    <a, c>2\nonArpeggiato q\nonArpeggiato
  }
>>

```




For a vertical slur designating a quasi-non-arpeggiated chord, it is better to use `\chordSlur` than to use `\arpeggio` and alter the appearance. This creates a ChordSlur object.

```

\new PianoStaff \fixed c <<
  \new Staff {
    \once \set PianoStaff.connectChordSlurs = ##t
    <e' g' g''>2\chordSlur q\chordSlur
  }
  \new Staff {
    \clef "bass"
    <a, a c'>2\chordSlur q\chordSlur
  }
>>

```



The dash properties of `ChordSlur` and the parenthesis `Arpeggio` are controlled with the dash-definition property (see Section 3.2.1 [Slurs], page 170).

Arpeggios can be explicitly written out with ties. For more information, see Section 2.1.4 [Ties], page 63.

Predefined commands

`\arpeggio`, `\arpeggioArrowUp`, `\arpeggioArrowDown`, `\arpeggioNormal`, `\arpeggioBracket`, `\arpeggioParenthesis`, `\arpeggioParenthesisDashed`, `\chordSlur`, `\nonArpeggiato`.

Selected snippets

Creating arpeggios across notes in different voices

An *arpeggio* can be drawn across notes in different voices on the same staff if the `Span_arpeggio_engraver` is added to the `Staff` context.

```
\new Staff \with {
  \consists "Span_arpeggio_engraver"
}
\relative c' {
  \set Staff.connectArpeggios = ##t
  <<
    { <e' g>4\arpeggio <d f> <d f>2 }
    \\\
    { <d, f>2\arpeggio <g b>2 }
  >>
}
```



See also

Music Glossary: Section “arpeggio” in *Music Glossary*.

Notation Reference: Section 3.2.1 [Slurs], page 170, Section 2.1.4 [Ties], page 63.

Installed Files: `ly/property-init.ly`.

Snippets: Section “Expressive marks” in *Snippets*.

Internals Reference: Section “Arpeggio” in *Internals Reference*, Section “ChordBracket” in *Internals Reference*, Section “ChordSlur” in *Internals Reference*, Section “Slur” in *Internals Reference*, Section “PianoStaff” in *Internals Reference*.

Known issues and warnings

Predefined commands such as `\arpeggioArrowUp` only apply to the current context, and thus will not affect arpeggios spanning several voices or staves. In such cases, these commands need to be used in a `\context` block within `\layout`, or in a `\with` block, as explained in Section 33.5 [Changing context default settings], page 744. Alternatively, rather than using predefined shortcuts, it may be advisable to directly override the relevant properties for the `Arpeggio` object in the appropriate context; for example:

```
\override Staff.Arpeggio.stencil = #ly:chord-bracket::print
\override Staff.Arpeggio.X-extent = #ly:chord-bracket::width
```

to print cross-voice arpeggio brackets at the Staff level, or

```
\override PianoStaff.Arpeggio.arpeggio-direction = #UP
```

to print cross-staff arrowed arpeggios (pointing upwards) in a PianoStaff context.

It is not possible to mix connected arpeggios and unconnected arpeggios in one PianoStaff at the same point in time.


The simple way of setting parenthesis-style arpeggio brackets does not work for cross-staff arpeggios; see [Cross-staff chord brackets], page 420.

3.3.3 Trills

Short trills without an extender line are printed with `\trill`; see Section 3.1.1 [Articulations and ornamentations], page 155.

Longer trills with an extender line are made with `\startTrillSpan` and `\stopTrillSpan`:

```
\relative {
  d' '1\startTrillSpan
  d1
  c2\stopTrillSpan
  r2
}
```




A trill spanner crossing a line break will restart exactly above the first note on the new line.

```
\relative {
  d' '1\startTrillSpan
  \break
  d1
  c2\stopTrillSpan
  r2
}
```



Consecutive trill spans will work without explicit `\stopTrillSpan` commands, since successive trill spanners will automatically become the right bound of the previous trill.

```
\relative {
  d' '1\startTrillSpan
  d1
  b1\startTrillSpan
  d2\stopTrillSpan
  r2
}
```

Trills can also be combined with grace notes. The syntax of this construct and the method to precisely position the grace notes are described in Section 2.6.1 [Grace notes], page 147.

```
\relative {
  d' '1~\afterGrace
  d1\startTrillSpan { c32[ d]\stopTrillSpan }
  c2 r2
}
```



Trills that require an auxiliary note with an explicit pitch can be typeset with the `\pitchedTrill` command. The first argument is the main note, and the second is the *trilled* note, printed as a stemless note head in parentheses.

```
\relative {
  \pitchedTrill
  d' '2\startTrillSpan fis
  d2
  c2\stopTrillSpan
  r2
}
```



The Accidental of the first pitched trill in a measure is always printed, even for naturals.

```
{
  \key d \major
  \pitchedTrill
  d'2\startTrillSpan cis d\stopTrillSpan
  \pitchedTrill
  d2\startTrillSpan c d\stopTrillSpan
  \pitchedTrill
  d2\startTrillSpan e d\stopTrillSpan
}
```



Subsequent accidentals (of the same note in the same measure) will need to be added manually.

```

\relative {
  \pitchedTrill
  eis''4\startTrillSpan fis
  eis4\stopTrillSpan
  \pitchedTrill
  eis4\startTrillSpan cis
  eis4\stopTrillSpan
  \pitchedTrill
  eis4\startTrillSpan fis
  eis4\stopTrillSpan
  \pitchedTrill
  eis4\startTrillSpan fis!
  eis4\stopTrillSpan
}

```



Predefined commands

\startTrillSpan, \stopTrillSpan.

See also

Music Glossary: Section “trill” in *Music Glossary*.

Notation Reference: Section 3.1.1 [Articulations and ornamentations], page 155, Section 2.6.1 [Grace notes], page 147.

Snippets: Section “Expressive marks” in *Snippets*.

Internals Reference: Section “TrillSpanner” in *Internals Reference*, Section “TrillPitchHead” in *Internals Reference*, Section “TrillPitchAccidental” in *Internals Reference*, Section “TrillPitchParentheses” in *Internals Reference*, Section “TrillPitchGroup” in *Internals Reference*, Section “Pitched_trill_engraver” in *Internals Reference*.

4 Repeats



Repetition is a central concept in music, and multiple notations exist for repetitions. LilyPond supports the following kinds of repeats:

- volta This is the standard notation for repeats with or without alternative endings. The repeated section is framed between repeat bar lines, but the starting bar line is omitted when the repeated section begins the piece. Alternative endings are printed in sequence, bracketed, and numbered with the volte to which they apply.
- segno This supports various *da capo* and *dal segno* cases. The repeated section begins with a segno mark, except at the start of the piece. Alternative endings are printed in sequence and marked with coda marks, and a section label such as ‘Coda’ can optionally be applied to the final alternative. The repeated section ends with an instruction such as *D.S.*
- unfold The repeated music is written out in full a specified number of times.
- percent These are beat or measure repeats. They look like single slashes or percent signs.
- tremolo This is used to write tremolo beams.

Chord constructs can be repeated using the chord repetition symbol, `q`. See Section 5.1.2 [Chord repetition], page 217.

4.1 Long repeats

This section discusses how to input long (usually multi-measure) repeats.

4.1.1 Written-out repeats

The `\repeat unfold` command repeats music by writing it out a number of times. The syntax is the same as the `\repeat volta` and `\repeat segno` commands, which are documented in following sections.

There is also a short form, `\*`, which can be convenient in a work that uses unfolded repetition heavily:

```
\*2 { c'8 d' e' f' }
```



To avoid redundancy, unfolding is not demonstrated in detail here; however, some of the examples in following sections illustrate repeats in multiple forms using the `\unfoldRepeats` command to convert the volta or segno form to the unfold form. For another important use of the `\unfoldRepeats` command, see Section 24.6 [Using repeats with MIDI], page 658.

There are some points of interest specific to the `\repeat unfold` command.

In some cases, especially in a `\relative` context, the outcome of unfolding is not the same as of writing the input music expression multiple times, e.g.,

```
\repeat unfold 2 { a'4 b c d | }
```

differs from the following by an octave change:

```
a'4 b c d |
a'4 b c d |
```

Also, nesting `\repeat unfold` can be practical in ways that nesting `\repeat volta` or `\repeat segno` would not be.

Note: If you include `\relative` inside a `\repeat` without explicitly instantiating the Voice context, extra (unwanted) staves will appear. See Section “An extra staff appears” in *Application Usage*.

See also

Snippets: Section “Repeats” in *Snippets*.

Internals Reference: Section “UnfoldedRepeatedMusic” in *Internals Reference*.

4.1.2 Simple repeats

This is the syntax for a repeat without variation:

```
\repeat volta repeatcount musicexpr
```

where *musicexpr* is the music expression to be repeated.

```
\fixed c' {
  \repeat volta 2 { c2 f }
  R1
  \repeat volta 2 { g2 c }
}
```



By default, a starting bar line is not automatically printed at the beginning of a piece, in accordance with classical engraving conventions. However, in some contexts, these bar lines are traditionally added, such as in lead sheets for jazz standards. This can be achieved by setting the `printInitialRepeatBar` property.

```
\fixed c'' {
  \set Score.printInitialRepeatBar = ##t
  \repeat volta 2 { c2 f }
}
```



A repeated section that starts in the middle of a measure usually ends at the same position in a later measure so that the two ends make a complete measure. The repeat bar lines are not measure boundaries in such cases, so no bar checks should be placed there. Likewise, no `\partial` command should be placed within the repeated music, because the measures are complete; however, a `\partial` command should be placed before the repeat when there is a truly incomplete measure the first time through.

```
\fixed c'' {
  \partial 4
  \repeat volta 2 {
    c4
    c2 d
    g4 g g
  }
  \repeat volta 2 {
    e4
    f2 g
    c2.
  }
}
```



4.1.3 Alternative endings

Repeats with alternative endings can be written two ways. This is the preferred syntax:

```
\repeat volta repeatcount {
  musicexpr...
  \alternative {
    \volta numberlist musicexpr
    \volta numberlist musicexpr
    ...
  }
}
```

where *musicexpr* is a music expression, *musicexpr...* is any number of them, and *numberlist* is a comma-separated list of volta numbers chosen from the range 1 to *repeatcount*.

```
\fixed c'' {
  \repeat volta 6 {
    c4 d e f
    \alternative {
      \volta 1,2,3 { c2 e }
      \volta 4,5 { f2 d }
      \volta 6 { e2 f }
    }
  }
}
```

```

    }
  }
  c1
}

```



An older syntax where the `\alternative` block follows outside the repeated music expression is still supported and has the same effect. This syntax requires `\repeat` to appear literally: a trailing `\alternative` does not attach to a music function or variable containing `\repeat`.

```

\repeat volta repeatcount musicexpr
\alternative {
  \volta numberlist musicexpr
  \volta numberlist musicexpr
  ...
}

```

`\volta` specifications within an `\alternative` block are optional on an all-or-none basis. If they are omitted, alternatives are used once each, but the first is repeated as needed to satisfy the repeat count.

```

\fixed c' {
  \repeat volta 6 {
    c4 d e f
    \alternative {
      { c2 e }
      { f2 d }
      { e2 f }
    }
  }
}
c1
}

```



`\alternative` blocks can be nested.

```

music = \fixed c' {
  \repeat volta 3 {
    s1_"A"
    \alternative {
      \volta 1 { s1_"B" }
      \volta 2,3 {
        \once \override Score.VoltaBracket.musical-length =
          \musicLength 1
        s1_"C"
        s1_"D"
        \alternative {
          \volta 2 { s1_"E" }
          \volta 3 { s1_"F" }
        }
      }
    }
  }
}


```

```

    }
  }
}
\fine
}

\score { \music }
\score { \unfoldRepeats \music }

```



Note: Every element in an `\alternative` block is treated as an alternative ending. Something as simple as a bar check on the wrong side of a bracket can produce unexpected results.

Note: If you include `\relative` inside a `\repeat` without explicitly instantiating the Voice context, extra (unwanted) staves will appear. See Section “An extra staff appears” in *Application Usage*.

Note: When alternative bar numbering is enabled, it is applied to the outermost bracketed alternatives.


4.1.4 Other variation in repeated sections

An `\alternative` block can be used within a `\repeat` block to produce notation similar to alternative endings (see Section 4.1.3 [Alternative endings], page 190).

```

\fixed c' {
  \repeat volta 2 {
    R1
    \alternative {
      \volta 1 { c1 }
      \volta 2 { d1 }
    }
    R1
  }
}

```




The `\volta` command is not limited to use on the elements of an `\alternative` block. It can be used anywhere within a `\repeat` to designate music for particular voltes, though it does not create brackets in other cases.

When a `\repeat` is unfolded, volta-specific music is omitted from every volta to which it does not apply. Providing an empty Scheme list in place of volta numbers removes the music entirely.

```
music = \repeat volta 3 {
  \volta #'() { <>^\markup { \bold "3×" } }
  \volta 1 { <>_\markup { \italic dolce } }
  g''1
}


\score { \music }
\score { \unfoldRepeats \music }
```



When a `\repeat` is unfolded, it may be desirable not only to filter out volta-specific music, but also to add music that was not present in the folded form. The `\unfolded` command designates music to be ignored until the enclosing `\repeat` is unfolded.

```
music = \fixed c' {
  \repeat volta 2 {
    c1
    <<
    \volta #'() {
      \once \override TextSpanner.bound-details.left.text =
        "2nd time tacet"
      s4*7\startTextSpan s4\stopTextSpan
    }
    \volta 1 { f4 f f f | f f f f }
    \volta 2 { \unfolded { R1*2 } }
    >>
    c'1
  }
  \fine
}

\score { \music }
\score { \unfoldRepeats \music }
```




Note: The `\volta` and `\unfolded` commands function with respect to the innermost repeat enclosing them.

4.1.5 All-fine repeats

The `\fine` command marks the end of the music but does not enforce it. When a repeat containing `\fine` is unfolded, the `\fine` command is unfolded like any other music. For correct unfolding, it is necessary to specify the volta in which the *Fine* should be performed and the volta in which any following music should be performed (see Section 4.1.4 [Other variation in repeated sections], page 192).

```
music = \fixed c' {
  \repeat volta 2 {
    f1
    \volta 2 \fine
    \volta 1 b1
  }
}

\score { \music }
\score { \unfoldRepeats \music }
```



As shown immediately above, at the written end of the music, `\fine` creates a final bar line without a *Fine* instruction. To force *Fine* to appear in such cases, set the `finalFineTextVisibility` context property.

```
\fixed c' {
  \set Score.finalFineTextVisibility = ##t
  f1
  \fine
}
```



To change the text that `\fine` prints, set the `fineText` context property.

```
\fixed c' {
  \set Score.fineText = "Fine."
  \repeat volta 2 {
    f1
    \volta 2 \fine
    \volta 1 b1
  }
}
```



For details on interactions with other types of bar lines and options for changing their appearance, see Section 2.5.2 [Automatic bar lines], page 130.

See also

Music Glossary: Section “fine” in *Music Glossary*.

Notation Reference: Section 2.5.2 [Automatic bar lines], page 130, Section 4.1.4 [Other variation in repeated sections], page 192, Section 2.5.7 [Section divisions], page 146.

Snippets: Section “Repeats” in *Snippets*.

Internals Reference: Section “FineEvent” in *Internals Reference*, Section “Jump-engraver” in *Internals Reference*, Section “JumpScript” in *Internals Reference*.

4.1.6 Segno repeat structure

`\repeat segno` differs from `\repeat volta` only in the resulting notation. Refer to the preceding sections for general information on entering music with repetition, alternatives, and variation. This section covers particulars of segno notation without fully reiterating the input syntax.

`\repeat segno` notates repetition with *D.C.* or *D.S.* instructions. It marks the beginning of the repeated section with a segno mark when it is not the beginning of the piece. It also marks alternative endings with coda marks in lieu of volta brackets, provided that the endings are intended to be performed in order, e.g., not `\volta 1,3` then `\volta 2,4`.

When alternative bar numbering is enabled, it is applied to alternatives notated with volta brackets whether they are created by `\repeat segno` or `\repeat volta`, but it is not applied to alternative endings notated with coda marks.


Demonstrations of common uses follow.

al fine

Repeat instructions include *al Fine* if a `\fine` command appears at any prior point (see Section 4.1.5 [Al-fine repeats], page 194).

```
music = \fixed c' {
  f1
  \repeat segno 2 {
    g1
    \volta 2 \fine
    \volta 1 a1
  }
  \section
}

\score { \music }
\score { \unfoldRepeats \music }
```



alla coda

The beginning of each alternative ending is marked with an implied \codaMark \default. Repeat instructions in alternatives include ‘*al . . . e poi la . . .*’ referring to the mark at the first alternative and the mark to skip to. Provided that the duration of the final alternative is zero, the automatic mark is suppressed, allowing a section label to be set instead.

```

music = \fixed c' {
  f1
  \repeat segno 2 {
    g1
    \alternative {
      \volta 1 { \*4 a2 }
      \volta 2 \volta #'() {
        \section
        \sectionLabel "Coda"
      }
    }
  }
}

b1
\fine

}

\score { \music }
\score { \unfoldRepeats \music }

```


The return instruction can be abbreviated by setting an alternative formatting procedure (see Section 4.1.7 [Segno repeat appearance], page 198).

da capo

Repeat instructions include *D.C.* when the repeated section begins at the beginning of the score. The supported *da capo* cases parallel the supported *dal segno* cases.

```
music = \fixed c' {
  \repeat segno 2 {
    g1
  }
  \fine
}

\score { \music }
\score { \unfoldRepeats \music }
```




dal segno

Repeat instructions include *D.S.* when the repeated section begins after the beginning of the score. The beginning of the repeated section is marked with an implied `\segnoMark \default`.

```
music = \fixed c' {
  f1
  \repeat segno 2 {
    g1
  }
  \repeat segno 2 {
    a1
  }
  \fine
}

\score { \music }
\score { \unfoldRepeats \music }
```



A *dal-segno* repeat starting at the beginning of the score can be forced (see Section 4.1.7 [Segno repeat appearance], page 198).


multiple return

A repeat instruction to be performed more than once includes '*... V.*'. The number of times the instruction is performed is one less than the number of times the passage is performed.

```
music = \fixed c' {
  \repeat segno 3 {
    g1
  }
  \fine
}

\score { \music }
\score { \unfoldRepeats \music }
```





See also

Music Glossary: Section “da capo” in *Music Glossary*, Section “dal segno” in *Music Glossary*, Section “fine” in *Music Glossary*.

Notation Reference: Section 4.1.5 [Al-fine repeats], page 194, Section 4.1.3 [Alternative endings], page 190, Section 2.5.2 [Automatic bar lines], page 130, Section 4.1.4 [Other variation in repeated sections], page 192, Section 2.5.7 [Section divisions], page 146, Section 8.1.4 [Section labels], page 312, Section 4.1.2 [Simple repeats], page 189.

Snippets: Section “Repeats” in *Snippets*.

Internals Reference: Section “CodaMark” in *Internals Reference*, Section “JumpScript” in *Internals Reference*, Section “SectionLabel” in *Internals Reference*, Section “SegnoMark” in *Internals Reference*.

4.1.7 Segno repeat appearance

The marks and return instructions that `\repeat segno` creates are adjustable in some respects.

Return instructions are formatted with the Scheme procedure specified in the `dalSegnoTextFormatter` property. There is a predefined alternative formatter that creates shorter instructions.

```
\fixed c' {
  \set Score.dalSegnoTextFormatter = #format-dal-segno-text-brief
  f1
  \repeat segno 2 {
    g1
    \alternative {
      \volta 1 { a1 }
      \volta 2 \volta #'() {
        \section
        \sectionLabel "Coda"
      }
    }
  }
  b1
  \fine
}
```



The sequence numbers of the marks at the beginning of the repeated section and the beginning of the first alternative may be set explicitly without interfering with automatic return instructions (see Section 4.1.8 [Manual repeat marks], page 204).


```

\fixed c' {
  \set Score.segnoMarkFormatter = #format-mark-numbers
  \set Score.segnoStyle = #'bar-line
  R1
  \repeat unfold 3 {
    \repeat segno 2 {
      R1*2
    }
  }
  \fine
}

```



There is a predefined alternative segno formatter that prints a mark even over the first bar line:

```

\fixed c' {
  \set Score.segnoMarkFormatter = #format-segno-mark
  \set Score.segnoStyle = #'bar-line
  R1
  \repeat unfold 3 {
    \segnoMark \default
    R1*2
  }
}

```




There is a predefined alternative coda mark formatter that uses `\varcoda` signs.

```

\fixed c' {
  \set Score.codaMarkFormatter = #format-varcoda-mark
  R1
  \repeat unfold 3 {
    \codaMark \default
    R1*2
  }
}

```



Selected snippets

Shortening volta brackets

By default, volta brackets are drawn over all of the alternative music, but it is possible to shorten them by overriding `VoltaBracket.musical-length`. In the next example, the bracket only spans one measure, which has a duration of $3/4$.

```
\fixed c' {
  \time 3/4
  c4 c c
  \repeat volta 5 {
    d4 d d
    \alternative {
      \volta 1,2,3,4 {
        \once \override Score.VoltaBracket.musical-length =
          \musicLength 2.
        e4 e e
        f4 f f
      }
      \volta 5 {
        g4 g g } } }
}
```




Volta brackets in multiple staves

By adding the `Volta_engraver` to the relevant staff, volte can be put over staves other than the topmost one in a score.

`\repeat` and related commands should be present in all staves.

```
voltaMusic = \relative c' {
  \repeat volta 2 {
    c1
    \alternative {
      \volta 1 { d1 }
      \volta 2 { e1 }
    }
  }
}

<<
\new StaffGroup <<
  \new Staff \voltaMusic
  \new Staff \voltaMusic
>>
\new StaffGroup <<
  \new Staff \with { \consists "Volta_engraver" }
  \voltaMusic
  \new Staff \voltaMusic
>>
>>
```

Alternative bar numbering

Setting the `alternativeNumberingStyle` context property, two additional methods are available for enumerating bar numbers in repeats.

```
music = \relative c' {
  \repeat volta 3 {
    c4 d e f |
    \alternative {
      \volta 1 { c4 d e f | c2 d \break }
      \volta 2 { f4 g a b | f4 g a b | f2 a | \break }
      \volta 3 { c4 d e f | c2 d } } }
  c1 \bar "|"
}

{
  \textMark \markup \large "default"
  \music
}

{
  \textMark \markup \large \typewriter "numbers"
  \set Score.alternativeNumberingStyle = #'numbers
  \music
}

{
  \textMark \markup \large \typewriter "numbers-with-letters"
  \set Score.alternativeNumberingStyle = #'numbers-with-letters
  \music
}

\layout {
  \context {
    \Score
    \override TextMark.Y-offset = #5
  }
}
```

default

4

7

numbers

2

2

numbers-with-letters

2b

2c

See also

Music Glossary: Section “repeat” in *Music Glossary*, Section “volta” in *Music Glossary*.

Notation Reference: Section 2.5.2 [Automatic bar lines], page 130, Section 2.5.1 [Bar lines], page 120, Section 2.3.1 [Measures], page 78, Section 33.4 [Modifying context plug-ins], page 743, Section 36.11.1 [Modifying ties and slurs], page 799.

Installed Files: `ly/engraver-init.ly`.

Snippets: Section “Repeats” in *Snippets*.

Internals Reference: Section “VoltaBracket” in *Internals Reference*, Section “Volta-RepeatedMusic” in *Internals Reference*, Section “UnfoldedRepeatedMusic” in *Internals Reference*.

Known issues and warnings

For repeats in volta form, spanners (slurs, etc.) that cross into alternatives work for the first alternative only. They likewise cannot wrap around from the end of an alternative back to the beginning of the repeated section.

The visual appearance of a continuing slur or tie in subsequent alternatives can be achieved with `\repeatTie` if the slur extends into only one note in the alternative block, although this method does not work in `TabStaff`; see [Repeat tie], page 64. Other methods which may be tailored to indicate continuing slurs over several notes in alternative blocks, and which also work in `TabStaff` contexts, are shown in Section 36.11.1 [Modifying ties and slurs], page 799.

The visual appearance of a continuing glissando in subsequent alternatives can be achieved by coding a glissando starting on a hidden grace note. See [Extending glissandi across repeats], page 180.

If a repeat that begins with an incomplete measure has an `\alternative` block that contains modifications to the `measureLength` property, using `\unfoldRepeats` will result in wrongly-placed bar lines and bar check warnings.

A nested repeat using the old `\alternative` syntax is ambiguous:

```
\repeat ...
\repeat ...
\alternative
```

It is not clear to which `\repeat` the `\alternative` belongs. This ambiguity is resolved by always having the `\alternative` belong to the inner `\repeat`. For clarity, it is advised to add braces and place the `\alternative` block inside the body of its repeat.

4.1.8 Manual repeat marks

Note: These methods are only used for displaying unusual repeat constructs, and may produce unexpected behavior. In most cases, repeats should be created using the standard `\repeat` command or by printing the relevant bar lines. For more information, see Section 2.5.1 [Bar lines], page 120.

The property `repeatCommands` can be used to control the layout of volta-style repeats. Its value is a Scheme list. In general, each element is itself a list, `'(command args...)`, but a command with no arguments may be abbreviated to a symbol; e.g., `'((start-repeat))` may be given as `'(start-repeat)`.

`end-repeat`

End a repeated section.

```
\relative {
  c'1
  d4 e f g
  \set Score.repeatCommands = #'(end-repeat)
  c1
}
```



`start-repeat`

Start a repeated section.

```

\relative {
  c''1
  \set Score.repeatCommands = #'(start-repeat)
  d4 e f g
  c1
}

```



As per standard engraving practice, repeat signs are not printed at the beginning of a piece.


volta text

If *text* is markup, start a volta bracket with that label; if *text* is #f, end a volta bracket. A volta bracket which is not ended explicitly will not be printed.

```

\relative {
  f''4 g a b
  \set Score.repeatCommands =
    #`((volta ,#{ \markup \volta-number "2" #}))
  g4 a g a
  \set Score.repeatCommands = #'((volta #f))
  c1
}

```




Multiple repeat commands may occur at the same point:

```

\relative {
  f''4 g a b
  \set Score.repeatCommands =
    #`((volta ,#{ \markup { \concat { \volta-number 2 , }
                      \volta-number 5 } #}))
    end-repeat)
  g4 a g a
  c1
  \set Score.repeatCommands =
    #`((volta #f)
      (volta ,#{ \markup \volta-number 95 #})
      end-repeat)
  b1
  \set Score.repeatCommands = #'((volta #f))
}

```



Text can be included with the volta bracket. The text can be a number or numbers or markup text, see Section 8.2 [Formatting text], page 319. The simplest way to use markup text is to define the markup first, then include the markup in a Scheme list.

```
voltaAdLib = \markup { \volta-number { 1. 2. 3... }
                      \italic { ad lib. } }

\relative {
  c''1
  \set Score.repeatCommands = #((volta ,voltaAdLib) start-repeat)
  c4 b d e
  \set Score.repeatCommands =
    #((volta #f)
      (volta ,#{ \markup \volta-number "4." #})
      end-repeat)
  f1
  \set Score.repeatCommands = #'((volta #f))
}
```




Segno and coda marks can be created with the `\segnoMark`, `\inStaffSegno`, and `\codaMark` commands. This is the syntax for the mark commands:

```
\codaMark n
\segnoMark n
```


where *n* is a sequence number, or `\default` to use the next automatically. Rehearsal, segno, and coda marks are counted independently.

```
\fixed c' {
  e1
  \segnoMark \default
  e1
  \segnoMark \default
  g1
  \codaMark \default
  g1
  \codaMark \default
  b1
  \codaMark 96
  b1
  \segnoMark 96
}
```



At the beginning of a piece, `\segnoMark \default` and `\codaMark \default` create no mark. Specify '1' to force a mark.

```
\fixed c' {
  \segnoMark 1
  f1
}
```



The `\inStaffSegno` command is equivalent to `\segnoMark \default` with the extra effect of temporarily setting the `segnoStyle` property to `bar-line` to force printing it as a bar line.

```
\fixed c' {
  e1
  \inStaffSegno
  g1
  \segnoMark \default
  b1
}
```



For more information on changing the appearance of segno and coda marks, see Section 4.1.7 [Segno repeat appearance], page 198.

To create arbitrary jump instructions, use the `\jump` command.

```
\fixed c' {
  \time 2/4
  f4 a
  b4 c'8 d'
  c'4 c
  \jump "Gavotte I D.C."
  \section
}
```



See also

Notation Reference: Section 2.5.1 [Bar lines], page 120, Section 8.2 [Formatting text], page 319, Section 2.5.5 [Rehearsal marks], page 141, Section 4.1.7 [Segno repeat appearance], page 198.

Snippets: Section “Repeats” in *Snippets*.

Internals Reference: Section “CodaMark” in *Internals Reference*, Section “Jump-engraver” in *Internals Reference*, Section “JumpScript” in *Internals Reference*, Section “Mark-engraver” in *Internals Reference*, Section “SegnoMark” in *Internals Reference*, Section “SegnoRepeated-Music” in *Internals Reference*, Section “VoltaBracket” in *Internals Reference*, Section “Volta-RepeatedMusic” in *Internals Reference*.

4.2 Short repeats

This section discusses how to input short repeats. Short repeats can take two forms: slashes or percent signs to represent repeats of a single note, a single measure or two measures, and tremolos otherwise.

4.2.1 Percent repeats

Repeated short patterns are printed once, and the repeated pattern is replaced with a special sign.

The syntax is

```
\repeat percent number musicexpr
```

where *musicexpr* is a music expression.

There is also a short form, `\%`, which can be convenient in a work that uses percent repetition heavily:

```
\%3 { c'4 d' e' f' }
```



Patterns that are shorter than one measure are replaced by slashes.

```
\relative c'' {
  \%4 { c128 d e f }
  \%4 { c64 d e f }
  \%5 { c32 d e f }
  \%4 { c16 d e f }
  \%4 { c8 d }
  \%4 { c4 }
  \%2 { c2 }
}
```



Patterns of one or two measures are replaced by percent-like symbols.

```
\relative c'' {
  \%2 { c4 d e f }
  \%2 { c2 d }
  \%2 { c1 }
}
```




```
\relative {
  \%3 { c''4 d e f | c2 g' }
}
```




Note that the correct time offset to access the `DoublePercentRepeat` grob is the beginning of the repeat's second bar, which can be easily achieved with `\after`.

```
\new Voice \with { \consists Balloon_engraver }
{ \after 1*3
  \balloonGrobText DoublePercentRepeat #'(-1 . 2) "repeat"
  \%2 { g'1 | a'1 } }
```



Patterns that are shorter than one measure but contain mixed durations use a double-percent symbol.

```
\relative {
  \%4 { c''8. <d f>16 }
  \%2 { \tuplet 3/2 { r8 c d } e4 }
}
```




Selected snippets

Percent repeat counter

Measure repeats of more than two repeats are printed with a counter if the `countPercentRepeats` context property is set.

```
\relative c'' {
  \set countPercentRepeats = ##t
  \%4 c1
}
```




Percent repeat count visibility

Percent repeat counters can be shown at regular intervals by setting the context property `repeatCountVisibility`.


```

\relative c'' {
  \set countPercentRepeats = ##t
  \set repeatCountVisibility = #(every-nth-repeat-count-visible 5)
  \%10 c1 \break
  \set repeatCountVisibility = #(every-nth-repeat-count-visible 2)
  \%6 { c1 d1 }
}

```



Isolated percent repeats

Isolated percents can also be printed.

```

makePercent =
#(define-music-function (note) (ly:music?)
  "Make a percent repeat the same length as NOTE."
  (make-music 'PercentEvent
    'length (ly:music-length note)))

\relative c'' {
  \makePercent s1
}

```



See also

Music Glossary: Section “percent repeat” in *Music Glossary*, Section “simile” in *Music Glossary*.

Snippets: Section “Repeats” in *Snippets*.

Internals Reference: Section “RepeatSlash” in *Internals Reference*, Section “RepeatSlashEvent” in *Internals Reference*, Section “DoubleRepeatSlash” in *Internals Reference*, Section “PercentRepeat” in *Internals Reference*, Section “PercentRepeatCounter” in *Internals Reference*, Section “PercentRepeatedMusic” in *Internals Reference*, Section “Percent_repeat_engraver” in *Internals Reference*, Section “DoublePercentEvent” in *Internals Reference*, Section “DoublePercentRepeat” in *Internals Reference*, Section “DoublePercentRepeatCounter” in *Internals Reference*, Section “Double_percent_repeat_engraver” in *Internals Reference*, Section “Slash_repeat_engraver” in *Internals Reference*.

Known issues and warnings

Percent repeats will not contain anything else apart from the percent sign itself; in particular, timing changes will not be repeated.

```

\%3 { \time 5/4 c2. 2 \time 4/4 2 2 }

```



Any meter changes or `\partial` commands need to occur in parallel passages *outside* of any percent repeat, e.g. in a separate timing track.

```
<<
  \%3 { c2. 2 2 2 }
  \*3 { \time 5/4 s4*5 \time 4/4 s1 }
>>
```




4.2.2 Tremolo repeats

Tremolos can take two forms: alternation between two chords or two notes, and rapid repetition of a single note or chord. Tremolos consisting of an alternation are indicated by adding beams between the notes or chords being alternated, while tremolos consisting of the rapid repetition of a single note are indicated by adding beams or slashes to a single note.

To place tremolo marks between notes, use `\repeat` with tremolo style:

```
\relative c' {
  \repeat tremolo 8 { c16 d }
  \repeat tremolo 6 { c16 d }
  \repeat tremolo 2 { c16 d }
}
```



The `\repeat tremolo` syntax expects exactly two notes within the braces, and the number of repetitions must correspond to a note value that can be expressed with plain or dotted notes. Thus, `\repeat tremolo 7` is valid and produces a double dotted note, but `\repeat tremolo 9` is not.

The duration of the tremolo equals the duration of the braced expression multiplied by the number of repeats: `\repeat tremolo 8 { c16 d16 }` gives a whole note tremolo, notated as two whole notes joined by tremolo beams.

There are two ways to put tremolo marks on a single note. The `\repeat tremolo` syntax is also used here, in which case the note should not be surrounded by braces:

```
\repeat tremolo 4 c'16
```



The same output can be obtained by adding `:N` after the note, where N indicates the duration of the subdivision (it must be at least 8). If N is 8, one beam is added to the note's stem. If N is omitted, the last value is used:

```
\relative {
  c' '2:8 c:32
  c: c:
}
```




Selected snippets

Cross-staff tremolos

Since `\repeat tremolo` expects exactly two musical arguments for chord tremolos, the note or chord which changes staff within a cross-staff tremolo should be placed inside curly braces together with its `\change Staff` command.

```
\new PianoStaff <<
  \new Staff = "up" \relative c' ' {
    \key a \major
    \time 3/8
    s4.
  }
  \new Staff = "down" \relative c' ' {
    \key a \major
    \time 3/8
    \voiceOne
    \repeat tremolo 6 {
      <a e'>32
      {
        \change Staff = "up"
        \voiceTwo
        <cis a' dis>32
      }
    }
  }
>>
```



Controlling the appearance of tremolo slashes

Using various properties of the `StemTremolo` grob it is possible to control the appearance of tremolo slashes.

- Property `slope` sets the slope for tremolo slashes.

- Property `shape` determines whether tremolo slashes look like rectangles (value `rectangle`) or like very small beams (value `beam-like`).
- Property `style` sets both the slope and the shape depending on whether the note has flags, beams, or only a plain stem. This is in contrast to the previous two properties, which change the slope and shape unconditionally. There are two styles defined.
 - `default`: slashes for down-stem flags are longer and more sloped than slashes for up-stem flags; slashes on beamed notes have a rectangular shape and are parallel to the beam.
 - `constant`: all slashes are beam-like and have the same slope except for down-stem flags.

```
music = {
  a''4:32 a':
  e''8: \noBeam e':
  a'':[ a':]
  f':[ g':]
  d':[ d':]
}

\new Staff {
  <>\markup "default"
  \music
}


\new Staff {
  <>\markup \typewriter "style = #'constant"
  \override StemTremolo.style = #'constant
  \music
}

\new Staff {
  <>\markup \typewriter "shape = #'rectangle"
  \override StemTremolo.shape = #'rectangle
  \music
}

\new Staff {
  <>\markup \typewriter "shape = #'beam-like"
  \override StemTremolo.shape = #'beam-like
  \music
}

\new Staff {
  <>\markup \typewriter "slope = -0.2"
  \override StemTremolo.slope = -0.2
  \music
}
```





See also

Snippets: Section “Repeats” in *Snippets*.

Known issues and warnings

While the `\repeat tremolo` syntax is unfolded by `\unfoldRepeats`, its shorthand is not (this is tracked in issue #6145 (<https://gitlab.com/lilypond/lilypond/-/issues/6145>)):

```
{
  \unfoldRepeats \repeat tremolo 4 c'16
  \unfoldRepeats c'4:16
}
```



5 Simultaneous notes

The image shows a musical score for a piano piece. It consists of two systems of music. The first system has four measures. The second system starts at measure 113 and also has four measures. The music is written for piano, with a 9/16 time signature and a key signature of one sharp (F#). The score is polyphonic, with multiple voices occurring simultaneously. Dynamics such as *f*, *p*, *dim.*, and *pp* are used. The notation includes various note values, rests, and articulations like trills.

Polyphony in music refers to having more than one voice occurring in a piece of music. Polyphony in LilyPond refers to having more than one voice on the same staff.

5.1 Single voice

This section discusses simultaneous notes inside the same voice.

5.1.1 Chorded notes

A chord is formed by enclosing a set of pitches between `<` and `>`. A chord may be followed by a duration just like simple notes.

```
\relative {
  <a' c e>1 <a c e>2 <f a c e>4 <a c>8. <g c e>16
}
```

The image shows a musical score in common time (C). It consists of five measures, each containing a chord. The chords are: a triad of A, C, and E (first measure, duration 1); a dyad of A and C (second measure, duration 2); a triad of F, A, and C (third measure, duration 4); a dyad of A and C (fourth measure, duration 8); and a dyad of A and C (fifth measure, duration 16). The notes are written on a single staff.


Chords may also be followed by articulations, again just like simple notes.

```
\relative {
  <a' c e>1\fermata <a c e>2-> <f a c e>4\prall <a c>8.^! <g c e>16-.
}
```

The image shows a musical score in common time (C). It consists of five measures, each containing a chord with an articulation. The chords are: a triad of A, C, and E (first measure, duration 1, with a fermata); a dyad of A and C (second measure, duration 2, with a fermata); a triad of F, A, and C (third measure, duration 4, with a fermata); a dyad of A and C (fourth measure, duration 8, with a fermata); and a dyad of A and C (fifth measure, duration 16, with a fermata). The notes are written on a single staff.


The notes within the chord themselves can also be followed by articulation and ornamentation.

```
\relative {
  <a' c\prall e>1 <a-> c-^ e>2 <f-. a c-. e-.>4
  <a-+ c-->8. <g\fermata c e\turn>16
}
```



However some notation, such as dynamics and hairpins must be attached to the chord rather than to notes within the chord, otherwise they will not print. Other notation like fingerings and slurs will get placed markedly different when attached to notes within a chord rather than to whole chords or single notes.

```
\relative {
  <a'\f c( e>1 <a c) e>\f <a< c e>( <a\! c e>)
  <a c e>\< <a c e> <a c e>\!
}
```




A chord acts merely as a container for its notes, its articulations and other attached elements. Consequently, a chord without notes inside does not actually have a duration. Any attached articulations will happen at the same musical time as the next following note or chord and be combined with them (for more complex possibilities of combining such elements, see Section 5.1.3 [Simultaneous expressions], page 219):

```
\relative {
  \grace { g'8( a b }
  <> \p \< -. -\markup \italic "sempre staccato"
  \*4 { c4 e } c1\f
}
```



Relative mode can be used for pitches in chords. The first note of each chord is always relative to the first note of the chord that came before it, or in the case where no preceding chord exists, the pitch of the last note that came before the chord. All remaining notes in the chord are relative to the note that came before it *within the same chord*.

```
\relative {
  <a' c e>1 <f a c> <a c e> <f' a c> <b, e b,>
}
```



For more information about chords, see Chapter 15 [Chord notation], page 507.

See also

Music Glossary: Section “chord” in *Music Glossary*.

Learning Manual: Section “Combining notes into chords” in *Learning Manual*.

Notation Reference: Chapter 15 [Chord notation], page 507, Section 3.1.1 [Articulations and ornamentations], page 155, Section 1.1.2 [Relative octave entry], page 4, Section 5.2 [Multiple voices], page 221.

Snippets: Section “Simultaneous notes” in *Snippets*.

Known issues and warnings


Chords containing more than two pitches within a staff space, such as ‘<e f! fis!>’, create overlapping note heads. Depending on the situation, better representations might involve

- temporary use of Section 5.2 [Multiple voices], page 221, ‘<< f! \\
<e fis!> >>’,
- enharmonic transcription of one or more pitches, ‘<e f ges>’, or
- Section 5.1.4 [Clusters], page 220.

5.1.2 Chord repetition


In order to save typing, a shortcut can be used to repeat the preceding chord. The chord repetition symbol is q:

```
\relative {
  <a' c e>1 q <f a c>2 q
}
```




As with regular chords, the chord repetition symbol can be used with durations, articulations, markups, slurs, beams, etc., as only the pitches of the previous chord are duplicated.

```
\relative {
  <a' c e>1\p~"text" q2\<( q8)[-! q8.]\\! q16-1-2-3 q8\prall
}
```



The chord repetition symbol always remembers the last instance of a chord so it is possible to repeat the most recent chord even if other non-chorded notes or rests have been added since.

```
\relative {
  <a' c e>1 c'4 q2 r8 q8 |
  q2 c, |
}
```




However, the chord repetition symbol does not retain any dynamics, articulation or ornamentation within, or attached to, the previous chord.


```
\relative {
  <a'-. c\prall e>1\sfz c'4 q2 r8 q8 |
  q2 c, |
}
```



To have some of them retained, the `\chordRepeats` function can be called explicitly with an extra argument specifying a list of *event types* to keep unless events of that type are already present on the `q` chord itself.


```
\relative {
  \chordRepeats #'(articulation-event)
  { <a'-. c\prall e>1\sfz c'4 q2 r8 q8-. } |
  q2 c, |
}
```



Here using `\chordRepeats` inside of a `\relative` construction produces unexpected results: once chord events have been expanded, they are indistinguishable from having been entered as regular chords, making `\relative` assign an octave based on their current context.

Since nested instances of `\relative` don't affect one another, another `\relative` inside of `\chordRepeats` can be used for establishing the octave relations before expanding the repeat chords. In that case, the whole content of the inner `\relative` does not affect the outer one; hence the different octave entry of the final note in this example.

```
\relative {
  \chordRepeats #'(articulation-event)
  \relative
  { <a'-. c\prall e>1\sfz c'4 q2 r8 q8-. } |
  q2 c' ' |
}
```



Interactions with `\relative` occur only with explicit calls of `\chordRepeats`: the implicit expansion at the start of typesetting is done at a time where all instances of `\relative` have already been processed.

See also

Notation Reference: Chapter 15 [Chord notation], page 507, Section 3.1.1 [Articulations and ornamentations], page 155.

Installed Files: `ly/chord-repetition-init.ly`.

5.1.3 Simultaneous expressions

One or more music expressions enclosed in double angle brackets are taken to be simultaneous. If the first expression begins with a single note or if the whole simultaneous expression appears explicitly within a single voice, the whole expression is placed on a single staff; otherwise the elements of the simultaneous expression are placed on separate staves.

The following examples show simultaneous expressions on one staff:

```
\new Voice { % explicit single voice
  << \relative { a'4 b g2 }
    \relative { d'4 g c,2 } >>
}
```



```
\relative {
  % single first note
  a' << \relative { a'4 b g }
    \relative { d'4 g c, } >>
}
```



This can be useful if the simultaneous sections have identical rhythms, but attempts to attach notes with different durations to the same stem will cause errors. Notes, articulations, and property changes in a *single* ‘Voice’ are collected and engraved in musical order:

```
\relative {
  <a' c>4-. <>-. << c a >> << { c-. <c a> } { a s-. } >>
}
```



Multiple stems or beams or different note durations or properties at the same musical time require the use of multiple voices.

The following example shows how simultaneous expressions can generate multiple staves implicitly:

```
% no single first note
<< \relative { a'4 b g2 }
  \relative { d'4 g2 c,4 } >>
```



Here different rhythms cause no problems because they are interpreted in different voices.

Known issues and warnings

If notes from two or more voices, with no shifts specified, have stems in the same direction, the message

warning: This voice needs a `\voiceXx` or `\shiftXx` setting
will appear during compilation. This message can be suppressed by:

```
\override NoteColumn.ignore-collision = ##t
```

However, this not only suppresses the warning but will prevent any collision resolution whatsoever and may have other unintended effects (also see *Known Issues* in Section 5.2.3 [Collision resolution], page 226).

5.1.4 Clusters

A cluster indicates a continuous range of pitches to be played. They can be denoted as the envelope of a set of notes. They are entered by applying the function `\makeClusters` to a sequence of chords, e.g.,

```
\relative \makeClusters { <g' b>2 <c g'> }
```



Ordinary notes and clusters can be put together in the same staff, even simultaneously. In such a case no attempt is made to automatically avoid collisions between ordinary notes and clusters.

The following cluster styles are supported: `ramp`, `leftsided-stairs`, `rightsided-stairs`, and `centered-stairs`.

```
fragment = { <e' d''>4 <g' a'> <e' a'> r }

{
  \omit Staff.Clef
  \omit Staff.TimeSignature

  <>\markup \typewriter "ramp"
  \override ClusterSpanner.style = #'ramp
  \makeClusters \fragment

  <>\markup \typewriter "leftsided-stairs"
  \override ClusterSpanner.style = #'leftsided-stairs
  \makeClusters \fragment

  <>\markup \typewriter "rightsided-stairs"
  \override ClusterSpanner.style = #'rightsided-stairs
  \makeClusters \fragment

  <>\markup \typewriter "centered-stairs"
  \override ClusterSpanner.style = #'centered-stairs
  \makeClusters \fragment
}
```



See also

Music Glossary: Section “cluster” in *Music Glossary*.

Snippets: Section “Simultaneous notes” in *Snippets*.

Internals Reference: Section “ClusterSpanner” in *Internals Reference*, Section “ClusterSpannerBeacon” in *Internals Reference*, Section “Cluster_spanner_engraver” in *Internals Reference*.

Known issues and warnings

Clusters look good only if they span at least two chords; otherwise they appear too narrow.

Clusters do not have a stem and cannot indicate durations by themselves, but the length of the printed cluster is determined by the durations of the defining chords. Separate clusters need a separating rest between them.

Clusters do not produce MIDI output.

5.2 Multiple voices

This section discusses simultaneous notes in multiple voices or multiple staves.

5.2.1 Single-staff polyphony

Explicitly instantiating voices

The basic structure needed to achieve multiple independent voices in a single staff is illustrated in the following example:

```
\new Staff <<
  \new Voice = "first"
    \relative { \voiceOne r8 r16 g' e8. f16 g8[ c,] f e16 d }
  \new Voice= "second"
    \relative { \voiceTwo d''16 c d8~ 16 b c8~ 16 b c8~ 16 b8. }
>>
```



Here, voices are instantiated explicitly and are given names. The `\voiceOne ... \voiceFour` commands set up the voices so that first and third voices get stems up, second and fourth voices get stems down, third and fourth voice note heads are horizontally shifted, and rests in the respective voices are automatically moved to avoid collisions. The `\oneVoice` command returns all the voice settings to the neutral default directions.

Note that `Voice` is a bottom-level context (see Section 33.1.5 [Bottom-level contexts – voices], page 736). In `TabStaff` one would use `TabVoice` instead.

Temporary polyphonic passages

A temporary polyphonic passage can be created with the following construct:

```
<< { \voiceOne ... }
  \new Voice { \voiceTwo ... }
>> \oneVoice
```

Here, the first expression within a temporary polyphonic passage is placed into the `Voice` context which was in use immediately before the polyphonic passage, and that same `Voice` context continues after the temporary section. Other expressions within the angle brackets are assigned

to distinct temporary voices. This allows lyrics to be assigned to one continuing voice before, during and after a polyphonic section:

```
\relative <<
  \new Voice = "melody" {
    a'4
    <<
    {
      \voiceOne
      g f
    }
    \new Voice {
      \voiceTwo
      d2
    }
    >>
    \oneVoice
    e4
  }
  \new Lyrics \lyricsto "melody" {
    This is my song.
  }
>>
```



Here, the `\voiceOne` and `\voiceTwo` commands are required to define the settings of each voice. In `TabStaff` one needs to use `TabVoice`.

If the same music should appear in `Staff` *and* `TabStaff` the general `Bottom` context may be used (see Section 33.1.5 [Bottom-level contexts – voices], page 736).

```
mus =
\relative
  \new Bottom = "melody" {
    a'4
    <<
    {
      \voiceOne
      g f
    }
    \new Bottom {
      \voiceTwo
      d2
    }
    >>
    \oneVoice
    e4
  }
<<
```

```


\new Staff \mus
\new Lyrics \lyricsto "melody" {
  This is my song.
}
>>

<<
\new TabStaff \mus
\new Lyrics \lyricsto "melody" {
  This is my song.
}
>>

```



This is my song.



This is my song.

The double backslash construct

The `<< {...} \\ {...} >>` construct, where the two (or more) expressions are separated by double backslashes, behaves differently to the similar construct without the double backslashes: *all* the expressions within this construct are assigned to new Bottom contexts of the current type, typically Voice or TabVoice (see Section 33.1.5 [Bottom-level contexts – voices], page 736). These new Bottom contexts are created implicitly and are given the fixed names "1", "2", etc.

The first example could be typeset as follows:

```

<<
\relative { r8 r16 g'' e8. f16 g8[ c,] f e16 d }
\\
\relative { d''16 c d8~ 16 b c8~ 16 b c8~ 16 b8. }
>>

```



This syntax can be used where it does not matter that temporary voices are created and then discarded. These implicitly created voices are given the settings equivalent to the effect of the `\voiceOne ... \voiceFour` commands, in the order in which they appear in the code.

In the following example, the intermediate voice has stems up, therefore we enter it in the third place, so it becomes voice three, which has the stems up as desired. Spacer rests are used to avoid printing doubled rests.

```

<<
  \relative { r8 g'' g g g f16 ees f8 d }
  \\
  \relative { ees'8 r ees r d r d r }
  \\
  \relative { d''8 s c s bes s a s }
>>

```



In all but the simplest works it is advisable to create explicit Voice contexts as explained in Section “Contexts and engravers” in *Learning Manual* and Section “Explicitly instantiating voices” in *Learning Manual*.

Voice order

When entering multiple voices in the input file, use the following order:

```

Voice 1: highest
Voice 2: lowest
Voice 3: second highest
Voice 4: second lowest
Voice 5: third highest
Voice 6: third lowest
etc.

```

Though this may seem counterintuitive, it simplifies the automatic layout process. Note that the odd-numbered voices are given up-stems, and the even-numbered voices are given down-stems:

```

\new Staff <<
  \time 2/4
  { f''2 } % 1: highest
  \\
  { c'2 } % 2: lowest
  \\
  { d''2 } % 3: second-highest
  \\
  { e'2 } % 4: second-lowest
  \\
  { b'2 } % 5: third-highest
  \\
  { g'2 } % 6: third-lowest
>>

```



When a different voice entry order is desired, the command `\voices` may be convenient:

```

\new Staff \voices 1,3,5,6,4,2 <<
  \time 2/4
  { f''2 } % 1: highest
  \\\
  { d''2 } % 3: second-highest
  \\\
  { b'2 } % 5: third-highest
  \\\
  { g'2 } % 6: third-lowest
  \\\
  { e'2 } % 4: second-lowest
  \\\
  { c'2 } % 2: lowest
>>

```



Note: Lyrics and spanners (such as slurs, ties, hairpins, etc.) cannot be created ‘across’ voices.

Identical rhythms

In the special case that we want to typeset parallel pieces of music that have the same rhythm, we can combine them into a single Voice context, thus forming chords. To achieve this, enclose them in a simple simultaneous music construct within an explicit voice:

```

\new Voice <<
  \relative { e''4 f8 d e16 f g8 d4 }
  \relative { c''4 d8 b c16 d e8 b4 }
>>

```



This method leads to strange beamings and warnings if the pieces of music do not have the same rhythm.

Predefined commands

\voiceOne, \voiceTwo, \voiceThree, \voiceFour, \oneVoice.

See also

Learning Manual: Section “Voices contain music” in *Learning Manual*, Section “Explicitly instantiating voices” in *Learning Manual*.


Notation Reference: Section 13.1.5 [Percussion staves], page 489, Section 2.2.2 [Invisible rests], page 69, Section 7.1.9 [Stems], page 296.

Snippets: Section “Simultaneous notes” in *Snippets*.

5.2.2 Voice styles

Voices may be given distinct colors and shapes, allowing them to be easily identified:

```
<<
  \relative { \voiceOneStyle d''4 c2 b4 }
  \\
  \relative { \voiceTwoStyle e'2 e }
  \\
  \relative { \voiceThreeStyle b2. c4 }
  \\
  \relative { \voiceFourStyle g'2 g }
>>
```



The `\voiceNeutralStyle` command is used to revert to the standard presentation.

Predefined commands

`\voiceOneStyle`, `\voiceTwoStyle`, `\voiceThreeStyle`, `\voiceFourStyle`,
`\voiceNeutralStyle`.

See also


Learning Manual: Section “I’m hearing voices” in *Learning Manual*, Section “Other sources of information” in *Learning Manual*.

Snippets: Section “Simultaneous notes” in *Snippets*.

5.2.3 Collision resolution

The note heads of notes in different voices with the same pitch, same note head and opposite stem direction are automatically merged, but notes with different note heads or the same stem direction are not. Rests opposite a stem in a different voice are shifted vertically. The following example shows three different circumstances, on beats 1 and 3 in bar 1 and beat 1 in bar 2, where the automatic merging fails.

```
<<
  \relative {
    c''8 d e d c d c4
    g'2 fis
  } \\
  \relative {
    c''2 c8. b16 c4
    e,2 r
  } \\
  \relative {
    \oneVoice
    s1
    e'8 a b c d2
  }
>>
```



Notes with different note heads may be merged as shown below. In this example the note heads on beat 1 of bar 1 are now merged:

```
<<
\relative {
  \mergeDifferentlyHeadedOn
  c''8 d e d c d c4
  g'2 fis
} \\\
\relative {
  c''2 c8. b16 c4
  e,2 r
} \\\
\relative {
  \oneVoice
  s1
  e'8 a b c d2
}
>>
```



Quarter and half notes are not merged in this way, since it would be difficult to tell them apart.

Note heads with different dots as shown in beat 3 of bar 1 may be also be merged:

```
<<
\relative {
  \mergeDifferentlyHeadedOn
  \mergeDifferentlyDottedOn
  c''8 d e d c d c4
  g'2 fis
} \\\
\relative {
  c''2 c8. b16 c4
  e,2 r
} \\\
\relative {
  \oneVoice
  s1
  e'8 a b c d2
}
>>
```



The half note and eighth note at the start of the second measure are incorrectly merged because the automatic merge cannot successfully complete the merge when three or more notes line up in the same note column, and in this case the merged note head is incorrect. To allow the merge to select the correct note head a `\shiftOn` must be applied to the note that should not be merged. Here, `\shiftOn` is applied to move the top *g* out of the column, and `\mergeDifferentlyHeadedOn` then works properly.

```
<<
  \relative {
    \mergeDifferentlyHeadedOn
    \mergeDifferentlyDottedOn
    c''8 d e d c d c4
    \shiftOn
    g'2 fis
  } \\\
  \relative {
    c''2 c8. b16 c4
    e,2 r
  } \\\
  \relative {
    \oneVoice
    s1
    e'8 a b c d2
  }
>>
```



The `\shiftOn` command allows (but does not force) the notes in a voice to be shifted. When `\shiftOn` is applied to a voice, a note or chord in that voice is shifted only if its stem would otherwise collide with a stem from another voice, and only if the colliding stems point in the same direction. The `\shiftOff` command prevents this type of shifting from occurring.

By default, the outer voices (normally voices one and two) have `\shiftOff` specified, while the inner voices (three and above) have `\shiftOn` specified. When a shift is applied, voices with up-stems (odd-numbered voices) are shifted to the right, and voices with down-stems (even-numbered voices) are shifted to the left.

Here is an example to help you visualize how an abbreviated polyphonic expression would be expanded internally.

Note: Note that with three or more voices, the vertical order of voices in your input file should not be the same as the vertical order of voices on the staff!

```
\new Staff \relative {
  %% abbreviated entry
  <<
    { f''2 } % 1: highest
    \\\
    { g,2 } % 2: lowest
    \\\
  >>
```

```

    { d'2 } % 3: upper middle
    \\\
    { b2 } % 4: lower middle
  >>
  %% internal expansion of the above
  <<
    \new Voice = "1" { \voiceOne \shiftOff f'2 }
    \new Voice = "2" { \voiceTwo \shiftOff g,2 }
    \new Voice = "3" { \voiceThree \shiftOn d'2 } % shifts right
    \new Voice = "4" { \voiceFour \shiftOn b2 } % shifts left
  >>
}

```



Two additional commands, `\shiftOnn` and `\shiftOnnn` provide further shift levels which may be specified temporarily to resolve collisions in complex situations – see Section “Real music example” in *Learning Manual*.

Notes are only merged if they have opposing stem directions (as they have, for example, in voices one and two by default or when the stems are explicitly set in opposite directions).

Predefined commands

`\mergeDifferentlyDottedOn`, `\mergeDifferentlyDottedOff`, `\mergeDifferentlyHeadedOn`, `\mergeDifferentlyHeadedOff`.

`\shiftOn`, `\shiftOnn`, `\shiftOnnn`, `\shiftOff`.

Selected snippets

Additional voices to avoid collisions

In some instances of complex polyphonic music, additional voices are necessary to prevent collisions between notes. If more than four parallel voices are needed, additional voices can be added by defining a variable using the Scheme function `context-spec-music`.

```
voiceFive = #(context-spec-music (make-voice-props-set 4) 'Voice)
```

```

\relative c'' {
  \time 3/4
  \key d \minor
  \partial 2
  <<
    \new Voice {
      \voiceOne
      a4. a8
      e'4 e4. e8
      f4 d4. c8
    }
    \new Voice {
      \voiceTwo
      d,2
      d4 cis2
    }
  >>
}

```

```

        d4 bes2
    }
    \new Voice {
        \voiceThree
        f'2
        bes4 a2
        a4 s2
    }
    \new Voice {
        \voiceFive
        s2
        g4 g2
        f4 f2
    }
    >>
}

```



Moving dotted notes in polyphony

When a dotted note in the upper voice is moved to avoid a collision with a note in another voice, the default is to move the upper note to the right. This behaviour can be changed setting the `prefer-dotted-right` property of the `NoteCollision` grob.

```
\new Staff \relative c' <<
{
  f2. f4
  \override Staff.NoteCollision.prefer-dotted-right = ##f
  f2. f4
  \override Staff.NoteCollision.prefer-dotted-right = ##t
  f2. f4
}
\\
{ e4 e e e e e e e e e e }
>>
```



Forcing horizontal shift of notes

When the typesetting engine cannot cope, the following syntax can be used to override typesetting decisions. The units of measure used here are staff spaces.

```
\relative c' <<
{
    <d g>2 <d g>
}
\\
{
```

```

<b f'>2
\once \override NoteColumn.force-hshift = 1.7
<b f'>2
}
>>

```



See also

Music Glossary: Section “polyphony” in *Music Glossary*.

Learning Manual: Section “Multiple notes at once” in *Learning Manual*, Section “Voices contain music” in *Learning Manual*, Section “Real music example” in *Learning Manual*.

Snippets: Section “Simultaneous notes” in *Snippets*.

Internals Reference: Section “NoteColumn” in *Internals Reference*, Section “NoteCollision” in *Internals Reference*, Section “RestCollision” in *Internals Reference*.

Known issues and warnings

Using `\override NoteColumn.ignore-collision = ##t` will cause differently headed notes in different voices to merge incorrectly.

```

\mergeDifferentlyHeadedOn
<< \relative { c'16 a' b a } \ \relative { c'2 } >>
\override NoteColumn.ignore-collision = ##t
<< \relative { c'16 a' b a } \ \relative { c'2 } >>

```



5.2.4 Merging rests

When using multiple voices it is common to merge rests which occur in both parts. This can be accomplished using `Merge_rests_engraver`.

```

voiceA = \relative { d''4 r d2 | R1 | }
voiceB = \relative { fis'4 r g2 | R1 | }
\score {
  <<
    \new Staff \with {
      instrumentName = "unmerged"
    }
  >>
  <<
    \new Voice { \voiceOne \voiceA }
    \new Voice { \voiceTwo \voiceB }
  >>
  \new Staff \with {
    instrumentName = "merged"
    \consists Merge_rests_engraver
  }
  <<

```

```

\new Voice { \voiceOne \voiceA }
\new Voice { \voiceTwo \voiceB }
>>
>>
}

```



Setting the context property `suspendRestMerging` to `#t` allows for turning off rest merging temporarily.

5.2.5 Automatic part combining

Automatic part combining is used to merge two separate parts of music onto a single staff. This can be especially helpful when typesetting orchestral scores. A single `Voice` is printed while the two parts of music are the same, but in places where they differ, a second `Voice` is printed. Stem directions are set up & down accordingly while *Solo* and *a due* parts are also identified and marked appropriately.

The syntax for automatic part combining is:

```
\partCombine musicexpr1 musicexpr2
```

The following example demonstrates the basic functionality, putting parts on a single staff as polyphony and setting stem directions accordingly. The same variables are used for the independent parts and the combined staff.


```

instrumentOne = \relative {
  c'4 d e f |
  R1 |
  d'4 c b a |
  b4 g2 f4 |
  e1 |
}

instrumentTwo = \relative {
  R1 |
  g'4 a b c |
  d4 c b a |
  g4 f( e) d |
  e1 |
}

<<
\new Staff \instrumentOne
\new Staff \instrumentTwo
\new Staff \partCombine \instrumentOne \instrumentTwo
>>

```




Both parts have identical notes in the third measure, so only one instance of the notes is printed. Stem, slur, and tie directions are set automatically, depending on whether the parts are playing solo or in unison. When needed in polyphony situations, the first part (with context called one) gets “up” stems, while the second (called two) always gets “down” stems. In solo situations, the first and second parts get marked with “Solo” and “Solo II”, respectively. The unison (*a due*) parts are marked with the text “a2”.

By default, the part combiner merges two notes of the same pitch as an *a due* note, combines notes with the same rhythm less than a ninth apart as chords and separates notes more than a ninth apart (or when the voices cross) into separate voices. This can be overridden with an optional argument of a pair of numbers after the `\partCombine` command: the first specifies the interval where notes start to be combined (the default is zero) and the second where the notes are split into separate voices. Setting the second argument to zero means that the part combiner splits notes with an interval of a second or more, setting it to one splits notes of a third or more, and so on.

```
instrumentOne = \relative {
  a4 b c d |
  e f g a |
  b c d e |
}

instrumentTwo = \relative {
  c'4 c c c |
  c c c c |
  c c c c |
}

<<
  \new Staff \partCombine \instrumentOne \instrumentTwo
  \new Staff \partCombine #'(2 . 3) \instrumentOne \instrumentTwo
>>
```



Both arguments to `\partCombine` will be interpreted as separate Voice contexts, so if the music is being specified in relative mode then *both* parts must contain a `\relative` function, i.e.,

```
\partCombine
  \relative ... musicexpr1
  \relative ... musicexpr2
```

A `\relative` section that encloses a `\partCombine` has no effect on the pitches of *musicexpr1* or *musicexpr2*.

In professional scores, voices are often kept apart from each other for long passages of music even if some of the notes are the same in both voices, and could just as easily be printed as unison. Combining notes into a chord, or showing one voice as solo is, therefore, not ideal as the `\partCombine` function considers each note separately. In this case the `\partCombine` function can be overridden with one of the following commands. All of the commands may be preceded with `\once` in order to have them only apply to the next note in the music expression.

- `\partCombineApart` keeps the notes as two separate voices, even if they can be combined into a chord or unison.
- `\partCombineChords` combines the notes into a chord.
- `\partCombineUnisono` combines both voices as “unison”.
- `\partCombineSoloI` prints only voice one, and marks it as a “Solo”.
- `\partCombineSoloII` prints only voice two and marks it as a “Solo”.
- `\partCombineAutomatic` ends the functions of the commands above, and reverts back to the standard `\partCombine` functionality.

```
instrumentOne = \relative c' {
  \partCombineApart c2^"apart" e |
  \partCombineAutomatic e2^"auto" e |
  \partCombineChords e'2^"chord" e |
  \partCombineAutomatic c2^"auto" c |
  \partCombineApart c2^"apart"
    \once \partCombineChords e^"chord once" |
  c2 c |
}
instrumentTwo = \relative {
  c'2 c |
  e2 e |
  a,2 c |
  c2 c' |
  c2 c |
  c2 c |
}

<<
  \new Staff { \instrumentOne }
  \new Staff { \instrumentTwo }
  \new Staff { \partCombine \instrumentOne \instrumentTwo }
>>
```

The image shows a musical score with three staves, each in treble clef and common time (C). The notes are as follows:

- Staff 1:** Notes are G4, A4, B4, C5, B4, A4, G4. Text directions above the staff are: "apart" (above G4), "auto" (above A4), "chord" (above B4), "auto" (above C5), "apart" (above B4), and "chord once" (above A4).
- Staff 2:** Notes are G4, A4, B4, C5, B4, A4, G4. Text directions above the staff are: "apart" (above G4), "a2 auto" (above A4), "chord" (above B4), "auto a2" (above C5), "apart" (above B4), and "chord once" (above A4).
- Staff 3:** Notes are G4, A4, B4, C5, B4, A4, G4. Text directions above the staff are: "apart" (above G4), "a2 auto" (above A4), "chord" (above B4), "auto a2" (above C5), "apart" (above B4), and "chord once" (above A4).

Using `\partCombine` with lyrics

The `\partCombine` command is not designed to work with lyrics; if one of the voices is explicitly named in order to attach lyrics to it, the part combiner will stop working. However, this effect can be achieved using a `NullVoice` context. See Section 9.2.6 [Polyphony with shared lyrics], page 376.

Selected snippets

Combining two parts on the same staff

The part combiner tool (i.e., the `\partCombine` command) allows the combination of several different parts on the same staff. Text directions such as “solo” or “a2” are added by default; to remove them, simply set the property `printPartCombineTexts` to `#f`.

For vocal scores (hymns), there is no need to add “solo/a2” texts, so they should be switched off. However, it might be better not to use them if there are any solos, as they won’t be indicated. In such cases, standard polyphonic notation may be preferable.

This snippet presents the three ways two parts can be printed on a same staff: standard polyphony, `\partCombine` without texts, and `\partCombine` with texts.

```
musicUp = \relative c'' {
  \time 4/4
  a4 c4.( g8) a4 |
  g4 e' g,( a8 b) |
  c b a2.
}

musicDown = \relative c'' {
  g4 e4.( d8) c4 |
  r2 g'4( f8 e) |
  d2 \stemDown a
}

\score {
  <<
    \new Staff \with {
      instrumentName = "standard polyphony"
    } << \musicUp \\\musicDown >>

    \new Staff \with {
```

```

    instrumentName =
      \markup { \typewriter "\\partCombine" without text}
    printPartCombineTexts = ##f
  } \partCombine \musicUp \musicDown

\new Staff \with {
  instrumentName =
    \markup { \typewriter "\\partCombine" with text}
} \partCombine \musicUp \musicDown
>>

\layout {
  indent = 6.0\cm
  \context {
    \Score
    % Setting this to a large value avoids a bar line at the
    % beginning that would connect the three staves otherwise.
    \override SystemStartBar.collapse-height = 30
  }
}

```

standard polyphony



\partCombine without text



\partCombine with text



Changing \partCombine texts

When using the automatic part combining feature, the printed text for the solo and unison sections may be changed.

```

\new Staff <<
  \set Staff.soloText = "girl"
  \set Staff.soloIIText = "boy"
  \set Staff.aDueText = "together"
  \partCombine
    \relative c'' {
      g4 g r r
      a2 g
    }
    \relative c'' {
      r4 r a( b)
      a2 g
    }
  }
>>

```



See also

Music Glossary: Section “a due” in *Music Glossary*, Section “part” in *Music Glossary*.

Notation Reference: Section 6.3 [Writing parts], page 261.

Snippets: Section “Simultaneous notes” in *Snippets*.

Internals Reference: Section “PartCombineMusic” in *Internals Reference*, Section “Voice” in *Internals Reference*.

Known issues and warnings

All `\partCombine...` functions can only accept two voices.

`\partCombine...` functions cannot be placed inside a `\tuplet` or `\relative` block.

If `printPartCombineTexts` is set and the two voices play the same notes “on and off”, in the same measure, the part combiner may typeset a2 more than once in that measure.

`\partCombine` only knows when a note starts in a Voice; it cannot, for example, remember if a note in one Voice has already started when combining notes that have just started in the other Voice. This can lead to a number of unexpected issues including “Solo” or “Unison” marks being printed incorrectly.

`\partCombine` keeps all spanners (slurs, ties, hairpins, etc.) in the same Voice so that if any such spanners start or end in a different Voice, they may not be printed properly or at all.

If the `\partCombine` function cannot combine both music expressions (i.e., when both voices have different durations), it will give the voices, internally, its own custom names: one and two respectively. This means if there is any “switch” to a differently named Voice context, the events in that differently named Voice will be ignored.

Because `\partCombine` is a two-pass feature, care must be taken to not mix up the two phases. For example, this code

```
one = { e''2 \tag #'score f''
      \tag #'part fis'' g''1 }
two = { e''2 d'' g'1 }
```

```
\removeWithTag #'score \partCombine \one \two
```

fails because the first pass does not know that you are removing tagged music, so the information it records is inconsistent with the music when it comes time for the second pass. If you want to use `\partCombine` with filtering, unfolded repeats, or other transformations, you must transform first so that the music is in its final form before the first pass, for example,

```
...
\partCombine
  \removeWithTag #'score \one
  \removeWithTag #'score \two
```

Refer also to *Known issues and warnings* when using `\partCombine` with tablature in Section 12.1.3 [Default tablatures], page 433, and the *Note* in Section 2.4.1 [Automatic beams], page 101, when using automatic beaming.

5.2.6 Writing music in parallel

Music for multiple parts can be interleaved in input code. The function `\parallelMusic` accepts a list with the names of a number of variables to be created, and a musical expression. The

content of alternate measures from the expression become the value of the respective variables, so you can use them afterwards to print the music.

Note: Bar checks | must be used, and the measures must be of the same length.

```
\parallelMusic voiceA,voiceB,voiceC {
  % Bar 1
  r8 g'16 c'' e'' g' c'' e'' r8 g'16 c'' e'' g' c'' e'' |
  r16 e'8.~ 4 r16 e'8.~ 4 |
  c'2 c'2 |

  % Bar 2
  r8 a'16 d'' f'' a' d'' f'' r8 a'16 d'' f'' a' d'' f'' |
  r16 d'8.~ 4 r16 d'8.~ 4 |
  c'2 c'2 |

}
\new StaffGroup <<
  \new Staff << \voiceA \ \ \voiceB >>
  \new Staff { \clef bass \voiceC }
>>
```



Relative mode may be used. Note that the `\relative` command is not used inside `\parallelMusic` itself. The notes are relative to the preceding note in the voice, not to the previous note in the input – in other words, relative notes for voiceA ignore the notes in voiceB.

```
\parallelMusic voiceA,voiceB,voiceC {
  % Bar 1
  r8 g16 c e g, c e r8 g,16 c e g, c e |
  r16 e8.~ 4 r16 e8.~ 4 |
  c2 c |

  % Bar 2
  r8 a,16 d f a, d f r8 a,16 d f a, d f |
  r16 d8.~ 4 r16 d8.~ 4 |
  c2 c |

}
\new StaffGroup <<
  \new Staff << \relative c' \voiceA \ \ \relative c' \voiceB >>
  \new Staff \relative c' { \clef bass \voiceC }
>>
```



This works quite well for piano music. This example maps four consecutive measures to four variables:

```

global = {
  \key g \major
  \time 2/4
}

\parallelMusic voiceA,voiceB,voiceC,voiceD {
  % Bar 1
  a8    b      c    d      |
  d4          e      |
  c16 d e fis d e fis g |
  a4          a      |

  % Bar 2
  e8      fis g      a      |
  fis4          g      |
  e16 fis g a fis g a b |
  a4          a      |

  % Bar 3 ...
}

\score {
  \new PianoStaff <<
    \new Staff {
      \global
      <<
        \relative c'' \voiceA
        \\
        \relative c' \voiceB
      >>
    }
    \new Staff {
      \global \clef bass
      <<
        \relative c \voiceC
        \\
        \relative c \voiceD
      >>
    }
  >>
}

```


6 Staff notation

The image shows a musical score for three instruments: Trumpet Bb, Tambourine, and Piano. The score is in 2/4 time and includes tempo markings 'Comodo' and 'p grazioso'. The Trumpet Bb part starts with a whole rest in the first measure and then plays a melodic line. The Tambourine part plays a rhythmic pattern of eighth notes. The Piano part plays a complex accompaniment with chords and single notes. The score is divided into two systems, with the second system starting with a measure rest (3) in the first measure.

This section explains how to influence the appearance of staves, how to print scores with more than one staff, and how to add tempo indications and cue notes to staves.

6.1 Displaying staves

This section describes the different methods of creating and grouping staves.

6.1.1 Instantiating new staves

Staves (singular: *staff*) are created with the `\new` or `\context` commands. For details, see Section 33.2 [Creating and referencing contexts], page 737.


The basic staff context is `Staff`:

```
\new Staff \relative { c''4 d e f }
```



The `DrumStaff` context creates a five-line staff set up for a typical drum set. Each instrument is shown with a different symbol. The instruments are entered in drum mode following a `\drummode` command, with each instrument specified by name. For details, see Section 13.1.5 [Percussion staves], page 489.


```
\new DrumStaff {
  \drummode { cymc hh ss tomh }
}
```




`RhythmicStaff` creates a single-line staff that only displays the rhythmic values of the input. Real durations are preserved. For details, see Section 2.3.8 [Showing melody rhythms], page 98.

```
\new RhythmicStaff { c4 d e f }
```



`TabStaff` creates a tablature with six strings in standard guitar tuning. For details, see Section 12.1.3 [Default tablatures], page 433.


```
\new TabStaff \relative { c''4 d e f }
```



There are staff contexts specific for the notation of ancient music, for example, `MensuralStaff` and `VaticanaStaff`. They are described in Section 17.2.1 [Predefined contexts], page 539.

The `GregorianTranscriptionStaff` context creates a staff to notate modern Gregorian chant. It engraves *divisiones* as bar lines, but it does not show measure bar lines.

```
\new GregorianTranscriptionStaff \relative { c''4 d e f e d }
```



New single staff contexts may be defined. For details, see Section 33.6 [Defining new contexts], page 749.

See also

Music Glossary: Section “staff” in *Music Glossary*, Section “staves” in *Music Glossary*.

Notation Reference: Section 33.2 [Creating and referencing contexts], page 737, Section 13.1.5 [Percussion staves], page 489, Section 2.3.8 [Showing melody rhythms], page 98, Section 12.1.3 [Default tablatures], page 433, Section 17.2.1 [Predefined contexts], page 539, Section 6.2.1 [Staff symbol], page 249, Section 17.4.1 [Gregorian chant contexts], page 554, Section 17.3.1 [Mensural contexts], page 541, Section 33.6 [Defining new contexts], page 749.

Snippets: Section “Staff notation” in *Snippets*.


Internals Reference: Section “Staff” in *Internals Reference*, Section “DrumStaff” in *Internals Reference*, Section “GregorianTranscriptionStaff” in *Internals Reference*, Section “RhythmicStaff” in *Internals Reference*, Section “TabStaff” in *Internals Reference*, Section “MensuralStaff” in *Internals Reference*, Section “VaticanaStaff” in *Internals Reference*, Section “StaffSymbol” in *Internals Reference*.

6.1.2 Grouping staves

Various contexts exist to group single staves together in order to form multi-staff systems. Each grouping context sets the style of the system start delimiter and the behavior of bar lines.


If no context is specified, the default properties will be used: the group is started with a vertical line, and the bar lines are not connected.

```
<<
  \new Staff \relative { c''1 c }
  \new Staff \relative { c''1 c }
>>
```




In the `StaffGroup` context, the group is started with a bracket and bar lines are drawn through all the staves.

```
\new StaffGroup <<
  \new Staff \relative { c''1 c }
  \new Staff \relative { c''1 c }
>>
```



In a `ChoirStaff`, the group starts with a bracket, but bar lines are not connected.

```
\new ChoirStaff <<
  \new Staff \relative { c''1 c }
  \new Staff \relative { c''1 c }
>>
```




In a `GrandStaff`, the group begins with a brace, and bar lines are connected between the staves.

```

\new GrandStaff <<
  \new Staff \relative { c''1 c }
  \new Staff \relative { c''1 c }
>>

```



The PianoStaff is identical to a GrandStaff, except that its staves are only removed together, never separately; see Section 6.2.3 [Hiding staves], page 256.


The OneStaff is a staff group that places separate contexts in the same vertical alignment. This example shows three staves sharing the same space. Here, the `Time_signature_engraver` has been moved from the staves to the `OneStaff` context to prevent it from being repeated for each staff.

```

\layout {
  \context {
    \OneStaff
    \consists Time_signature_engraver
  }
  \context {
    \Staff
    \remove Time_signature_engraver
  }
  \context {
    \DrumStaff
    \remove Time_signature_engraver
  }
}

\new OneStaff {
  \new Staff {
    c'4 4 d'4 4 e'2 d'
  }
  \drums {
    hihat4 hh bassdrum bd
  }
  \new Staff {
    c'4 4 d'4 4 e'2 d'
  }
}

```



Each staff group context sets the property `systemStartDelimiter` to one of the following values: `SystemStartBar`, `SystemStartBrace`, or `SystemStartBracket`. A fourth delimiter, `SystemStartSquare`, is also available, but it must be explicitly specified.

New staff group contexts may be defined. For details, see Section 33.6 [Defining new contexts], page 749.

Selected snippets

Use square bracket at the start of a staff group

The system start delimiter `SystemStartSquare` can be used by setting it explicitly in a `StaffGroup` or `ChoirStaff` context.

```
\score {
  \new StaffGroup { <<
    \set StaffGroup.systemStartDelimiter = #'SystemStartSquare
    \new Staff { c'4 d' e' f' }
    \new Staff { c'4 d' e' f' }
  >> }
}
```




Display bracket with only one staff in a system

If there is only one staff in a `ChoirStaff` or `StaffGroup` context, the bracket and the starting bar line will not be displayed by default. This can be changed by setting the `collapse-height` property to a value less than the number of staff lines in the staff.

Note that in contexts such as `PianoStaff` and `GrandStaff` where the systems begin with a brace instead of a bracket, another property has to be set, as shown on the second system in the example.

```
\score {
  \new StaffGroup <<
    % Must be lower than the actual number of staff lines
    \override StaffGroup.SystemStartBracket.collapse-height = 4
    \override Score.SystemStartBar.collapse-height = 4
    \new Staff {
      c'1
    }
  >>
}

\score {
  \new PianoStaff <<
    \override PianoStaff.SystemStartBrace.collapse-height = 4
    \override Score.SystemStartBar.collapse-height = 4
    \new Staff {
      c'1
    }
  >>
}
```




Mensurstriche layout (bar lines between the staves)

Mensurstriche, bar lines between but not through staves, can be printed by setting `measureBarType` to `"-span|"` and using a grouping context that allows span bars, such as `StaffGroup`.

```
\layout {
  \context {
    \Staff
    measureBarType = "-span|"
  }
}

music = \fixed c'' {
  c1
  d2 \section e2
  f1 \fine
}

\new StaffGroup <<
  \new Staff \music
  \new Staff \music
>>
```



See also

Music Glossary: Section “brace” in *Music Glossary*, Section “bracket” in *Music Glossary*, Section “grand staff” in *Music Glossary*, Section “mensurstrich” in *Music Glossary*.

Notation Reference: Section 6.3.1 [Instrument names], page 261, Section 33.6 [Defining new contexts], page 749.

Snippets: Section “Staff notation” in *Snippets*.

Internals Reference: Section “Staff” in *Internals Reference*, Section “StaffGroup” in *Internals Reference*, Section “ChoirStaff” in *Internals Reference*, Section “GrandStaff” in *Internals Reference*, Section “PianoStaff” in *Internals Reference*, Section “OneStaff” in *Internals Reference*, Section “SystemStartBar” in *Internals Reference*, Section “SystemStartBracket” in *Internals Reference*, Section “SystemStartSquare” in *Internals Reference*.

6.1.3 Nested staff groups

Staff-group contexts can be nested to arbitrary depths. In this case, each child context creates a new bracket adjacent to the bracket of its parent group.

```
\new StaffGroup <<
  \new Staff \relative { c'2 c | c2 c }
  \new StaffGroup <<
    \new Staff \relative { g'2 g | g2 g }
    \new StaffGroup \with {
      systemStartDelimiter = #'SystemStartSquare
    }
    <<
      \new Staff \relative { e'2 e | e2 e }
      \new Staff \relative { c'2 c | c2 c }
    >>
  >>
>>
```



New nested staff group contexts can be defined. For details, see Section 33.6 [Defining new contexts], page 749.

Selected snippets

Nesting staves

The property `systemStartDelimiterHierarchy` can be used to make more complex nested staff groups. The `systemStartDelimiterHierarchy` property of the `StaffGroup` context takes an alphabetical list of the number of staves produced. Before each staff a system start delimiter can be given. It has to be enclosed in brackets and takes as much staves as the brackets enclose. Elements in the list can be omitted, but the first bracket takes always the complete number of staves. The possibilities are `SystemStartBar`, `SystemStartBracket`, `SystemStartBrace`, and `SystemStartSquare`.


```
\new StaffGroup
\relative c'' <<
  \override StaffGroup.SystemStartSquare.collapse-height = 4
  \set StaffGroup.systemStartDelimiterHierarchy
    = #'(SystemStartSquare
        (SystemStartBrace
```

```

      (SystemStartBracket a
      (SystemStartSquare b))
    c)
  d)

\new Staff { c1 }
\new Staff { c1 }
\new Staff { c1 }
\new Staff { c1 }
\new Staff { c1 }
>>

```



See also

Notation Reference: Section 6.1.2 [Grouping staves], page 243, Section 6.3.1 [Instrument names], page 261, Section 33.6 [Defining new contexts], page 749.

Snippets: Section “Staff notation” in *Snippets*.

Internals Reference: Section “StaffGroup” in *Internals Reference*, Section “ChoirStaff” in *Internals Reference*, Section “SystemStartBar” in *Internals Reference*, Section “SystemStartBrace” in *Internals Reference*, Section “SystemStartBracket” in *Internals Reference*, Section “SystemStartSquare” in *Internals Reference*.

6.1.4 Separating systems

If the number of systems per page changes from page to page it is customary to separate the systems by placing a system separator mark between them. By default the system separator is blank, but can be turned on with a `\paper` option.

```

\book {
  \score {
    \new StaffGroup <<
      \new Staff {
        \relative {
          c' '4 c c c
          \break
          c4 c c c
        }
      }
    }
  }

```

```

    }
    \new Staff {
      \relative {
        c''4 c c c
        \break
        c4 c c c
      }
    }
  >>
}
\paper {
  system-separator-markup = \slashSeparator
  tagline = ##f
}
}

```



See also

Notation Reference: Chapter 26 [Page layout], page 669.

Snippets: Section “Staff notation” in *Snippets*.

6.2 Modifying single staves

This section explains how to change specific attributes of one staff: for example, modifying the number of staff lines or the staff size. Methods to start and stop staves and set ossia sections are also described.

6.2.1 Staff symbol

The `\stopStaff` and `\startStaff` commands can be used to stop or (re)start the staff lines respectively, from being printed at any point within a score.

```

\relative {
  \stopStaff f''4 d \startStaff g, e
  f'4 d \stopStaff g, e
  f'4 d \startStaff g, e
}

```



Predefined commands

`\startStaff`, `\stopStaff`.

The lines of a staff belong to the `StaffSymbol` grob (including ledger lines) and can be modified using `StaffSymbol` properties, but these modifications must be made before the staff is (re)started.

The number of staff lines can be altered:

```
\relative {
  f'4 d \stopStaff
  \override Staff.StaffSymbol.line-count = 2
  \startStaff g, e |

  f'4 d \stopStaff
  \revert Staff.StaffSymbol.line-count
  \startStaff g, e |
}
```



The position of each staff line can also be altered. A list of numbers sets each line's position. 0 corresponds to the normal center line, and the normal line positions are (-4 -2 0 2 4). A single staff line is printed for every value entered so that the number of staff lines, as well as their position, can be changed with a single override (thus, the `line-count` property is disregarded if `line-positions` is set).

```
\relative {
  f'4 d \stopStaff
  \override Staff.StaffSymbol.line-positions = #'(1 3 5 -1 -3)
  \startStaff g, e |
  f'4 d \stopStaff
  \override Staff.StaffSymbol.line-positions = #'(8 6.5 -6 -8 -0.5)
  \startStaff g, e |
}
```



To preserve typical stem directions (in the bottom half of the staff stems point up, in the top half they point down), align the center line (or space) of the customized staff with the position of the normal center line (0). The clef position and the position of middle C may need to be adjusted accordingly to fit the new lines. See Section 1.3.1 [Clef], page 19.

Staff line thickness can be altered. Ledger lines and note stems, by default, are also affected.

```
\new Staff \with {
  \override StaffSymbol.thickness = 3
} \relative {
  f'4 d g, e
}
```



It is also possible to set ledger line thickness independently of staff lines.


```
\new Staff \with {
  \override StaffSymbol.thickness = 2
  \override StaffSymbol.ledger-line-thickness = #'(0.5 . 0.4)
} \relative {
  f'''4 a, a,, f
}
```



The first value is multiplied by the staff line thickness, the second by the staff space and then the two values are added together to give the new thickness of the ledger line.

The vertical positions of ledger lines can be altered,

```
\new Staff \with {
  \override StaffSymbol.ledger-positions = #'(-3 -2 -1 2 5 6)
} \relative {
  f'''4 a, a,, f
}
```



Additional ledger lines can be made to appear above or below note heads depending on the current position relative to other note heads that also have their own ledger lines.

```
\new Staff \with {
  \override StaffSymbol.ledger-extra = 4
} \relative {
  f'''4 a, d, f,
}
```



Ledger lines can also be made to appear inside the staff where custom staff lines are required. The example shows the default position of ledger lines when the explicit ledger-position is and is not set. The `\stopStaff` is needed in the example to revert the `\override` for the whole `StaffSymbol`.

```
\relative d' {
  \override Staff.StaffSymbol.line-positions = #'(-8 0 2 4)
  d4 e f g
  \stopStaff
  \startStaff
  \override Staff.StaffSymbol.ledger-positions = #'(-8 -6 (-4 -2) 0)
  d4 e f g
}
```

```
}
```



The distance between staff lines can be altered. This affects ledger line spacing as well.

```
\new Staff \with {
  \override StaffSymbol.staff-space = 1.5
} \relative {
  f'' '4 d, g, e,
}
```



The width of a staff can be modified. The units are staff spaces. The spacing of objects inside the staff is not affected by this setting.

```
\new Staff \with {
  \override StaffSymbol.width = 23
}
\relative { a4 e' f b | d1 }
```



Selected snippets

Making some staff lines thicker than the others

For educational purposes, a staff line can be thickened (e.g., the middle line, or to emphasize the line of the G clef). This can be achieved by adding extra lines very close to the line that should be emphasized, using the `line-positions` property of the `StaffSymbol` object.

```
{
  \override Staff.StaffSymbol.line-positions =
    #'(-4 -2 -0.2 0 0.2 2 4)
  d'4 e' f' g'
}
```



See also

Music Glossary: Section “line” in *Music Glossary*, Section “ledger line” in *Music Glossary*, Section “staff” in *Music Glossary*.

Notation Reference: Section 1.3.1 [Clef], page 19.

Snippets: Section “Staff notation” in *Snippets*.

Internals Reference: Section “StaffSymbol” in *Internals Reference*, Section “staff-symbol-interface” in *Internals Reference*.

6.2.2 Ossia staves

Ossia staves can be set by creating a new simultaneous staff in the appropriate location:

```
\new Staff \relative {
  c' '4 b d c
  <<
    { c4 b d c }
    \new Staff { e4 d f e }
  >>
  c4 b c2
}
```




However, the above example is not what is usually desired. To create ossia staves that are above the original staff, have no time signature or clef, and have a smaller font size, tweaks must be used. The Learning Manual describes a specific technique to achieve this goal, beginning with Section “Nesting music expressions” in *Learning Manual*.

The following example uses the `alignAboveContext` property to align the ossia staff. This method is most appropriate when only a few ossia staves are needed.

```
\new Staff = "main" \relative {
  c' '4 b d c
  <<
    { c4 b d c }

    \new Staff \with {
      \remove Time_signature_engraver
      alignAboveContext = "main"
      \magnifyStaff #2/3
      firstClef = ##f
    }
    { e4 d f e }
  >>
  c4 b c2
}
```



If many isolated ossia staves are needed, creating an empty Staff context with a specific *context id* may be more appropriate; the ossia staves may then be created by *calling* this context

and using `\startStaff` and `\stopStaff` at the desired locations. The benefits of this method are more apparent if the piece is longer than the following example.

```
<<
  \new Staff = "ossia" \with {
    \remove Time_signature_engraver
    \hide Clef
    \magnifyStaff #2/3
  }
  { \stopStaff s1*6 }

  \new Staff \relative {
    c'4 b c2
    <<
      { e4 f e2 }
      \context Staff = "ossia" {
        \startStaff e4 g8 f e2 \stopStaff
      }
    >>
    g4 a g2 \break
    c4 b c2
    <<
      { g4 a g2 }
      \context Staff = "ossia" {
        \startStaff g4 e8 f g2 \stopStaff
      }
    >>
    e4 d c2
  }
>>
```



Using the `\RemoveAllEmptyStaves` command to create ossia staves may be used as an alternative. This method is most convenient when ossia staves occur immediately following a line break. For more information about `\RemoveAllEmptyStaves`, see Section 6.2.3 [Hiding staves], page 256.

```

<<
\new Staff = "ossia" \with {
  \remove Time_signature_engraver
  \hide Clef
  \magnifyStaff #2/3
  \RemoveAllEmptyStaves
} \relative {
  R1*3
  c' '4 e8 d c2
}
\new Staff \relative {
  c'4 b c2
  e4 f e2
  g4 a g2 \break
  c4 b c2
  g4 a g2
  e4 d c2
}
>>

```



Selected snippets

Vertically aligning ossias and lyrics

This snippet demonstrates the use of the context properties `alignBelowContext` and `alignAboveContext` to control the positioning of lyrics and ossias.

```

\relative c' <<
\new Staff = "1" { c4 c c c }
\new Staff = "2" { d4 d d d }
\new Staff = "3" { e4 e e e }


{ \skip 2
  <<
    \lyrics {
      \set alignBelowContext = "1"
      lyrics4 below
    }
    \new Staff \with {
      alignAboveContext = "3"
      fontSize = -2
      \override StaffSymbol.staff-space = #(magstep -2)
    }
  }
}
>>

```

```

\remove "Time_signature_engraver"
\override VerticalAxisGroup.staff-staff-spacing =
  #'((minimum-distance . 0)
     (basic-distance . 0)
     (padding . 1))
} {
  \tuplet 6/4 {
    \override TextScript.padding = 2
    c8["ossia above" d e d e f]
  }
}
>>
}
>>

```



See also

Music Glossary: Section “ossia” in *Music Glossary*, Section “staff” in *Music Glossary*, Section “Frenched staff” in *Music Glossary*.

Learning Manual: Section “Nesting music expressions” in *Learning Manual*, Section “Size of objects” in *Learning Manual*, Section “Length and thickness of objects” in *Learning Manual*.

Notation Reference: Section 6.2.3 [Hiding staves], page 256.

Snippets: Section “Staff notation” in *Snippets*.

Internals Reference: Section “StaffSymbol” in *Internals Reference*.


6.2.3 Hiding staves

Staff lines can be hidden by removing the `Staff_symbol_engraver` from the `Staff` context. As an alternative, `\stopStaff` may be used.

```

\new Staff \with {
  \remove Staff_symbol_engraver
}
\relative { a''8 f e16 d c b a2 }

```




Empty staves can be hidden (for a so-called ‘Frenched Score’) by applying the `\RemoveEmptyStaves` command on a context, which can be done globally (in a `\layout` block)

as well as for specific staves only (in a `\with` block). This command removes all empty staves in a score except for those in the first system. If you want those in the first system to be hidden also, use `\RemoveAllEmptyStaves`.

```
\layout {
  \context {
    \Staff
    \RemoveEmptyStaves
  }
}
```

```
\relative <<
  \new Staff {
    e'4 f g a \break
    b1 \break
    a4 b c2
  }
  \new Staff {
    c,4 d e f \break
    R1 \break
    f4 g c,2
  }
  >>
```



A staff is considered empty when it contains only multi-measure rests, rests, skips, or a combination of these elements. All *other* musical objects (that cause a staff not to be considered as empty) are listed in the `keepAliveInterfaces` context property, as initially set in the `ly/engraver-init.ly` file.

`\RemoveEmptyStaves` and `\RemoveAllEmptyStaves` are both predefined shortcuts that set such properties as `remove-empty` and `remove-first` for the `VerticalAxisGroup` object, as explained in Section B.22 [Context modification identifiers], page 962.

The `Keep_alive_together_engraver` allows groups of staves to only be removed together and not individually. By default, it is part of the `PianoStaff` context: a piano part will only be hidden when both of its staves are empty. Similarly, a common engraving practice in orchestral scores is to remove empty groups of staves rather than individual staves; that can be

achieved by adding the `Keep_alive_together_engraver` to the relevant staff grouping context, as explained Section 33.4 [Modifying context plug-ins], page 743, (see Section 6.1.2 [Grouping staves], page 243, for the context names).

```
\layout {
  \context {
    \StaffGroup
    \RemoveEmptyStaves
    \consists Keep_alive_together_engraver
  }
}
```

In the following example, staves devoted to wind instruments are removed in the second system; however, the double bass is not, because it is part of the string section, which is playing.

The image displays a musical score for a symphony orchestra, consisting of seven staves: Flute, Oboe, Bassoon, Violin I, Violin II, Alto, and Cello/Double bass. The score is written in B-flat major (two flats) and common time (C). The first system shows the initial measures for all instruments. The second system shows the Flute, Oboe, and Bassoon staves removed, indicated by a large bracket on the left side of the staves. The Violin I, Violin II, Alto, and Cello/Double bass staves continue to play. The Flute part features several triplet markings (3) in the first system. The Oboe part also has triplet markings (3) in the first system. The Bassoon part has a triplet marking (3) in the first system. The Violin I part has a triplet marking (3) in the first system. The Violin II part has a triplet marking (3) in the first system. The Alto part has a triplet marking (3) in the first system. The Cello/Double bass part has a triplet marking (3) in the first system.

The `Keep_alive_together_engraver` internally uses the `remove-layer` property of a staff's `VerticalAxisGroup` to decide whether to print it or not when it is considered empty. That property may also be set directly, in which case it acts as a priority index: values closest to zero take precedence over higher numbers, and thus staves whose `remove-layer` is higher will be masked in favor of staves of a lower number.

This is particularly useful for ‘divisi’ staves, where some individual parts (see Section 6.3 [Writing parts], page 261) occasionally need to be expanded to more than one staff. In the following example, two parts are routed to *three* staves; however, all three staves are never printed at the same time:

- in the first systems, only a single one of them is shown, as the `keepAliveInterfaces` property has been set to an empty list – therefore the other two staves are considered empty and thus hidden, regardless of what they may contain;
- when that property gets unset (and thus reverts to its default setting), it is no longer preventing the two other staves from being printed; however, as their `remove-layer` setting is lower than the single staff's, these two staves are now printed in its place.

Such substitutions are applied not just to notes, chords and other musical events that occur immediately after the new setting, but to the whole system where it takes place.

```
\layout {
  short-indent = 2\cm
  indent = 3\cm
  \context {
    \Staff
    keepAliveInterfaces = #'()
  }
}

violI = {
  \*24 d'4
  \once \unset Staff.keepAliveInterfaces
  <d' g' '>2
  \*14 d'4
  \bar "|."
}
```

```

violIII = {
  \*24 g4
  <g d'>2
  \*14 g4
  \bar "|"
}

\new StaffGroup \with { \consists Keep_alive_together_engraver } <<
  \new Staff \with {
    instrumentName = "Violins"
    shortInstrumentName = "V I & II"
    \override VerticalAxisGroup.remove-layer = 2
  } << \violI \\\violIII >>
  \new Staff \with {
    instrumentName = "Violin I"
    shortInstrumentName = "V I"
    \RemoveAllEmptyStaves
    \override VerticalAxisGroup.remove-layer = 1
  } \violI
  \new Staff \with {
    instrumentName = "Violin II"
    shortInstrumentName = "V II"
    \RemoveAllEmptyStaves
    \override VerticalAxisGroup.remove-layer = 1
  } \violII
>>

```

The image displays a musical score with four staves. The first staff is labeled 'Violins' and contains a treble clef, a common time signature 'C', and a series of eighth notes. The second staff is labeled 'V I & II' and contains a treble clef, a common time signature, and a series of eighth notes. The third staff is labeled 'V I' and 'V II' and contains a treble clef, a common time signature, and a series of eighth notes. The fourth staff is labeled 'V I & II' and contains a treble clef, a common time signature, and a series of eighth notes. The staves are grouped together with a large brace on the left.

`\RemoveAllEmptyStaves` can also be used to create ossia sections for a staff. For details, see Section 6.2.2 [Ossia staves], page 253.

Predefined commands

`\RemoveEmptyStaves`, `\RemoveAllEmptyStaves`.

See also

Music Glossary: Section “Frenched staff” in *Music Glossary*.

Learning Manual: Section “Visibility and color of objects” in *Learning Manual*.

Notation Reference: Section 33.5 [Changing context default settings], page 744, Section 6.2.1 [Staff symbol], page 249, Section 6.2.2 [Ossia staves], page 253, Section 7.1.4 [Hidden notes], page 288, Section 2.2.2 [Invisible rests], page 69, Section 36.7 [Visibility of objects], page 782, Section B.22 [Context modification identifiers], page 962, Section 6.1.2 [Grouping staves], page 243, Section 33.4 [Modifying context plug-ins], page 743.

Installed Files: `ly/engraver-init.ly`.

Snippets: Section “Staff notation” in *Snippets*.

Internals Reference: Section “ChordNames” in *Internals Reference*, Section “FiguredBass” in *Internals Reference*, Section “Lyrics” in *Internals Reference*, Section “Staff” in *Internals Reference*, Section “VerticalAxisGroup” in *Internals Reference*, Section “Staff-symbol-engraver” in *Internals Reference*, Section “Axis-group-engraver” in *Internals Reference*, Section “Keep-alive-together-engraver” in *Internals Reference*.

Known issues and warnings

Removing `Staff_symbol_engraver` also hides bar lines. If bar line visibility is forced, formatting errors may occur. In this case, use the following overrides instead of removing the engraver:

```
\omit StaffSymbol
\override NoteHead.no-ledgers = ##t
```

For the Known issues and warnings associated with `\RemoveEmptyStaves` see Section 33.5 [Changing context default settings], page 744.

6.3 Writing parts

This section explains how to prepare parts for orchestral or ensemble music, which often requires to insert instrument names into the score. Methods to quote other voices and to format cue notes are also described, as well as a way to contract multiple consecutive empty measures in individual parts.

Additionally, a method for printing *divisi* staves, sometimes used in individual or desk parts, can be found in Section 6.2.3 [Hiding staves], page 256.

6.3.1 Instrument names

Instrument names can be printed on the left side of staves in the `Staff`, `PianoStaff`, `StaffGroup`, `GrandStaff` and `ChoirStaff` contexts. The value of `instrumentName` is used for the first staff, and the value of `shortInstrumentName` is used for all succeeding staves.

```
\new Staff \with {
  instrumentName = "Violin "
  shortInstrumentName = "Vln. "
} \relative {
  c'4.. g'16 c4.. g'16 \break | c1 |
}
```





`\markup` can be used to create more complex instrument names:

```
\new Staff \with {
  instrumentName = \markup {
    \column { "Clarineti"
      \line { "in B" \smaller \flat }
    }
  }
} \relative {
  c''4 c,16 d e f g2
}
```



When two or more staff contexts are grouped together, the instrument names and short instrument names are centered by default. To center multi-line instrument names, `\center-column` must be used:

```
<<
  \new Staff \with {
    instrumentName = "Flute"
  } \relative {
    f''2 g4 f
  }
  \new Staff \with {
    instrumentName = \markup {
      \center-column { "Clarinet"
        \line { "in B" \smaller \flat }
      }
    }
  } \relative { c''4 b c2 }
>>
```



However, if the instrument names are longer, the instrument names in a staff group may not be centered unless the indent and short-indent settings are increased. For details about these settings, see Section 26.5.3 [paper variables for shifts and indents], page 676.

```

<<
  \new Staff \with {
    instrumentName = "Alto Flute in G"
    shortInstrumentName = "Flt."
  } \relative {
    f''2 g4 f \break
    g4 f g2
  }
  \new Staff \with {
    instrumentName = "Clarinet"
    shortInstrumentName = "Clar."
  } \relative {
    c'4 b c2 \break
    c2 b4 c
  }
>>

\layout {
  indent = 3.0\cm
  short-indent = 1.5\cm
}

```

The image displays a musical score with four staves. The first two staves are grouped under the label 'Alto Flute in G' and 'Clarinet' respectively. The next two staves are grouped under the label 'Flt.' and 'Clar.' respectively. The notation shows a sequence of notes: f''2, g4, f, g4, f, g2 for the first staff; c'4, b, c2, c2, b4, c for the second staff. The third staff starts with a '2' above it, indicating a second ending or measure repeat.

To add instrument names to other contexts (such as ChordNames or FiguredBass), `Instrument_name_engraver` must be added to that context. For details, see Section 33.4 [Modifying context plug-ins], page 743.

The `shortInstrumentName` may be changed in the middle of a piece, along with other settings as needed for the new instrument. However, only the first instance of `instrumentName` will be printed and subsequent changes will be ignored:

```

prepPiccolo = <>^\markup \italic { muta in Piccolo }

prepFlute = <>^\markup \italic { muta in Flauto }

setPiccolo = {
  <>^\markup \bold { Piccolo }
  \transposition c''
}

setFlute = {




```

```

<>^\markup \bold { Flute }
\transposition c'
}

\new Staff \with {
  instrumentName = "Flute"
  shortInstrumentName = "Flt."
}
\relative {
  g'1 g g g \break
  g1 g \prepPiccolo R R \break
  \set Staff.instrumentName = "Piccolo"
  \set Staff.shortInstrumentName = "Picc."
  \setPiccolo
  g1 g g g \break
  g1 g \prepFlute R R \break
  \set Staff.instrumentName = "Flute"
  \set Staff.shortInstrumentName = "Flt."
  \setFlute
  g1 g g g
}

```



See also

Notation Reference: Section 26.5.3 [\paper variables for shifts and indents], page 676, Section 33.4 [Modifying context plug-ins], page 743.

Snippets: Section “Staff notation” in *Snippets*.

Internals Reference: Section “InstrumentName” in *Internals Reference*, Section “Piano-Staff” in *Internals Reference*, Section “Staff” in *Internals Reference*.

6.3.2 Quoting other voices

It is very common for one voice to use the same notes as those from another voice. For example, first and second violins playing the same phrase during a particular passage of the music. This is done by letting one voice *quote* the other, without having to reenter the music all over again for the second voice.

The `\addQuote` command, used in the top level scope, defines a stream of music from which fragments can be quoted.

The `\quoteDuring` command is used to indicate the point where the quotation begins. It is followed by two arguments: the name of the quoted voice, as defined with `\addQuote`, and a music expression for the duration of the quote.

```
fluteNotes = \relative {
  a'4 gis g gis | b4~"quoted" r8 ais\p a4( f)
}

oboeNotes = \relative {
  c'4 cis c b \quoteDuring "flute" { s1 }
}

\addQuote "flute" { \fluteNotes }

\score {
  <<
    \new Staff \with { instrumentName = "Flute" } \fluteNotes
    \new Staff \with { instrumentName = "Oboe" } \oboeNotes
  >>
}
```



If the music expression used in `\quoteDuring` contains notes instead of spacer or multi-measure rests then the quote will appear as polyphony and may produce unexpected results.

```
fluteNotes = \relative {
  a'4 gis g gis | b4~"quoted" r8 ais\p a4( f)
}

oboeNotes = \relative {
  c'4 cis c b \quoteDuring "flute" { e4 r8 ais b4 a }
}

\addQuote "flute" { \fluteNotes }

\score {
  <<
    \new Staff \with { instrumentName = "Flute" } \fluteNotes
    \new Staff \with { instrumentName = "Oboe" } \oboeNotes
  >>
}
```


Flute

Oboe

quoted

quoted

p

p

```

fluteNotes = \relative {
  \repeat volta 2 { a'4 gis g gis }
}

oboeNotesDW = \relative {
  \repeat volta 2 \quoteDuring "incorrect" { s1 }
}

oboeNotesW = \relative {
  \repeat volta 2 \quoteDuring "correct" { s1 }
}

\addQuote "incorrect" { \fluteNotes }

\addQuote "correct" { \unfoldRepeats \fluteNotes }

\score {
  \unfoldRepeats
  <<
    \new Staff \with { instrumentName = "Flute" }
    \fluteNotes
    \new Staff \with { instrumentName = "Oboe (incorrect)" }
    \oboeNotesDW
    \new Staff \with { instrumentName = "Oboe (correct)" }
    \oboeNotesW
  >>
}

```

Flute

Oboe (incorrect)

Oboe (correct)

The `\quoteDuring` command uses the `\transposition` settings of both quoted and quoting parts to produce notes for the quoting part that have the same sounding pitch as those in the quoted part.

```
clarinetNotes = \relative c'' {
  \transposition bes
  \key d \major
  b4 ais a ais | cis4~"quoted" r8 bis\p b4( f)
}

oboeNotes = \relative {
  c''4 cis c b \quoteDuring "clarinet" { s1 }
}

\addQuote "clarinet" { \clarinetNotes }

\score {
  <<
    \new Staff \with { instrumentName = "Clarinet" } \clarinetNotes
    \new Staff \with { instrumentName = "Oboe" } \oboeNotes
  >>
}
```

Clarinet

Oboe

By default quoted music will include all articulations, dynamics, markups, etc., in the quoted expression. It is possible to choose which of these objects from the quoted music are displayed by using the `quotedEventTypes` context property.

```
fluteNotes = \relative {
  a'2 g2 |
  b4\<~"quoted" r8 ais a4\f( c->)
}

oboeNotes = \relative {
  c''2. b4 |
```

```

\quoteDuring "flute" { s1 }
}

\addQuote "flute" { \fluteNotes }

\score {
  <<
    \set Score.quotedEventTypes = #'(note-event articulation-event
                                     crescendo-event rest-event
                                     slur-event dynamic-event)
    \new Staff \with { instrumentName = "Flute" } \fluteNotes
    \new Staff \with { instrumentName = "Oboe" } \oboeNotes
  >>
}

```



Quotes can also be tagged, see Section 22.2.2 [Using tags], page 628.

See also

Notation Reference: Section 1.3.4 [Instrument transpositions], page 30, Section 22.2.2 [Using tags], page 628.

Installed Files: scm/define-event-classes.scm.

Snippets: Section “Staff notation” in *Snippets*.

Internals Reference: Section “Music classes” in *Internals Reference*, Section “QuoteMusic” in *Internals Reference*, Section “Voice” in *Internals Reference*.

Known issues and warnings

Only the contents of the first Voice occurring in an `\addQuote` command will be considered for quotation, so if the music expression contains `\new` or `\context Voice` statements, their contents will not be quoted. Quoting grace notes is unsupported and may cause LilyPond to crash whereas quoting nested triplets may result in poor notation.

6.3.3 Formatting cue notes

The simplest way to format cue notes is to explicitly create a `CueVoice` context within the part.

```

\relative {
  R1
  <<
    { e'2\rest r4. e8 }
    \new CueVoice {
      \stemUp d'8~"flute" c d e fis2
    }
  >>
  d,4 r a r
}

```



The `\cueClef` command can also be used with an explicit `CueVoice` context if a change of clef is required and will print an appropriately sized clef for the cue notes. The `\cueClefUnset` command can then be used to switch back to the original clef, again with an appropriately sized clef.

```
\relative {
  \clef "bass"
  R1
  <<
    { e'2\rest r4. \cueClefUnset e,8 }
    \new CueVoice {
      \cueClef "treble" \stemUp d''8^"flute" c d e fis2
    }
  >>
  d,,4 r a r
}
```



The `\cueClef` and `\cueClefUnset` commands can also be used without a `CueVoice` if required.

```
\relative {
  \clef "bass"
  R1
  \cueClef "treble"
  d''8^"flute" c d e fis2
  \cueClefUnset
  d,,4 r a r
}
```



For more complex cue note placement like including transposition, or inserting cue notes from multiple music sources, the `\cueDuring` or `\cueDuringWithClef` commands can be used. These are more specialized forms of `\quoteDuring`, see Section 6.3.2 [Quoting other voices], page 265, in the previous section.

The syntax is

```
\cueDuring quotename direction music
```

and

```
\cueDuringWithClef quotename direction clef music
```

The music from the corresponding measures of *quotename* is added as a `CueVoice` context and occurs simultaneously with *music*, which then creates a polyphonic situation. The *direction* variable takes the argument `#UP` or `#DOWN`, and corresponds to the first and second voice, respectively, determining how the cue notes are printed in relation to the other voice.

```


fluteNotes = \relative {
  r2. c''4 | d8 c d e fis2 | g2 d |
}

oboeNotes = \relative c'' {
  R1
  <>~\markup \tiny { flute }
  \cueDuring "flute" #UP { R1 }
  g2 c,
}

\addQuote "flute" { \fluteNotes }

\new Staff {
  \oboeNotes
}

```



It is possible to adjust which aspects of the music are quoted with `\cueDuring` by setting the `quotedCueEventTypes` property. Its default value is `'(note-event rest-event tie-event beam-event tuplet-span-event)`, which means that only notes, rests, ties, beams and tuplets are quoted, but not articulations, dynamic marks, markup, etc.

Note: When a Voice starts with `\cueDuring`, as in the following example, the Voice context must be explicitly declared, or else the entire music expression would belong to the CueVoice context.

```

oboeNotes = \relative {
  r2 r8 d''16(\f f e g f a)
  g8 g16 g g2.
}

\addQuote "oboe" { \oboeNotes }

\new Voice \relative c'' {
  \set Score.quotedCueEventTypes = #'(note-event rest-event tie-event
                                     beam-event tuplet-span-event
                                     dynamic-event slur-event)

  \cueDuring "oboe" #UP { R1 }
  g2 c,
}

```



Markup can be used to show the name of the quoted instrument. If the cue notes require a change in clef, this can be done manually but the original clef should also be restored manually at the end of the cue notes.

```


fluteNotes = \relative {
  r2. c''4 d8 c d e fis2 g2 d2
}

bassoonNotes = \relative c {
  \clef bass
  R1
  \clef treble
  <>^\markup \tiny { flute }
  \cueDuring "flute" #UP { R1 }
  \clef bass
  g4. b8 d2
}

\addQuote "flute" { \fluteNotes }

\new Staff {
  \bassoonNotes
}

```



Alternatively, the `\cueDuringWithClef` function can be used instead. This command takes an extra argument to specify the change of clef that needs to be printed for the cue notes but will automatically print the original clef once the cue notes have finished.

```


fluteNotes = \relative {
  r2. c''4 d8 c d e fis2 g2 d2
}

bassoonNotes = \relative c {
  \clef bass
  R1
  <>^\markup { \tiny "flute" }
  \cueDuringWithClef "flute" #UP "treble" { R1 }
  g4. b8 d2
}

\addQuote "flute" { \fluteNotes }

\new Staff {
  \bassoonNotes
}

```



Like `\quoteDuring`, `\cueDuring` takes instrument transpositions into account. Cue notes are produced at the pitches that would be written for the instrument receiving the cue to produce the sounding pitches of the source instrument.


To transpose cue notes differently, use `\transposedCueDuring`. This command takes an extra argument to specify (in absolute mode) the printed pitch that you want to represent the sound of a concert middle C. This is useful for taking cues from an instrument in a completely different register.

```
piccoloNotes = \relative {
  \clef "treble^8"
  R1
  c''8 c c e g2
  c4 g g2
}

bassClarinetNotes = \relative c' {
  \key d \major
  \transposition bes,
  d4 r a r
  \transposedCueDuring "piccolo" #UP d { R1 }
  d4 r a r
}

\addQuote "piccolo" { \piccoloNotes }

<<
  \new Staff \piccoloNotes
  \new Staff \bassClarinetNotes
>>
```



The `\killCues` command removes cue notes from a music expression, so the same music expression can be used to produce the instrument part with cues and the score. The `\killCues` command removes only the notes and events that were quoted by `\cueDuring`. Other markup associated with cues, such as clef changes and a label identifying the source instrument, can be tagged for selective inclusion in the score; see Section 22.2.2 [Using tags], page 628.

```
fluteNotes = \relative {
  r2. c''4 d8 c d e fis2 g2 d2
}

bassoonNotes = \relative c {
  \clef bass
  R1
  \tag #'part {
    \clef treble
    <>^\markup \tiny { flute }
  }
  \cueDuring "flute" #UP { R1 }
  \tag #'part \clef bass
```

```

    g4. b8 d2
  }

  \addQuote "flute" { \fluteNotes }

  \new Staff {
    \bassoonNotes
  }

  \new StaffGroup <<
    \new Staff {
      \fluteNotes
    }
    \new Staff {
      \removeWithTag #'part { \killCues { \bassoonNotes } }
    }
  >>

```



See also

Notation Reference: Section 6.3.2 [Quoting other voices], page 265, Section 1.3.4 [Instrument transpositions], page 30, Section 6.3.1 [Instrument names], page 261, Section 1.3.1 [Clef], page 19, Section 9.6.3 [Musical cues], page 395, Section 22.2.2 [Using tags], page 628.

Snippets: Section “Staff notation” in *Snippets*.

Internals Reference: Section “CueVoice” in *Internals Reference*, Section “Voice” in *Internals Reference*.

Known issues and warnings

Collisions can occur with rests, when using `\cueDuring`, between `Voice` and `CueVoice` contexts. When using `\cueDuringWithClef` or `\transposedCueDuring` the extra argument required for each case must come after the quote and the direction.


6.3.4 Compressing empty measures

By default, all measures are printed even if they are empty – which can happen if a rhythmic event (such as notes, rests or invisible rests) is so long as to span several measures. This behavior can be changed by contracting all empty measures into a single one, as illustrated here (the second part of this example, with expanded measures, actually reverts back to the default behavior):


```

\override Score.BarNumber.break-visibility = ##(f #t #t)
\time 2/4
\compressEmptyMeasures
c'1 d'1. e'\breve
\bar "||"
\expandEmptyMeasures
c'1 d'1. e'\breve

```




Although that notation is syntactically correct, it may be confusing from a musical point of view, as illustrated in the previous example; hence the need for measure numbers to be explicitly printed, using the syntax described in Section 36.7.4 [Using break-visibility], page 784.

Where such a notation may become more useful is when applied to Section 2.2.3 [Full measure rests], page 71. A multi-measure rest will then be shown as a single measure containing a multi-measure rest symbol, with the number of measures of rest printed above the measure:

```

% Default behavior
\time 3/4 r2. | R2.*2 |
\time 2/4 R2 |
\time 4/4
% Rest measures contracted to single measure
\compressEmptyMeasures
r1 | R1*17 | R1*4 |
\expandEmptyMeasures
% Rest measures expanded again
\time 3/4
R2.*2 |

```



Unlike `\compressEmptyMeasures`, the music function `\compressMMRests` will only apply to rests, leaving any other events uncompressed. As a function rather than a property setting, its syntax differs slightly in that it must be followed by a music expression:

```

\compressMMRests {
  % Rests are compressed...
  R1*7
  % ... but notes can still span multiple measures.
  g'1 a'1*2 d'1
  R1*2
}

```



All of the commands described in this section actually rely on the `skipBars` internal property, which is set in the `Score` context, see Section 35.2 [`\set` and `\unset`], page 758.

Predefined commands


`\compressEmptyMeasures`, `\expandEmptyMeasures`, `\compressMMRests`.

Selected snippets

Numbering single measure rests

Multi-measure rests show their length by a number except for single measures. This can be changed by setting `restNumberThreshold`.


```
{
  \compressEmptyMeasures
  R1 R1*10 R1*11 \bar "||"
  \set restNumberThreshold = 0
  R1 R1*10 R1*11 \bar "||"
  \set restNumberThreshold = 10
  R1 R1*10 R1*11
}
```



Changing form of multi-measure rests

If there are ten or fewer measures of rests, a series of longa and breve rests (called in German “Kirchenpausen” – church rests) is printed within the staff; otherwise a long, thick horizontal line is shown. This default value of ten may be changed by overriding the `expand-limit` property.

```
\relative c' {
  \compressMMRests {
    R1*2 | R1*5 | R1*9
    \override MultiMeasureRest.expand-limit = 3
    R1*2 | R1*5 | R1*9
  }
}
```




See also

Notation Reference: Section 36.7.4 [Using break-visibility], page 784, Section 2.2.3 [Full measure rests], page 71, Section 35.2 [`\set` and `\unset`], page 758.

Internals Reference: Section “MultiMeasureRest” in *Internals Reference*, Section “MultiMeasureRestNumber” in *Internals Reference*, Section “MultiMeasureRestScript” in *Internals Reference*, Section “MultiMeasureRestText” in *Internals Reference*.

7 Editorial annotations



This section discusses the various ways to change the appearance of notes and add analysis or educational emphasis.

7.1 Inside the staff

This section discusses how to add emphasis to elements that are inside the staff.

7.1.1 Selecting notation font size

Note:

For font sizes of text, see Section 8.2.2 [Selecting font and font size], page 323.

For staff size, see Section 27.2 [Setting the staff size], page 683.

For cue notes, see Section 6.3.3 [Formatting cue notes], page 268.

For ossia staves, see Section 6.2.2 [Ossia staves], page 253.

To change the size of the notation without changing the staff size, specify a magnification factor with the `\magnifyMusic` command:

```
\new Staff <<
  \new Voice \relative {
    \voiceOne
    <e' e'>4 <f f'>8. <g g'>16 <f f'>8 <e e'>4 r8
  }
  \new Voice \relative {
    \voiceTwo
    \magnifyMusic 0.63 {
      \override Score.SpacingSpanner.spacing-increment = #(* 1.2 0.63)
      r32 c' a c a c a c r c a c a c a c
      r c a c a c a c a c a c a c a c
    }
  }
>>
```




The `\override` in the example above is a bug workaround. See the “Known issues and warnings” at the end of this section.

If a normal sized note head is merged with a smaller one, the size of the smaller note may need to be reset (with `\once \normalsize`) so that the stems and accidentals align properly:

```
\new Staff <<
  \key fis \minor
  \mergeDifferentlyDottedOn
  \new Voice \relative {
    \voiceOne
    \magnifyMusic 0.63 {
      \override Score.SpacingSpanner.spacing-increment =
        #(* 1.2 0.63)

      \once \normalsize cis'32( cis' gis b a fis
        \once \normalsize d d'
      \once \normalsize cis, cis' gis b a gis
        \once \normalsize fis fis'
      \once \normalsize fis, fis' ais, cis b gis
        \once \normalsize eis eis'
      \once \normalsize a, a' bis, d cis b
        \once \normalsize gis gis')
    }
  }
  \new Voice \relative {
    \voiceTwo
    cis'8. d16 cis8. fis16 fis8. eis16 a8. gis16
  }
}>>
```



The `\magnifyMusic` command is not intended for cue notes, grace notes, or ossia staves—there are more appropriate methods of entering each of those constructs. Instead, it is useful when the notation size changes in a single instrumental part on one staff, and where grace notes are not appropriate, such as in cadenza-like passages or in cases such as the above examples. Setting the `\magnifyMusic` value to 0.63 duplicates the dimensions of the CueVoice context.

Note: The `\magnifyMusic` command should *not* be used when also resizing the staff. See Section 27.2 [Setting the staff size], page 683.

Resizing individual layout objects

An individual layout object can be resized by using the `\tweak` or `\override` commands to adjust its font-size property:

it scale stems, beams, or horizontal spacing. To scale stems, beams, and horizontal spacing along with the notation size (without changing the staff size), use the `\magnifyMusic` command discussed above. To scale everything, including the staff size, see Section 27.2 [Setting the staff size], page 683.

Whenever the `fontSize` *context property* is set, its value is added to the value of the `font-size` *grob property* for individual layout objects, before any glyphs are printed. This can cause confusion when setting individual font-size properties while `fontSize` is already set:

```
% the default font-size for NoteHead is 0
% the default font-size for Fingering is -5
c''4-3

\set fontSize = -3
% the effective font size for NoteHead is now -3
% the effective font size for Fingering is now -8
c''4-3

\override Fingering.font-size = 0
% the effective font size for Fingering is now -3
c''4-3
```



The following shorthand commands are also available:

Command	Equivalent to	Relative size
<code>\teeny</code>	<code>\set fontSize = -3</code>	71%
<code>\tiny</code>	<code>\set fontSize = -2</code>	79%
<code>\small</code>	<code>\set fontSize = -1</code>	89%
<code>\normalsize</code>	<code>\set fontSize = 0</code>	100%
<code>\large</code>	<code>\set fontSize = 1</code>	112%
<code>\huge</code>	<code>\set fontSize = 2</code>	126%

```
\relative c'' {
  \teeny
  c4.-> d8---3
  \tiny
  c4.-> d8---3
  \small
  c4.-> d8---3
  \normalsize
  c4.-> d8---3
  \large
  c4.-> d8---3
  \huge
  c4.-> d8---3
}
```



Font size changes are achieved by scaling the design size that is closest to the desired size. The standard font size (for `font-size = 0`) depends on the standard staff height. For a 20 pt staff, an 11 pt font is selected.

Predefined commands

`\magnifyMusic`, `\teeny`, `\tiny`, `\small`, `\normalsize`, `\large`, `\huge`.

See also

Notation Reference: Section 8.2.2 [Selecting font and font size], page 323, Section 27.2 [Setting the staff size], page 683, Section 6.3.3 [Formatting cue notes], page 268, Section 6.2.2 [Ossia staves], page 253.

Installed Files: `ly/music-functions-init.ly`, `ly/property-init.ly`.

Snippets: Section “Editorial annotations” in *Snippets*.

Internals Reference: Section “font-interface” in *Internals Reference*.

Known issues and warnings

There are currently two bugs that are preventing proper horizontal spacing when using `\magnifyMusic`. There is only one available workaround, and it is not guaranteed to work in every case. In the example below, replace the *mag* variable with your own value. You may also try removing one or both of the `\newSpacingSection` commands, and/or the `\override` and `\revert` commands:

```
\magnifyMusic mag {
  \newSpacingSection
  \override Score.SpacingSpanner.spacing-increment = #(* 1.2 mag)
  [music]
  \newSpacingSection
  \revert Score.SpacingSpanner.spacing-increment
}
```

7.1.2 Fingering instructions

LilyPond provides two engravers for handling fingering instructions. In both cases, the fingering can be entered using the syntax ‘*note-digit*’.

- The first engraver is `Fingering_engraver`, which takes care of fingering instructions that are outside of chord constructs (i.e., outside of `<...>`). The order of fingering given in the input code is directly reflected in the output, and the fingering markup is always stacked vertically within a single column above or below the note or chord.

```
\relative {
  c''4-1 d-2 f-4 e-3 |
  <g, b f' g>2_2_1^4^5 <g a c e>_2_1^3^5
}
```



If you want markup texts or strings for fingering, use the `\finger` command instead.


```
\relative {
  c''4-1 d-2 f\finger \markup \tied-lyric "4~3" c\finger "2 - 3"
}
```



- The second engraver is `New_fingering_engraver`, which handles fingering instructions, articulations, and harmonic note heads inside of chords (i.e., inside of `<...>`).

```
\relative {
  <g'-1 b-2 f'-4 g-5>2 <e'-5 c-3 a-2 g-1>
}
```



A thumb fingering can also be added (e.g., for cello music) to indicate that a note should be played with the thumb.

```
\relative { <a'_{\thumb a'-3}>2 <b_{\thumb b'-3}> }
```



Fingering instructions may be manually placed above or below the staff, see Section 36.1 [Direction and placement], page 772.

See the next section for snippet examples that demonstrate how to control the positioning of fingering instructions.

Selected snippets

Controlling the placement of chord fingerings


The placement of fingering numbers can be controlled precisely by using the property `fingeringOrientation`. For fingering orientation to apply, the fingering command must be used within a chord construct (`<...>`), even for single notes. Orientation for string numbers and right-hand fingerings may be controlled in a similar way by using the properties `stringNumberOrientation` and `strokeFingerOrientation`, respectively.

These properties can be set to a list of one to three values. They control whether fingerings may be placed above (if up appears in the list), below (if down appears), to the left (if left appears), or to the right (if right appears). Conversely, if a location is not listed, no fingering is placed there. LilyPond takes these constraints and works out the best placement for the fingering of the notes of the following chords. Note that left and right are mutually exclusive – fingerings may be placed only on one side or the other, not both.

```

\relative c' {
  \set fingeringOrientations = #'(left)
  <c-1 e-3 a-5>4
  \set fingeringOrientations = #'(down)
  <c-1 e-3 a-5>4
  \set fingeringOrientations = #'(down right up)
  <c-1 e-3 a-5>4
  \set fingeringOrientations = #'(up)
  <c-1 e-3 a-5>4
  \set fingeringOrientations = #'(left)
  <c-1>2
  \set fingeringOrientations = #'(down)
  <e-3>2
  \set stringNumberOrientations = #'(up left down)
  <f\3 a\2 c\1>1
  \set strokeFingerOrientations = #'(down right up)
  <c\rightHandFinger 1 e\rightHandFinger 2 c'\rightHandFinger 4 >
}

```



Allowing fingerings to be printed inside the staff

By default, vertically oriented fingerings are positioned outside the staff; that behavior, however, may be disabled. Attention needs to be paid to situations where fingerings and stems are in the same direction: by default, fingerings will avoid only beamed stems. That setting can be changed to avoid no stems or all stems; the following example demonstrates these two options, as well as how to go back to the default behavior.

```

\relative c' {
  <c-1 e-2 g-3 b-5>2
  \override Fingering.staff-padding = #'()
  <c-1 e-2 g-3 b-5>4 g'-0
  a8[-1 b]-2 g-0 r
  \override Fingering.add-stem-support = ##f
  a[-1 b]-2 g-0 r
  \override Fingering.add-stem-support = ##t
  a[-1 b]-2 g-0 r
  \override Fingering.add-stem-support = #only-if-beamed
  a[-1 b]-2 g-0 r
}

```



See also

Notation Reference: Section 36.1 [Direction and placement], page 772.

Snippets: Section “Editorial annotations” in *Snippets*.


Internals Reference: Section “FingeringEvent” in *Internals Reference*, Section “fingering-event” in *Internals Reference*, Section “Fingering-engraver” in *Internals Reference*, Section “New_fingering-engraver” in *Internals Reference*, Section “Fingering” in *Internals Reference*.

7.1.3 Gliding fingers

For stringed instruments a gliding finger is often indicated by a line connecting the same finger to be used for notes played at different positions on the same string. This line is initiated with `\glide` entered before a Fingering and ends with the next occurrence of the same finger. The line may be printed in various styles.

```
mus = {
  \set fingeringOrientations = #'(right)
  <a'\glide-1>2.
  \set fingeringOrientations = #'(left)
  <d'-1>4
}

{
  <>^"line"
  \mus
  <>^"stub-left"
  \override FingerGlideSpanner.style = #'stub-left
  \mus
  <>^"stub-right"
  \override FingerGlideSpanner.style = #'stub-right
  \mus
  <>^"stub-both"
  \override FingerGlideSpanner.style = #'stub-both
  \mus
  <>^"dashed-line"
  \override FingerGlideSpanner.style = #'dashed-line
  \mus
  \break
  <>^"dotted-line"
  \override FingerGlideSpanner.style = #'dotted-line
  \mus
  <>^"bow"
  \override FingerGlideSpanner.style = #'bow
  \mus
  <>^"trill"
  \override FingerGlideSpanner.style = #'trill
  \mus
  <>^"zigzag"
  \override FingerGlideSpanner.style = #'zigzag
  \mus
}
```





If style is set to 'bow the direction of the bow may be adjusted using direction modifiers.

```
{
  \override FingerGlideSpanner.style = #'bow
  \set fingeringOrientations = #'(down)
  <b\glide-1>4 <d'-1>
  \set fingeringOrientations = #'(up)
  <e''\glide-2> <c''-2>

  \set fingeringOrientations = #'(down)
  <b^\glide-1>4 <d'-1>
  \set fingeringOrientations = #'(up)
  <e''^\glide-2> <c''-2>

  \set fingeringOrientations = #'(down)
  <b_\glide-1>4 <d'-1>
  \set fingeringOrientations = #'(up)
  <e''_\glide-2> <c''-2>
}
```




If the Finger_glide_engraver is moved to Staff context Fingering grobs from different Voice contexts may be connected.

```
\score {
  \new Staff <<
    \new Voice {
      \voiceOne
      \set fingeringOrientations = #'(right)
      <e''-3>2
      \set fingeringOrientations = #'(left)
      <d''-\tweak bound-details.left.padding 2.5 \glide-2>
      <c''-2>
      \bar "||"
    }
    \new Voice {
      \voiceTwo
      \set fingeringOrientations = #'(right)
      <c''\glide-2>
      \set fingeringOrientations = #'(left)
      <b''-\tweak bound-details.left.padding 2.5 \glide-4>
      <a'-4>
    }
  }
  >>
  \layout {
    ragged-right = ##f
  }
```

```

\context {
  \Voice
  \remove Finger_glide_engraver
}
\context {
  \Staff
  \consists Finger_glide_engraver
}
}

```




To connect different fingers or multiple instances of the same finger set the `id` property with `\=` taking a non-negative integer or a symbol or `\tweak` the text property.

```

{
  b2 \glide \= #'foo ^1
  \glide \= #'bar ^1
  \glide _2
  \glide _1
  b' \= #'foo ^2
  \= #'bar ^1
  _2
  _1

  \set fingeringOrientations = #'(up)
  <
    b\glide \=1 -1
    f'\glide \=2 -2
    d''\glide \=3 -3
    b''\glide \=4 -4
  >
  <
    b\=4 -5
    f'\=3 -6
    d''\=2 -7
    b''\=1 -8
  >
  b\glide -1 b\tweak text "2" -1
}

```




The `FingerGlideSpanner` may also connect string numbers indicating to play on the same string, or stroke fingers indicating an *Arrastre*.

```

{
  \override StringNumber.staff-padding = 7
  \omit TupletNumber
  \set fingeringOrientations = #'(left)
  \tuplet 5/4 4 {
    \set strokeFingerOrientations = #'(down)
    <
      g-\tweak style #'stub-right \glide-1
      \glide \rightHandFinger #1
      -\tweak style #'dashed-line \glide _\6
    >16
    <d'-\tweak style #'stub-right \glide -3 >
    <g'-\tweak style #'stub-right \glide -4 \rightHandFinger #1 >
    \set strokeFingerOrientations = #'(up)
    <b'-\tweak style #'stub-right \glide -2 \rightHandFinger #2 >
    <b'-0\rightHandFinger #3 >
    e''\glide \rightHandFinger #4
    b' a' f' c'
  }
  g2\rightHandFinger #4

  \tuplet 5/4 4 {
    \set strokeFingerOrientations = #'(down)
    <f-1 \glide \rightHandFinger #1 _\6 >16
    % Raise a bit, otherwise the stub line would be hidden
    % by the ledger line.
    <c'\tweak Y-offset #0.5 -3>
    <f' -4 \rightHandFinger #1 >
    \set strokeFingerOrientations = #'(up)
    <a'-2\rightHandFinger #2 >
    b'\rightHandFinger #3
    e''\glide \rightHandFinger #4
    b' a' f' c'
  }
  f2\rightHandFinger #4
}

```



See also

Music Glossary: Section “arrastre” in *Music Glossary*.


Notation Reference: Section 36.1 [Direction and placement], page 772.

Internals Reference: Section “FingerGlideEvent” in *Internals Reference*, Section “finger-glide-event” in *Internals Reference*, Section “Finger_glide_engraver” in *Internals Reference*, Section “finger-glide-interface” in *Internals Reference*, Section “FingerGlideSpanner” in *Internals Reference*.

7.1.4 Hidden notes

Hidden (or invisible or transparent) notes can be useful in preparing theory or composition exercises.

```
\relative {
  c' '4 d
  \hideNotes
  e4 f
  \unHideNotes
  g a
  \hideNotes
  b
  \unHideNotes
  c
}
```



Note heads, stems, and flags, and rests are invisible. Beams are invisible if they start on a hidden note. Objects that are attached to invisible notes are still visible.

```
\relative c' ' {
  e8(\p f g a)--
  \hideNotes
  e8(\p f g a)--
}
```



Predefined commands

\hideNotes, \unHideNotes.

See also

Learning Manual: Section “Visibility and color of objects” in *Learning Manual*.

Notation Reference: Section 2.2.2 [Invisible rests], page 69, Section 36.7 [Visibility of objects], page 782, Section 6.2.3 [Hiding staves], page 256.

Snippets: Section “Editorial annotations” in *Snippets*.

Internals Reference: Section “Note-spacing-engraver” in *Internals Reference*, Section “NoteSpacing” in *Internals Reference*.

7.1.5 Coloring objects

Individual objects may be assigned colors. Valid color names are listed in the Section B.7 [List of colors], page 900.

```

\override NoteHead.color = #red
c''4 c''
\override NoteHead.color = #(x11-color 'SlateGrey)
d''
\override Stem.color = "deepskyblue"
e''

```



In addition to a limited set of simple colors available as predefined variables (see ‘Normal colors’ in Section B.7 [List of colors], page 900), any color may be entered as a string. That string may be either a CSS (<https://www.w3.org/Style/CSS/>)-style predefined color name, or a hexadecimal color code prefixed by the ‘#’ character (*inside* the double quotes):

```

\override NoteHead.color = "lightsalmon"
\override Flag.color = "#E30074"
\override Beam.color = "#5e45ad"
\override Rest.color = "#3058"
g'8 \huge r4 a'16 f'

```



If that color code includes an alpha channel for semi-transparency, by using an eight-character code “#RRGGBBAA” or its shorthand form “#RGBA”, it will be used in SVG output but not in PostScript/PDF output. In the previous example, the rest can be seen through only if the code is compiled with the SVG backend, as explained in Section 23.3 [Alternative output formats], page 648.

In a different way, the full range of colors defined for X11 (https://en.wikipedia.org/wiki/X11_color_names) can be accessed by using the Scheme function `x11-color`. That function takes one argument, which can be a symbol, such as ‘DarkSeaGreen4’, or a string, such as “DarkSeaGreen4”. The first form is quicker to write and slightly more efficient; however, the second form also makes it possible to specify X11 colors as multiple words: in this instance, “dark sea green 4”.

If `x11-color` cannot make sense of the parameter, then the color returned defaults to black.

```

\new Staff \with {
  instrumentName = \markup {
    \with-color #(x11-color 'SlateGrey) "Clarinet"
  }
}
\relative c'' {
  \override Staff.StaffSymbol.color = #(x11-color 'SlateBlue2)
  gis8 a
  \override Beam.color = #(x11-color "medium turquoise")
  gis a
  \override Accidental.color = #(x11-color 'orange)
  gis a
  \override NoteHead.color = #(x11-color "LimeGreen")
  gis a
  % this is deliberate nonsense; note that the stems remain black

```



```
\override Stem.color = #(x11-color 'Boggle)
b2 cis
}
```



LilyPond also supports a set of eight color names (<https://jfly.uni-koeln.de/color>) that is unambiguous to both color-blind and non-color-blind people. Use `universal-color` to access them.

```
\markup \with-color #(universal-color 'vermillion) vermillion
```

vermillion

Exact RGB colors can be specified using the Scheme function `rgb-color`. This function takes three arguments used respectively for the *red*, *green* and *blue* channels, and an optional *alpha* number for semi-transparency. (All values must be numbers from 0 to 1.) Again, transparency is only supported in SVG output; for example, in the following fragment the staff's clef can be seen through when rendered in SVG.

```
\new Staff \with {
  instrumentName = \markup {
    \with-color #(x11-color 'red) "Clarinet"
  }
  \override Clef.color = #(rgb-color 0 0 0 0.5)
}
\relative c'' {
  \override Staff.StaffSymbol.color = #(x11-color 'SlateBlue2)
  \override Stem.color = #(rgb-color 0 0 0)
  gis8 a
  \override Stem.color = #(rgb-color 1 1 1)
  gis8 a
  \override Stem.color = #(rgb-color 0 0 0.5)
  gis4 a
}
```



See also

Notation Reference: Section B.7 [List of colors], page 900, Section 35.6 [`\tweak` and `\single`], page 762.

Snippets: Section “Editorial annotations” in *Snippets*.

Known issues and warnings

An X11 color is not necessarily exactly the same shade as a similarly named normal color.

Not all X11 colors are distinguishable in a web browser, i.e., a web browser might not display a difference between `LimeGreen` and `ForestGreen`. For web use CSS colors are recommended, as detailed in Section B.7 [List of colors], page 900.

Notes in a chord cannot be separately colored with `\override`; use `\tweak` or the equivalent `\single\override` before the respective note instead, see Section 35.6 [`\tweak` and `\single`], page 762.

7.1.6 Staff highlights


For analytical or pedagogical purposes, it may be useful to “highlight” musical passages, for example in order to show local tonality. This can be done using the `\staffHighlight` command, which expects a color. For all ways to enter colors, see Section 7.1.5 [Coloring objects], page 288. The highlight is terminated using `\stopStaffHighlight`.

```
\relative {
  \time 2/4
  c'4 4
  \staffHighlight "lightsteelblue"
  g'8( fis g4)-.
  \stopStaffHighlight
  c2
}
```



If there are consecutive highlights, it is not necessary to write `\stopStaffHighlight`, as `\staffHighlight` also implicitly terminates the current highlight, if any. Similarly, it is not necessary to add `\stopStaffHighlight` at the end of the piece. This is particularly handy if every measure is to be highlighted.


```
\relative {
  \time 2/4
  \staffHighlight "lightpink"
  c'4 4
  \staffHighlight "lightsteelblue"
  g'8( fis g4)-.
  \staffHighlight "lightpink"
  c2
}
```



By default, staves are highlighted separately.

```
music = {
  \time 2/4
  \staffHighlight "lightpink"
  c'4 4
  \staffHighlight "lightsteelblue"
  g'8( fis g4)-.
  \staffHighlight "lightpink"
  c2
}
```

```
<<
  \new Staff \music
  \new Staff \music
>>
```




However, several staves can be highlighted together by moving `Staff_highlight_engraver` to a higher context than `Staff` (or `RhythmicStaff`, or similar). This is done using the `\consists` and `\remove` commands; See Section 33.4 [Modifying context plug-ins], page 743, for more information. For example, if the engraver is moved to `Score`, the highlights are shared by all staves.

```
\layout {
  \context {
    \Staff
    \remove Staff_highlight_engraver
  }
  \context {
    \Score
    \consists Staff_highlight_engraver
  }
}

music = {
  \time 2/4
  \staffHighlight "lightpink"
  c'4 4
  \staffHighlight "lightsteelblue"
  g'8( fis g4)-.
  \staffHighlight "lightpink"
  c2
}

<<
  \new Staff \music
  \new Staff \music
>>
```




`Staff_highlight_engraver` may also be moved to intermediate contexts such as `StaffGroup`.

```

music = {
  \time 2/4
  \staffHighlight "lightpink"
  c'4 4
  \staffHighlight "lightsteelblue"
  g'8( fis g4)-.
  \staffHighlight "lightpink"
  c2
}

<<
  \new StaffGroup \with { \consists Staff_highlight_engraver } <<
    \new Staff \with { \remove Staff_highlight_engraver } \music
    \new Staff \with { \remove Staff_highlight_engraver } \music
  >>
  \new Staff \music
>>

```



The `StaffHighlight.shorten-pair` property may be used to tweak the horizontal start and end of the highlight span.

```

{
  c'1
  \once \override Staff.StaffHighlight.shorten-pair = #'(1.0 . 1.0)
  \staffHighlight lightsteelblue
  c'1
}

```



Predefined commands

`\staffHighlight`, `\stopStaffHighlight`.

See also

Notation Reference: Section 7.1.5 [Coloring objects], page 288, Section 33.4 [Modifying context plug-ins], page 743.


Internals Reference: Section “StaffHighlight” in *Internals Reference*, Section “staff-highlight-interface” in *Internals Reference*, Section “Staff_highlight_engraver” in *Internals*

Reference, Section “StaffHighlightEvent” in *Internals Reference*, Section “staff-highlight-event” in *Internals Reference*.

Known issues and warnings

The behavior of highlights may not be what is expected at start repeat bar lines. The shorten-pair property demonstrated above can be used to work around this issue.

```
{
  \staffHighlight "lightsteelblue"
  c'1
  \stopStaffHighlight
  \repeat volta 2 { c'1 }
  c'1
}
```



7.1.7 Brackets for optional material

Optional additional material can be enclosed in brackets that pass through the staff.

```
{
  \startOptionalMaterial
  c'1
  \stopOptionalMaterial
}
```



The note positions that the bracket encompasses can be overridden. The endpoints of the interval are measured in staff spaces from the center of the staff to the center of the note.

```
{
  \tweak OptionalMaterialBracket.positions #'(-4 . 1)
  \startOptionalMaterial
  c'1
  \once \override Staff.OptionalMaterialBracket.positions =
  #'(-2 . 4)
  \stopOptionalMaterial
}
```



Predefined commands

`\startOptionalMaterial`, `\stopOptionalMaterial`.

See also

Snippets: Section “Editorial annotations” in *Snippets*.

Internals Reference: Section “Optional_material_bracket_engraver” in *Internals Reference*, Section “OptionalMaterialBracket” in *Internals Reference*, Section “optional-material-bracket-interface” in *Internals Reference*.

7.1.8 Parentheses

Objects may be parenthesized by prefixing the music event with `\parenthesize`.

```
\relative {
  c'2 \parenthesize d
  c2 \tweak Parentheses.font-size 2 \parenthesize <c e g>
  c2 <c e \parenthesize g>
}
```



Non-note objects may be parenthesized as well. For articulations, a hyphen is needed before the `\parenthesize` command.

```
\relative {
  c'2-\parenthesize -. d
  c2 \parenthesize r
}
```




To parenthesize a group of notes in a chord, use a parallel music construct `<< ... >>`.

```
\new Voice \relative c {
  <<
    { \tweak Parentheses.font-size 0 \parenthesize <ces des> }
    { \parenthesize ees' }
    { \tweak Parentheses.font-size -2 \parenthesize <c' e> }
  >>
}
```



In tablature specify `NoteColumn` to parenthesize the chord.

```
\new TabVoice {
  \override Parentheses.font-size = 0
  \parenthesize <f g>
  \parenthesize NoteColumn <f g>
}
```



This second form of the `\parenthesize` command involves a grob path: either `\parenthesize ContextName.GrobName` or just `\parenthesize GrobName` (the latter implying

the bottommost context, typically *Voice*). This should be added before the musical moment, like a `\once \override`. This form makes it possible to parenthesize grobs that are only caused indirectly by events.

```
\new Staff \relative <<
{
  \parenthesize NoteHead
  c'1
}
\new CueVoice {
  s2
  \voiceOne
  \once \override Staff.Parentheses.font-size = 3
  \parenthesize Staff.CueClef
  \cueClef treble
  e'8 f a g
}
>>
```



See also

Snippets: Section “Editorial annotations” in *Snippets*.

Internals Reference: Section “Parenthesis_engraver” in *Internals Reference*, Section “Parentheses” in *Internals Reference*, Section “parentheses-interface” in *Internals Reference*.

Known issues and warnings

Currently, the `font-size` property of the *Parentheses* grob has to be adjusted manually to obtain correctly sized parentheses on chords and some other objects.

7.1.9 Stems

Whenever a note is found, a *Stem* object is created automatically. For whole notes and rests, they are also created but made invisible.

Stems may be manually placed to point up or down; see Section 36.1 [Direction and placement], page 772.

Predefined commands

`\stemUp`, `\stemDown`, `\stemNeutral`.

Selected snippets

Default direction of stems on the center line of the staff

The default direction of stems on the center line of the staff is set by the *Stem* property `neutral-direction`.

```

\relative c'' {
  a4 b c b
  \override Stem.neutral-direction = #up
  a4 b c b
  \override Stem.neutral-direction = #down
  a4 b c b
}

```



Automatically changing the stem direction of the middle note based on the melody

LilyPond can alter the stem direction of the middle note on a staff so that it follows the melody, by adding the `Melody_engraver` to the `Voice` context.

The context property `suspendMelodyDecisions` may be used to turn off this behavior locally.

```

\relative c'' {
  \time 3/4
  a8 b g f b g |
  \set suspendMelodyDecisions = ##t
  a b g f b g |
  \unset suspendMelodyDecisions
  c b d c b c |
}

```

```

\layout {
  \context {
    \Voice
    \consists "Melody_engraver"
    \autoBeamOff
  }
}

```



See also

Notation Reference: Section 36.1 [Direction and placement], page 772.

Snippets: Section “Editorial annotations” in *Snippets*.

Internals Reference: Section “Stem_engraver” in *Internals Reference*, Section “Stem” in *Internals Reference*, Section “stem-interface” in *Internals Reference*.

7.2 Outside the staff

This section discusses how to add emphasis to elements in the staff from outside of the staff.

7.2.1 Note names

Note names can be printed as text, by using the `NoteNames` context. When used simultaneously with a regular staff, that makes it possible to synchronize each note with its name, printed above or below the Staff.


```

\language "italiano"
melody = \relative do'' {
  fad2 si,8 dod re mi fad4. re8 fad2
}

<<
  \new NoteNames { \melody }
  \new Staff { \key si \minor \melody }
  \new NoteNames {
    \set printNotesLanguage = "deutsch"
    \set printAccidentalNames = ##f
    \melody
  }
>>

```



By default, note names are printed in the same language used for music entry; however, the `printNotesLanguage` property allows to select any other language available (see Section 1.1.5 [Note names in other languages], page 10). Whether accidentals should be printed or not is determined through the `printAccidentalNames` property.

By setting both that property to a symbol and `printOctaveNames` to `#t`, note names can be obtained that closely resemble LilyPond entry syntax. If a more general result is desired, ‘scientific’ octave names may also be obtained.

```

melody = \relative c'' {
  fis2 b,8 cis d e fis4. d8 fis2
}

<<
  \new NoteNames {
    \set printOctaveNames = ##t
    \set printAccidentalNames = #'lily
    \melody
  }
  \new Staff { \key b \minor \melody }
  \new NoteNames {
    \set printOctaveNames = #'scientific
    \melody
  }
>>

```



The `noteNameSeparator` property defines how chords will be printed. Other formatting functions may be defined as `noteNameFunction`; such a function must expect a pitch and a context argument, even if one of these can then be ignored.

```

somechords = \relative c' {
  <b d fis>2 <b cis e g> <b d fis> q
}

<<
  \new NoteNames {
    \set noteNameSeparator = "+"
    \somechords
  }
  \new Staff { \key b \minor \somechords }
  \new NoteNames {
    \set noteNameFunction =
      #(lambda (pitch ctx)
        (accidental->text-markup
          (ly:pitch-alteration pitch)))
    \somechords
  }
>>

```



See also

Notation Reference: Section 1.1.5 [Note names in other languages], page 10.

Internals Reference: Section “NoteName” in *Internals Reference*, Section “NoteNames” in *Internals Reference*, Section “Note_name_engraver” in *Internals Reference*.

7.2.2 Balloon help

Elements of notation can be marked and named with the help of a square balloon. The primary purpose of this feature is to explain notation.

```

\new Voice \with { \consists Balloon_engraver }
\relative c'' {
  \balloonGrobText #'Stem #'(3 . 4) \markup { "I'm a Stem" }
  a8
  \balloonGrobText #'Rest #'(-4 . -4) \markup { "I'm a rest" }
  r
  <c, g'-\balloonText #'(-2 . -2) \markup { "I'm a note head" } c>2.
}


```




There are two music functions, `\balloonText` and `\balloonGrobText`; the former is used like `\tweak`, but only within chords, to attach text to an individual note of the chord; the latter is used like `\once \override` to attach text to any grob anywhere.

Balloon text does not influence note spacing, but this can be altered:

```
\new Voice \with { \consists Balloon_engraver }
\relative c'' {
  \balloonGrobText #'Stem #'(3 . 4) \markup { "I'm a Stem" }
  a8
  \balloonGrobText #'Rest #'(-4 . -4) \markup { "I'm a rest" }
  r
  \balloonLengthOn
  <c, g'-\balloonText #'(-2 . -2) \markup { "I'm a note head" } c>2.
}
```



The default behavior for the attachment point of the line on the frame and the alignment of the balloon text is demonstrated below.



The default calculation of the attachment point can be overruled using the X-attachment and Y-attachment properties, which take values between -1 and 1, with the limits corresponding to the left (resp. bottom) and right (resp. top) of the frame. Alignment of the text is controlled by the properties text-alignment-X and text-alignment-Y, which have a similar form.

```
\new Voice \with {
  \consists Balloon_engraver
}
{
  \once \override BalloonText.Y-attachment = -0.5
  \once \override BalloonText.text-alignment-X = 0.0
  \balloonGrobText Rest #'(1 . 3.5) "rest"
  r4
}
```



Predefined commands

\balloonLengthOn, \balloonLengthOff.

See also

Snippets: Section “Editorial annotations” in *Snippets*.

Internals Reference: Section “AnnotateOutputEvent” in *Internals Reference*, Section “Balloon_engraver” in *Internals Reference*, Section “BalloonText” in *Internals Reference*, Section “balloon-interface” in *Internals Reference*.


7.2.3 Grid lines

Vertical lines can be drawn between staves synchronized with the notes.

The `Grid_point_engraver` must be used to create the end points of the lines, while the `Grid_line_span_engraver` must be used to actually draw the lines. By default this centers grid lines horizontally below and to the left side of each note head. Grid lines extend from the middle lines of each staff. The `gridInterval` must specify the duration between the grid lines.

```
\layout {
  \context {
    \Staff
    \consists Grid_point_engraver
    gridInterval = #1/4
  }
  \context {
    \Score
    \consists Grid_line_span_engraver
  }
}

\score {
  \new ChoirStaff <<
    \new Staff \relative {
      \stemUp
      c''4. d8 e8 f g4
    }
    \new Staff \relative {
      \clef bass
      \stemDown
      c4 g' f e
    }
  >>
}
```



Selected snippets

Grid lines: changing their appearance

The appearance of grid lines can be changed by overriding some of their properties.

```
\new ChoirStaff <<
  \new Staff {
    \relative c'' {
      \stemUp
      c'4. d8 e8 f g4
    }
  }
}
```

```

\new Staff {
  \relative c {
    % this moves them up one staff space from the default position
    \override Score.GridLine.extra-offset = #'(0.0 . 1.0)
    \stemDown
    \clef bass
    \once \override Score.GridLine.thickness = 5.0
    c4
    \once \override Score.GridLine.thickness = 1.0
    g'4
    \once \override Score.GridLine.thickness = 3.0
    f4
    \once \override Score.GridLine.thickness = 5.0
    e4
  }
}
>>

\layout {
  \context {
    \Staff
    % set up grids
    \consists "Grid_point_engraver"
    % set the grid interval to one quarter note
    gridInterval = #1/4
  }
  \context {
    \Score
    \consists "Grid_line_span_engraver"
    % this moves them to the right half a staff space
    \override NoteColumn.X-offset = -0.5
  }
}

```



See also

Snippets: Section “Editorial annotations” in *Snippets*.

Internals Reference: Section “Grid_line_span_engraver” in *Internals Reference*, Section “Grid_point_engraver” in *Internals Reference*, Section “GridLine” in *Internals Reference*, Section “GridPoint” in *Internals Reference*, Section “grid-line-interface” in *Internals Reference*, Section “grid-point-interface” in *Internals Reference*.

7.2.4 Analysis brackets

Brackets are used in musical analysis to indicate structure in musical pieces. Simple horizontal brackets are supported.

```
\layout {
  \context {
    \Voice
    \consists Horizontal_bracket_engraver
  }
}
\relative {
  c' '2\startGroup
  d\stopGroup
}
```



Analysis brackets may be nested.

```
\layout {
  \context {
    \Voice
    \consists Horizontal_bracket_engraver
  }
}
\relative {
  c' '4\startGroup\startGroup
  d4\stopGroup
  e4\startGroup
  d4\stopGroup\stopGroup
}
```



Selected snippets

Analysis brackets above the staff

Simple horizontal analysis brackets are added below the staff by default. The following example shows a way to place them above the staff instead.

```
\layout {
  \context {
    \Voice
    \consists "Horizontal_bracket_engraver"
  }
}

\relative c'' {
  \once \override HorizontalBracket.direction = #UP
```

```

c2\startGroup
d2\stopGroup
}

```



Analysis brackets with labels

Text markup may be added to analysis brackets using the `text` property of the `HorizontalBracketText` grob. Adding different texts to brackets beginning at the same time requires the `\tweak` command.



Bracket text gets parenthesized after a line break. The vertical order of nested brackets can be controlled with the `outside-staff-priority` property.

```

\layout {
  \context {
    \Voice
    \consists "Horizontal_bracket_engraver"
    \override HorizontalBracket.direction = #UP
  }
}

{
  \once\override HorizontalBracketText.text = "a"
  c''\startGroup d''\stopGroup
  \once\override HorizontalBracketText.text = "a'"
  e''\startGroup d''\stopGroup |
  c''-\tweak outside-staff-priority #801
    \tweak HorizontalBracketText.text
      \markup \bold \huge "b" \startGroup
    -\tweak HorizontalBracketText.text "a" \startGroup
  d''\stopGroup
  e''-\tweak HorizontalBracketText.text "a'" \startGroup
  d''\stopGroup\stopGroup |
  c''-\tweak HorizontalBracketText.text foo \startGroup
  d'' e'' f'' | \break
  g'' a'' b'' c'''\stopGroup
}

```



Measure spanner

Measure spanners are an alternate way to print annotated brackets. As opposed to horizontal brackets, they extend between two bar lines rather than two notes. The text is displayed in the center of the bracket.

```

\layout {
  \context {
    \Staff
    \consists Measure_spanner_engraver
  }
}

<<
\new Staff \relative c'' {
  \key d \minor
  R1*2
  \tweak text "Answer"
  \startMeasureSpanner
  \tuplet 3/2 8 {
    a16[ b c] d[ c b] c[ d e] f[ e d]
  }
  e8 a gis g
  fis f e d~ d c b e
  \stopMeasureSpanner
}
\new Staff \relative c' {
  \key d \minor
  \tweak text "Subject"
  \tweak direction #DOWN
  \startMeasureSpanner
  \tuplet 3/2 8 {
    d16[ e f] g[ f e] f[ g a] bes[ a g]
  }
  a8 d cis c
  b bes a g~ g f e a
  \stopMeasureSpanner
  \tweak text "Counter-subject"
  \tweak direction #DOWN
  \startMeasureSpanner
  f8 e a r r16 b, c d e fis g e
  a gis a b c fis, b a gis e a4 g8
  \stopMeasureSpanner
}
>>

```


The image displays two musical staves, each with a bracketed section labeled 'Answer' above and 'Counter-subject' below. The first staff is in G major (one flat) and 3/4 time. The 'Answer' section (top staff) begins with a treble clef and a key signature of one flat. It features a series of eighth notes, with the first four grouped by a bracket and a '3' below them, indicating a triplet. The 'Counter-subject' section (bottom staff) begins with a treble clef and a key signature of one flat. It features a series of eighth notes, with the first four grouped by a bracket and a '3' below them, indicating a triplet. The second staff is in D major (two sharps) and 3/4 time. The 'Answer' section (top staff) begins with a treble clef and a key signature of two sharps. It features a series of eighth notes, with the first four grouped by a bracket and a '3' below them, indicating a triplet. The 'Counter-subject' section (bottom staff) begins with a treble clef and a key signature of two sharps. It features a series of eighth notes, with the first four grouped by a bracket and a '3' below them, indicating a triplet.

See also

Internals Reference: Section “Horizontal_bracket_engraver” in *Internals Reference*, Section “HorizontalBracket” in *Internals Reference*, Section “horizontal-bracket-interface” in *Internals Reference*, Section “HorizontalBracketText” in *Internals Reference*, Section “horizontal-bracket-text-interface” in *Internals Reference*, Section “Measure_spanner_engraver” in *Internals Reference*, Section “MeasureSpanner” in *Internals Reference*, Section “measure-spanner-interface” in *Internals Reference*, Section “Staff” in *Internals Reference*.

8 Text



This section explains how to include text (with various formatting) in music scores.

8.1 Writing text

This section introduces different ways of adding text to a score.

Note: To write accented and special text (such as characters from other languages), simply insert the characters directly into the LilyPond file. The file must be saved as UTF-8. For more information, see Section 22.4.1 [Text encoding], page 644.

8.1.1 Text objects overview

Simple text objects are entered as strings between double quotes (these are optional for a single word). The markup mode is a richer tool that can accept a variety of advanced text formatting and graphical enhancements, as detailed in Section 8.2 [Formatting text], page 319.

As such, markup blocks may be used:

- in any TextScript object (attached to notes with -, ^ or _); see Section 8.1.2 [Text scripts], page 309;
- as ‘spanners’, when some indications are prolonged over several beats or bars; see Section 8.1.3 [Text spanners], page 311;

- in any mark printed above the score, such as `RehearsalMark` or `MetronomeMark` objects respectively introduced with the `\mark` or `\tempo` keywords; see Section 8.1.5 [Text marks], page 313;
- as stand-alone text blocks, entered at the top level outside of any `\score` block (in this specific case the `\markup` or `\markuplist` command is mandatory, and cannot be omitted in favor of a simple text string between double quotes); see Section 8.1.6 [Separate text], page 317;
- in any definition inside the `\header` block (e.g., `title`, `subtitle`, `composer`), or in specific elements defined inside the `\paper` block such as `evenHeaderMarkup` for page numbers. This is explained in Chapter 21 [Titles and headers], page 597.

Many other text-based objects may be entered as markup blocks, even if that is not their primary use.

- Fingerings may easily be replaced with markup blocks, if introduced with the `\finger` command; see Section 7.1.2 [Fingering instructions], page 281.
- Lyric syllables may be formatted through the `\markup` command; see Section 9.1 [Common notation for vocal music], page 345.
- Chord names are in fact defined as markup blocks, and therefore may be redefined in the same way for customizing chord modifiers or chord exceptions; see Section 15.2 [Displaying chords], page 512.
- Dynamics are usually entered in a simple way; however it is possible to define Section 3.1.3 [New dynamic marks], page 167, as markup objects. Some dynamics such as *crescendo* are printed as spanners and may be redefined through properties such as `crescendoText`; see Section 3.1.2 [Dynamics], page 159.
- Less common objects are also made of markup blocks, such as Section 7.2.2 [Balloon help], page 299, indications.

In fact, it is possible to use `\markup` to customize the appearance of virtually any graphical object (or ‘grob’), by overriding either its text property if it has one, or its `stencil` property. Some of the logic that makes this a possibility is explained in Section “Flexible architecture” in *Essay*.

The following example illustrates the ubiquity of markup blocks, not only as some of the objects listed above, but also by replacing musical objects with text objects through various methods.

```
\header { title = \markup "Header" }

dyn =
#(make-dynamic-script #{ \markup \serif "DynamicText" #})

\markup \box "Top-level markup"

\score {
  <<
    \new ChordNames
    \with {
      majorSevenSymbol = \markup "majorSevenSymbol"
    }
    \chordmode { c1:maj7 }
    \new Staff {
      \tempo \markup "MetronomeMark"
      \textMark "TextMark"
```


```

\once \override TupletNumber.text =
  \markup "TupletNumber"
\tuplet 3/2 {
  \once \override NoteHead.stencil =
    #ly:text-interface::print
  \once \override NoteHead.text =
    \markup \lower #0.5 "NoteHead"
  c''8^\markup \italic "TextScript"
  a'\finger \markup \serif "Fingering"
  \once \override Rest.stencil =
    #(lambda (grob)
      (grob-interpret-markup grob #{
        \markup "Rest"
      #}))
    r
}
}
\new Lyrics \lyricmode {
  \markup \smallCaps "LyricText" 1
}
\new Dynamics { s1\dyn }
>>
}

```

Header

Top-level markup



See also

Notation Reference: Section 8.2 [Formatting text], page 319, Section 8.1.2 [Text scripts], page 309, Section 8.1.3 [Text spanners], page 311, Section 8.1.5 [Text marks], page 313, Section 8.1.6 [Separate text], page 317, Section 7.1.2 [Fingering instructions], page 281, Section 9.1 [Common notation for vocal music], page 345, Section 15.2 [Displaying chords], page 512, Section 3.1.3 [New dynamic marks], page 167, Section 3.1.2 [Dynamics], page 159, Section 7.2.2 [Balloon help], page 299.

Essay on automated music engraving: Section “Flexible architecture” in *Essay*.

Snippets: Section “Text” in *Snippets*.

8.1.2 Text scripts

Simple “quoted text” indications may be added to a score, as demonstrated in the following example. Such indications may be manually placed above or below the staff, using the syntax described in Section 36.1 [Direction and placement], page 772.

```
\relative { a'8^"pizz." g f e a4-"scherz." f }
```



This syntax is actually a shorthand; more complex text formatting may be added to a note by explicitly using a `\markup` block, as described in Section 8.2 [Formatting text], page 319.

```
\relative {
  a'8^\markup { \italic pizz. } g f e
  a4_\markup { \tiny scherz. \bold molto } f }
```



By default, text indications do not influence the note spacing. However, their widths can be taken into account: in the following example, the first text string does not affect spacing, whereas the second one does.

```
\relative {
  a'8^"pizz." g f e
  \textLength0n
  a4_"scherzando" f
}
```



In addition to text scripts, articulations can be attached to notes. For more information, see Section 3.1.1 [Articulations and ornamentations], page 155.

For more information about the relative ordering of text scripts and articulations, see Section “Placement of objects” in *Learning Manual*.

Predefined commands

`\textLength0n`, `\textLength0ff`.

See also

Learning Manual: Section “Placement of objects” in *Learning Manual*.

Notation Reference: Section 8.2 [Formatting text], page 319, Section 36.1 [Direction and placement], page 772, Section 3.1.1 [Articulations and ornamentations], page 155.

Snippets: Section “Text” in *Snippets*.

Internals Reference: Section “TextScript” in *Internals Reference*.

Known issues and warnings

Checking to make sure that text scripts and lyrics are within the margins requires additional calculations. In cases where slightly faster performance is desired, use

```
\override Score.PaperColumn.keep-inside-line = ##f
```

8.1.3 Text spanners

Some performance indications, e.g., *rallentando* or *accelerando*, are written as text and are extended over multiple notes with dotted lines. Such objects, called “spanners”, may be created from one note to another using the following syntax:

```
\relative {
  \override TextSpanner.bound-details.left.text = "rit."
  b'1\startTextSpan
  e,\stopTextSpan
}
```



The string to be printed is set through object properties. By default it is printed in italic characters, but different formatting can be obtained using `\markup` blocks, as described in Section 8.2 [Formatting text], page 319.

```
\relative {
  \override TextSpanner.bound-details.left.text =
    \markup { \upright "rit." }
  b'1\startTextSpan c
  e,\stopTextSpan
}
```



The line style, as well as the text string, can be defined as an object property. This syntax is described in Section 36.5 [Line styles], page 780.

Predefined commands

`\textSpannerUp`, `\textSpannerDown`, `\textSpannerNeutral`, `\startTextSpan`, `\stopTextSpan`.

Known issues and warnings

LilyPond is only able to handle one text spanner per voice.

The texts at the bounds of a text spanner may collide.

```
{
  \once \override TextSpanner.bound-details.left.text = "The text is"
  \once \override TextSpanner.bound-details.right.text = "too long"
  c'2\startTextSpan d'2\stopTextSpan
}
```



Workarounds can be found in Chapter 30 [Horizontal spacing], page 711.

Selected snippets


Dynamics spanner with custom text

Postfix functions for custom crescendo text spanners. The spanners should start on the first note of the measure. One has to use `-\mycresc`, otherwise the spanner start will rather be assigned to the next note.

```
% Two functions for (de)crescendo spanners where you can explicitly
% give the spanner text.
mycresc =
#(define-music-function (mymarkup) (markup?)
  (make-music 'CrescendoEvent
    'span-direction START
    'span-type 'text
    'span-text mymarkup))

mydecresc =
#(define-music-function (mymarkup) (markup?)
  (make-music 'DecrescendoEvent
    'span-direction START
    'span-type 'text
    'span-text mymarkup))

\relative c' {
  c4-\mycresc "custom cresc" c4 c4 c4 |
  c4 c4 c4 c4 |
  c4-\mydecresc "custom decresc" c4 c4 c4 |
  c4 c4 c4 c4 |
  c4 c4\! c4 c4
}
```



See also

Notation Reference: Section 36.5 [Line styles], page 780, Section 3.1.2 [Dynamics], page 159, Section 8.2 [Formatting text], page 319.

Snippets: Section “Text” in *Snippets*, Section “Expressive marks” in *Snippets*.

Internals Reference: Section “TextSpanner” in *Internals Reference*.

8.1.4 Section labels

The `\sectionLabel` command marks the beginning of a named passage. It is well suited for use at a section division created with `\section`, but it does not imply `\section` and may be used alone.

```
\fixed c' {
  \sectionLabel "Verse"
  c2 g
  \section
  \sectionLabel \markup { \rounded-box { Chorus } }
  g2 c
  \bar " | . "
```

}



See also

Notation Reference: Section 8.2 [Formatting text], page 319, Section 2.5.5 [Rehearsal marks], page 141, Section 2.5.7 [Section divisions], page 146.

Snippets: Section “Text” in *Snippets*.

Internals Reference: Section “SectionLabel” in *Internals Reference*, Section “SectionLabel-Event” in *Internals Reference*.

8.1.5 Text marks

Text marks are textual objects that, unlike text scripts (see Section 8.1.2 [Text scripts], page 309), are not printed over notes but between notes, often aligned to a bar line.

Note: Older LilyPond versions used the `\mark` command for text marks, even though it is primarily intended for rehearsal marks (see Section 2.5.5 [Rehearsal marks], page 141). The `\textMark` and `\textEndMark` commands are better suited for text marks with regard to their default settings as well as the ability to have several text marks at the same moment. It is therefore recommended to use `\textMark` and `\textEndMark` instead of `\mark "Text"` or `\mark \markup ....`. Note that if converting code that uses `\mark` for text marks, overrides using `RehearsalMark` should be changed to `TextMark`.

Before using text marks, it is recommended to seek a more specific command, if available. For text that identifies a section, use `\sectionLabel` (see Section 8.1.4 [Section labels], page 312). For jump instructions, use `\jump` (see Section 4.1.8 [Manual repeat marks], page 204). These commands have different default layout settings, and they create separate objects which can be styled differently from generic text marks in style sheets.

A text mark is entered using either `\textMark` or `\textEndMark`. The `\textMark` command draws a left-aligned mark.

```
\fixed c' {
  \textMark "Fl. 1 solo"
  c4 e g2
  \textMark "A due"
  e4 g c'2
}
```



If a line break occurs at the point `\textMark` is used, the text appears on the next system.


```
\fixed c' {
  \textMark "Fl. 1 solo"
  c4 e g2
  \break
  \textMark "A due"
  e4 g c'2
}
```



Unlike `\textMark`, `\textEndMark` creates a right-aligned mark. If it occurs on a line break, it is printed on the preceding system.

```
\fixed c' {
  \repeat volta 2 {
    c4 e8 f g2
    e4 f8 g c'2
    \textEndMark "ad lib"
  }
  \break
  c'4 8 8 4 8 8
  c'1
}
```




Complex text formatting may be added using a `\markup` block (see Section 8.2 [Formatting text], page 319).

```
\relative {
  <c' e>1
  \textMark \markup { \italic { colla parte } }
  <d f>2 <e g>
  <c f aes>1
}
```



The `\markLengthOn` and `\markLengthOff` commands (see Section 2.3.3 [Metronome marks], page 86) can also be used on text marks.

```
{
  \mark \default
  c'2 2
  \textEndMark "long mark text"
  \markLengthOn
  2 2
  \mark \default
  2 2
  \textEndMark "long mark text"
}
```



Text marks may be printed below the staff.

```
\fixed c' {
  c4 g c'8 b c4 e' c' c2
  c4 g c'8 b c4 e' c' g2
  e'4 c' c'8 b c'4
  g4 c' c2~ c1
  \tweak direction #DOWN
  \tweak font-size -1
  \textEndMark "Composed on November 13th, 2020"
}
```



There can be several text marks at the same moment. Their stacking order can be overridden using the `outside-staff-priority` property (see Section 29.3 [Vertical collision avoidance], page 708). Alternatively, a single text mark with `\markup \column { ... }` can achieve the same effect.

```
\fixed c' {
  \repeat volta 2 {
    c4 g c'8 b c4 e' c' c2
    \textEndMark "ad lib."
    \tweak outside-staff-priority 1200
    \tweak font-size -1
    \textEndMark "2nd time a due"
  }
}
```



The alignment of a text mark can be changed.


```

{
  c'8 8 8 8 8 8 8 8
  \textMark \markup \column {
    \line { Left-aligned mark }
    \line { (default for \concat { \typewriter "\\textMark" ) } }
  }
  d'8 8 8 8 8 8 8 8
}

{
  c'8 8 8 8 8 8 8 8
  \tweak self-alignment-X #CENTER
  \textMark "Centered mark"
  d'8 8 8 8 8 8 8 8
}

{
  c'8 8 8 8 8 8 8 8
  \tweak self-alignment-X #RIGHT
  \textMark \markup \right-column {
    \line { Right-aligned mark }
    \line { (default for \concat { \typewriter "\\textEndMark" ) } }
  }
  d'8 8 8 8 8 8 8 8
}

```



Predefined commands

\textMark, \textEndMark, \markLengthOn, \markLengthOff.

Selected snippets


Printing marks on every staff

Although rehearsal and text marks are normally only printed above the topmost staff, they may also be printed on every staff.

```

\score {
  <<
    \new Staff { \mark \default c'1 \textMark "molto" c' }
    \new Staff { \mark \default c'1 \textMark "molto" c' }
  >>
  \layout {
    \context {
      \Score
      \remove Mark_engraver
      \remove Text_mark_engraver
      \remove Staff_collecting_engraver
    }
    \context {
      \Staff
      \consists Mark_engraver
      \consists Text_mark_engraver
      \consists Staff_collecting_engraver
    }
  }
}

```



See also

Notation Reference: Section 2.3.3 [Metronome marks], page 86, Section 2.5.5 [Rehearsal marks], page 141, Section 8.1.4 [Section labels], page 312, Section 8.2 [Formatting text], page 319, Section 8.2.5 [Music notation inside markup], page 334, Section B.8 [The Emmen-taler font], page 905.

Snippets: Section “Text” in *Snippets*.

Internals Reference: Section “TextMarkEvent” in *Internals Reference*, Section “Text_mark_engraver” in *Internals Reference*, Section “TextMark” in *Internals Reference*.

8.1.6 Separate text

A `\markup` or `\markuplist` block can exist by itself, outside of any `\score` block, as a “top-level expression”. This syntax is described in Section 20.5 [File structure], page 594.

```

\markup {
  Tomorrow, and tomorrow, and tomorrow...
}

```

Tomorrow, and tomorrow, and tomorrow...

This allows printing text separately from the music, which is particularly useful when the input file contains several music pieces, as described in Section 20.2 [Multiple scores in a book], page 591.

```

\score {
  c'1
}
\markup {
  Tomorrow, and tomorrow, and tomorrow...
}
\score {
  c'1
}

```



Tomorrow, and tomorrow, and tomorrow...



Using `\markuplist`, separate text blocks can be spread over multiple pages, making it possible to print text documents or books entirely within LilyPond. For a description of this feature and the specific syntax it requires, see Section 8.2.1 [Text markup introduction], page 319.

Predefined commands

`\markup`, `\markuplist`.

Selected snippets

Stand-alone two-column markup

Stand-alone text may be arranged in several columns using `\markup` commands.

```

\markup {
  \fill-line {
    \hspace #1
    \column {
      \line { 0 sacrum convivium }
      \line { in quo Christus sumitur, }
      \line { recolitur memoria passionis ejus, }
      \line { mens impletur gratia, }
      \line { futurae gloriae nobis pignus datur. }
      \line { Amen. }
    }
  }
  \hspace #2
  \column \italic {
    \line { 0 sacred feast }
    \line { in which Christ is received, }
    \line { the memory of His Passion is renewed, }
    \line { the mind is filled with grace, }
    \line { and a pledge of future glory is given to us. }
    \line { Amen. }
  }
}
\hspace #1

```

```
}
}
```

O sacrum convivium	<i>O sacred feast</i>
in quo Christus sumitur,	<i>in which Christ is received,</i>
recolitur memoria passionis ejus,	<i>the memory of His Passion is renewed,</i>
mens impletur gratia,	<i>the mind is filled with grace,</i>
futurae gloriae nobis pignus datur.	<i>and a pledge of future glory is given to us.</i>
Amen.	<i>Amen.</i>

See also

Notation Reference: Section 8.2 [Formatting text], page 319, Section 20.5 [File structure], page 594, Section 20.2 [Multiple scores in a book], page 591.

Snippets: Section “Text” in *Snippets*.

Internals Reference: Section “TextScript” in *Internals Reference*.

8.2 Formatting text

This section presents basic and advanced text formatting, using the markup mode specific syntax.

8.2.1 Text markup introduction

A `\markup` or `\markuplist` block is used to typeset text with an extensible syntax called “markup mode”. Such blocks can be used in many contexts (see Section 8.1.1 [Text objects overview], page 307).

In markup mode, words are written as-is. A single word does not need any quotes.

```
\markup intenso
```

intenso

Several words can be grouped together by enclosing them in quotes.

```
\markup "molto intenso"
```

molto intenso

Apart from grouping, quoting also allows writing special characters such as ‘\’ and ‘#’ without affecting the formatting of the text. Double quotation marks themselves may be printed by preceding them with backslashes.

```
\relative {
  a'1^"\\italic markup..."
  a_\markup { \italic "... prints \"italic\" letters!" }
  a a
}
```

\italic markup...



... prints "italic" letters!

Formatting is achieved through markup commands. Their name is written preceded by a backslash. They expect a number of arguments specific to the command. For an exhaustive list of `\markup`-specific commands, see Section A.1 [Text markup commands], page 807.

```
\markup \italic "string. assai"
\markup \with-color "red" intenso
```

string. assai

intenso

Markup commands can be nested. The markup block ends when all commands have received their arguments.

```
\markup \with-color "red" \italic intenso
```

intenso

Several markup expressions can be grouped together within braces to form a so-called *markup list*. Without further formatting, the elements of a markup list are typeset in a row.

```
\markup { molto \italic intenso }
```

molto intenso

Some commands do not expect a markup but a markup list, allowing for more complex text arrangements than printing in a row.

```
\markup \center-column {
  \bold "Des Simplicius Simplicissimus Jugend"
  "Karl Amadeus Hartmann"
}
```

Des Simplicius Simplicissimus Jugend

Karl Amadeus Hartmann

Also, some commands do not return a markup but a markup list. The result can then be used where a markup list is expected. For a list of these commands, see Section A.2 [Text markup list commands], page 884.

```
\markup \string-lines
  "Twinkle, twinkle, little star,
  How I wonder what you are!"
```

Twinkle, twinkle, little star, How I wonder what you are!

```
\markup \center-column \string-lines
  "Twinkle, twinkle, little star,
  How I wonder what you are!"
```

Twinkle, twinkle, little star,
How I wonder what you are!

Elements of a nested markup list are simply treated as elements of the main markup list.

```
\markup \center-column {
  \bold "Des Simplicius Simplicissimus Jugend"
  { Karl Amadeus \smallCaps Hartmann }
}
```

Des Simplicius Simplicissimus Jugend

Karl
Amadeus
HARTMANN

To group elements of a nested markup list in a row, apply the `\line` command to the markup list. This stacks elements from the markup list horizontally into a single markup.

```
\markup \center-column {
  \bold "Des Simplicius Simplicissimus Jugend"
  \line { Karl Amadeus \smallCaps Hartmann }
}
```

Des Simplicius Simplicissimus Jugend

Karl Amadeus HARTMANN

A special feature is the handling of commands taking markups when applied to markup lists. When a command expects a markup as its last argument, and a markup list is given for this argument, the markup command is applied to each of the individual markups in the list.

```
\markup \box { Karl Amadeus \smallCaps Hartmann }
```

Karl Amadeus HARTMANN

In this case, the result is in turn a markup list, which can be passed to a command expecting a markup list, or to one expecting a markup, with again the mapping behavior described above in the latter case.

```
\markup \center-column \box { Karl Amadeus \smallCaps Hartmann }
\markup \rotate #30 \box { Karl Amadeus \smallCaps Hartmann }
```

Karl

Amadeus

HARTMANN

Karl

Amadeus

HARTMANN

Apply `\line` to a markup list in order to make it treated as a single markup argument.

```
\markup \box { Karl Amadeus \smallCaps Hartmann }
\markup \box \line { Karl Amadeus \smallCaps Hartmann }
```

Karl Amadeus HARTMANN

Karl Amadeus HARTMANN

When the entire content of a `\markup` expression is a markup list, it is implicitly typeset using the `\line` command. Thus, elements are stacked horizontally and grouped as a single, unbreakable text block. The `\markuplist` command acts differently: it expects a markup list, and prints the individual markups on the page, stacking them vertically, and allowing page breaks. The following example illustrates this difference.

```
\markup \box \wordwrap {
  Lorem ipsum dolor sit amet, consectetur
  adipiscing elit, sed do eiusmod tempor incididunt
  ut labore et dolore magna aliqua. Ut enim ad minim
  veniam, quis nostrud exercitation ullamco laboris
  nisi ut aliquip ex ea commodo consequat.
}
```

```
\markuplist \box \wordwrap-lines {
  Lorem ipsum dolor sit amet, consectetur
  adipiscing elit, sed do eiusmod tempor incididunt
```



```

    ut labore et dolore magna aliqua. Ut enim ad minim
    veniam, quis nostrud exercitation ullamco laboris
    nisi ut aliquip ex ea commodo consequat.
}

```

```

Lorem ipsum dolor sit amet, consectetur adipisicing elit, sed do eiusmod
tempor incididunt ut labore et dolore magna aliqua. Ut enim ad minim
veniam, quis nostrud exercitation ullamco laboris nisi ut aliquip ex ea
commodo consequat.

```

```

Lorem ipsum dolor sit amet, consectetur adipisicing elit, sed do eiusmod

```

```

tempor incididunt ut labore et dolore magna aliqua. Ut enim ad minim

```

```

veniam, quis nostrud exercitation ullamco laboris nisi ut aliquip ex ea

```

```

commodo consequat.

```

Markups can be stored in variables, to be reused in any context where a markup is accepted. For example, such a variable can be directly attached to notes:

```

allegro = \markup \bold \large Allegro

{
  d'8.^allegro
  d'16 d'4 r2
}

```



The `\etc` syntax allows to define custom shorthands usable as markup commands.

```

\markup reddish = \markup \with-color "tomato" \etc

\markup { molto \reddish intenso }

molto intenso

```

The inner workings of markup commands and how to implement more complex ones is explained in Section “Markup functions” in *Extending*.

See also

Notation Reference: Section 8.1.1 [Text objects overview], page 307, Section A.1 [Text markup commands], page 807, Section A.2 [Text markup list commands], page 884.

Extending LilyPond: Section “Markup functions” in *Extending*.

Installed Files: `scm/markup.scm`, `scm/define-markup-commands.scm`.

Snippets: Section “Text” in *Snippets*.

Internals Reference: Section “TextScript” in *Internals Reference*.

Known issues and warnings

Syntax error messages for markup mode can be confusing.

8.2.2 Selecting font and font size

Basic font switching is supported in markup mode:

```
\relative {
  d''1^\markup {
    \bold { Più mosso }
    \italic { non troppo \underline Vivo }
  }
  r2 r4 r8
  d,_\markup { \italic quasi \smallCaps Tromba }
  f1 d2 r
}
```




The global text size to be used in markups can be set with the `text-font-size` paper variable. This is useful to adjust to a different main font that might appear smaller or larger despite of having the same nominal font sizes. The value is given in points (without specifying a unit); the default value depends on the staff height and is computed as $(\text{staff-height} / 20 * 11)$.

See Section 36.2 [Distances and measurements], page 773, for more information on dimensions used by LilyPond.

```
\score {
  { f'~"Default text size" }
  \layout { text-font-size = 10 }
}
```

```
\score {
  { f'~"Default text size" }
  \layout { text-font-size = 20 }
}
```



The font size can be altered, relative to the global text size, in a number of different ways. It can be set to predefined size.

```
\relative b' {
  b1_\markup { \huge Sinfonia }
  b1^\markup { \teeny da }
  b1-\markup { \normalsize camera }
}
```




It can be set relative to its previous value.

```
\relative b' {
  b1_\markup { \larger Sinfonia }
  b1^\markup { \smaller da }
  b1-\markup { \magnify #0.6 camera }
}
```



It can be increased or decreased relative to the value set by the global staff size.

```
\relative b' {
  b1_\markup { \fontsize #-2 Sinfonia }
  b1^\markup { \fontsize #1 da }
  b1-\markup { \fontsize #3 camera }
}
```



It can also be set to a fixed point size, regardless of the global staff size.

```
\relative b' {
  b1_\markup { \abs-fontsize #20 Sinfonia }
  b1^\markup { \abs-fontsize #8 da }
  b1-\markup { \abs-fontsize #14 camera }
}
```



If the text includes spaces, then it is best to put it all inside quote marks, so that the size of each space is appropriate for the size of the other characters.

```
\markup \fontsize #6 \bold { Sinfonia da camera }
\markup \fontsize #6 \bold { "Sinfonia da camera" }
```

Sinfonia da camera

Sinfonia da camera

Text may be printed as subscript or superscript. By default these are printed in a smaller size, but a normal size can be used as well:

```

\markup {
  \column {
    \line { 1 \super st movement }
    \line { 1 \normal-size-super st movement }
    \sub { (part two) } }
  }
}

1st movement
1st movement(part two)

```

The markup mode provides an easy way to select alternate font families. A serif font is selected by default unless specified otherwise; on the last line of the following example, there is no difference between the first and the second word.

```

\markup {
  \column {
    \line { Act \number 1 }
    \line { \sans { Scene I. } }
    \line { \typewriter { Verona. An open place. } }
    \line { Enter \serif Valentine and Proteus. }
  }
}

```

Act 1
Scene I.
 Verona. An open place.
 Enter Valentine and Proteus.

Some of these font families, used for specific items such as numbers or dynamics, do not provide all characters, as mentioned in Section 3.1.3 [New dynamic marks], page 167, and Section 4.1.8 [Manual repeat marks], page 204.

When used inside a word, some font-switching or formatting commands may produce an unwanted blank space. This can easily be solved by concatenating the text elements together:

```

\markup {
  \column {
    \line {
      \concat { 1 \super st }
      movement
    }
    \line {
      \concat { \dynamic p , }
      \italic { con dolce espressione }
    }
  }
}

1st movement


p, con dolce espressione


```

An exhaustive list of font switching commands and custom font usage commands can be found in Section A.1.1 [Font markup], page 807.

Defining custom font sets is also possible, as explained in Section 8.3 [Fonts], page 336.

Predefined commands

`\teeny`, `\tiny`, `\small`, `\normalsize`, `\large`, `\huge`, `\smaller`, `\larger`.

See also

Notation Reference: Section A.1.1 [Font markup], page 807, Section 3.1.3 [New dynamic marks], page 167, Section 4.1.8 [Manual repeat marks], page 204, Section 8.3 [Fonts], page 336.

Installed Files: `scm/define-markup-commands.scm`.

Snippets: Section “Text” in *Snippets*.

Internals Reference: Section “TextScript” in *Internals Reference*.

Known issues and warnings

Using the font sizing commands `\teeny`, `\tiny`, `\small`, `\normalsize`, `\large`, and `\huge` will lead to inconsistent line spacing compared to using `\fontsize`.

8.2.3 Text alignment

This subsection discusses how to place text in markup mode. Markup objects can also be moved as a whole, using the syntax described in Section “Moving objects” in *Learning Manual*.


Markup objects may be aligned in different ways. By default, a text indication is aligned on its left edge: in the following example, there is no difference between the first and the second markup. That example also demonstrates various syntactically correct ways of placing the alignment commands:

```
\relative {
  d'1-\markup { poco }
  f
  d-\markup { \left-align poco }
  f
  d-\markup { \center-align { poco } }
  f
  d-\markup \right-align { poco }
}
```




Horizontal alignment may be fine-tuned using a numeric value:

```
\relative {
  a'1-\markup { \halign #-1 poco }
  e'
  a,-\markup { \halign #0 poco }
  e'
  a,-\markup { \halign #0.5 poco }
  e'
  a,-\markup { \halign #2 poco }
}
```



Lastly, words and any other objects may be moved horizontally by preceding them with `\hspace`. Negative values are also supported and move any objects that follow into the opposite direction. Here, we put `\hspace` into a box to better show its effect.


```
\relative {
  d''1-\markup { poco }
  f
  d-\markup \concat { \with-color #darkred \box \hspace #4 poco }
  f
  d-\markup \concat { \with-color #darkred \box \hspace #-4 poco }
  f
  d-\markup \concat { \with-color #darkred \box \hspace #10 poco }
}
```



Some objects may have alignment procedures of their own, and therefore are not affected by these commands. It is possible to move such markup objects as a whole, as shown for instance in Section 8.1.5 [Text marks], page 313.

Vertical alignment can be set in a similar way. As stated above, markup objects can be moved as a whole; however, it is also possible to move specific elements inside a markup block.

```
\relative {
  d'2^\markup {
    Acte I
    \raise #2 { Scène 1 }
  }
  a'
  g_\markup {
    \lower #4 \bold { Très modéré }
  }
  a
  d,^\markup \raise #4 \italic {
    Une forêt.
  }
  a'4 a g2 a
}
```




Some commands can affect both the horizontal and vertical alignment of text objects in markup mode:

```

\relative {
  d'2^\markup {
    Acte I
    \translate #'(2 . 2) "Scène 1"
  }
  a'
  g_\markup {
    \general-align #Y #5 \bold "Très modéré"
  }
  a
  d,^\markup \translate-scaled #'(-3 . 2) \teeny {
    "Une forêt."
  }
  a'4 a g2 a
}

```



Très modéré

Note that `\vspace` can *not* be used in general to move arbitrary objects up or down within a `\column` markup due to the way the latter is implemented. The following naïve approach thus fails.

```

\relative {
  d'2^\markup {
    Acte I
    \column {
      \vspace #-2
      "Scène 1"
    }
  }
  a'
  g_\markup \column {
    \vspace #1
    "Très modéré"
  }
  a
  d,^\markup \column {
    "Une forêt."
    \vspace #2
  }
  a'4 a g2 a
}

```



Très modéré

What actually works is to put `\vspace` between two objects that have non-empty extents.

```

\relative {
  d'2^\markup {
    Acte I
    \column {
      " "
      \vspace #-2
      "Scène 1"
    }
  }
  a'
  g_\markup \column {
    " "
    \vspace #1
    "Très modéré"
  }
  a
  d,\^{\markup \column {
    "Une forêt."
    \vspace #2
    " "
  }}
  a'4 a g2 a
}

```

Une forêt.



Très modéré

A markup object may include several lines of text. In the following example, each element or expression is placed on its own line, either left-aligned or centered:

```

\markup {
  \column {
    a
    "b c"
    \line { d e f }
  }
  \hspace #10
  \center-column {
    a
    "b c"
    \line { d e f }
  }
}

```

a	a
b c	b c
d e f	d e f

Similarly, a list of elements or expressions may be spread to fill the entire horizontal line width (if there is only one element, it will be centered on the page). These expressions can, in turn, include multi-line text or any other markup expression:

```
\markup {
  \fill-line {
    \line { William S. Gilbert }
    \center-column {
      \huge \smallCaps "The Mikado"
      or
      \smallCaps "The Town of Titipu"
    }
    \line { Sir Arthur Sullivan }
  }
}
```

William S. Gilbert

THE MIKADO

Sir Arthur Sullivan

or

THE TOWN OF TITIPU

1885

Elements may be spread to fill any specified width by overriding the line-width property. By default it is set to #f which indicates the entire line:

```
\markup {
  \column {
    \fill-line { left center right }
    \null
    \override #'(line-width . 30)
    \fill-line { left center right }
  }
}
```

left

center

right

left

center

right

Long text indications can also be automatically wrapped accordingly to the given line width. These will be either left-aligned or justified, as shown in the following example.

```
\markup {
  \column {
    \line \smallCaps { La vida breve }
    \line \bold { Acto I }
    \wordwrap \italic {
      (La escena representa el corral de una casa de
      gitanos en el Albaicín de Granada. Al fondo una
      puerta por la que se ve el negro interior de
      una Fragua, iluminado por los rojos resplandores
      del fuego.)
    }
  }
}
```

```

\hspace #0

\line \bold { Acto II }
\override #'(line-width . 50)
\justify \italic {
  (Calle de Granada. Fachada de la casa de Carmela
  y su hermano Manuel con grandes ventanas abiertas
  a través de las que se ve el patio
  donde se celebra una alegre fiesta)
}
}
}

```

LA VIDA BREVE

Acto I

(La escena representa el corral de una casa de gitanos en el Albaicín de Granada. Al fondo una puerta por la que se ve el negro interior de una Fragua, iluminado por los rojos resplandores del fuego.)

Acto II

(Calle de Granada. Fachada de la casa de Carmela y su hermano Manuel con grandes ventanas abiertas a través de las que se ve el patio donde se celebra una alegre fiesta)

An exhaustive list of text alignment commands can be found in Section A.1.2 [Markup for text alignment], page 820.

See also

Learning Manual: Section “Moving objects” in *Learning Manual*.

Notation Reference: Section A.1.2 [Markup for text alignment], page 820, Section 8.1.5 [Text marks], page 313.

Installed Files: scm/define-markup-commands.scm.

Snippets: Section “Text” in *Snippets*.

Internals Reference: Section “TextScript” in *Internals Reference*.

8.2.4 Graphic notation inside markup

Various graphic objects may be added to a score, using markup commands.

Some markup commands allow decoration of text elements with graphics, as demonstrated in the following example.

```

\markup \fill-line {
  \center-column {
    \circle Jack
    \box "in the box"
    \null
  }
  \line {
    Erik Satie
    \hspace #3
    \bracket "1866 - 1925"
  }
}

```

```

\markup \null
\rounded-box \bold Prelude
}
}

```


in the box

Erik Satie [1866 - 1925]

Prelude

Some commands may require increased padding around the text; this is achieved with some markup commands exhaustively described in Section A.1.2 [Markup for text alignment], page 820.

```

\markup \fill-line {
  \center-column {
    \box \pad-x-left #3 "Charles Ives"
    \box \pad-x-right #3 "(1874 - 1954)"
    \null
    \box \pad-markup #2 "THE UNANSWERED QUESTION"
    \box \pad-x #8 "A Cosmic Landscape"
    \null
  }
}
\markup \column {
  \line {
    \hspace #10
    \box \pad-to-box #'(-5 . 20) #'(0 . 5)
    \bold "Largo to Presto"
  }
}
\box \pad-around #3 "String quartet keeps very even time."
}

```

Charles Ives

(1874 - 1954)

THE UNANSWERED QUESTION

A Cosmic Landscape

Largo to Presto

String quartet keeps very even time.


Other graphic elements or symbols may be printed without requiring any text. As with any markup expression, such objects can be combined.

```

\markup {
  \combine
    \draw-circle #4 #0.4 ##f
    \filled-box #'(-4 . 4) #'(-0.5 . 0.5) #1
  \hspace #5

  \center-column {
    \triangle ##t
    \combine
      \draw-line #'(0 . 4)
      \arrow-head #Y #DOWN ##f
  }
}

```




Advanced graphic features include the ability to include external image files converted to the Encapsulated PostScript format (*eps*), or to directly embed graphics into the input file, using native PostScript code. In such a case, it may be useful to explicitly specify the size of the drawing, as demonstrated below:

```

c'1~\markup {
  \combine
    \epsfile #X #10 "./context-example.eps"
    \with-dimensions #'(-0.5 . 10.5) #'(-2 . 8)
    \postscript "
      -0.3 1 translate
      2.7 2 scale
      newpath
      2 -1 moveto
      4 -2 4 1 1 arct
      4 2 3 3 1 arct
      0 4 0 3 1 arct
      0 0 1 -1 1 arct
      closepath
      stroke"
  }
c'

```



An exhaustive list of graphics-specific commands can be found in Section A.1.3 [Graphical markup], page 838.

See also

Notation Reference: Section A.1.2 [Markup for text alignment], page 820, Section 36.3 [Dimensions], page 774, Chapter 7 [Editorial annotations], page 277, Section A.1.3 [Graphical markup], page 838.

Installed Files: `scm/define-markup-commands.scm`, `scm/stencil.scm`.

Snippets: Section “Text” in *Snippets*.


Internals Reference: Section “TextScript” in *Internals Reference*.

8.2.5 Music notation inside markup

Various musical notation elements may be added to a score, inside a markup object.


Notes and accidentals can be entered using markup commands:

```
a'2 a'^\markup {
  \note {4} #1
  =
  \note-by-number #1 #1 #1.5
}
b'1_\markup {
  \natural \semiflat \flat
  \sesquiflat \doubleflat
}
\glissando
a'1_\markup {
  \natural \semisharp \sharp
  \sesquisharp \doublesharp
}
\glissando b'
```




Other notation objects may also be printed in markup mode:

```
\relative {
  g1 bes
  ees\finger \markup \tied-lyric "4~1"
  fis_\markup { \dynamic rf }
  bes^\markup {
    \beam #8 #0.1 #0.5
  }
  cis
  d-\markup {
    \markalphabet #8
    \markletter #8
  }
}
```




More generally, any available musical symbol may be included separately in a markup object, as demonstrated below; an exhaustive list of these symbols and their names can be found in Section B.8 [The Emmentaler font], page 905.

```
\relative {
  c''2
  c'^\markup { \musicglyph "eight" }
  c,4_\markup { \left-brace #40 }
  c,8._\markup { \musicglyph "clefs.G_change" }
  c16
  c2^\markup { \musicglyph "timesig.neomensural94" }
}
```



The markup mode also supports diagrams for specific instruments:

```
\relative {
  c''1^\markup {
    \fret-diagram-terse "x;x;o;2;3;2;"
  }
  c^\markup {
    \harp-pedal "^-v|--ov^"
  }
  c
  c^\markup {
    \combine
    \musicglyph "accordion.discant"
    \combine
    \raise #0.5 \musicglyph "accordion.dot"
    \raise #1.5 \musicglyph "accordion.dot"
  }
}
```




Such diagrams are documented in Section A.1.6 [Instrument-specific markup], page 862.

A whole score can even be nested inside a markup object:

```

\relative {
  c'4 d^\markup {
    \score {
      \relative { c'4 d e f }
    }
  }
  e f |
  c d e f
}

```



An exhaustive list of music notation related commands can be found in Section A.1.4 [Markup for music and musical symbols], page 849.

See also

Notation Reference: Section A.1.4 [Markup for music and musical symbols], page 849, Section B.8 [The Emmmentaler font], page 905.

Installed Files: `scm/define-markup-commands.scm`, `scm/fret-diagrams.scm`, `scm/harp-pedals.scm`.

Snippets: Section “Text” in *Snippets*.

Internals Reference: Section “TextScript” in *Internals Reference*.

Known issues and warnings

Vertical spacing of a `\score` inside a markup object is controlled by `baseline-skip`. Any `\paper` settings are ignored.

8.3 Fonts

Fonts in LilyPond are handled by several libraries; two of them are of relevance to the user: *FontConfig* (<https://fontconfig.org>) is used to detect available fonts, and selected fonts are then rendered by *Pango* (<https://pango.org>) to display text strings.

This section shows how to access fonts in LilyPond, and how to change them in scores.

8.3.1 Unsupported font formats

A word of caution at the beginning: LilyPond creates its final PDF output using an intermediate PostScript file. As a consequence, some font formats cannot be used because PostScript, being an old standard and no longer receiving any updates, lacks support for them. Here is a list of font formats that won’t work.

CFF2 In the last years this font format became the default for OpenType (`.otf`) fonts. While its predecessor (CFF, also using the extension `.otf`) is supported, the more compact CFF2 is not. LilyPond warns on the console if it encounters such a font, and the conversion to a PDF will either fail or the PDF will miss glyphs from this font.

Font Variations

Such fonts usually have ‘VF’ somewhere in their name; unfortunately, they are not supported regardless of whether they are TrueType or OpenType Font Variations, and consequently filtered out in advance.

color fonts Not supported; this affects in particular scalable Emoji fonts. Some fonts, however, also contain B/W versions of the Emojis (as normal outline glyphs), and these should work just fine – provided they come in a supported font format.

OpenType collections

This is a container format (usually with extension .otc) that holds multiple fonts in a single file. Today, it is often used as a last resort font, i.e., it gets used by the OS if no other font fits, for whatever reason.

bitmap fonts

Not supported at all and automatically filtered out before LilyPond sees the list of available fonts. This includes some older Emoji color fonts.

Many fonts are available in both the TrueType and the OpenType format; if the .otf version fails, try the .ttf one. If you cannot find an alternative to a CFF2 font, try LilyPond’s `-dbackend=cairo` command line option; this currently experimental backend bypasses the PostScript step and directly creates PDF output, thus being able to support CFF2 (and also OpenType collections).

8.3.2 Finding fonts

In addition to any font already installed on the operating system, more fonts may be added to the ones detected by FontConfig (and thus available in LilyPond scores) by the following commands:

```
#(ly:font-config-add-font "path/to/font-file")
#(ly:font-config-add-directory "path/to/directory/")
```

Both commands accept either absolute or relative paths, which makes it possible to compile a score on any system by simply distributing the relevant font files together with the LilyPond input files.

To verify that the desired fonts are found by FontConfig, use the command `$(ly:font-config-display-fonts)`, which prints the complete list of available fonts to the console log. It also shows the actual font names to be used with LilyPond; these may differ from the file names themselves. Alternatively, running `lilypond -dshow-available-fonts` in a terminal has the same effect.

8.3.3 Font families

Three generic aliases for text font families¹ are available: ‘serif’, ‘sans’, and ‘typewriter’. Depending on the backend, these families get mapped to different font family aliases.

For the svg backend:

generic family	SVG font family
serif	serif
sans	sans-serif
typewriter	monospace

‘serif’, ‘sans-serif’, and ‘monospace’ are ‘generic-family’ in SVG and CSS specifications.

For other backends:

¹ In its simplest form, a *font family* usually contains fonts in roman, italic, bold, and bold italic styles.

generic family	default font family alias	font families contained in alias
serif	LilyPond Serif	C059, Century SchoolBook URW, Century Schoolbook L, TeX Gyre Schola, DejaVu Serif, . . . , serif
sans	LilyPond Sans Serif	Nimbus Sans, Nimbus Sans L, TeX Gyre Heros, DejaVu Sans, . . . , sans-serif
typewriter	LilyPond Monospace	Nimbus Mono PS, Nimbus Mono, Nimbus Mono L, TeX Gyre Cursor, DejaVu Sans Mono, . . . , monospace

If a character does not exist in the appropriate font of the first listed family, the appropriate font of the next listed family gets used instead for that character.

Note that the URW font families distributed with LilyPond ('C059', 'Nimbus Sans', and 'Nimbus Mono PS') have a peculiarity: By default, in addition to the standard ligatures like 'fl' or 'ffi', they substitute the string 'Nr.' with the Numero Sign (U+2116) if the 'latn' script is selected. To circumvent this locally, insert a *zero-width non-joiner character* (ZWJ, U+200C) between the 'N' and 'r' characters. To circumvent this globally, use the following code to make LilyPond always insert a ZWJ character.

```
\paper {
  #(add-text-replacements!
    `(("Nr." . ,(format #f "N~ar." (ly:wide-char->utf-8 #x200C))))
}
```

'LilyPond Serif', 'LilyPond Sans Serif', and 'LilyPond Monospace' are font family aliases defined in the additional FontConfig configuration file 00-lilypond-fonts.conf, which can be usually found in directory /usr/local/share/lilypond/2.27.3/fonts, and which is used exclusively by LilyPond.

The exact mapping from these three font families to the actual fonts can be controlled via the fonts property, see Section 8.3.5 [Changing fonts], page 340.

Each font family may include different shapes and series. The following example demonstrates that, including code to also change the size. The value supplied to font-size is taken relative to the default font size.

```
\override Score.TextMark.font-family = #'typewriter
\textMark "Ouverture"
\override Voice.TextScript.font-shape = #'italic
\override Voice.TextScript.font-series = #'bold
d''2.^{\markup "Allegro"}
\override Voice.TextScript.font-size = -3
c''4^"smaller"
```



A similar syntax may be used in markup mode; however, in most cases it is preferable to use the simpler syntax explained in Section 8.2.2 [Selecting font and font size], page 323:

```

\markup {
  \column {
    \line {
      \override #'((font-shape . italic) (font-size . 4))
      Idomeneo,
    }
    \line {
      \override #'(font-family . typewriter) {
        \override #'(font-series . bold) re
        di
      }
      \override #'(font-family . sans) Creta
    }
  }
}

```

Idomeneo,
re di Creta

8.3.4 Font features

When using OpenType fonts, font features can be used.² Note that not all OpenType fonts have all features. If you request a feature that does not exist in the chosen font, the feature is simply ignored. The example below uses the font ‘TeX Gyre Schola’ (this is, the roman style of the family).

```

\paper {
  property-defaults.fonts.serif = "TeX Gyre Schola"
}

\markup "normal style: Hello HELLO"

\markup \caps "small caps: Hello"

\markup \override #'(font-features . ("smcp")) "true small caps: Hello"

\markup "normal number style: 0123456789"

\markup \override #'(font-features . ("onum"))
  "old number style: 0123456789"

\markup \override #'(font-features . ("salt 0"))
  "stylistic alternate 0:  $\epsilon\phi\pi\rho\theta$ "

\markup \override #'(font-features . ("salt 1"))
  "stylistic alternate 1:  $\epsilon\phi\pi\rho\theta$ "

\markup \override #'(font-features . ("onum" "smcp" "salt 1"))
  "multiple features: Hello 0123456789  $\epsilon\phi\pi\rho\theta$ "

normal style: Hello HELLO

SMALL CAPS: HELLO

```

² Selecting OpenType font scripts and languages is not supported yet.

TRUE SMALL CAPS: **HELLO**

normal number style: 0123456789

old number style: 0123456789

stylistic alternate 0: εφπρθ

stylistic alternate 1: €φωρϑ

MULTIPLE FEATURES: **HELLO** 0123456789 €φωρϑ

For the full OpenType font feature list see <https://www.microsoft.com/typography/otspec/featurelist.htm>; for identifying features of OpenType fonts see <https://lists.gnu.org/archive/html/lilypond-devel/2017-08/msg00004.html>.

See also

Notation Reference: Section B.8 [The Emmmentaler font], page 905, Section 8.2.5 [Music notation inside markup], page 334, Section 36.8 [Rotating objects], page 789, Section 8.2.2 [Selecting font and font size], page 323, Section A.1.1 [Font markup], page 807. Section 8.3.2 [Finding fonts], page 337, Section 8.3.3 [Font families], page 337, Section 8.3.5 [Changing fonts], page 340.


Snippets: Section “Text” in *Snippets*.

8.3.5 Changing fonts

It is possible to change the fonts used in LilyPond’s default font families.

```
\paper {
  property-defaults.fonts.serif = "Linux Libertine 0"
  property-defaults.fonts.sans = "DejaVu Sans"
  property-defaults.fonts.typewriter = "DejaVu Sans Mono"
}

\relative c' {
  c1-\markup {
    serif,
    \sans sans,
    \typewriter typewriter. }
}
```



The same syntax can be used to change the music font; see Section 23.5 [Replacing the notation font], page 649.


To change the fonts used for one specific grob, override its `fonts` property. The following example changes the font for normal tablature “note heads” (which use the `serif` family) while keeping the default font for those that are drawn as a cross (which use the `music` family).

```

\layout {
  \override TabVoice.TabNoteHead.property-defaults.fonts.serif =
    "Linux Libertine 0"
}

\new TabStaff { c' d' e' \deadNote c' }

```



To change the fonts in one specific markup, use the `\font-select` command:

```

\markup \font-select #'((serif . "Linux Libertine 0")
                        (typewriter . "DejaVu Sans Mono")) {
  Copyright © John Doe \typewriter john@doe.org
}

```

Copyright ' John Doe john@doe.org

Known issues and warnings

There are rare situations where the FontConfig library is not able to unambiguously select a font: if the font family name and the font weight (i.e., the value of LilyPond's `font-series` subproperty) of two different fonts are identical, they are handled as being equal. An example for this situation is 'Minion Pro' and 'Minion Pro Display', which both have the family name 'Minion Pro' and the weight 'Regular'. The only solution to fix this is to make the unwanted font unknown to FontConfig.

- If your fonts are in a separate directory not scanned by FontConfig by default, use `ly:font-config-add-font` instead of `ly:font-config-add-directory` to explicitly load the wanted font only.
- If the fonts are in directory searched by default (for example, `~/ .fonts`), you have to remove the offending font so that FontConfig only finds the wanted font.

See also

Notation Reference: Section 8.3.2 [Finding fonts], page 337, Section 8.3.3 [Font families], page 337, Section 8.2.2 [Selecting font and font size], page 323, Section A.1.1 [Font markup], page 807, Section 23.5 [Replacing the notation font], page 649.

Specialist notation

9 Vocal music

Recitativo
Baritono

216 O Freun - - de, nicht die - se Töne!

222 Sondern laßt uns an - - ge -

228 nehmere an - stimmen, und freu -

232 - - - - - *ad libitum* denvollere!

This section explains how to typeset vocal music, and make sure that the lyrics will be aligned with the notes of their melody.

9.1 Common notation for vocal music

This section discusses issues common to most types of vocal music.

9.1.1 References for vocal music

This section indicates where to find details of notation issues that may arise in any type of vocal music.

- Most styles of vocal music use written text as lyrics. An introduction to this notation is to be found in Section “Setting simple songs” in *Learning Manual*.
- Vocal music is likely to require the use of markup mode, either for lyrics or for other text elements (characters’ names, etc.). This syntax is described in Section 8.2.1 [Text markup introduction], page 319.
- *Ambitus* may be added at the beginning of vocal staves, as explained in Section 1.3.7 [Ambitus], page 40.
- Dynamic markings by default are placed below the staff, but in choral music they are usually placed above the staff in order to avoid the lyrics, as explained in Section 9.5.2 [Score layouts for choral], page 390.

See also

Music Glossary: Section “ambitus” in *Music Glossary*.

Learning Manual: Section “Setting simple songs” in *Learning Manual*.

Notation Reference: Section 8.2.1 [Text markup introduction], page 319, Section 1.3.7 [Ambitus], page 40, Section 9.5.2 [Score layouts for choral], page 390.

Snippets: Section “Vocal music” in *Snippets*.

9.1.2 Entering lyrics

Lyrics are entered in a special input mode, which can be introduced by the keyword `\lyricmode`, or by using `\addlyrics` or `\lyricsto`. In this special input mode, the input `d` is not parsed as the pitch *D*, but rather as a one-letter syllable of text. In other words, syllables are entered like notes but with pitches replaced by text.

For example:

```
\lyricmode { Three4 blind mice,2 three4 blind mice2 }
```

There are two main methods for specifying the horizontal placement of the syllables, either by specifying the duration of each syllable explicitly, as in the example above, or by leaving the lyrics to be aligned automatically to a melody or other voice of music, using `\addlyrics` or `\lyricsto`. The former method is described below in Section 9.1.5 [Manual syllable durations], page 352. The latter method is described in Section 9.1.4 [Automatic syllable durations], page 349.

A word or syllable of lyrics begins with an alphabetic character (plus some other characters, see below) and is terminated by any white space or a digit. Later characters in the syllable can be any character that is not a digit or white space.

Because any character that is not a digit or white space is regarded as part of the syllable, a word is valid even if it ends with `}`, which often leads to the following mistake:

```
\lyricmode { lah lah lah }
```

In this example, the `}` is included in the final syllable, so the opening brace is not balanced and the input file will probably not compile. Instead, braces should always be surrounded with white space:

```
\lyricmode { lah lah lah }
```

Punctuation, lyrics with accented characters, characters from non-English languages, or special characters (such as the heart symbol or slanted quotes), may simply be inserted directly into the input file, providing it is saved with UTF-8 encoding. For more information, see Section 22.4 [Special characters], page 644.

```
\relative { d'8 c16 a bes8 f ees' d c4 }
\addlyrics { „Schad’ um das schö -- ne grü -- ne Band, }
```



Normal quotes may be used in lyrics, but they have to be preceded with a backslash character and the whole syllable has to be enclosed between additional quotes. For example,

```
\relative { \time 3/4 e'4 e4. e8 d4 e d c2. }
\addlyrics { "\"I" am so lone -- "ly,\"" said she }
```



The full definition of a word start in lyrics mode is somewhat more complex. A word in lyrics mode is one that begins with an alphabetic character, `_`, `?`, `!`, `:`, `'`, the control characters `^A` through `^F`, `^Q` through `^W`, `^Y`, `^^`, any 8-bit character with an ASCII code over 127, or a two-character combination of a backslash followed by one of ```, `'`, `"`, or `^`.

Great control over the appearance of lyrics comes from using `\markup` inside the lyrics themselves. For explanation of many options, see Section 8.2 [Formatting text], page 319.


Selected snippets

Formatting lyrics syllables

The `\markup` command can be used in `\lyricmode` blocks to format individual syllables in lyrics.

```
mel = \relative c'' { c4 c c c c1 }
lyr = \lyricmode {
  Your lyrics \markup { \italic can }
  \markup { \with-color #red contain }
  \markup { \fontsize #8 \bold Markup! }
}

<<
  \new Voice = "melody" \mel
  \new Lyrics \lyricsto "melody" \lyr
>>
```



See also

Learning Manual: Section “Songs” in *Learning Manual*.

Notation Reference: Section 9.1.4 [Automatic syllable durations], page 349, Section 8.3 [Fonts], page 336, Section 8.2 [Formatting text], page 319, Chapter 19 [Input modes], page 587, Section 9.1.5 [Manual syllable durations], page 352, Section 22.4 [Special characters], page 644.

Internals Reference: Section “LyricText” in *Internals Reference*.

Snippets: Section “Text” in *Snippets*.

9.1.3 Aligning lyrics to a melody

Lyrics are interpreted in `\lyricmode` and printed in a Lyrics context, see Section 33.1 [Contexts explained], page 734.

```
\new Lyrics \lyricmode { ... }
```

Two variants of `\lyricmode` additionally set an associated context used to synchronize the lyric syllables to music. The more convenient `\addlyrics` immediately follows the musical content of the Voice context with which it should be synchronized, implicitly creating a Lyrics context of its own. The more versatile `\lyricsto` requires both specifying the associated Voice context by name and explicitly creating a containing Lyrics context. For details see Section 9.1.4 [Automatic syllable durations], page 349.

Lyrics can be aligned with melodies in two main ways:

- Lyrics can be aligned automatically, with the durations of the syllables being taken from another voice of music or (in special circumstances) an associated melody, using `\addlyrics`, `\lyricsto`, or by setting the `associatedVoice` property. For more details, see Section 9.1.4 [Automatic syllable durations], page 349.

```

<<
\new Staff <<
  \time 2/4
  \new Voice = "one" \relative {
    \voiceOne
    c''4 b8. a16 g4. r8 a4 ( b ) c2
  }
  \new Voice = "two" \relative {
    \voiceTwo
    s2 s4. f'8 e4 d c2
  }
>>

% takes durations and alignment from notes in "one"
\new Lyrics \lyricsto "one" {
  Life is __ _ love, live __ life.
}

% takes durations and alignment from notes in "one" initially
% then switches to "two"
\new Lyrics \lyricsto "one" {
  No more let
  \set associatedVoice = "two" % must be set one syllable early
  sins and sor -- rows grow.
}
>>

```



The first stanza shows the normal way of entering lyrics.

The second stanza shows how the voice from which the lyric durations are taken can be changed. This is useful if the words to different stanzas fit the notes in different ways and all the durations are available in Voice contexts. For more details, see Section 9.3 [Stanzas], page 377.

- Lyrics can be aligned independently of the duration of any notes if the durations of the syllables are specified explicitly, and entered with `\lyricmode`.

```

<<
\new Voice = "one" \relative {
  \time 2/4
  c''4 b8. a16 g4. f8 e4 d c2
}

% uses previous explicit duration of 2;
\new Lyrics \lyricmode {
  Joy to the earth!
}

```

```
% explicit durations, set to a different rhythm
\new Lyrics \lyricmode {
  Life4 is love,2. live4 life.2
}
>>
```



The first stanza is not aligned with the notes because the durations were not specified, and the previous value of 2 is used for each word.

The second stanza shows how the words can be aligned quite independently from the notes. This is useful if the words to different stanzas fit the notes in different ways and the required durations are not available in a music context. For more details see Section 9.1.5 [Manual syllable durations], page 352. This technique is also useful when setting dialogue over music; for examples showing this, see Section 9.6.5 [Dialogue over music], page 399.

See also

Learning Manual: Section “Aligning lyrics to a melody” in *Learning Manual*.

Notation Reference: Section 33.1 [Contexts explained], page 734, Section 9.1.4 [Automatic syllable durations], page 349, Section 9.3 [Stanzas], page 377, Section 9.1.5 [Manual syllable durations], page 352, Section 9.6.5 [Dialogue over music], page 399, Section 9.1.5 [Manual syllable durations], page 352.

Internals Reference: Section “Lyrics” in *Internals Reference*.

9.1.4 Automatic syllable durations

Lyrics can be automatically aligned to the notes of a melody in three ways:

- by specifying the named Voice context containing the melody with `\lyricsto`,
- by introducing the lyrics with `\addlyrics` and placing them immediately after the Voice context containing the melody,
- by setting the `associatedVoice` property, the alignment of the lyrics may be switched to a different named Voice context at any musical moment.


In all three methods hyphens can be drawn between the syllables of a word and extender lines can be drawn beyond the end of a word. For details, see Section 9.1.8 [Extenders and hyphens], page 357.

The Voice context containing the melody to which the lyrics are being aligned must not have “died”, or the lyrics after that point will be lost. This can happen if there are periods when that voice has nothing to do. For methods of keeping contexts alive, see Section 33.3 [Keeping contexts alive], page 740.

Using `\lyricsto`

Lyrics can be aligned under a melody automatically by specifying the named Voice context containing the melody with `\lyricsto`:

```
<<
  \new Voice = "melody" \relative {
    a'1 a4. a8 a2
  }
  \new Lyrics \lyricsto "melody" {
    These are the words
  }
>>
```



This aligns the lyrics to the notes of the named Voice context, which must already exist. Therefore normally the Voice context is specified first, followed by the Lyrics context. The lyrics themselves follow the `\lyricsto` command. The `\lyricsto` command invokes lyric mode automatically. By default, the lyrics are placed underneath the notes. For other placements, see Section 9.2.2 [Placing lyrics vertically], page 360.

Using `\addlyrics`

The `\addlyrics` command is just a convenient shortcut that can sometimes be used instead of having to set up the lyrics through a more complicated LilyPond structure.

```
{ MUSIC }
\addlyrics { LYRICS }
```

is the same as

```
\new Voice = "blah" { MUSIC }
\new Lyrics \lyricsto "blah" { LYRICS }
```

Here is an example,

```
{
  \time 3/4
  \relative { c'2 e4 g2. }
  \addlyrics { play the game }
}
```



More stanzas can be added by adding more `\addlyrics` sections:

```
{
  \time 3/4
  \relative { c'2 e4 g2. }
  \addlyrics { play the game }
  \addlyrics { speel het spel }
  \addlyrics { joue le jeu }
}
```



The command `\addlyrics` cannot handle polyphonic settings. Also, it cannot be used to associate lyrics to a `TabVoice`. For these cases one should use `\lyricsto`.

Using `associatedVoice`

The melody to which the lyrics are being aligned can be changed by setting the `associatedVoice` property,

```
\set associatedVoice = "lala"
```

The value of the property (here: "lala") should be the name of a `Voice` context. For technical reasons, the `\set` command must be placed one syllable before the one to which the change in voice is to apply.

Here is an example demonstrating its use:

```
<<
  \new Staff <<
    \time 2/4
    \new Voice = "one" \relative {
      \voiceOne
      c'4 b8. a16 g4. r8 a4 ( b ) c2
    }
    \new Voice = "two" \relative {
      \voiceTwo
      s2 s4. f'8 e8 d4. c2
    }
  >>
  % takes durations and alignment from notes in "one" initially
  % then switches to "two"
  \new Lyrics \lyricsto "one" {
    No more let
    \set associatedVoice = "two" % must be set one syllable early
    sins and sor -- rows grow.
  }
>>
```



See also

Notation Reference: Section 9.1.8 [Extenders and hyphens], page 357, Section 33.3 [Keeping contexts alive], page 740, Section 9.2.2 [Placing lyrics vertically], page 360.

9.1.5 Manual syllable durations

In some complex vocal music, it may be desirable to place lyrics completely independently of notes. In this case do not use `\lyricsto` or `\addlyrics` and do not set `associatedVoice`. Syllables are entered like notes – but with pitches replaced by text – and the duration of each syllable is entered explicitly after the syllable.

Hyphenated lines may be drawn between syllables as usual, but extender lines cannot be drawn when there is no associated voice.

Here are two examples:

```
<<
  \new Voice = "melody" \relative {
    c''2 a f f e e
  }
  \new Lyrics \lyricmode {
    c4. -- a -- f -- f -- e2. -- e
  }
>>
```



```
<<
  \new Staff {
    \relative {
      c''2 c2
      d1
    }
  }
  \new Lyrics {
    \lyricmode {
      I2 like4. my8 cat!1
    }
  }
  \new Staff {
    \relative {
      c'8 c c c c c c c
      c8 c c c c c c c
    }
  }
>>
```



This technique is useful when writing dialogue over music, see Section 9.6.5 [Dialogue over music], page 399.

To change syllable alignment, simply override the `self-alignment-X` property:

```
<<
\new Voice = "melody" \relative {
  \time 3/4
  c'2 e4 g2 f
}
\new Lyrics \lyricmode {
  \override LyricText.self-alignment-X = #LEFT
  play1 a4 game4
}
>>
```



See also


Notation Reference: Section 9.6.5 [Dialogue over music], page 399.

Internals Reference: Section “Lyrics” in *Internals Reference*, Section “Voice” in *Internals Reference*.

9.1.6 Multiple syllables to one note

In order to assign more than one syllable to a single note with spaces between the syllables, you can surround the phrase with quotes or use a `_` character. Alternatively, you can use the tilde symbol (`~`) to get a lyric tie.

```
{
  \relative {
    \autoBeamOff
    r8 b' c fis, fis c' b e,
  }
  \addlyrics
  {
    % Ensure hyphens are visible
    \override LyricHyphen.minimum-distance = 1.0
    Che_in ques -- ta_e_in quel -- l'al -- tr'on -- da
  }
  \addlyrics { "Che in" ques -- "ta e in" quel -- l'al -- tr'on -- da }
  \addlyrics { Che~in ques -- ta~e~in quel -- l'al -- tr'on -- da }
}
```



See also

Internals Reference: Section “LyricCombineMusic” in *Internals Reference*.

9.1.7 Multiple notes to one syllable

Sometimes, particularly in medieval and Baroque music, several notes are sung on one syllable; this is called *melisma*, see Section “*melisma*” in *Music Glossary*. The syllable to a melisma is usually left-aligned with the first note of the melisma.

When a melisma occurs on a syllable other than the last one in a word, that syllable is usually joined to the following one with a hyphenated line. This is indicated by placing a double hyphen, --, immediately after the syllable.

Alternatively, when a melisma occurs on the last or only syllable in a word an extender line is usually drawn from the end of the syllable to the last note of the melisma. This is indicated by placing a double underscore, __, immediately after the word.

There are five ways in which melismata can be indicated:

- Melismata are created automatically over notes which are tied together:

```
<<
\new Voice = "melody" \relative {
  \time 3/4
  f''4 g2 ~ |
  4 e2 ~ |
  8
}
\new Lyrics \lyricsto "melody" {
  Ky -- ri -- e __
}
>>
```



- Melismata can be created automatically from the music by placing slurs over the notes of each melisma. This is the usual way of entering lyrics:

```
<<
\new Voice = "melody" \relative {
  \time 3/4
  f''4 g8 ( f e f )
  e8 ( d e2 )
}
\new Lyrics \lyricsto "melody" {
  Ky -- ri -- e __
}
>>
```



Note that phrasing slurs do not affect the creation of melismata.

- Notes are considered a melisma if they are manually beamed, providing automatic beaming is switched off. See Section 2.4.2 [Setting automatic beam behavior], page 104.

```
<<
\new Voice = "melody" \relative {
  \time 3/4
  \autoBeamOff
  f''4 g8[ f e f]
  e2.
}
\new Lyrics \lyricsto "melody" {
  Ky -- ri -- e
}
>>
```



Clearly this is not suited to melismata over notes which are longer than eighth notes.

- An unslurred group of notes will be treated as a melisma if they are bracketed between `\melisma` and `\melismaEnd`.

```
<<
\new Voice = "melody" \relative {
  \time 3/4
  f''4 g8
  \melisma
  f e f
  \melismaEnd
  e2.
}
\new Lyrics \lyricsto "melody" {
  Ky -- ri -- e
}
>>
```



- A melisma can be defined entirely in the lyrics by entering a single underscore character, `_`, for every extra note that has to be added to the melisma.

```
<<
\new Voice = "melody" \relative {
  \time 3/4
  f''4 g8 f e f
  e8 d e2
}
\new Lyrics \lyricsto "melody" {
  Ky -- ri -- _ _ _ e _ _ _
}
>>
```



It is possible to have ties, slurs and manual beams in the melody without their indicating melismata. To do this, set `melismaBusyProperties`:

```
<<
\new Voice = "melody" \relative {
  \time 3/4
  \set melismaBusyProperties = #'()
  c'4 d ( e )
  g8 [ f ] f4 ~ 4
}
\new Lyrics \lyricsto "melody" {
  Ky -- ri -- e e -- le -- i -- son
}
>>
```



Other settings for `melismaBusyProperties` can be used to selectively include or exclude ties, slurs, and beams from the automatic detection of melismata; see `melismaBusyProperties` in Section “Tunable context properties” in *Internals Reference*.

Alternatively, if all melismata indications are to be ignored, `ignoreMelismata` may be set true; see Section 9.3.5 [Stanzas with different rhythms], page 382.

If a melisma is required during a passage in which `melismaBusyProperties` is active, it may be indicated by placing a single underscore in the lyrics for each note which should be included in the melisma:

```
<<
\new Voice = "melody" \relative {
  \time 3/4
  \set melismaBusyProperties = #'()
  c'4 d ( e )
  g8 [ f ] ~ 4 ~ f
}
\new Lyrics \lyricsto "melody" {
  Ky -- ri -- _ e -- - - -
}
>>
```



Predefined commands

`\autoBeamOff`, `\autoBeamOn`, `\melisma`, `\melismaEnd`.

See also

Musical Glossary: Section “melisma” in *Music Glossary*.

Learning Manual: Section “Aligning lyrics to a melody” in *Learning Manual*.

Notation Reference: Section 9.1.3 [Aligning lyrics to a melody], page 347, Section 9.1.4 [Automatic syllable durations], page 349, Section 2.4.2 [Setting automatic beam behavior], page 104, Section 9.3.5 [Stanzas with different rhythms], page 382.

Internals Reference: Section “Tunable context properties” in *Internals Reference*.

Known issues and warnings

Extender lines under melismata are not created automatically; they must be inserted manually with a double underscore.

9.1.8 Extenders and hyphens

In the last syllable of a word, melismata are sometimes indicated with a long horizontal line starting in the melisma syllable, and ending in the next one. Such a line is called an extender line, and it is entered manually as ‘`--`’ (note the spaces before and after the two underscore characters). It is also possible to create extender lines automatically by setting `autoExtenders` to `#t`.

Note: Melismata are indicated in the score with extender lines, which are entered as one double underscore; but short melismata can also be entered by skipping individual notes, which are entered as single underscore characters; these do not make an extender line to be typeset by default.

Centered hyphens are entered as ‘`--`’ between syllables of a same word (note the spaces before and after the two hyphen characters). The hyphen will be centered between the syllables, and its length will be adjusted depending on the space between the syllables.

In tightly engraved music, hyphens can be removed. Whether this happens can be controlled with the `minimum-distance` (minimum distance between two syllables) and the `minimum-length` (threshold below which hyphens are removed) properties of `LyricHyphen`.

By default a hyphen is not repeated after a system break when the next line begins with a new syllable. Setting the `after-line-breaking` property to `#t` allows hyphens to be drawn in such situations.

See also

Internals Reference: Section “`LyricExtender`” in *Internals Reference*, Section “`LyricHyphen`” in *Internals Reference*.


9.1.9 Gradual changes of vowel

Vowel transitions (gradual changes of vowel or sustained consonant), which may be indicated by arrows between syllables, are entered with the command `\vowelTransition` (see Gould pp. 452–453). The arrow shows the length of the transition, and it is by default always drawn (space is added if necessary in tightly engraved music). Ties between notes of unchanged pitch or slurs show that there is no new articulation, despite a change of vowel. The minimum length of the arrows may be adjusted with the `minimum-length` property of `VowelTransition`.

```

{
  c'2 c'
  \set melismaBusyProperties = #'()
  c'2 ~ c'
  \time 3/2
  d'4( e' f' e' f'2
  e'2.)
}
\addlyrics
{
  Ah \vowelTransition oh,
  ah \vowelTransition oh,
  ah \vowelTransition _ _ _ _
  oh.
}

```



See also

Musical Glossary: Section “vowel transition” in *Music Glossary*.

Internals Reference: Section “VowelTransition” in *Internals Reference*.

9.2 Techniques specific to lyrics

9.2.1 Working with lyrics and variables

Variables containing lyrics can be created, but the lyrics must be entered in lyric mode:

```

musicOne = \relative {
  c''4 b8. a16 g4. f8 e4 d c2
}
verseOne = \lyricmode {
  Joy to the world, the Lord is come.
}
\score {
  <<
    \new Voice = "one" {
      \time 2/4
      \musicOne
    }
    \new Lyrics \lyricsto "one" {
      \verseOne
    }
  >>
}

```



Durations do not need to be added if the variable is to be invoked with `\addlyrics` or `\lyricsto`.

For different or more complex orderings, the best way is to define the music and lyric variables first, then set up the hierarchy of staves and lyrics, omitting the lyrics themselves, and then add the lyrics using `\context` underneath. This ensures that the voices referenced by `\lyricsto` have always been defined earlier. For example:

```
sopranoMusic = \relative { c''4 c c c }
contraltoMusic = \relative { a'4 a a a }
sopranoWords = \lyricmode { Sop -- ra -- no words }
contraltoWords = \lyricmode { Con -- tral -- to words }

\score {
  \new ChoirStaff <<
    \new Staff {
      \new Voice = "sopranos" {
        \sopranoMusic
      }
    }
    \new Lyrics = "sopranos"
    \new Lyrics = "contraltos"
    \new Staff {
      \new Voice = "contraltos" {
        \contraltoMusic
      }
    }
    \context Lyrics = "sopranos" {
      \lyricsto "sopranos" {
        \sopranoWords
      }
    }
    \context Lyrics = "contraltos" {
      \lyricsto "contraltos" {
        \contraltoWords
      }
    }
  }
  >>
}
```



See also


Notation Reference: Section 9.2.2 [Placing lyrics vertically], page 360.

Internals Reference: Section “LyricCombineMusic” in *Internals Reference*, Section “Lyrics” in *Internals Reference*.

9.2.2 Placing lyrics vertically

Depending on the type of music, lyrics may be positioned above the staff, below the staff, or between staves. Placing lyrics below the associated staff is the easiest, and can be achieved by simply defining the Lyrics context below the Staff context:


```
\score {
  <<
    \new Staff {
      \new Voice = "melody" {
        \relative { c' '4 c c c }
      }
    }
    \new Lyrics {
      \lyricsto "melody" {
        Here are the words
      }
    }
  >>
}
```



Lyrics may be positioned above a staff using one of two methods. The simplest (and preferred) method is to use the same syntax as described above, explicitly specifying the position of the lyrics. The argument to `alignAboveContext` is the name of a Staff context or one of its siblings (using Voice doesn't work).

Use `alignBelowContext` to position lyrics below a staff. This is usually only needed to enforce alignment to a staff that is not the default.

```
\score {
  <<
    \new Staff = "staff" {
      \new Voice = "melody" {
        \relative { c' '4 c c c }
      }
    }
    \new Lyrics \with { alignAboveContext = "staff" } {
      \lyricsto "melody" {
        Here are the words
      }
    }
  >>
}
```




Alternatively, a two-step process may be used. First the Lyrics context is declared (without any content) before the Staff and Voice contexts, then the `\lyricsto` command is placed after the Voice declaration it references by using `\context`, as follows:

```

\score {
  <<
    \new Lyrics = "lyrics" \with {
      % lyrics above a staff should have this override
      \override VerticalAxisGroup.staff-affinity = #DOWN
    }
    \new Staff {
      \new Voice = "melody" {
        \relative { c''4 c c c }
      }
    }
    \context Lyrics = "lyrics" {
      \lyricsto "melody" {
        Here are the words
      }
    }
  >>
}

```




When there are two voices on separate staves the lyrics may be placed between the staves using either of these methods. Here is an example of the second method:

```

\score {
  \new ChoirStaff <<
    \new Staff {
      \new Voice = "sopranos" {
        \relative { c''4 c c c }
      }
    }
    \new Lyrics = "sopranos"
    \new Lyrics = "contraltos" \with {
      % lyrics above a staff should have this override
      \override VerticalAxisGroup.staff-affinity = #DOWN
    }
    \new Staff {
      \new Voice = "contraltos" {
        \relative { a'4 a a a }
      }
    }
    \context Lyrics = "sopranos" {
      \lyricsto "sopranos" {
        Sop -- ra -- no words
      }
    }
    \context Lyrics = "contraltos" {
      \lyricsto "contraltos" {
        Con -- tral -- to words
      }
    }
  >>
}

```

Other combinations of lyrics and staves may be generated by elaborating these examples, or by examining the templates in the Learning Manual, see Section “Vocal ensembles templates” in *Learning Manual*.

Selected snippets

Arranging separate lyrics on a single line

Sometimes you may want to put lyrics for different performers on a single line: where there is rapidly alternating text, for example. This snippet shows how it can be done with adjusting the `nonstaff-nonstaff-spacing` property of the `VerticalAxisGroup` grob.

```
\layout {
  \context {
    \Lyrics
    \override VerticalAxisGroup
      .nonstaff-nonstaff-spacing
      .minimum-distance = ##f
  }
}

aliceSings = \markup { \smallCaps "Alice" }
eveSings = \markup { \smallCaps "Eve" }

<<
\new Staff <<
  \new Voice = "alice" {
    f'4^\aliceSings g' r2 |
    s1 |
    f'4^\aliceSings g' r2 |
    s1 | \break
    % ...

    \voiceOne
    s2 a'8^\aliceSings a' b'4 |
    \oneVoice
    g'1
  }
  \new Voice = "eve" {
    s1 |
    a'2^\eveSings g' |
    s1 |
    a'2^\eveSings g'
  }
}
```

```

% ...

\voiceTwo
f'4^\eveSings a'8 g' f'4 e' |
\oneVoice
s1
}
>>

\new Lyrics \lyricsto "alice" {
  may -- be
  sec -- ond
  % ...
  Shut up, you fool!
}

\new Lyrics \lyricsto "eve" {
  that the
  words are
  % ...
  ...and then I was like--
}
>>

```

The musical score consists of two staves. The first staff has four measures. The first measure has a treble clef, a common time signature, and a whole note. Above the note is the label 'ALICE' and below it is the lyric 'may-be'. The second measure has a whole note. Above the note is the label 'EVE' and below it is the lyric 'that the'. The third measure has a whole note. Above the note is the label 'ALICE' and below it is the lyric 'sec-ond'. The fourth measure has a whole note. Above the note is the label 'EVE' and below it is the lyric 'words are'. The second staff starts with a measure rest labeled '5'. The first measure has a whole note. Above the note is the label 'EVE' and below it is the lyric '...and then I'. The second measure has a whole note. Above the note is the label 'ALICE' and below it is the lyric 'Shut up, you like--'. The third measure has a whole note. Above the note is the label 'ALICE' and below it is the lyric 'fool!'.

See also

Learning Manual: Section “Vocal ensembles templates” in *Learning Manual*.

Notation Reference: Section 33.7 [Context layout order], page 753, Section 33.2 [Creating and referencing contexts], page 737.


9.2.3 Placing syllables horizontally

To increase the spacing between lyrics, set the minimum-distance property of `LyricSpace`.

```


\relative c' {
  c c c c
  \override Lyrics.LyricSpace.minimum-distance = 1.0
  c c c c
}
\addlyrics {
  longtext longtext longtext longtext
  longtext longtext longtext longtext
}

```



To make this change for all lyrics in the score, set the property in the `\layout` block.

```
\score {
  \relative {
    c' c c c
    c c c c
  }
  \addlyrics {
    longtext longtext longtext longtext
    longtext longtext longtext longtext
  }
  \layout {
    \context {
      \Lyrics
      \override LyricSpace.minimum-distance = 1.0
    }
  }
}
```



Selected snippets

Lyrics alignment

Horizontal alignment for lyrics can be set by overriding the `self-alignment-X` property of the `LyricText` object. Value `-1` means left-aligned, `0` centered, and `1` right-aligned. Alternatively, you can use the Scheme values `LEFT`, `CENTER`, and `RIGHT` instead of numbers. Other numeric values are possible, too – don't forget to add the `'#` Scheme prefix for negative numbers!

```
\layout {
  ragged-right = ##f
}

\relative c'' {
  c1 c c c
}
```

```

\addlyrics {
  \once \override LyricText.self-alignment-X = #LEFT
  "left-aligned"
  \once \override LyricText.self-alignment-X = #CENTER
  "centered"
  \once \override LyricText.self-alignment-X = 1
  "right-aligned"
  \once \override LyricText.self-alignment-X = #-1.5
  "overly left-aligned"
}

```



Aligning syllables with melisma


By default, lyrics syllables that start a melisma are left-aligned on their note. The alignment can be altered using the `lyricMelismaAlignment` property.

```

<<
  \new Staff {
    \new Voice = "vocal" \relative c'' {
      \override TextScript.staff-padding = #2
      c d~\markup default d e
      c d~\markup "right aligned" d e
      c d~\markup "center aligned" d e
      c d~\markup "reset to default" d e
    }
  }
  \new Lyrics \lyricsto "vocal" {
    word word word
    \set lyricMelismaAlignment = #RIGHT
    word word word
    \set lyricMelismaAlignment = #CENTER
    word word word
    \unset lyricMelismaAlignment
    word word word
  }
>>

\layout {
  ragged-right = ##f
}

```





Known issues and warnings

Checking to make sure that text scripts and lyrics are within the margins requires additional calculations. To speed up processing slightly, this feature can be disabled:

```
\override Score.PaperColumn.keep-inside-line = ##f
```

To make lyrics avoid bar lines as well, use

```
\layout {
  \context {
    \Lyrics
    \consists Bar_engraver
    \consists Separating_line_group_engraver
    \hide BarLine
  }
}
```

9.2.4 Lyrics and repeats

Simple repeats

Repeats in *music* are fully described elsewhere; see Chapter 4 [Repeats], page 188. This section explains how to add lyrics to repeated sections of music.

Lyrics to a section of music that is repeated should be surrounded by exactly the same repeat construct as the music, if the words are unchanged.

```
\score {
  <<
    \new Staff {
      \new Voice = "melody" {
        \relative {
          a'4 a a a
          \repeat volta 2 { b4 b b b }
        }
      }
    }
    \new Lyrics {
      \lyricsto "melody" {
        Not re -- peat -- ed.
        \repeat volta 2 { Re -- peat -- ed twice. }
      }
    }
  >>
}
```



The words will then be correctly expanded if the repeats are unfolded.

```

\score {
  \unfoldRepeats {
    <<
      \new Staff {
        \new Voice = "melody" {
          \relative {
            a'4 a a a
            \repeat volta 2 { b4 b b b }
          }
        }
      }
      \new Lyrics {
        \lyricsto "melody" {
          Not re -- peat -- ed.
          \repeat volta 2 { Re -- peat -- ed twice. }
        }
      }
    >>
  }
}

```



If the repeated section is to be unfolded and has different words, simply enter all the words:

```

\score {
  <<
    \new Staff {
      \new Voice = "melody" {
        \relative {
          a'4 a a a
          \*2 { b4 b b b }
        }
      }
    }
    \new Lyrics {
      \lyricsto "melody" {
        Not re -- peat -- ed.
        The first time words.
        Sec -- ond time words.
      }
    }
  >>
}

```



When the words to a repeated volta section are different, the words to each repeat must be entered in separate Lyrics contexts, correctly nested in parallel sections:

```
\score {
  <<
    \new Staff {
      \new Voice = "melody" {
        \relative {
          a'4 a a a
          \repeat volta 2 { b4 b b b }
        }
      }
    }
  \new Lyrics \lyricsto "melody" {
    Not re -- peat -- ed.
    <<
      { The first time words. }
      \new Lyrics {
        \set associatedVoice = "melody"
        Sec -- ond time words.
      }
    >>
  }
  >>
}
```




More verses may be added in a similar way:

```
\score {
  <<
    \new Staff {
      \new Voice = "singleVoice" {
        \relative {
          a'4 a a a
          \repeat volta 3 { b4 b b b }
          c4 c c c
        }
      }
    }
  \new Lyrics \lyricsto "singleVoice" {
    Not re -- peat -- ed.
    <<
      { The first time words. }
      \new Lyrics {
        \set associatedVoice = "singleVoice"
        Sec -- ond time words.
      }
      \new Lyrics {
```

```

        \set associatedVoice = "singleVoice"
        The third time words.
    }
    >>
    The end sec -- tion.
}
>>
}

```



However, if this construct is embedded within a multi-staff context such as a `ChoirStaff` the lyrics of the second and third verses will appear beneath the bottom staff.

To position them correctly use `alignBelowContext`:

```

\score {
  <<
    \new Staff {
      \new Voice = "melody" {
        \relative {
          a'4 a a a
          \repeat volta 3 { b4 b b b }
          c4 c c c
        }
      }
    }
    \new Lyrics = "firstVerse" \lyricsto "melody" {
      Not re -- peat -- ed.
    }
    <<
      { The first time words. }
      \new Lyrics = "secondVerse"
      \with { alignBelowContext = "firstVerse" } {
        \set associatedVoice = "melody"
        Sec -- ond time words.
      }
      \new Lyrics = "thirdVerse"
      \with { alignBelowContext = "secondVerse" } {
        \set associatedVoice = "melody"
        The third time words.
      }
    }
    >>
    The end sec -- tion.
  }
  \new Voice = "harmony" {
    \relative {
      f'4 f f f
      \repeat volta 3 { g8 g g4 g2 }
      a4 a8. a16 a2
    }
  }
}


```



```

    }
  }
>>
}

```



Not re-peat-ed. The first time words. The end section.
 Sec - ond time words.
 The third time words.

Repeats with alternative endings

If the words of the repeated section are the same, and none of the `\alternative` blocks start with a rest, exactly the same structure can be used for both the lyrics and music. This has the advantage that `\unfoldRepeats` will expand both music and lyrics correctly.

```

\score {
  <<
    \new Staff {
      \time 2/4
      \new Voice = "melody" {
        \relative {
          a'4 a a a
          \repeat volta 2 { b4 b }
          \alternative {
            \volta 1 { b b }
            \volta 2 { b c }
          }
        }
      }
    }
  }
  \new Lyrics {
    \lyricsto "melody" {
      Not re -- peat -- ed.
      \repeat volta 2 { Re -- peat -- }
      \alternative {
        \volta 1 { ed twice. }
        \volta 2 { ed twice. }
      }
    }
  }
  >>
}

```



Not re-peated. Repeated twice. ed twice.

But when the repeated section has different words, or when one of the `\alternative` blocks starts with a rest, a repeat construct cannot be used around the words and `\skip` commands have to be inserted manually to skip over the notes in the alternative sections which do not apply.

Note: do not use an underscore, `_`, to skip notes – an underscore indicates a melisma, causing the preceding syllable to be left-aligned.

Note: The `\skip` command must be followed by a number, but this number is ignored in lyrics which derive their durations from the notes in an associated melody through `\addlyrics` or `\lyricsto`. Each `\skip` skips a single note of any value, irrespective of the value of the following number.

```
\score {
  <<
    \new Staff {
      \time 2/4
      \new Voice = "melody" {
        \relative {
          \repeat volta 2 { b'4 b }
          \alternative {
            \volta 1 { b b }
            \volta 2 { b c }
          }
          c4 c
        }
      }
    }
  }
  \new Lyrics {
    \lyricsto "melody" {
      The first time words.
      \*2 \skip 1
      End here.
    }
  }
  \new Lyrics {
    \lyricsto "melody" {
      Sec -- ond
      \*2 \skip 1
      time words.
    }
  }
}
>>
```



When a note is tied over into two or more alternative endings a tie is used to carry the note into the first alternative ending and a `\repeatTie` is used in the second and subsequent endings. This structure causes difficult alignment problems when lyrics are involved and increasing the length of the alternative sections so the tied notes are contained wholly within them may give a more acceptable result.

The tie creates a melisma into the first alternative, but not into the second and subsequent alternatives, so to align the lyrics correctly it is necessary to disable the automatic creation of melismata over the volta section and insert manual skips.

```
\score {
  <<
    \new Staff {
      \time 2/4
      \new Voice = "melody" {
        \relative {
          \set melismaBusyProperties = #'()
          \repeat volta 2 { b'4 b ~}
          \alternative {
            \volta 1 { b b }
            \volta 2 { b \repeatTie c }
          }
          \unset melismaBusyProperties
          c4 c
        }
      }
    }
  }
  \new Lyrics {
    \lyricsto "melody" {
      \repeat volta 2 { Here's a __ }
      \alternative {
        \volta 1 { \skip 1 verse }
        \volta 2 { \skip 1 sec }
      }
      ond one.
    }
  }
  >>
}
```




Note that if `\unfoldRepeats` is used around a section containing `\repeatTie`, the `\repeatTie` should be removed to avoid both types of tie being printed.

When the repeated section has different words a `\repeat` cannot be used around the lyrics and `\skip` commands need to be inserted manually, as before.

```

\score {
  <<
    \new Staff {
      \time 2/4
      \new Voice = "melody" {
        \relative {
          \repeat volta 2 { b'4 b ~}
          \alternative {
            \volta 1 { b b }
            \volta 2 { b \repeatTie c }
          }
          c4 c
        }
      }
    }
    \new Lyrics {
      \lyricsto "melody" {
        Here's a __ verse.
        \*2 \skip 1
      }
    }
    \new Lyrics {
      \lyricsto "melody" {
        Here's one
        \*2 \skip 1
        more to sing.
      }
    }
  >>
}

```



If you wish to show extenders and hyphens into and out of alternative sections these must be inserted manually.

```

\score {
  <<
    \new Staff {
      \time 2/4
      \new Voice = "melody" {
        \relative {
          \repeat volta 2 { b'4 b ~}
          \alternative {
            \volta 1 { b b }
            \volta 2 { b \repeatTie c }
          }
          c4 c
        }
      }
    }
  >>
}

```

```

    }
  }
  \new Lyrics {
    \lyricsto "melody" {
      Here's a __ verse.
      \*2 \skip 1
    }
  }
  \new Lyrics {
    \lyricsto "melody" {
      Here's "a_"
      \skip 1
      "_ " sec -- ond one.
    }
  }
}
>>
}

```



See also

Notation Reference: Section 33.3 [Keeping contexts alive], page 740, Chapter 4 [Repeats], page 188.


9.2.5 Divisi lyrics

When just the words and rhythms of the two parts differ while the pitches remain the same, temporarily turning off the automatic detection of melismata and indicating the melisma in the lyrics may be the appropriate method to use:

```


\score {
  <<
    \new Voice = "melody" {
      \relative c' {
        \set melismaBusyProperties = #'()
        \slurDashed
        e4 e8( e) c4 c |
        \unset melismaBusyProperties
        c
      }
    }
    \new Lyrics \lyricsto "melody" {
      They shall not o -- ver -- come
    }
    \new Lyrics \lyricsto "melody" {
      We will _ rock you, yeah
    }
  >>
}

```



When both music and words differ it may be better to display the differing music and lyrics by naming voice contexts and attaching lyrics to those specific contexts:

```
\score {
  <<
    \new Voice = "melody" {
      \relative {
        <<
          {
            \voiceOne
            e'4 e8 e
          }
          \new Voice = "splitpart" {
            \voiceTwo
            c4 c
          }
        >>
        \oneVoice
        c4 c |
        c
      }
    }
    \new Lyrics \lyricsto "melody" {
      They shall not o -- ver -- come
    }
    \new Lyrics \lyricsto "splitpart" {
      We will
    }
  >>
}
```



It is common in choral music to have a voice part split for several measures. The `<< {...} \\ {...} >>` construct, where the two (or more) musical expressions are separated by double backslashes, might seem the proper way to set the split voices. This construct, however, will assign **all** the expressions within it to **NEW Voice contexts** which will result in *no lyrics* being set for them since the lyrics will be set to the original voice context – not, typically, what one wants. The temporary polyphonic passage is the proper construct to use, see section *Temporary polyphonic passages* in Section 5.2.1 [Single-staff polyphony], page 221.

9.2.6 Polyphony with shared lyrics

When two voices with different rhythms share the same lyrics, aligning the lyrics to one of the voices may lead to problems in the other voice. For example, the second lyric extender below is too short, since the lyrics are aligned only to the top voice:

```
soprano = \relative { b'8( c d c) d2 }
alto = \relative { g'2 b8( a g a) }
words = \lyricmode { la __ la __ }


\new Staff <<
  \new Voice = "sopranoVoice" { \voiceOne \soprano }
  \new Voice { \voiceTwo \alto }
  \new Lyrics \lyricsto "sopranoVoice" \words
>>
```



To get the desired result, align the lyrics to a new NullVoice context containing a suitable combination of the two voices. The notes of the NullVoice context do not appear on the printed page, but can be used to align the lyrics appropriately:

```
soprano = \relative { b'8( c d c) d2 }
alto = \relative { g'2 b8( a g a) }
aligner = \relative { b'8( c d c) b( a g a) }
words = \lyricmode { la __ la __ }

\new Staff <<
  \new Voice { \voiceOne \soprano }
  \new Voice { \voiceTwo \alto }
  \new NullVoice = "aligner" \aligner
  \new Lyrics \lyricsto "aligner" \words
>>
```



This method also can be used with the `\partCombine` function, which does not allow lyrics on its own:

```
soprano = \relative { b'8( c d c) d2 }
alto = \relative { g'2 b8( a g a) }
aligner = \relative { b'8( c d c) b( a g a) }
words = \lyricmode { la __ la __ }

\new Staff <<
  \new Voice \partCombine \soprano \alto
  \new NullVoice = "aligner" \aligner
  \new Lyrics \lyricsto "aligner" \words
>>
```




Known issues and warnings

The `\addlyrics` function only works with `Voice` lyrics and so cannot be used with `NullVoice`. The `\partCombine` function is described in Section 5.2.5 [Automatic part combining], page 232.

Lastly, this method can be used even when the voices are in different staves, and is not limited to only two voices:

```
soprano = \relative { b'8( c d c) d2 }
altoOne = \relative { g'2 b8( a b4) }
altoTwo = \relative { d'2 g4( fis8 g) }
aligner = \relative { b'8( c d c) d( d d d) }
words = \lyricmode { la __ la __ }

\new ChoirStaff \with {\accepts NullVoice } <<
  \new Staff \soprano
  \new NullVoice = "aligner" \aligner
  \new Lyrics \lyricsto "aligner" \words
  \new Staff \partCombine \altoOne \altoTwo
>>
```




9.3 Stanzas

9.3.1 Adding stanza numbers

Stanza numbers can be added with the setting `\stanza` command, e.g.,

```
\new Voice \relative {
  \time 3/4 g'2 e4 a2 f4 g2.
} \addlyrics {
  \stanza "1."
  Hi, my name is Bert.
} \addlyrics {
  \stanza "2."
  Oh, ché -- ri, je t'aime
}
```



These numbers are put just before the start of the first syllable. Two lines of a stanza can also be grouped together, for example in case of a repeat with different lyrics:

```
stanzaOneOne = \lyricmode {
  \stanza \markup {
    \column {
      \vspace #.2
      \line { "1." \left-brace #30 }
    }
  }
  Child, you're mine and I love you.
  Lend thine ear to what I say.
}
```

```
stanzaOneThree = \lyricmode {
  Child, I have no great -- er joy
  Than to have you walk in truth.
}
```

```
\new Voice {
  \repeat volta 2 {
    c'8 c' c' c' c' c' c'4
    c'8 c' c' c' c' c' c'4
  }
}
\addlyrics { \stanzaOneOne }
\addlyrics { \stanzaOneThree }
```

1. { Child, you're mine and I love you.
Child, I have no greater joy

2
Lend thine ear to what I say.
Than to have you walk in truth.

9.3.2 Stanza reminders

Sometimes it is desirable to repeat the stanza numbers at the beginning of each system. This can be accomplished by setting the `stanzaReminders` context property:

```
\layout {
  \set stanzaReminders = ##t
}
```

```
\new Voice \relative {
  \key e \minor
  b'4 b a g
  fis2 e
  b'4 cis d b \break
}
```

```

e2 dis
e4 g fis fis
e1
}
\addlyrics {
  \stanza "1."
  Je -- su, mei -- ne Freu -- de,
  mei -- nes Her -- zens Wei -- de,
  Je -- su, mei -- ne Zier.
}
\addlyrics {
  \stanza "2."
  Un -- ter dei -- nem Schir -- men
  bin ich vor den Stür -- men
  al -- ler Fein -- de frei.
}
\addlyrics {
  \stanza "3."
  Trotz dem al -- ten Dra -- chen,
  trotz des To -- des Ra -- chen,
  trotz der Furcht dar -- zu!
}
\addlyrics {
  \stanza "4."
  Weg mit al -- len Schät -- zen!
  Du bist mein Er -- göt -- zen,
  Je -- su, mei -- ne Lust!
}
\addlyrics {
  \stanza "5."
  Gu -- te Nacht, o We -- sen,
  das die Welt er -- le -- sen,
  mir ge -- fällt du nicht.
}
\addlyrics {
  \stanza "6."
  Weicht, ihr Trau -- er -- geis -- ter,
  denn mein Freu -- den -- meis -- ter,
  Je -- sus, tritt her -- ein.
}

```



1. Je - su, mei-ne Freu-de, mei - nes Herzens
2. Un - ter dei-nem Schirmen bin ich vor den
3. Trotz dem al - ten Dra-chen, trotz des To - des
4. Weg mit al - len Schätzen! Du bist mein Er-
5. Gu - te Nacht, o We - sen, das die Welt er-
6. Weicht, ihr Trau-er - geis-ter, denn mein Freuden-



1. Wei-de, Je-su, mei-ne Zier.
2. Stürmen al-ler Fein-de frei.
3. Ra-chen, trotz der Furcht dar-zu!
4. göt-zen, Je-su, mei-ne Lust!
5. le-sen, mir ge-fällst du nicht.
6. meister, Je-sus, tritt her-ein.

By default, the stanza reminders are identical to their respective stanza numbers. By setting the `stanzaReminderText` property, this behavior can be changed, by either directly supplying a markup or by giving a function that accepts the original stanza number markup as an argument:

```
\new Voice \relative {
  \key e \minor
  b'4 b a g
  fis2 e \break
  b'4 cis d b
  e2 dis \break
  e4 g fis fis
  e1
}
\addlyrics {
  \stanza "1."
  \set stanzaReminders = ##t
  \set stanzaReminderText = #make-bracket-markup
  Je -- su, mei -- ne Freu -- de,
  mei -- nes Her -- zens Wei -- de,
  \set stanzaReminderText = "(1st)"
  Je -- su, mei -- ne Zier.
}
```



1. Jesu, meine Freude,



[1.] meines Herzens Wei-de,



(1st) Jesu, meine Zier.

The `\noStanza` command resets the stanza number so that no subsequent automatic stanza reminders are printed:

```

\layout {
  \set stanzaReminders = ##t
}

\new Voice \relative {
  \repeat volta 2 {
    a'4 e a b
    c d b2
    a\fermata c4 b
    \break
    a b c d
    e1\fermata
  }
  e4 f g c, \break
  f e d2
  c2 \fermata
}
\addlyrics {
  \stanza "1."
  Herr, ich ha -- be miss -- ge -- han -- del,
  ja mich drückt der Sün -- den Last;
  \noStanza
  und itzt wollt' ich gern aus Schre -- cken
}
\addlyrics {
  \stanza "2."
  ich bin nicht den Weg ge -- wan -- del,
  den du mir ge -- zei -- get hast;
}

```

1. Herr, ich ha - be missgehan-delt, ja mich
2. ich bin nicht den Weg gewan-delt, den du

1. drückt der Sünden Last; und itzt wollt' ich
2. mir ge - zei - get hast;

gern aus Schrecken

9.3.3 Adding dynamics marks to stanzas

Stanzas differing in loudness may be indicated by putting a dynamics mark before each stanza. While there is no special support for such pre-stanza markings, they can easily be included in the stanza number itself:


```
<<
  \new Voice = tune {
    \time 3/4
    g'4 c'2
  }
  \new Lyrics \lyricsto tune {
    \stanza \markup { \dynamic ff 1. }
    Big bang
  }
>>
```



9.3.4 Adding singers' names to stanzas

Names of singers can also be added. They are printed at the start of the line, just like instrument names. They are created by setting `vocalName`. A short version may be entered as `shortVocalName`.

```
\new Voice \relative {
  \time 3/4 g'2 e4 a2 f4 g2.
} \addlyrics {
  \set vocalName = "Bert"
  Hi, my name is Bert.
} \addlyrics {
  \set vocalName = "Ernie"
  Oh, ché -- ri, je t'aime
}
```



9.3.5 Stanzas with different rhythms

Often, different stanzas of one song are put to one melody in slightly differing ways. Such variations can still be captured with `\lyricsto`.

Ignoring melismata


One possibility is that the text has a melisma in one stanza, but multiple syllables in another. One solution is to make the faster voice ignore the melisma. This is done by setting `ignoreMelismata` in the Lyrics context.

```
<<
  \relative \new Voice = "lahlah" {
    \set Staff.autoBeaming = ##f
    c'4
    \slurDotted
    f8.[( g16)]
    a4
  }
>>
```

```

}
\new Lyrics \lyricsto "lahlah" {
  more slow -- ly
}
\new Lyrics \lyricsto "lahlah" {
  go
  \set ignoreMelismata = ##t
  fas -- ter
  \unset ignoreMelismata
  still
}
>>

```



Known issues and warnings

Unlike most `\set` commands, `\set ignoreMelismata` does not work if prefixed with `\once`. It is necessary to use `\set` and `\unset` to bracket the lyrics where melismata are to be ignored.

Adding syllables to grace notes

By default, grace notes (e.g., via `\grace`) do not get assigned syllables when using `\lyricsto`, but this behavior can be changed:

```

<<
\new Voice = melody \relative {
  f'4 \appoggiatura a32 b4
  \grace { f16 a16 } b2
  \afterGrace b2 { f16[ a16] }
  \appoggiatura a32 b4
  \acciaccatura a8 b4
}
\new Lyrics
\lyricsto melody {
  normal
  \set includeGraceNotes = ##t
  case,
  gra -- ce case,
  after -- grace case,
  \set ignoreMelismata = ##t
  app. case,
  acc. case.
}
>>

```



Known issues and warnings

Like `associatedVoice`, `includeGraceNotes` needs to be set at latest one syllable before the one which is to be put under a grace note. In the case of a grace note at the very beginning of a piece of music, using a `\with`, or a `\context` block within `\layout`, is recommended:

```
<<
  \new Voice = melody \relative c' {
    \grace { c16( d e f }
    g1) f
  }
  \new Lyrics \with { includeGraceNotes = ##t }
  \lyricsto melody {
    Ah __ fa
  }
>>
```



Switching to an alternative melody


More complex variations in setting lyrics to music are possible. The melody to which the lyrics are being set can be changed from within the lyrics by setting the `associatedVoice` property:

```
<<
  \relative \new Voice = "lahlah" {
    \set Staff.autoBeaming = ##f
    c'4
    <<
      \new Voice = "alternative" {
        \voiceOne
        \tuplet 3/2 {
          % show associations clearly.
          \override NoteColumn.force-hshift = -3
          f8 f g
        }
      }
    {
      \voiceTwo
      f8.[ g16]
      \oneVoice
    } >>
    a8( b) c
  }
  \new Lyrics \lyricsto "lahlah" {
    Ju -- ras -- sic Park
  }
  \new Lyrics \lyricsto "lahlah" {
    % Tricky: need to set associatedVoice
    % one syllable too soon!
    \set associatedVoice = "alternative" % applies to "ran"
    Ty --
  }
>>
```

```

ran --
no --
\set associatedVoice = "lahlah" % applies to "rus"
sau -- rus Rex
} >>

```



The text for the first stanza is set to the melody called ‘lahlah’ in the usual way, but the second stanza is set initially to the lahlah context and is then switched to the alternative melody for the syllables ‘ran’ to ‘sau’ by the lines:

```

\set associatedVoice = "alternative" % applies to "ran"
Ty --
ran --
no --
\set associatedVoice = "lahlah" % applies to "rus"
sau -- rus Rex

```

Here, *alternative* is the name of the Voice context containing the triplet.

Note the placement of the `\set associatedVoice` command – it appears to be one syllable too early, but this is correct.

Note: The `\set associatedVoice` command must be placed one syllable *before* the one at which the switch to the new voice is to occur. In other words, changing the associated Voice happens one syllable later than expected. This is for technical reasons, and it is not a bug.

9.3.6 Printing stanzas at the end

Sometimes it is appropriate to have one stanza set to the music, and the rest added in verse form at the end of the piece. This can be accomplished by adding the extra verses into a `\markup` section outside of the main score block. Notice that there are several different ways to force line breaks when using `\markup`. For inputting a whole string you may use `\string-lines` with manually inserted `\n` or automatic line breaks as entered or `\wordwrap-string`. If inner formatting code is used a combination of `\line` and `\column` is recommended.

```

melody = \relative {
  e' d c d | e e e e |
  d d e d | c1 | }

text = \lyricmode {
  \stanza "1."
  Ma- ry had a lit- tle lamb,
  its fleece was white as snow.
}

\score {
  <<
  \new Voice = "one" { \melody }

```



```

    \new Lyrics \lyricsto "one" \text
  >>
}

\markup \column \string-lines
  "Verse 2. \n Everywhere that Mary went \n The lamb was sure to go."

\markup \column \string-lines
  "Verse 3.
  All the children laughed and played,
  To see a lamb at school."


\markup \column {
  \line \italic { Verse 4. }
  \line { And so the teacher turned it out, }
  \line { But still it lingered near. }
}

\markup \wordwrap-string "
  Verse 5.

```

Mary took it home again,

It was against the rule."



Verse 2.

Everywhere that Mary went
The lamb was sure to go.

Verse 3.

All the children laughed and played,
To see a lamb at school.

Verse 4.

And so the teacher turned it out,
But still it lingered near.

Verse 5.

Mary took it home again,
It was against the rule.

9.3.7 Printing stanzas at the end in multiple columns

When a piece of music has many verses, they are often printed in multiple columns across the page. An outdented verse number often introduces each verse. The following example shows how to produce such output in LilyPond.

```

melody = \relative {
  c'4 c c c | d d d d
}

text = \lyricmode {
  \stanza "1." This is verse one.
  It has two lines.
}

\score {
  <<
    \new Voice = "one" { \melody }
    \new Lyrics \lyricsto "one" \text
  >>
  \layout { }
}

\markup {
  \fill-line {
    % moves the column off the left margin;
    % can be removed if space on the page is tight
    \hspace #0.1
    \column {
      \line { \bold "2."
        \column {
          "This is verse two."
          "It has two lines."
        }
      }
      % adds vertical spacing between verses
      \combine \null \vspace #0.1
      \line { \bold "3."
        \column {
          "This is verse three."
          "It has two lines."
        }
      }
    }
  }
  % adds horizontal spacing between columns
  \hspace #0.1
  \column {
    \line { \bold "4."
      \column {
        "This is verse four."
        "It has two lines."
      }
    }
  }
  % adds vertical spacing between verses
  \combine \null \vspace #0.1
  \line { \bold "5."
    \column {
      "This is verse five."
    }
  }
}

```

```

        "It has two lines."
    }
}
}
% gives some extra space on the right margin;
% can be removed if page space is tight
\hspace #0.1
}
}

```



1. This is verse one. It has two lines.

2. This is verse two.

It has two lines.

3. This is verse three.

It has two lines.

4. This is verse four.

It has two lines.

5. This is verse five.

It has two lines.

See also

Internals Reference: Section “LyricText” in *Internals Reference*, Section “StanzaNumber” in *Internals Reference*.

9.4 Songs

9.4.1 References for songs

Songs are usually written on three staves with the melody for the singer on the top staff and two staves of piano accompaniment at the bottom. The lyrics of the first stanza are printed immediately underneath the top staff. If there are just a small number of further stanzas these can be printed immediately under the first one, but if there are more stanzas than can be easily accommodated there the second and subsequent stanzas are printed after the music as stand-alone text.

All the notational elements needed to write songs are fully described elsewhere:

- For constructing the staff layout, see Section 6.1 [Displaying staves], page 241.
- For writing piano music, see Chapter 10 [Keyboard and other multi-staff instruments], page 413.
- For writing the lyrics to a melody line, see Section 9.1 [Common notation for vocal music], page 345.
- For placing the lyrics, see Section 9.2.2 [Placing lyrics vertically], page 360.
- For entering stanzas, see Section 9.3 [Stanzas], page 377.
- Songs are frequently printed with the chording indicated by chord names above the staves. This is described in Section 15.2 [Displaying chords], page 512.
- To print fret diagrams of the chords for guitar accompaniment or accompaniment by other fretted instruments, see “Fret diagram markups” in Section 12.1 [Common notation for fretted strings], page 431.

See also

Learning Manual: Section “Songs” in *Learning Manual*.

Notation Reference: Section 9.1 [Common notation for vocal music], page 345, Section 15.2 [Displaying chords], page 512, Section 6.1 [Displaying staves], page 241, Chapter 10 [Keyboard and other multi-staff instruments], page 413, Section 9.2.2 [Placing lyrics vertically], page 360, Section 9.3 [Stanzas], page 377.

Snippets: Section “Vocal music” in *Snippets*.

9.4.2 Lead sheets

Lead sheets may be printed by combining vocal parts and ‘chord mode’; this syntax is explained in Chapter 15 [Chord notation], page 507.

Selected snippets

Simple lead sheet

When put together, chord names, a melody, and lyrics form a lead sheet.

```
<<
\chords { c2 g:sus4 f e }
\new Staff \relative c'' {
  a4 e c8 e r4
  b2 c4( d)
}
\addlyrics { One day this shall be free __ }
>>
```



See also

Notation Reference: Chapter 15 [Chord notation], page 507.

9.5 Choral

This section discusses notation issues that relate most directly to choral music. This includes anthems, part songs, oratorio, etc.

9.5.1 References for choral

Choral music is usually notated on two, three or four staves within a *ChoirStaff* group. Accompaniment, if required, is placed beneath in a *PianoStaff* group, which is usually reduced in size for rehearsal of a *cappella* choral works. The notes for each vocal part are placed in a *Voice* context, with each staff being given either a single vocal part (i.e., one *Voice*) or a pair of vocal parts (i.e., two *Voices*).

Words are placed in *Lyrics* contexts, either underneath each corresponding music staff, or one above and one below the music staff if this contains the music for two parts.

Several common topics in choral music are described fully elsewhere:

- An introduction to creating an SATB vocal score can be found in the *Learning Manual*, see Section “Four-part SATB vocal score” in *Learning Manual*. There is also a built-in template which simplifies the entry of SATB vocal music, see Section “Built-in templates” in *Learning Manual*.

- Several templates suitable for various styles of choral music can also be found in the Learning Manual, see Section “Vocal ensembles templates” in *Learning Manual*.
- For information about `ChoirStaff` and `PianoStaff` see Section 6.1.2 [Grouping staves], page 243.
- Shape note heads, as used in Sacred Harp and similar notation, are described in Section 1.4.3 [Shape note heads], page 46.
- When two vocal parts share a staff the stems, ties, slurs, etc., of the higher part will be directed up and those of the lower part down. To do this, use `\voiceOne` and `\voiceTwo`. See Section 5.2.1 [Single-staff polyphony], page 221.
- When a vocal part temporarily splits, you should use *Temporary polyphonic passages* (see Section 5.2.1 [Single-staff polyphony], page 221).

Predefined commands

`\oneVoice`, `\voiceOne`, `\voiceTwo`.

See also

Learning Manual: Section “Four-part SATB vocal score” in *Learning Manual*, Section “Vocal ensembles templates” in *Learning Manual*.

Notation Reference: Section 33.7 [Context layout order], page 753, Section 6.1.2 [Grouping staves], page 243, Section 1.4.3 [Shape note heads], page 46, Section 5.2.1 [Single-staff polyphony], page 221.

Snippets: Section “Vocal music” in *Snippets*.

Internals Reference: Section “ChoirStaff” in *Internals Reference*, Section “Lyrics” in *Internals Reference*, Section “PianoStaff” in *Internals Reference*.

9.5.2 Score layouts for choral

Choral music containing four staves, with or without piano accompaniment, is usually laid out with two systems per page. Depending on the page size, achieving this may require changes to several default settings. The following settings should be considered:

- The global staff size can be modified to change the overall size of the elements of the score. See Section 27.2 [Setting the staff size], page 683.
- The distances between the systems, the staves and the lyrics can all be adjusted independently. See Chapter 29 [Vertical spacing], page 695.
- The dimensions of the vertical layout variables can be displayed as an aid to adjusting the vertical spacing. This and other possibilities for fitting the music onto fewer pages are described in Chapter 31 [Fitting music onto fewer pages], page 727.
- If the number of systems per page changes from one to two it is customary to indicate this with a system separator mark between the two systems. See Section 6.1.4 [Separating systems], page 248.
- For details of other page formatting properties, see Chapter 26 [Page layout], page 669.

Dynamic markings by default are placed below the staff, but in choral music they are usually placed above the staff in order to avoid the lyrics. The predefined command `\dynamicUp` does this for the dynamic markings in a single Voice context. If there are many Voice contexts this predefined command would have to be placed in every one. Alternatively its expanded form can be used to place all dynamic markings in the entire score above their respective staves, as shown here:

```

\score {
  \new ChoirStaff <<
    \new Staff {
      \new Voice {
        \relative { g'4\f g g g }
      }
    }
    \new Staff {
      \new Voice {
        \relative { d'4 d d\p d }
      }
    }
  >>
  \layout {
    \context {
      \Score
      \override DynamicText.direction = #UP
      \override DynamicLineSpanner.direction = #UP
    }
  }
}

```



Predefined commands

`\dynamicUp`, `\dynamicDown`, `\dynamicNeutral`.

See also

Notation Reference: Section 31.2 [Changing spacing], page 728, Section 31.1 [Displaying spacing], page 727, Chapter 31 [Fitting music onto fewer pages], page 727, Chapter 26 [Page layout], page 669, Chapter 27 [Score layout], page 681, Section 6.1.4 [Separating systems], page 248, Section 27.2 [Setting the staff size], page 683, Chapter 28 [Breaks], page 687, Chapter 29 [Vertical spacing], page 695.

Internals Reference: Section “VerticalAxisGroup” in *Internals Reference*, Section “Staff-Grouper” in *Internals Reference*.

Selected snippets

Using a bracket to clarify divisi


The `\nonArpeggiato` command can be used to indicate the division of voices where there are no stems to provide the information. This is often seen in choral music.

```

\include "english.ly"

\score {
  \relative c'' {
    \key a \major
    \time 2/2
    <<
      \new Voice = "upper" <<
        {
          \voiceOne
          a2( b2
          <b d>1\nonArpeggiato)
          <cs e>\nonArpeggiato ~
          <cs e>4
          \fine
        }
      \addlyrics { \lyricmode { A -- men. } }
    >>
    \new Voice = "lower" {
      \voiceTwo
      a1 ~
      a
      a ~
      a4
      \fine
    }
  }
  >>
}

```



See also

Notation Reference: Section 3.3 [Expressive marks as lines], page 176.

9.6 Opera and stage musicals

The music, lyrics and dialogue to opera and stage musicals are usually set out in one or more of the following forms:

- A *Conductors' Score* containing the full orchestral and vocal parts, together with libretto cues if there are spoken passages.
- *Orchestral Parts* containing the music for the individual instruments of the orchestra or band.
- A *Vocal Score* containing all vocal parts with piano accompaniment. The accompaniment is usually an orchestral reduction, and if so the name of the original orchestral instrument is often indicated. Vocal scores sometimes includes stage directions and libretto cues.
- A *Vocal Book* containing just the vocal parts (no accompaniment), sometimes combined with the libretto.

- A *Libretto* containing the extended passages of spoken dialogue usually found in musicals, together with the words to the sung parts. Stage directions are usually included. LilyPond can be used to typeset libretti but as they contain no music alternative methods may be preferable.

The sections in the LilyPond documentation which cover the topics needed to create scores in the styles commonly found in opera and musicals are indicated in the References below. This is followed by sections covering those techniques which are peculiar to typesetting opera and musical scores.

9.6.1 References for opera and stage musicals

In addition to vocal and stage ensembles, most of the following notions may apply to nearly any orchestral and ensemble music:

- A conductors' score contains many grouped staves and lyrics. Ways of grouping staves is shown in Section 6.1.2 [Grouping staves], page 243. To nest groups of staves see Section 6.1.3 [Nested staff groups], page 247.
- The printing of empty staves in conductors' scores and vocal scores is often suppressed. To create such a "Frenched score" see Section 6.2.3 [Hiding staves], page 256.
- Writing orchestral parts is covered in Section 6.3 [Writing parts], page 261. Other sections in the Specialist notation chapter may be relevant, depending on the orchestration used. Many instruments are transposing instruments, see Section 1.3.4 [Instrument transpositions], page 30.
- If the number of systems per page changes from page to page it is customary to separate the systems with a system separator mark. See Section 6.1.4 [Separating systems], page 248.
- For details of other page formatting properties, see Chapter 26 [Page layout], page 669.
- Dialogue cues, stage directions and footnotes can be inserted, see Section 21.4 [Creating footnotes], page 610, and Chapter 8 [Text], page 307. Extensive stage directions can also be added with a section of stand-alone markups between two `\score` blocks, see Section 8.1.6 [Separate text], page 317.

See also

Musical Glossary: Section "Frenched score" in *Music Glossary*, Section "Frenched staves" in *Music Glossary*, Section "transposing instrument" in *Music Glossary*.

Notation Reference: Section 21.4 [Creating footnotes], page 610, Section 6.1.2 [Grouping staves], page 243, Section 6.2.3 [Hiding staves], page 256, Section 1.3.4 [Instrument transpositions], page 30, Section 6.1.3 [Nested staff groups], page 247, Chapter 26 [Page layout], page 669, Section 6.1.4 [Separating systems], page 248, Section 1.2.2 [Transpose], page 13, Section 6.3 [Writing parts], page 261, Section 8.1 [Writing text], page 307.

Snippets: Section "Vocal music" in *Snippets*.

9.6.2 Character names

Character names are usually shown to the left of the staff when the staff is dedicated to that character alone:

```
\score {
  <<
    \new Staff {
      \set Staff.vocalName = \markup \smallCaps Kaspar
      \set Staff.shortVocalName = \markup \smallCaps Kas.
      \relative {
        \clef "G_8"
```



```

        c'4 c c c
        \break
        c4 c c c
    }
}
\new Staff {
    \set Staff.vocalName = \markup \smallCaps Melchior
    \set Staff.shortVocalName = \markup \smallCaps Mel
    \clef "bass"
    \relative {
        a4 a a a
        a4 a a a
    }
}
>>
}

```

When two or more characters share a staff the character's name is usually printed above the staff at the start of every section applying to that character. This can be done with markup. Often a specific font is used for this purpose.

```

\relative c' {
    \clef "G_8"
    c4~\markup \fontsize #1 \smallCaps Kaspar
    c c c
    \clef "bass"
    a4~\markup \fontsize #1 \smallCaps Melchior
    a a a
    \clef "G_8"
    c4~\markup \fontsize #1 \smallCaps Kaspar
    c c c
}

```

Alternatively, if there are many character changes, it may be easier to set up variables to hold the definitions for each character so that the switch of characters can be indicated easily and concisely.

```

kaspar = {
  \clef "G_8"
  \set Staff.shortVocalName = "Kas."
  \set Staff.midiInstrument = "voice oohs"
  <>^\markup \smallCaps "Kaspar"
}

melchior = {
  \clef "bass"
  \set Staff.shortVocalName = "Mel."
  \set Staff.midiInstrument = "choir aahs"
  <>^\markup \smallCaps "Melchior"
}

\relative c' {
  \kaspar
  c4 c c c
  \melchior
  a4 a a a
  \kaspar
  c4 c c c
}

```



See also

Learning Manual: Section “Organizing pieces with variables” in *Learning Manual*.

Notation Reference: Chapter 8 [Text], page 307, Section A.1 [Text markup commands], page 807.

9.6.3 Musical cues

Musical cues can be inserted in Vocal Scores, Vocal Books and Orchestral Parts to indicate what music in another part immediately precedes an entry. Also, cues are often inserted in the piano reduction in Vocal Scores to indicate what each orchestral instrument is playing. This aids the conductor when a full Conductors’ Score is not available.

The basic mechanism for inserting cues is fully explained in the main text, see Section 6.3.2 [Quoting other voices], page 265, and Section 6.3.3 [Formatting cue notes], page 268. But when many cues have to be inserted, for example, as an aid to a conductor in a vocal score, the instrument name must be positioned carefully just before and close to the start of the cue notes. The following example shows how this is done.

```

flute = \relative {
  s4 s4 e' ' g
}
\addQuote "flute" { \flute }

pianoRH = \relative {
  c' '4. g8
  % position name of cue-ing instrument just before the cue notes,
  % and above the staff
}


```

```

<>\markup { \right-align { \tiny "Flute" } }
\cueDuring "flute" #UP { g4 bes4 }
}
pianoLH = \relative { c4 <c' e> e, <g c> }

\score {
  \new PianoStaff <<
    \new Staff {
      \pianoRH
    }
    \new Staff {
      \clef "bass"
      \pianoLH
    }
  >>
}

```



If a transposing instrument is being quoted the instrument part should specify its key so the conversion of its cue notes will be done automatically. The example below shows this transposition for a B-flat clarinet. The notes in this example are low on the staff so DOWN is specified in `\cueDuring` (so the stems are down) and the instrument name is positioned below the staff.

```

clarinet = \relative c' {
  \transposition bes
  fis4 d d c
}
\addQuote "clarinet" { \clarinet }

pianoRH = \relative c'' {
  \transposition c'
  % position name of cue-ing instrument below the staff
  <>\markup { \right-align { \tiny "Clar." } }
  \cueDuring "clarinet" #DOWN { c4. g8 }
  g4 bes4
}
pianoLH = \relative { c4 <c' e> e, <g c> }

\score {
  <<
    \new PianoStaff <<
      \new Staff {
        \new Voice {
          \pianoRH
        }
      }
    >>
  }
}

```

```

\new Staff {
  \clef "bass"
  \pianoLH
}
>>
>>
}

```



From these two examples it is clear that inserting many cues in a Vocal Score would be tedious, and the notes of the piano part would become obscured. However, as the following snippet shows, it is possible to define a music function to reduce the amount of typing and to make the piano notes clearer.

Selected snippets

Adding orchestral cues to a vocal score

This snippet shows one approach to simplify adding many orchestral cues to the piano reduction in a vocal score. The music function `\cueWhile` takes four arguments: the music from which the cue is to be taken, as defined by `\addQuote`, the name to be inserted before the cue notes, then either UP or DOWN to specify either `\voiceOne` with the name above the staff or `\voiceTwo` with the name below the staff, and finally the piano music in parallel with which the cue notes are to appear. The name of the cued instrument is positioned to the left of the cued notes. Many passages can be cued, but they cannot overlap each other in time.

```

cueWhile =
#(define-music-function
  (instrument name dir music)
  (string? string? ly:dir? ly:music?)
  #{
    \cueDuring $instrument #dir {
      \once \override TextScript.self-alignment-X = #RIGHT
      \once \override TextScript.direction = $dir
      <>-\markup { \tiny #name }
      $music
    }
  })

flute = \relative c' {
  \transposition c'
  s4 s4 e g
}
\addQuote "flute" { \flute }

clarinet = \relative c' {
  \transposition bes
  fis4 d d c
}

```

```


}
\addQuote "clarinet" { \clarinet }

singer = \relative c'' { c4. g8 g4 bes4 }
words = \lyricmode { here's the lyr -- ics }

pianoRH = \relative c'' {
  \transposition c'
  \cueWhile "clarinet" "Clar." #DOWN { c4. g8 }
  \cueWhile "flute" "Flute" #UP { g4 bes4 }
}
pianoLH = \relative c { c4 <c' e> e, <g c> }

\score {
  <<
    \new Staff {
      \new Voice = "singer" {
        \singer
      }
    }
    \new Lyrics {
      \lyricsto "singer"
      \words
    }
    \new PianoStaff <<
      \new Staff {
        \new Voice {
          \pianoRH
        }
      }
      \new Staff {
        \clef "bass"
        \pianoLH
      }
    }
  >>
}

```



See also

Musical Glossary: Section “cue-notes” in *Music Glossary*.

Notation Reference: Section 36.9 [Aligning objects], page 789, Section 36.1 [Direction and placement], page 772, Section 6.3.3 [Formatting cue notes], page 268, Section 6.3.2 [Quoting other voices], page 265, Section 22.3 [Using music functions], page 638.

Snippets: Section “Vocal music” in *Snippets*.

Internals Reference: Section “CueVoice” in *Internals Reference*.

Known issues and warnings

`\cueDuring` automatically inserts a `CueVoice` context and all cue notes are placed in that context. This means it is not possible to have two overlapping sequences of cue notes by this technique. Overlapping sequences could be entered by explicitly declaring separate `CueVoice` contexts and using `\quoteDuring` to extract and insert the cue notes.

9.6.4 Spoken music

Such effects as ‘parlato’ or ‘Sprechgesang’ require performers to speak without pitch but still with rhythm; these are notated by cross note heads, as demonstrated in Section 1.4.1 [Special note heads], page 43.

9.6.5 Dialogue over music

Dialogue over music is usually printed over the staves in an italic font, with the start of each phrase keyed in to a particular music moment.

For short interjections a simple markup suffices.

```
\relative {
  a'4^\markup { \smallCaps { Alex - } \italic { He's gone } } a a a
  a4 a a^\markup { \smallCaps { Bethan - } \italic Where? } a
  a4 a a a
}
```



For longer phrases it may be necessary to expand the music to make the words fit neatly. There is no provision in LilyPond to do this fully automatically, and some manual intervention to layout the page will be necessary.

For long phrases or for passages with a lot of closely packed dialogue, using a `Lyrics` context will give better results. The `Lyrics` context should not be associated with a music `Voice`; instead each section of dialogue should be given an explicit duration. If there is a gap in the dialogue, the final word should be separated from the rest and the duration split between them so that the underlying music spaces out smoothly.

If the dialogue extends for more than one line it will be necessary to manually insert `\breaks` and adjust the placing of the dialogue to avoid running into the right margin. The final word of the last measure on a line should also be separated out, as above.

Here is an example illustrating how this might be done.

```
music = \relative {
  \*3 { a'4 a a a }
}

dialogue = \lyricmode {
  \markup {
    \fontsize #1 \upright \smallCaps Abe:
```

```

    "Say this over measures one and"
  }4*7
  "two"4 |
  \break
  "and this over measure"4*3
  "three"4 |
}

\score {
  <<
    \new Lyrics \with {
      \override LyricText.font-shape = #'italic
      \override LyricText.self-alignment-X = #LEFT
    }
    { \dialogue }
    \new Staff {
      \new Voice { \music }
    }
  >>
}

```



See also

Notation Reference: Section 9.1.5 [Manual syllable durations], page 352, Chapter 8 [Text], page 307.

Internal Reference: Section “LyricText” in *Internals Reference*.

9.7 Chants psalms and hymns

The music and words for chants, psalms and hymns usually follow a well-established format in any particular church. Although the formats may differ from church to church the typesetting problems which arise are broadly similar, and are covered in this section.

9.7.1 References for chants and psalms

Typesetting Gregorian chant in various styles of ancient notation is described in Chapter 17 [Ancient notation], page 537.

See also

Notation reference: Chapter 17 [Ancient notation], page 537.

Snippets: Section “Vocal music” in *Snippets*.

9.7.2 Setting a chant

Modern chant settings use modern notation with varying numbers of elements taken from ancient notation. Some of the elements and methods to consider are shown here.

Chants often use quarter notes without stems to indicate the pitch, with the rhythm being taken from the spoken rhythm of the words.

```
stemOff = { \hide Staff.Stem }
```

```
\relative c' {  
  \stemOff  
  a'4 b c2 |  
}
```



Chants often omit measure bar lines or use shortened or dotted bar lines to indicate pauses in the music. To set a chant with no musical meter, see Section 2.3.5 [Unmetered music], page 91. To retain all the effects of a time signature but disable automatic measure bar lines, set `measureBarType` to `'()`. Without regular bar lines, you might need to take steps to control horizontal spacing; see Section 28.1 [Line breaking], page 687.

```
\score {  
  \new StaffGroup <<  
    \new Staff {  
      \relative {  
        a'4 b c2 |  
        a4 b c2 | \section  
        a4 b c2 |  
      }  
    }  
    \new Staff {  
      \relative {  
        a'4 b c2 |  
        a4 b c2 | \section  
        a4 b c2 |  
      }  
    }  
  >>  
  \layout {  
    \context {  
      \Staff  
      measureBarType = #'()  
      forbidBreakBetweenBarLines = ##f  
    }  
  }  
}
```



Measure bar lines can also be modified on a staff-by-staff basis; see Section 33.4 [Modifying context plug-ins], page 743.

Rests or pauses in chants can be indicated by modified bar lines.

```
\relative a' {
  a4
  \cadenzaOn
  b c2
  a4 b c2
  \bar " '"
  a4 b c2
  \bar " ,"
  a4 b c2
  \bar " ; "
  a4 b c2
  \bar " ! "
  a4 b c2
  \bar " || "
}
```



Alternatively, the notation used in Gregorian chant for pauses or rests is sometimes used even though the rest of the notation is modern.

```
\score {
  \relative {
    g'2 a4 g
    \divisioMinima
    g2 a4 g
    \divisioMaior
    g2 a4 g
    \divisioMaxima
    g2 a4 g
    \finalis
  }
  \layout {
    \context {
      \Staff
      \remove Caesura_engraver
      \consists Divisio_engraver
      \EnableGregorianDivisiones
      caesuraType = #'((breath . chantquarterbar))
      measureBarType = #'()
      forbidBreakBetweenBarLines = ##f
    }
  }
}
```



Chants usually omit the time signature and often omit the clef too.

```

\score {
  \new Staff {
    \relative {
      a'4 b c2 |
      a4 b c2 |
      a4 b c2 |
    }
  }
  \layout {
    \context {
      \Staff
      \remove Time_signature_engraver
      \remove Clef_engraver
      measureBarType = #'()
      forbidBreakBetweenBarLines = ##f
    }
  }
}

```



Chants for psalms in the Anglican tradition are usually either *single*, with 7 bars of music, or *double*, with two lots of 7 bars. Each group of 7 bars is divided into two halves, corresponding to the two halves of each verse, usually separated by a double bar line. Only whole and half notes are used. The 1st bar in each half always contains a single chord of whole notes. This is the “reciting note”. Chants are usually centered on the page.

```

SopranoMusic = \relative {
  g'1 | c2 b | a1 |
  a1 | d2 c | c b | c1 |
}

AltoMusic = \relative {
  e'1 | g2 g | f1 |
  f1 | f2 e | d d | e1 |
}

TenorMusic = \relative {
  c'1 | c2 c | c1 |
  d1 | g,2 g | g g | g1 |
}

BassMusic = \relative {
  c1 | e2 e | f1 |
  d1 | b2 c | g' g | c,1 |
}


global = {
  \time 2/2
  \skip 1*3 \section
  \skip 1*4 \fine
}

```

```

% Use markup to center the chant on the page
\markup {
  \fill-line {
    \score { % centered
      <<
        \new ChoirStaff <<
          \new Staff <<
            \global
            \clef "treble"
            \new Voice = "Soprano" <<
              \voiceOne
              \SopranoMusic
            >>
            \new Voice = "Alto" <<
              \voiceTwo
              \AltoMusic
            >>
          >>
          \new Staff <<
            \clef "bass"
            \global
            \new Voice = "Tenor" <<
              \voiceOne
              \TenorMusic
            >>
            \new Voice = "Bass" <<
              \voiceTwo
              \BassMusic
            >>
          >>
        >>
      >>
    \layout {
      \context {
        \Score
        \override SpacingSpanner.base-shortest-duration =
          \musicLength 2
        \fineBarType = "||"
      }
      \context {
        \Staff
        \remove Time_signature_engraver
      }
    }
  } % End score
} % End markup

```



Some other approaches to setting such a chant are shown in the first of the following snippets.


Selected snippets

Chant or psalm notation

This form of notation is used for psalm chant, where verses are not always of the same length.

```
stemOff = \hide Staff.Stem
stemOn  = \undo \stemOff

\score {
  \new Staff \with { \remove "Time_signature_engraver" }
  {
    \key g \minor
    \cadenzaOn
    \stemOff a'\breve bes'4 g'4
    \stemOn a'2 \section
    \stemOff a'\breve g'4 a'4
    \stemOn f'2 \section
    \stemOff a'\breve^\markup { \italic flexe }
    \stemOn g'2 \fine
  }
}
```



Canticles and other liturgical texts may be set more freely, and may use notational elements from ancient music. Often the words are shown underneath and aligned with the notes. If so, the notes are spaced in accordance with the syllables rather than the notes' durations.

Ancient notation template – modern transcription of Gregorian music

This example demonstrates how to do modern transcription of Gregorian music. Gregorian music has no measure, no stems; it uses only half and quarter note heads, and special marks, indicating rests of different length.

```
chant = \relative c' {
  \set Score.timing = ##f
  f4 a2 \divisioMinima
  g4 b a2 f2 \divisioMaior
  g4( f) f( g f) a2 \finalis \break
  f4 a2 \divisioMinima
  g4 b a2 f2 \divisioMaior
  g4( f) f( g a) g2( f) \finalis
```


```

}

verba = \lyricmode {
  Lo -- rem ip -- sum do -- lor sit a -- met,
  lo -- rem ip -- sum do -- lor sit a -- met.
}

\score {
  \new GregorianTranscriptionStaff <<
    \new GregorianTranscriptionVoice = "melody" \chant
    \new GregorianTranscriptionLyrics = "one" \lyricsto melody \verba
  >>
}

```



See also

Learning Manual: Section “Visibility and color of objects” in *Learning Manual*, Section “Vocal ensembles templates” in *Learning Manual*.

Notation Reference: Chapter 17 [Ancient notation], page 537, Section 2.5.1 [Bar lines], page 120, Section 33.4 [Modifying context plug-ins], page 743, Section 17.4 [Typesetting Gregorian chant], page 553, Section 2.3.5 [Unmetered music], page 91, Section 36.7 [Visibility of objects], page 782.

9.7.3 Pointing a psalm

The words to an Anglican psalm are usually printed in separate verses centered underneath the chant.

Single chants (with 7 bars) are repeated for every verse. Double chants (with 14 bars) are repeated for every pair of verses. Marks are inserted in the words to show how they should be fitted to the chant. Each verse is divided into two halves. A colon is usually used to indicate this division. This corresponds to the double bar line in the music. The words before the colon are sung to the first three bars of music; the words after the colon are sung to the last four bars.

Single bar lines (or in some psalters an inverted comma or similar symbol) are inserted between words to indicate where the bar lines in the music fall. In markup mode a single bar line can be entered with the bar check symbol, |.

```

\markup {
  \fill-line {
    \column {
      \line { 0 come let us sing | unto the | Lord : let }
      \line { us heartily rejoice in the | strength of | our }
      \line { sal- | -vation. }
    }
  }
}

```

O come let us sing | unto the | Lord : let
us heartily rejoice in the | strength of | our
sal- | -vation.

Other symbols may require glyphs from the fetaMusic fonts. For details, see Section 8.3 [Fonts], page 336.

```
tick = \markup {
  \raise #1 \fontsize #-5 \musicglyph "scripts.rvarcomma"
}
\markup {
  \fill-line {
    \column {
      \line { O come let us sing \tick unto the \tick Lord : let }
      \line { us heartily rejoice in the \tick strength of \tick our }
      \line { sal \tick vation. }
    }
  }
}
```

O come let us sing' unto the' Lord : let
us heartily rejoice in the' strength of' our
sal' vation.

Where there is one whole note in a bar all the words corresponding to that bar are recited on that one note in speech rhythm. Where there are two notes in a bar there will usually be only one or two corresponding syllables. If there are more than two syllables a dot is usually inserted to indicate where the change in note occurs.

```
dot = \markup {
  \raise #0.7 \musicglyph "dots.dot"
}
tick = \markup {
  \raise #1 \fontsize #-5 \musicglyph "scripts.rvarcomma"
}
\markup {
  \fill-line {
    \column {
      \line { O come let us sing \tick unto \dot the \tick Lord : let }
      \line { us heartily rejoice in the \tick strength of \tick our }
      \line { sal \tick vation. }
    }
  }
}
```

O come let us sing' unto • the' Lord : let
us heartily rejoice in the' strength of' our
sal' vation.

In some psalters an asterisk is used to indicate a break in a recited section instead of a comma, and stressed or slightly lengthened syllables are indicated in bold text.

```

dot = \markup {
  \raise #0.7 \musicglyph "dots.dot"
}
tick = \markup {
  \raise #1 \fontsize #-5 \musicglyph "scripts.rvarcomma"
}
\markup {
  \fill-line {
    \column {
      \line { Today if ye will hear his voice * }
      \line { \concat { \bold hard en } |
        not your | hearts : as in the pro- }
      \line { vocation * and as in the \bold day of tempt- | }
      \line { -ation | in the | wilderness. }
    }
  }
}

```

Today if ye will hear his voice *
harden | not your | hearts : as in the pro-
 vocation * and as in the **day** of tempt- |
 -ation | in the | wilderness.

In other psalters an accent is placed over the syllable to indicate stress.

```

tick = \markup {
  \raise #2 \fontsize #-5 \musicglyph "scripts.rvarcomma"
}
\markup {
  \fill-line {
    \column {
      \line { O come let us \concat { si \combine \tick ng } |
        unto the | Lord : let }
      \line { us heartily \concat { rejo \combine \tick ice }
        in the | strength of | our }
      \line { sal- | -vation. }
    }
  }
}

```

O come let us **síng** | unto the | Lord : let
 us heartily re**jóice** in the | strength of | our
 sal- | -vation.

The use of markup to center text, and arrange lines in columns is described in Section 8.2 [Formatting text], page 319.

Most of these elements are shown in one or other of the two verses in the template, see Section “Psalms” in *Learning Manual*.

See also

Learning Manual: Section “Psalms” in *Learning Manual*, Section “Vocal ensembles templates” in *Learning Manual*.

Notation Reference: Section 8.3 [Fonts], page 336, Section 8.2 [Formatting text], page 319.


9.7.4 Phrase bar lines in hymn tunes

The `\caesura` command can be configured to create phrase bar lines that interact well with other automatic bar lines (see Section 2.5.2 [Automatic bar lines], page 130).

In the following examples, the source code for the tune in `old-hundredth-example.ly` uses `\caesura` between poetic lines and `\fine` at the end. There are no `\fermata` or `\bar` commands; those symbols appear in the output because of the `caesura` configuration.


The Boston Handel and Haydn Society Collection of Church Music (1830) has a thick bar after each phrase. For this tune, it also has fermatas over the bar lines:

```
\layout {
  \context {
    \Score
    caesuraType = #'((bar-line . ".")
                  (scripts . (fermata)))
    fineBarType = ".."
  }
}
\include "old-hundredth-example.ly"
```



J.S. James' *Original Sacred Harp* (1911) has a thick bar when a line is broken in mid-measure at the end of a phrase.

```
\layout {
  \context {
    \Score
    caesuraType = #'((underlying-bar-line . "x-."))
    fineBarType = ".."
  }
}
\include "old-hundredth-example.ly"
```





9.7.5 Partial measures in hymn tunes

Hymn tunes frequently start and end every line of music with partial measures so that each line of music corresponds exactly with a line of text. This requires a `\partial` command at the start of the music and a bar line at the end of each line.

Hymn template

This code shows one way of setting out a hymn tune where each line starts and ends with a partial measure. It also shows how to add the verses as stand-alone text under the music.

```
Timeline = {
  \time 4/4
  \tempo 4=96
  \partial 2
  s2 | s1 | s2 \breathe s2 | s1 | s2 \caesura \break
  s2 | s1 | s2 \breathe s2 | s1 | s2 \fine
}

SopranoMusic = \relative g' {
  g4 g | g g g g | g g g g | g g g g | g2
  g4 g | g g g g | g g g g | g g g g | g2
}

AltoMusic = \relative c' {
  d4 d | d d d d | d d d d | d d d d | d2
  d4 d | d d d d | d d d d | d d d d | d2
}

TenorMusic = \relative a {
  b4 b | b b b b | b b b b | b b b b | b2
  b4 b | b b b b | b b b b | b b b b | b2
}

BassMusic = \relative g {
  g4 g | g g g g | g g g g | g g g g | g2
  g4 g | g g g g | g g g g | g g g g | g2
}

global = {
  \key g \major
}

\score { % Start score
  \new PianoStaff << % Start pianostaff
  \new Staff << % Start Staff = RH
  \global
```

```

\clef "treble"
\new Voice = "Soprano" << % Start Voice = "Soprano"
  \Timeline
  \voiceOne
  \SopranoMusic
>> % End Voice = "Soprano"
\new Voice = "Alto" << % Start Voice = "Alto"
  \Timeline
  \voiceTwo
  \AltoMusic
>> % End Voice = "Alto"
>> % End Staff = RH

\new Staff << % Start Staff = LH
  \global
  \clef "bass"
  \new Voice = "Tenor" << % Start Voice = "Tenor"
    \Timeline
    \voiceOne
    \TenorMusic
  >> % End Voice = "Tenor"
  \new Voice = "Bass" << % Start Voice = "Bass"
    \Timeline
    \voiceTwo
    \BassMusic
  >> % End Voice = "Bass"
>> % End Staff = LH
>> % End pianostaff
} % End score


\markup \fill-line {
  \left-column {
    "This is line one of the first verse"
    "This is line two of the same"
    \null
    "And here's line one of the second verse"
    "And the next line of the same"
  }
}

\layout {
  \context {
    \Score
    caesuraType = #'((bar-line . "||"))
    fineBarType = "||"
  }
}

\paper { % Start paper block
  indent = 0 % don't indent first system
  line-width = 130 % shorten line length to suit music
  tagline = ##f % Don't print tag line, can be removed
}

```

} % End paper block



This is line one of the first verse

This is line two of the same

And here's line one of the second verse

And the next line of the same

9.8 Ancient vocal music

Ancient vocal music is supported, as explained in Chapter 17 [Ancient notation], page 537.

See also

Notation Reference: Chapter 17 [Ancient notation], page 537.

10 Keyboard and other multi-staff instruments

Un peu retenu
très expressif

ppp

rall. - - - - - *a tempo*

long

pp

ral - - len - - tan - - do - - - - - **Lent** 8^{va}

ppp

This section discusses several aspects of music notation that are unique to keyboard instruments and other instruments notated on many staves, such as harps and vibraphones. For the purposes of this section this entire group of multi-staff instruments is called “keyboards” for short, even though some of them do not have a keyboard.

10.1 Common notation for keyboards

This section discusses notation issues that may arise for most keyboard instruments.

10.1.1 References for keyboards

Keyboard instruments are usually notated with Piano staves. These are two or more normal staves coupled with a brace. The same notation is also used for other keyed instruments. Organ music is normally written with two staves inside a `PianoStaff` group and third, normal staff for the pedals.

The staves in keyboard music are largely independent, but sometimes voices can cross between the two staves. This section discusses notation techniques particular to keyboard music.

Several common issues in keyboard music are covered elsewhere:

- Keyboard music usually contains multiple voices and the number of voices may change regularly; this is described in Section 5.2.3 [Collision resolution], page 226.
- Keyboard music can be written in parallel, as described in Section 5.2.6 [Writing music in parallel], page 237.
- Dynamics may be placed in a Dynamics context, between the two Staff contexts to align the dynamic marks on a horizontal line centered between the staves; see Section 3.1.2 [Dynamics], page 159.
- Fingerings are indicated with Section 7.1.2 [Fingering instructions], page 281.
- Organ pedal indications are inserted as articulations, see Section 10.3.1 [Organ pedal marks], page 423, and Section B.13 [List of articulations], page 927.
- Vertical grid lines can be shown with Section 7.2.3 [Grid lines], page 301.
- Keyboard music often contains *Laissez vibrer* ties as well as ties on arpeggios and tremolos, described in Section 2.1.4 [Ties], page 63.
- Placing arpeggios across multiple voices and staves is covered in Section 3.3.2 [Arpeggio], page 181.
- Tremolo marks are described in Section 4.2.2 [Tremolo repeats], page 211.
- Several of the tweaks that can occur in keyboard music are demonstrated in Section “Real music example” in *Learning Manual*.
- Hidden notes can be used to produce ties that cross voices, as shown in Section “Other uses for tweaks” in *Learning Manual*.

See also

Learning Manual: Section “Real music example” in *Learning Manual*, Section “Other uses for tweaks” in *Learning Manual*.

Notation Reference: Section 6.1.2 [Grouping staves], page 243, Section 6.3.1 [Instrument names], page 261, Section 5.2.3 [Collision resolution], page 226, Section 5.2.6 [Writing music in parallel], page 237, Section 7.1.2 [Fingering instructions], page 281, Section B.13 [List of articulations], page 927, Section 7.2.3 [Grid lines], page 301, Section 2.1.4 [Ties], page 63, Section 3.3.2 [Arpeggio], page 181, Section 4.2.2 [Tremolo repeats], page 211.

Internals Reference: Section “PianoStaff” in *Internals Reference*.

Snippets: Section “Keyboard and other multi-staff instruments” in *Snippets*.

10.1.2 Changing staff manually

Voices can be switched between staves manually, using the command

```
\change Staff = staffname
```

The string *staffname* is the name of the staff. It switches the current voice from its current staff to the staff called *staffname*. Typical values for *staffname* are "up" and "down", or "RH" and "LH".

The staff to which the voice is being switched must exist at the time of the switch. If necessary, staves should be “kept alive”, see Section 33.3 [Keeping contexts alive], page 740, or


explicitly instantiated, for example by using the empty chord, <>, see Section 5.1.1 [Chorded notes], page 215.

```
\new PianoStaff <<
  \new Staff = "up" {
    % enforce creation of all contexts at this point of time
    <>
    \change Staff = "down" c2
    \change Staff = "up" c'2
  }
  \new Staff = "down" {
    \clef bass
    % keep staff alive
    s1
  }
>>
```



Cross-staff notes are beamed automatically:

```
\new PianoStaff <<
  \new Staff = "up" {
    <e' c'>8
    \change Staff = "down"
    g8 fis g
    \change Staff = "up"
    <g' c'>8
    \change Staff = "down"
    e8 dis e
    \change Staff = "up"
  }
  \new Staff = "down" {
    \clef bass
    % keep staff alive
    s1
  }
>>
```




If the beaming needs to be tweaked, make any changes to the stem directions first. The beam positions are then measured from the center of the staff that is closest to the beam. For a simple example of beam tweaking, see Section “Fixing overlapping notation” in *Learning Manual*.

Overlapping notation can result when voices cross staves:

```

\new PianoStaff <<
  \new Staff = "up" {
    \voiceOne
    % Make space for fingering in the cross-staff voice
    \once\override DynamicLineSpanner.staff-padding = 4
    e''2\p\< d''\>
    c''1\!
  }
  \new Staff = "down" <<
  {
    \clef bass
    s4. e,8\rest g,2\rest
    c1
  } \ {
    c8\ ( g c'
    \change Staff = "up"
    e' g' b'-3 a' g'\ )
    f'1
  }
>>
>>

```



The stem and slur overlap the intervening line of dynamics because automatic collision resolution is suspended for beams, slurs and other spanners that connect notes on different staves, as well as for stems and articulations if their placement is affected by a cross-staff spanner. The resulting collisions must be resolved manually, where necessary, using the methods in Section “Fixing overlapping notation” in *Learning Manual*.

See also

Learning Manual: Section “Fixing overlapping notation” in *Learning Manual*.

Notation Reference: Section 7.1.9 [Stems], page 296, Section 2.4.1 [Automatic beams], page 101, Section 33.3 [Keeping contexts alive], page 740.

Snippets: Section “Keyboard and other multi-staff instruments” in *Snippets*.

Internals Reference: Section “Beam” in *Internals Reference*, Section “ContextChange” in *Internals Reference*.

Known issues and warnings

Beam collision avoidance does not work for automatic beams that end right before a change in staff. In this case use manual beams.

10.1.3 Changing staff automatically

Voices can be made to switch automatically between the top and the bottom staff. The syntax for this is

```
\autoChange ...music...
```

This will create two staves inside the current staff group (usually a `PianoStaff`), called "up" and "down". The lower staff will be in the bass clef by default. The auto-changer switches on the basis of the pitch (middle C is the turning point), and it looks ahead skipping over rests to switch in advance.



```
\new PianoStaff {
  \autoChange {
    g4 a b c'
    d'4 r a g
  }
}
```



It is possible to specify other pitches for the turning point. If the staves are not instantiated explicitly, other clefs may be used.

```
music = {
  g8 b a c' b8 d' c'8 e'
  d'8 r f' g' a'2
}
```

```
\autoChange d' \music
\autoChange b \with { \clef soprano } \music
\autoChange d' \with { \clef alto } \with { \clef tenor } \music
```




A `\relative` section that is outside of `\autoChange` has no effect on the pitches of the music, so if necessary, put `\relative` inside `\autoChange`.

If additional control is needed over the individual staves, they can be created manually with the names "up" and "down". The `\autoChange` command will then switch its voice between the existing staves.

Note: If staves are created manually, they *must* be named "up" and "down".

For example, staves must be created manually in order to place a key signature in the lower staff:

```
\new PianoStaff <<
  \new Staff = "up" {
    \new Voice = "melOne" {
      \key g \major
      \autoChange \relative {
        g8 b a c b d c e
        d8 r fis, g a2
      }
    }
  }
  \new Staff = "down" {
    \key g \major
    \clef bass
  }
>>
```



See also

Notation Reference: Section 10.1.2 [Changing staff manually], page 414.

Snippets: Section “Keyboard and other multi-staff instruments” in *Snippets*.

Known issues and warnings

The staff switches may not end up in optimal places. For high quality output, staff switches should be specified manually.

Chords will not be split across the staves; they will be assigned to a staff based on the first note named in the chord construct.

10.1.4 Staff-change lines


Whenever a voice switches to another staff, a line connecting the notes can be printed automatically:

```
\new PianoStaff <<
  \new Staff = "one" {
    \showStaffSwitch
    c'1
    \change Staff = "two"
    b2 a
  }
```

```

    }
    \new Staff = "two" {
      \clef bass
      s1*2
    }
  >>

```




A staff-change line between chords connects the chords’ “last notes” as written in the source file; this can be used to quickly adjust the line’s vertical start and end positions.

```

\new PianoStaff <<
  \new Staff = "one" {
    <c' e' g'>1
    \showStaffSwitch
    \change Staff = "two"
    <a c' f>1
    \hideStaffSwitch
    \change Staff = "one"
    <e' g' c'>1
    \showStaffSwitch
    \change Staff = "two"
    <f a c'>1
  }
  \new Staff = "two" {
    \clef bass
    s1*4
  }
>>

```



Predefined commands

\showStaffSwitch, \hideStaffSwitch.

See also

Snippets: Section “Keyboard and other multi-staff instruments” in *Snippets*.

Internals Reference: Section “Note_head_line_engraver” in *Internals Reference*, Section “VoiceFollower” in *Internals Reference*.

Selected snippets

Cross-staff stems

This snippet shows how to use `Span_stem_engraver` and `\crossStaff` to connect stems across staves automatically.

The stem lengths need not be specified, as the variable distance between noteheads and staves is calculated automatically. However, it is important that `\crossStaff` is applied to the correct voice or staff (i.e., on the opposite side of where a beam is or would be positioned) to get the desired effect.

```
\layout {
  \context {
    \PianoStaff
    \consists "Span_stem_engraver"
  }
}

\new PianoStaff <<
  \new Staff {
    <b d'>4 r d'16\> e'8. g8 r\! |
    e'8 f' g'4
    \voiceTwo
    % Down to lower staff
    \crossStaff { e'8 e'8 } e'4 |
  }

  \new Staff {
    \clef bass
    \voiceOne
    % Up to upper staff
    \crossStaff { <e g>4 e, g16 a8. c8 } d |
    g8 f g4 \voiceTwo g8 g g4 |
  }
}>>
```



Indicating cross-staff chords with a bracket

A non-arpeggiato bracket can indicate that notes on two different staves are to be played with the same hand. In order to do this, the `PianoStaff` must be set to accept cross-staff brackets.

The following example typesets measure 65 of Debussy's prelude *Les collines d'Anacapri*.


```

\new PianoStaff <<
  \once \set PianoStaff.connectChordBrackets = ##t

  \new Staff \relative c' {
    \key b \major
    \time 6/8
    b8-.(\nonArpeggiato fis'-.\> cis-.
      e-. gis-. b-.)\!\fermata^\laissezVibrer
    \section
  }

  \new Staff \relative c' {
    \clef bass
    \key b \major
    << { <a e cis>2.\nonArpeggiato } \
      { <a, e a,>2. } >>
    \section
  }
>>

```



See also

Snippets: Section “Keyboard and other multi-staff instruments” in *Snippets*.

Internals Reference: Section “Stem” in *Internals Reference*.

10.2 Piano

This section discusses notation issues that relate most directly to the piano.

10.2.1 Piano pedals

Pianos generally have three pedals that alter the way sound is produced: *sustain*, *sostenuto* (*sos.*), and *una corda* (*U.C.*). Sustain pedals are also found on vibraphones and celestas.

```

\relative {
  c' '4\sustainOn d e g
  <c, f a>1\sustainOff
  c4\sostenutoOn e g c,
  <bes d f>1\sostenutoOff
  c4\unaCorda d e g
  <d fis a>1\treCorde
}

```



There are three styles of pedal indications: text, bracket, and mixed. The sustain pedal and the una corda pedal use the text style by default while the sostenuto pedal uses mixed by default.

```

\relative {
  c' '4\sustainOn g c2\sustainOff
  \set Staff.pedalSustainStyle = #'mixed
  c4\sustainOn g c d
  d\sustainOff\sustainOn g, c2\sustainOff
  \set Staff.pedalSustainStyle = #'bracket
  c4\sustainOn g c d
  d\sustainOff\sustainOn g, c2
  \bar "|"
}

```



The placement of the pedal commands matches the physical movement of the sustain pedal during piano performance. Pedaling to the final bar line is indicated by omitting the final pedal off command.

Pedal indications may be placed in a Dynamics context, which aligns them on a horizontal line.

See also

Notation Reference: Section 2.1.4 [Ties], page 63.

Snippets: Section “Keyboard and other multi-staff instruments” in *Snippets*.

Internals Reference: Section “SustainPedal” in *Internals Reference*, Section “SustainPedal-LineSpanner” in *Internals Reference*, Section “SustainEvent” in *Internals Reference*, Section “SostenutoPedal” in *Internals Reference*, Section “SostenutoPedalLineSpanner” in *Internals Reference*, Section “SostenutoEvent” in *Internals Reference*, Section “UnaCordaPedal” in *Internals Reference*, Section “UnaCordaPedalLineSpanner” in *Internals Reference*, Section “UnaCordaEvent” in *Internals Reference*, Section “PianoPedalBracket” in *Internals Reference*, Section “Piano_pedal_engraver” in *Internals Reference*.

10.3 Organ

This section discusses notation issues that relate to the (church) organ.

10.3.1 Organ pedal marks

Mostly in organ method books you can find marks that indicate how to use the toe and heel of the left and right foot while playing the pedal. Depending on the style of the book, different glyphs are used for such marks. In almost all cases, however, the pedal marks above the staff are for the right foot, and the marks below the staff are for the left foot.


The main commands to print such marks are `\rtoe`, `\ltoe`, `\rheel`, and `\lheel`. Use `toeHeelStyle` context property to select the pedal mark style. Available options are as follows.

- `default` The default at start-up, mainly for backward compatibility.
- `standard` The most common scheme in use today; the shapes are identical above and below the staff.
- `reversed` The glyph ‘tips’ point to the staff.
- `circleheels`
 Use a circle glyph for the heel.
- `below` This is for the rare cases where the pedal is notated in the same staff as the left hand, which makes it necessary that marks for both the left and right foot are below the staff.

For toe-heel and heel-toe substitutions the commands `\rtoeheel`, `\ltoeheel`, `\rheeltoe`, and `\lheeltoe` are provided.

```
music = { g'4_\rtoe g'\rheel g'\rtoeheel g'\rheeltoe |
          e'4\ltoe e'\lheel e'\ltoeheel e'\lheeltoe \bar "||" }


{
  \music          % #'default
  \set toeHeelStyle = #'standard \music
  \set toeHeelStyle = #'reversed \music
  \set toeHeelStyle = #'circleheels \music
  \set toeHeelStyle = #'below \music
}
```



`\rtoe` and siblings look similar to other articulation commands like `\flageolet` or `\prall`, and they are indeed Script grobs. However, they ignore direction changes (i.e., ‘`^`’, ‘`_`’, and ‘`tweak`’ direction are ignored). This is due to the `Toe_heel_engraver`, which is enabled by default. The idea behind this decision is separation of content and representation, letting a style control the position of the marks.

If the need arises to position pedal marks individually above or below the staff, use the standard articulation commands `\toe`, `\vartoe`, `\heel`, `\varheel`, and `\heelcircle`.

```
{
  f'2\toe f'2\vartoe |
  f'2\heel f'2\varheel |
  f'1\heelcircle
}
```



10.4 Accordion

This section discusses notation that is unique to the accordion.

10.4.1 Discant symbols

Accordions are often built with more than one set of reeds that may be in unison with, an octave above, or an octave below the written pitch. Each accordion maker has different names for the *shifts* that select the various reed combinations, such as *oboe*, *musette*, or *bandonium*, so a system of symbols has come into use to simplify the performance instructions.

A complete list of all available accordion registers can be found in Section A.1.7 [Accordion registers], page 867.

Selected snippets

Accordion register symbols

Accordion register symbols are available as `\markup` as well as as standalone music events (as register changes tend to occur between actual music events). Bass registers are not overly standardized. The available commands can be found in ‘Discant symbols’ in the Notation Reference (<https://lilypond.org/doc/v2.24/Documentation/notation/accordion#discant-symbols>).

```
#(use-modules (lily accreg))
```

```
\new PianoStaff <<
  \new Staff \relative {
    \clef treble
    \discant "10"
    r8 s32 f'[ bes f] s e[ a e] s d[ g d] s16 e32[ a]
    <<
      { r16 <f bes> r <e a> r <d g> }
      \
      { d r a r bes r }
    >> |
    <cis e a>1
  }

  \new Staff \relative {
    \clef treble
    \freeBass "1"
    r8 d'32 s16. c32 s16. bes32 s16. a32[ cis] s16
    \clef bass \stdBass "Master"
    <<
      { r16 <f, bes d>^~"b" r <e a c>^~"am" r <d g bes>^~"gm" |
```

```

    <e a cis>1^"a" }
    \
    { d8_"D" c_"C" bes_"B" | a1_"A" }
  >>
}
>>

```



See also

Snippets: Section “Keyboard and other multi-staff instruments” in *Snippets*.

10.5 Harp

This section discusses notation issues that are unique to the harp.

10.5.1 References for harps

Some common characteristics of harp music are covered elsewhere:

- The glissando is the most characteristic harp technique, Section 3.3.1 [Glissando], page 176.
- A *bisbigliando* is written as a tremolo Section 4.2.2 [Tremolo repeats], page 211.
- Natural harmonics are covered under Section 11.1.3 [Harmonics], page 428.
- For directional arpeggios and non-arpeggios, see Section 3.3.2 [Arpeggio], page 181.

See also

Notation Reference: Section 4.2.2 [Tremolo repeats], page 211, Section 3.3.1 [Glissando], page 176, Section 3.3.2 [Arpeggio], page 181, Section 11.1.3 [Harmonics], page 428.

10.5.2 Harp pedals

Harp have seven strings per octave that may be sounded at the natural, flattened, or sharpened pitch. In lever harps, each string is adjusted individually, but in pedal harps every string with the same pitch name is controlled by a single pedal. From the player’s left to right, the pedals are D, C, and B on the left and E, F, G, and A on the right. The position of the pedals may be indicated with text marks:

```


\textLengthOn
cis''1_\markup \concat \vcenter {
  [D \flat C \sharp B|E \sharp F \sharp G A \flat] }
c''!1_\markup \concat \vcenter {
  [ C \natural ] }

```



or pedal diagrams:

```
\textLengthOn
cis''1_\markup { \harp-pedal "^v-|vv-^" }
c''!1_\markup { \harp-pedal "^o--|vv-^" }
```



The `\harp-pedal` command accepts a string of characters, where `^` is the highest pedal position (flattened pitch), `-` is the middle pedal position (natural pitch), `v` is the lowest pedal position (sharpened pitch), and `|` is the divider. A prefixed `o` will circle the following pedal symbol.

See also

Notation Reference: Section 8.1.2 [Text scripts], page 309, Section A.1.6 [Instrument-specific markup], page 862.

11 Unfretted string instruments

1 **lentement**

fatigué s. vib. IV V ... 1) n. 2) s.p. n. p. vib. s. vib.

mf *mf* *mf* *ff* *pp*

accel... s.p. n. s.p. n. p. vib.

mf *ff*

s.p. n. s.p. n. p. vib. m. vib.

ritar...

ppp

This section provides information and references which are helpful when writing for unfretted string instruments, principally orchestral strings.

11.1 Common notation for unfretted strings

There is little specialist notation for unfretted string instruments. The music is notated on a single staff, and usually only a single voice is required. Two voices might be required for some double-stopped or divisi passages.

11.1.1 References for unfretted strings

Most of the notation which is useful for orchestral strings and other bowed instruments is covered elsewhere:

- Textual indications such as “pizz.” and “arco” are added as simple text – see Section 8.1.2 [Text scripts], page 309.
- Fingerings, including the thumb indication, are described in Section 7.1.2 [Fingering instructions], page 281.
- String numbers may be added (generally in roman numbers for bowed instruments) as explained in Section 12.1.2 [String number indications], page 432.
- Double stopping is normally indicated by writing a chord, see Section 5.1.1 [Chorded notes], page 215. Directives for playing chords may be added, see Section 3.3.2 [Arpeggio], page 181.
- Templates for string quartets can be found in Section “String quartet templates” in *Learning Manual*. Others are shown in the snippets.

See also

Learning Manual: Section “String quartet templates” in *Learning Manual*.

Notation Reference: Section 8.1.2 [Text scripts], page 309, Section 7.1.2 [Fingering instructions], page 281, Section 5.1.1 [Chorded notes], page 215, Section 3.3.2 [Arpeggio], page 181.

Snippets: Section “Unfretted string instruments” in *Snippets*.

11.1.2 Bowing indications

Bowing indications are created as articulations, which are described in Section 3.1.1 [Articulations and ornamentations], page 155.

The bowing commands, `\upbow` and `\downbow`, are used with slurs as follows:


```
\relative { c''4(\downbow d) e(\upbow f) }
```



Roman numerals can be used for string numbers (rather than the default circled Arabic numbers), as explained in Section 12.1.2 [String number indications], page 432.

Alternatively, string indications may be printed using markup commands; articulation scripts may also indicate open strings.

```
a'4 \open
\romanStringNumbers
a'\2
a'2^\markup { \small "sul A" }
```



Predefined commands

`\downbow`, `\upbow`, `\open`, `\romanStringNumbers`.

See also

Notation Reference: Section 3.1.1 [Articulations and ornamentations], page 155, Section 12.1.2 [String number indications], page 432, Section 3.2.1 [Slurs], page 170.

11.1.3 Harmonics

Natural harmonics

Natural harmonics can be notated in several ways. A diamond-shaped note head generally means to touch the string where you would stop the note if it were not a diamond.

```
\relative d'' {
  d4 e4.
  \harmonicsOn
  d8 e e
  d4 e4.
  \harmonicsOff
  d8 e e
}
```



Alternatively a normal note head is shown at the pitch to be sounded together with a small circle to indicate it should be played as a harmonic:

```
d''2^\flageolet d''_\flageolet
```



Artificial harmonics

Artificial harmonics are notated with two notes, one with a normal note head indicating the stopped position and one with an open diamond note head to indicate the harmonic position.

Artificial harmonics indicated with `\harmonic` do not show the dots. The context property `harmonicDots` should be set if dots are required.

```
\relative e' {
  <e a\harmonic>2. <c g'\harmonic>4
  \set harmonicDots = ##t
  <e a\harmonic>2. <c g'\harmonic>4
}
```



See also


Music Glossary: Section “harmonics” in *Music Glossary*.

Notation Reference: Section 1.4.1 [Special note heads], page 43, Section 11.1.1 [References for unfretted strings], page 427.

Known issues and warnings

If you want to center a harmonic on a whole note, make it part of a chord.


```
{
  << { d''1\harmonic } \ { a'1 } >>
  <a' d''\harmonic>1
}
```



11.1.4 Snap (Bartók) pizzicato

A *snap pizzicato* (also known as “Bartok pizz”) is a type of pizzicato where the string is deliberately plucked upwards (rather than sideways) such that it hits the fingerboard.

```
\relative {  
  c'4\snappizzicato  
  <c' e g>4\snappizzicato  
  <c' e g>4^\snappizzicato  
  <c, e g>4_\snappizzicato  
}
```



12 Fretted string instruments

This section discusses several aspects of music notation that are unique to fretted string instruments.

12.1 Common notation for fretted strings

This section discusses common notation that is unique to fretted string instruments.

12.1.1 References for fretted strings

Music for fretted string instruments is normally notated on a single staff, either in traditional music notation or in tablature. Sometimes the two types are combined, and it is especially common in popular music to use chord diagrams above a staff of traditional notation. The guitar and the banjo are transposing instruments, sounding an octave lower than written. Scores for these instruments should use the "treble_8" clef (or `\transposition c` to get correct MIDI output). Some other elements pertinent to fretted string instruments are covered elsewhere:

- Fingerings are indicated as shown in Section 7.1.2 [Fingering instructions], page 281.

- Instructions for *Laissez vibrer* ties as well as ties on arpeggios and tremolos can be found in Section 2.1.4 [Ties], page 63.
- Instructions for handling multiple voices can be found in Section 5.2.3 [Collision resolution], page 226.
- Instructions for indicating harmonics can be found in Section 11.1.3 [Harmonics], page 428.


See also

Notation Reference: Section 7.1.2 [Fingering instructions], page 281, Section 2.1.4 [Ties], page 63, Section 5.2.3 [Collision resolution], page 226, Section 6.3.1 [Instrument names], page 261, Section 5.2.6 [Writing music in parallel], page 237, Section 3.3.2 [Arpeggio], page 181, Section B.13 [List of articulations], page 927, Section 1.3.1 [Clef], page 19, Section 1.3.4 [Instrument transpositions], page 30.

12.1.2 String number indications


The string on which a note should be played may be indicated by appending `\number` to a note.

```
\clef "treble_8"
c4\5 e\4 g2\3
<c\5 e\4 g\3>1
```




When fingerings and string indications are used together, their vertical placement can be controlled with the `script-priority` property, see [Controlling the vertical ordering of scripts], page 157, and Section B.18 [Default values for script-priority], page 937; the ordering in the source code has no influence.

```
\clef "treble_8"
g4\3-0
g-0\3
g-\tweak script-priority 200 -0 \3
```



String numbers may also, as is customary with unfretted strings, be printed in Roman numerals and placed below the staff rather than above.

```
\clef "treble_8"
c'2\2
a\3
\romanStringNumbers
c'\2
\set stringNumberOrientations = #'(down)
a\3
\arabicStringNumbers
g1\4
```



Most behaviors of string number indications (namely, the `StringNumber` object), including their placement, may be set in the same way as fingerings: see Section 7.1.2 [Fingering instructions], page 281.

Predefined commands

`\arabicStringNumbers`, `\romanStringNumbers`.

See also

Notation Reference: Section 7.1.2 [Fingering instructions], page 281.

Snippets: Section “Fretted string instruments” in *Snippets*.


Internals Reference: Section “StringNumber” in *Internals Reference*, Section “Fingering” in *Internals Reference*.

12.1.3 Default tablatures

Music for plucked string instruments is frequently notated using a finger/touch notation or tablature. In contrast to traditional notation pitches are not denoted with note heads, but by numbers (or letter-like symbols in historical intavolatura). The staff lines in tablature indicate the string on which the note is to be played, and a number placed on a staff line indicates the fret at which the corresponding string is to be pressed. Notes that are to be played simultaneously are vertically aligned.

By default, string 1 is the highest string, and corresponds to the top line on the `TabStaff`. The tuning of the `TabStaff` strings defaults to the standard guitar tuning (with 6 strings). The notes are printed as tablature, by using `TabStaff` and `TabVoice` contexts. A calligraphic tablature clef is added automatically.

```
\new TabStaff \relative {
  a,8 a' <c e> a
  d,8 a' <d f> a
}
```



Default tablatures do not contain any symbols for tone duration nor any other musical symbols such as expressive marks, for example.

```
symbols = {
  \time 3/4
  c4-.\^"Allegro" d( e)
  f4-.\f g a^\fermata
  \mark \default
  c8_.\<\( c16 c~ 2\!
  c'2.\prall\
}
```

```
\score {
  <<
```


[illegible]

```
symbols = {
  \time 3/4
  c4-.^"Allegro" d( e)
  f4-. \f g a^\fermata
  \mark \default
  c8_. \< \< c16 c~ 2\!
  c'2. \prall\}
}
```

[illegible]

Even when `minimumFret` is set, open strings are used whenever possible. This behavior can be changed by setting `restrainOpenStrings` to `#t`.

```

\layout { \omit Voice.StringNumber }
\new StaffGroup <<
  \new Staff \relative {
    \clef "treble_8"
    \time 2/4
    c16 d e f g4
    c,16\5 d\5 e\4 f\4 g4\4
    c,16 d e f g4
  }
  \new TabStaff \relative {
    c16 d e f g4
    c,16\5 d\5 e\4 f\4 g4\4
    \set TabStaff.minimumFret = 5
    \set TabStaff.restrainOpenStrings = ##t
    c,16 d e f g4
  }
>>

```

Chord constructs can be repeated by the chord repetition symbol ‘q’, (see Section 5.1.2 [Chord repetition], page 217, for more). In combination with tabulatures, its behavior of removing string and fingering numbers alongside with other events may lead to unwanted results, in particular different fret positions. The command `\tabChordRepeats` keeps the fingering consistent across repetitions. In the following example, the default fingering for this chord (without fingering indications) would be ‘gis’ on 4th string, ‘b’ on 3rd string, and ‘cis’ on 2nd string. As we use `b-0` in the input, ‘b’ is on the second string, and ‘cis’ moves to the 3rd string. `\tabChordRepeats` allows to keep the same fingering in the following q chords:

```

guitar = \relative {
  r8 <gis-2 cis-3 b-0>~ q4 q8~ 8 q4
}

\new StaffGroup <<
  \new Staff {
    \clef "treble_8"
    \guitar
  }
  \new TabStaff {
    \tabChordRepeats \guitar
  }
>>

```

Ties over a line break are parenthesized by default. The same holds for the second alternative of a repeat.

```

ties = \relative {
  \repeat volta 2 {
    e'2. f4~
    2 g2~
  }
  \alternative {
    \volta 1 { g4 f2. }
    \volta 2 { g4\repeatTie c,2. }
  }
  b1~
  \break
  b1
  \bar "|"
}

\score {
  <<
    \new StaffGroup <<
      \new Staff {
        \clef "treble_8"
        \ties
      }
      \new TabStaff {
        \ties
      }
    >>
  >>
  \layout {

```

```

indent = 0
ragged-right = ##t
}
}

```

The command `\hideSplitTiedTabNotes` cancels the behavior of engraving fret numbers in parentheses:

```

ties = \relative {
  \repeat volta 2 {
    e'2. f4~
    2 g2~ }
  \alternative {
    \volta 1 { g4 f2. }
    \volta 2 { g4\repeatTie c,2. }
  }
  b1~
  \break
  b1
  \bar "|"
}

\score {
  <<
    \new StaffGroup <<
      \new Staff {
        \clef "treble_8"
        \ties
      }
      \new TabStaff {
        \hideSplitTiedTabNotes
        \ties
      }
    >>
  >>
  \layout {

```

```

indent = 0
ragged-right = ##t
}
}

```

Harmonic indications can be added to tablature notation as sounding pitches:

```

\layout { \omit Voice.StringNumber }
firstHarmonic = {
  d'4\4\harmonic
  g'4\3\harmonic
  b'2\2\harmonic
}
\score {
  <<
    \new Staff {
      \clef "treble_8"
      \firstHarmonic
    }
    \new TabStaff { \firstHarmonic }
  >>
}

```

Note that the command `\harmonic` must always be attached to single notes (possibly inside of a chord) instead of whole chords. It only makes sense for open-string harmonics in the 12th fret. All other harmonics should be calculated by LilyPond. This can be achieved by indicating the fret where a finger of the fretting hand should touch a string.

```
fretHarmonics = {
  \harmonicByFret 5 d16\4
  \harmonicByFret 4 d16\4
  \harmonicByFret 3 d8\4
  \harmonicByFret 5 <g\3 b\2>2.
}
\score {
  <<
    \new Staff {
      \clef "treble_8"
      \fretHarmonics
    }
    \new TabStaff { \fretHarmonics }
  >>
}
```

Alternatively, harmonics can be computed by defining the ratio of string lengths above and below the harmonic fingering.

```
ratioHarmonics = {
  \harmonicByRatio #1/2 <g\3 b\2 e'\1>4
  \harmonicByRatio #1/3 <g\3 b\2 e'\1>4
  \harmonicByRatio #1/4 { g8\3 b8\2 e'4\1 }
}
\score {
  <<
    \new Staff {
      \clef "treble_8"
      \ratioHarmonics
    }
    \new TabStaff { \ratioHarmonics }
  >>
}
```

String bendings can be added to tablature notation. A bending is introduced by appending `\^` to the note or chord to be bent; it terminates automatically at the next note or chord. Available are the following styles: the default prints a curve with an arrow head up or down, 'hold a dashed horizontal line, 'pre-bend a vertical line with an arrow head, and 'pre-bend-hold a vertical line with an arrow head continued by a dashed line.

The commands `\bendHold`, `\preBend`, and `\preBendHold` are shortcuts for setting the bending style.

```

bend-styles = {
  <>^"default"
  f'4\^ g'4\^ f'2

  <>^\markup \typewriter "'hold"
  \grace f'4\^ g'1\bendHold \^ g'1

  <>^\markup \typewriter "'pre-bend"
  \grace f'4\preBend \^ g'1\bendHold \^ g'1

  <>^\markup \typewriter "'pre-bend-hold"
  \grace f'4\preBendHold \^ g'1\bendHold \^ g'1\^ f'

  \bar "|."
}

\score {
  \new StaffGroup
  <<
    \new Staff {
      \override TextScript.font-size = -2
      \clef "G_8"
      \bend-styles
    }
    \new TabStaff \bend-styles
  >>
  \layout {
    \context {
      \Voice
      \omit StringNumber
    }
    \context {
      \TabStaff
      minimumFret = 5
    }
  }
}

```

The image shows a musical score for a guitar piece. It consists of a single staff with a treble clef and a common time signature (C). The staff is divided into four measures, each labeled with a technique: 'default', 'hold', 'pre-bend', and 'pre-bend-hold'. The notation includes a guitar-specific staff with fret numbers (6, 8) and bend indicators (1, 6, 8, 6). The first measure shows a 'default' technique with a note on the 6th fret. The second measure shows a 'hold' technique with a note on the 6th fret. The third measure shows a 'pre-bend' technique with a note on the 6th fret. The fourth measure shows a 'pre-bend-hold' technique with a note on the 6th fret. The notation includes a guitar-specific staff with fret numbers (6, 8) and bend indicators (1, 6, 8, 6).

Open strings are usually not bent. To have them bent as well set the property `bend-me` to `#t`. To exclude other notes from being bent set it to `#f`.

```
mus = {
  <>~"default"
  <a b f'>4\^
  <ais b fis'>\^
  <a b f'>2

  <>~"bend open strings"
  <a \tweak bend-me ##t b f'>4\^
  <ais \tweak bend-me ##t bis fis'>\^
  <a b f'>2

  <>~"exclude other strings"
  <g \tweak bend-me ##f b\3 d'>4\^
  <a e'\2 >\^
  <g \tweak bend-me ##f b\3 d'>2

  \bar "|"
}

\score {
  \new StaffGroup
  <<
    \new Staff {
      \override TextScript.font-size = -2
      \clef "G_8"
      \mus
    }
    \new TabStaff \mus
  >>
  \layout {
    \context {
      \Voice
      \omit StringNumber
    }
  }
}
```


For consecutive bendings the starting bend may need to have an appropriate setting for `details.successive-level`. For convenience there is the function `bendStartLevel`, taking an integer.

```
printNext = -\tweak details.target-visibility ##t \etc

mus = {
  c'4\3\^ cis'\3 \^ d'2\3

  \grace bes4\3\preBendHold \bendStartLevel 2 \printNext \^
  d'4\3\bendHold \^ d'2\3\^ des'4\3 \^ c'1\3

  \bar "|."
}

\score {
  \new StaffGroup
  <<
    \new Staff {
      \override TextScript.font-size = -2
      \clef "G_8"
      \mus
    }
    \new TabStaff \mus
  >>
  \layout {
    \context {
      \Voice
      \omit StringNumber
    }
  }
}
```

Per default the BendSpanner ends at the following note or chord even if it is tied to the starting note or chord. A single NoteColumn may be skipped by using `\skipNC`. A group of NoteColumns can be skipped by using `\skipNCs` at the beginning and `\endSkipNCs` at the end.

```

bends-with-ties-and-skips = {
  a'4~\^ \skipNC a'4~ \skipNC a'4 b'4
  a'4~ a'4~\^ \skipNC a'4 b'4
  a'4~ a'4~ a'4~\^ b'4
  c'2~\^ d'~ \bendHold \^ \skipNC d'~ d'\^ c'
  \grace { c'8~\preBendHold \^ }
  \skipNCs d'2~ d'2~ \endSkipNCs d'\^ c'2
  \bar "|"
}

\score {
  \new StaffGroup
  <<
    \new Staff {
      \clef "G_8"
      \bends-with-ties-and-skips
    }
    \new TabVoice \bends-with-ties-and-skips
  >>
  \layout {
    \context {
      \Voice
      \omit StringNumber
    }
    \context {
      \TabStaff
      minimumFret = 3
      restrainOpenStrings = ##t
    }
  }
}

```

Predefined commands


`\skipNCs`, `\skipNC`, `\endSkipNCs`.

Selected snippets

Stem and beam behavior in tablature

The direction of stems is controlled the same way in tablature as in traditional notation. Beams can be made horizontal, as shown in this example.

```
\new TabStaff {
  \relative c {
    \tabFullNotation
    g16 b d g b d g b
    \stemDown
    \override Beam.concaveness = 10000
    g,,16 b d g b d g b
  }
}
```



Polyphony in tablature


Polyphony is created the same way in a TabStaff as in a regular staff.

```
upper = \relative c' {
  \time 12/8
  \key e \minor
  \voiceOne
  r4. r8 e, fis g16 b g e e' b c b a g fis e
}

lower = \relative c {
  \key e \minor
  \voiceTwo
  r16 e d c b a g4 fis8 e fis g a b c
}

\score {
  \new StaffGroup = "tab with traditional" <<
    \new Staff = "guitar traditional" <<
      \clef "treble_8"
      \new Voice = "upper" \upper
      \new Voice = "lower" \lower
    >>

    \new TabStaff = "guitar tab" <<
      \new TabVoice = "upper" \upper
      \new TabVoice = "lower" \lower
    >>
  >>
}
```



Open-string harmonics in tablature

This snippet demonstrates open-string harmonics.

```
openStringHarmonics = {
  \textSpannerDown
  \override TextSpanner.staff-padding = 3
  \override TextSpanner.dash-fraction = 0.3
  \override TextSpanner.dash-period = 1

  % first harmonic
  \override TextSpanner.bound-details.left.text =
    \markup\small "1st harm. "
  \harmonicByFret 12 e,\6\startTextSpan
  \harmonicByRatio #1/2 e,\6\stopTextSpan

  % second harmonic
  \override TextSpanner.bound-details.left.text =
    \markup\small "2nd harm. "
  \harmonicByFret 7 e,\6\startTextSpan
  \harmonicByRatio #1/3 e,\6
  \harmonicByFret 19 e,\6
  \harmonicByRatio #2/3 e,\6\stopTextSpan
  %\harmonicByFret 19 < e,\6 a,\5 d\4 >
  %\harmonicByRatio #2/3 < e,\6 a,\5 d\4 >

  % third harmonic
  \override TextSpanner.bound-details.left.text =
    \markup\small "3rd harm. "
  \harmonicByFret 5 e,\6\startTextSpan
  \harmonicByRatio #1/4 e,\6
  \harmonicByFret 24 e,\6
  \harmonicByRatio #3/4 e,\6\stopTextSpan
  \break

  % fourth harmonic
  \override TextSpanner.bound-details.left.text =
    \markup\small "4th harm. "
  \harmonicByFret 4 e,\6\startTextSpan
  \harmonicByRatio #1/5 e,\6
  \harmonicByFret 9 e,\6
  \harmonicByRatio #2/5 e,\6
  \harmonicByFret 16 e,\6
  \harmonicByRatio #3/5 e,\6\stopTextSpan
}
```

```

% fifth harmonic
\override TextSpanner.bound-details.left.text =
  \markup\small "5th harm. "
\harmonicByFret 3 e,\6\startTextSpan
\harmonicByRatio #1/6 e,\6\stopTextSpan
\break

% sixth harmonic
\override TextSpanner.bound-details.left.text =
  \markup\small "6th harm. "
\harmonicByFret 2.7 e,\6\startTextSpan
\harmonicByRatio #1/7 e,\6\stopTextSpan

% seventh harmonic
\override TextSpanner.bound-details.left.text =
  \markup\small "7th harm. "
\harmonicByFret 2.3 e,\6\startTextSpan
\harmonicByRatio #1/8 e,\6\stopTextSpan

% eighth harmonic
\override TextSpanner.bound-details.left.text =
  \markup\small "8th harm. "
\harmonicByFret 2 e,\6\startTextSpan
\harmonicByRatio #1/9 e,\6\stopTextSpan
}

\score {
  <<
    \new Staff \with { \omit StringNumber } {
      \new Voice {
        \clef "treble_8"
        \openStringHarmonics
      }
    }
    \new TabStaff {
      \new TabVoice {
        \openStringHarmonics
      }
    }
  >>
}

```

The image shows a musical score for a fretted string instrument. The top staff is a treble clef with a common time signature. The bottom staff is a tab staff with fret numbers. The first harmonic is at fret 12, the second at fret 7, and the third at fret 19. The notes are marked with diamond symbols.

Harmonic	Fret	Ratio
1st	12	1/6
2nd	7	1/7
3rd	19	1/8

The image displays two systems of musical notation for fretted string harmonics in tablature. Each system consists of three staves: a treble clef staff with a diamond symbol, a tablature staff with fret numbers in parentheses, and a three-string staff labeled T, A, and B.

System 1 (Measures 6-9):

- Measure 6: Treble staff has a diamond on the 4th line. Tablature has (4) on the 4th string. T, A, B staff has a diamond on the 4th line.
- Measure 7: Treble staff has a diamond on the 4th line. Tablature has (4) on the 4th string. T, A, B staff has a diamond on the 4th line.
- Measure 8: Treble staff has a diamond on the 4th line. Tablature has (9) on the 9th string. T, A, B staff has a diamond on the 4th line.
- Measure 9: Treble staff has a diamond on the 4th line. Tablature has (9) on the 9th string. T, A, B staff has a diamond on the 4th line.

System 2 (Measures 10-12):

- Measure 10: Treble staff has a diamond on the 6th line. Tablature has (2.7) on the 2nd and 7th strings. T, A, B staff has a diamond on the 6th line.
- Measure 11: Treble staff has a diamond on the 6th line. Tablature has (2.7) on the 2nd and 7th strings. T, A, B staff has a diamond on the 6th line.
- Measure 12: Treble staff has a diamond on the 6th line. Tablature has (2.3) on the 2nd and 3rd strings. T, A, B staff has a diamond on the 6th line.

Fretted-string harmonics in tablature

The following demonstrates fretted-string harmonics in a tablature.

```

pinchedHarmonics = {
  \textSpannerDown
  \override TextSpanner.bound-details.left.text =
    \markup { \halign #-0.5 \teeny "PH" }
  \override TextSpanner.style = #'dashed-line
  \override TextSpanner.dash-period = 0.6
  \override TextSpanner.bound-details.right.attach-dir = 1
  \override TextSpanner.bound-details.right.text =
    \markup { \draw-line #'(0 . 1) }
  \override TextSpanner.bound-details.right.padding = -0.5
}

harmonics = {
  % artificial harmonics (AH)
  \textLengthOn
  <\parenthesize b b'\harmonic>4_\markup { \teeny "AH 16" }
  <\parenthesize g g'\harmonic>4_\markup { \teeny "AH 17" }
  <\parenthesize d' d'\harmonic>2_\markup { \teeny "AH 19" }

  % pinched harmonics (PH)
  \pinchedHarmonics
  <a'\harmonic>2\startTextSpan
  <d'\harmonic>4
  <e'\harmonic>4\stopTextSpan

  % tapped harmonics (TH)
  <\parenthesize g\4 g'\harmonic>4_\markup { \teeny "TH 17" }
  <\parenthesize a\4 a'\harmonic>4_\markup { \teeny "TH 19" }
  <\parenthesize c'\3 c'\harmonic>2_\markup { \teeny "TH 17" }

  % touch harmonics (TCH)
  a4( <e'\harmonic>2. )_\markup { \teeny "TCH" }

```

```

}

frettedStrings = {
  % artificial harmonics (AH)
  \harmonicByFret 4 g4\3
  \harmonicByFret 5 d4\4
  \harmonicByFret 7 g2\3

  % pinched harmonics (PH)
  \harmonicByFret 7 d2\4
  \harmonicByFret 5 d4\4
  \harmonicByFret 7 a4\5

  % tapped harmonics (TH)
  \harmonicByFret 5 d4\4
  \harmonicByFret 7 d4\4
  \harmonicByFret 5 g2\3

  % touch harmonics (TCH)
  a4 \harmonicByFret 9 g2.\3
}

\score {
  <<
    \new Staff
    \with { \omit StringNumber } {
      \new Voice {
        \clef "treble_8"
        \harmonics
      }
    }
    \new TabStaff {
      \new TabVoice {
        \frettedStrings
      }
    }
  >>
}

```

The image displays a musical score for a fretted string instrument. The top staff is a treble clef staff in C major, 8/8 time. It contains a sequence of notes, each marked with a diamond symbol indicating a harmonic. The notes are labeled below the staff: 8, AH 16, AH 17, AH 19, PH, TH 17, TH 19, TH 17, and TCH. The bottom staff is a tablature staff with three lines (T, A, B). It shows the fret numbers for each note in parentheses: (4), (5), (7), (7), (5), (5), (7), (5), and 2 (9). The tablature staff is divided into measures by vertical bar lines.

Slides in tablature

Slides can be typeset in both Staff and TabStaff contexts.


```

slides = {
  c'8\3(\glissando d'8\3)
  c'8\3\glissando d'8\3
  \hideNotes
  \grace { g16\glissando }
  \unHideNotes
  c'4\3
  \afterGrace d'4\3\glissando {
    \stemDown \hideNotes
    g16 }
  \unHideNotes
}

\score {
  <<
    \new Staff { \clef "treble_8" \slides }
    \new TabStaff { \slides }
  >>

  \layout {
    \context {
      \Score
      \override Glissando.minimum-length = 4
      \override Glissando.springs-and-rods =
        #ly:spanner::set-spacing-rods
      \override Glissando.thickness = 2
      \omit StringNumber
      % or:
      \%override StringNumber.stencil = ##f
    }
  }
}

```



Chord glissando in tablature

Slides for chords are indicated by default in both Staff and TabStaff.

String numbers may be necessary for TabStaff because automatic string calculations are different for chords and for single notes.

```

myMusic = \relative c' {
  <c e g>1 \glissando <f a c>
  <cis, eis gis>1 \glissando <f a c>
  <cis eis gis>1 \glissando <f a c\3>
}

\score {

```



```

<<
  \new Staff {
    \clef "treble_8"
    \omit StringNumber
    \myMusic
  }
  \new TabStaff \myMusic
>>
}

\score {
  <<
    \new Staff {
      \clef "treble_8"
      \omit StringNumber
      \myMusic
    }
    \new TabStaff \with { \override Glissando.style = #'none } {
      \myMusic
    }
  >>
}

```

Hammer-on and pull-off

Hammer-on and pull-off can be obtained using slurs.

```


\new TabStaff {
  \relative c' {
    d4( e\2)
    a( g)
  }
}

```

Hammer-on and pull-off using voices

The arc of hammer-on and pull-off is upwards in voices one and three and downwards in voices two and four:


```
\new TabStaff {
  \relative c' {
    << { \voiceOne g2( a) }
    \\ { \voiceTwo a,( b) }
    >> \oneVoice
  }
}
```



Hammer-on and pull-off using chords

When using hammer-on or pull-off with chorded notes, only a single arc is drawn. However “double arcs” are possible by setting the `doubleSlurs` property to `#t`.

```
\new TabStaff {
  \relative c' {
    % chord hammer-on and pull-off
    \set doubleSlurs = ##t
    <g' b>8( <a c> <g b>)
  }
}
```



See also

Notation Reference: Section 5.1.2 [Chord repetition], page 217, Section 3.3.1 [Glissando], page 176, Section 11.1.3 [Harmonics], page 428, Section 7.1.9 [Stems], page 296, Section 4.1.1 [Written-out repeats], page 188.

Snippets: Section “Fretted string instruments” in *Snippets*.

Internals Reference: Section “TabNoteHead” in *Internals Reference*, Section “TabStaff” in *Internals Reference*, Section “TabVoice” in *Internals Reference*, Section “Beam” in *Internals Reference*.

Known issues and warnings

Chords are not handled in a special way, and hence the automatic string selector may easily select the same string for two notes in a chord.


In order to handle `\partCombine`, a `TabStaff` must use specially-created voices:

```
melodia = \partCombine { e4 g g g } { e4 e e e }
<<
\new TabStaff <<
  \new TabVoice = "one" s1
  \new TabVoice = "two" s1
  \new TabVoice = "shared" s1
```

```

\new TabVoice = "solo" s1
{ \melodia }
>>
>>

```



Guitar special effects are limited to harmonics and slides.

12.1.4 Custom tablatures


LilyPond tablature automatically calculates the fret for a note based on the string to which the note is assigned. In order to do this, the tuning of the strings must be specified. The tuning of the strings is given in the `stringTunings` property.

LilyPond comes with predefined string tunings for banjo, mandolin, guitar, bass guitar, ukulele, violin, viola, cello, and double bass. LilyPond automatically sets the correct transposition for predefined tunings. The following example is for bass guitar, which sounds an octave lower than written.

```

<<
\new Voice \with {
  \omit StringNumber
} {
  \clef "bass_8"
  \relative {
    c,4 d e f
  }
}
\new TabStaff \with {
  stringTunings = #bass-tuning
} {
  \relative {
    c,4 d e f
  }
}
>>

```



The default string tuning is guitar-tuning, which is the standard EADGBE tuning. Some other predefined tunings are guitar-open-g-tuning, mandolin-tuning and banjo-open-g-tuning. The predefined string tunings are found in `ly/string-tunings-init.ly`.

Any desired string tuning can be created. The `\stringTuning` function can be used to define a string tuning which can be used to set `stringTunings` for the current context.

Its argument is a chord construct defining the pitches of each string in the tuning. The chord construct must be in absolute octave mode, see Section 1.1.1 [Absolute octave entry], page 3.


The string with the highest number (generally the lowest string) must come first in the chord. For example, we can define a string tuning for a four-string instrument with pitches of a'', d'', g', and c':

```

mynotes = {
  c'4 e' g' c'' |
  e''4 g'' b'' c'''
}

<<
\new Staff {
  \clef treble
  \mynotes
}
\new TabStaff {
  \set Staff.stringTunings = \stringTuning <c' g' d'' a''>
  \mynotes
}
>>

```



The `stringTunings` property is also used by `FretBoards` to calculate automatic fret diagrams.

String tunings are used as part of the hash key for predefined fret diagrams (see Section 12.1.6 [Predefined fret diagrams], page 466).

The previous example could also be written as follows:


```

custom-tuning = \stringTuning <c' g' d'' a''>

mynotes = {
  c'4 e' g' c'' |
  e''4 g'' b'' c'''
}

<<
\new Staff {
  \clef treble
  \mynotes
}
\new TabStaff {
  \set TabStaff.stringTunings = #custom-tuning
  \mynotes
}
>>

```



Internally, a string tuning is a Scheme list of string pitches, one for each string, ordered by string number from 1 to N, where string 1 is at the top of the tablature staff and string N is at the bottom. This ordinarily results in ordering from highest pitch to lowest pitch, but some instruments (e.g., ukulele) do not have strings ordered by pitch.

A string pitch in a string tuning list is a LilyPond pitch object. Pitch objects are created with the Scheme function `ly:make-pitch` (see Section “Scheme functions” in *Internals Reference*).

`\stringTuning` creates such an object from chord input.


LilyPond automatically calculates the number of lines in the `TabStaff` and the number of strings in an automatically calculated `FretBoard` as the number of elements in `stringTunings`.

To let all `TabStaff` contexts use the same custom tuning by default, you can use


```
\layout {
  \context {
    \TabStaff
    stringTunings = \stringTuning <c' g' d'' a''>
  }
}
```

A modern tab clef can also be used.

```
\new TabStaff {
  \clef moderntab
  <a, e a>1
  \break
  \clef tab
  <a, e a>1
}
```



2



The modern tab clef supports tablatures from 4 to 7 strings.

`TabStaff` may support microtones like quarter tones, which can be played using bendings. `supportNonIntegerFret = ##t` needs to be set in `Score` context. However, microtones are not supported in `FretBoards`.


The image shows a musical score for the song "The Rose Tree". It consists of a vocal melody line and a piano accompaniment line. The vocal line is written in treble clef with a common time signature (C). The key signature has one flat (B-flat). The melody starts on a G4, goes up to a B4, then down to an A4, and continues with various intervals. The piano accompaniment is written in bass clef and features a steady eighth-note bass line (G2, F2, E2, D2) and a treble line that plays chords corresponding to the melody. The score is divided into measures by vertical bar lines.

Fret diagrams can be added to music as a markup to the desired note. The markup contains information about the desired fret diagram. There are three different fret diagram markup interfaces: standard, terse, and verbose. The three interfaces produce equivalent markups, but have varying amounts of information in the markup string. Details about the syntax of the

different markup strings used to define fret diagrams are found at Section A.1.6 [Instrument-specific markup], page 862.

The standard fret diagram markup string indicates the string number and the fret number for each dot to be placed on the string. In addition, open and unplayed (muted) strings can be indicated.

```
<<
  \new ChordNames {
    \chordmode {
      c1 d:m
    }
  }
  \new Staff {
    \clef "treble_8"
    <c e g c' e'>1^\markup {
      \fret-diagram "6-x;5-3;4-2;3-o;2-1;1-o;"
    }
    <d a d' f'>1^\markup {
      \fret-diagram "6-x;5-x;4-o;3-2;2-3;1-1;"
    }
  }
}>>
```




Barré indications can be added to the diagram from the fret diagram markup string.

```

<<
  \new ChordNames {
    \chordmode {
      f1 g
    }
  }
  \new Staff {
    \clef "treble_8"
    <f, c f a c' f'>1^\markup {
      \fret-diagram "c:6-1-1;6-1;5-3;4-3;3-2;2-1;1-1;"
    }
    <g, d g b d' g'>1^\markup {
      \fret-diagram "c:6-1-3;6-3;5-5;4-5;3-4;2-3;1-3;"
    }
  }
}
>>

```




The size of the fret diagram, and the number of frets in the diagram can be changed in the fret diagram markup string.

```


<<
  \new ChordNames {
    \chordmode {
      f1 g
    }
  }
  \new Staff {
    \clef "treble_8"
    <f, c f a c' f'>1^\markup {
      \fret-diagram "s:1.5;c:6-1-1;6-1;5-3;4-3;3-2;2-1;1-1;"
    }
    <g, b, d g b g'>1^\markup {
      \fret-diagram "h:6;6-3;5-2;4-o;3-o;2-o;1-3;"
    }
  }
}
>>

```




The number of strings in a fret diagram can be changed to accommodate different instruments such as banjos and ukuleles with the fret diagram markup string.

```
<<
  \new ChordNames {
    \chordmode {
      a1
    }
  }
  \new Staff {
    % An 'A' chord for ukulele
    a'1^\markup {
      \fret-diagram "w:4;4-2-2;3-1-1;2-o;1-o;"
    }
  }
>>
```



Fingering indications can be added, and the location of fingering labels can be controlled by the fret diagram markup string.

```
<<
  \new ChordNames {
    \chordmode {
      c1 d:m
    }
  }
  \new Staff {
    \clef "treble_8"
    <c e g c' e'>1^\markup {
      \fret-diagram "f:1;6-x;5-3-3;4-2-2;3-o;2-1-1;1-o;"
    }
    <d a d' f'>1^\markup {
      \fret-diagram "f:2;6-x;5-x;4-o;3-2-2;2-3-3;1-1-1;"
    }
  }
>>
```




Dot radius and dot position can be controlled with the fret diagram markup string.

```

<<
  \new ChordNames {
    \chordmode {
      c1 d:m
    }
  }
  \new Staff {
    \clef "treble_8"
    <c e g c' e'>1^\markup {
      \fret-diagram "d:0.35;6-x;5-3;4-2;3-o;2-1;1-o;"
    }
    <d a d' f'>1^\markup {
      \fret-diagram "p:0.2;6-x;5-x;4-o;3-2;2-3;1-1;"
    }
  }
}
>>

```



Fret-diagrams may be printed left-handed

```

\markup
  \center-column {
    "C"
    "(left-handed)"
    \override #`(fret-diagram-details . ((handedness . ,LEFT)))
    \fret-diagram "6-x;5-3-3;4-2-2;3-o;2-1;1-o;"
  }

```

C
(left-handed)



The `\fret-diagram-terse` markup string omits string numbers; the string number is implied by the presence of semicolons. There is one semicolon for each string in the diagram. The first semicolon corresponds to the highest string number and the last semicolon corresponds to the first string. Mute strings, open strings, and fret numbers can be indicated.

```


<<
  \new ChordNames {
    \chordmode {
      c1 d:m
    }
  }
  \new Staff {
    \clef "treble_8"
    <c e g c' e'>1^\markup {

```

```

    \fret-diagram-terse "x;3;2;o;1;o;"
  }
  <d a d' f'>1^\markup {
    \fret-diagram-terse "x;x;o;2;3;1;"
  }
}
>>

```




Barré indicators can be included in the `\fret-diagram-terse` markup string.

```

<<
  \new ChordNames {
    \chordmode {
      f1 g
    }
  }
  \new Staff {
    \clef "treble_8"
    <f, c f a c' f'>1^\markup {
      \fret-diagram-terse "1-(;3;3;2;1;1-);"
    }
    <g, d g b d' g'>1^\markup {
      \fret-diagram-terse "3-(;5;5;4;3;3-);"
    }
  }
}
>>

```



Fingering indications can be included in the `\fret-diagram-terse` markup string.

```


<<
  \new ChordNames {
    \chordmode {
      c1 d:m
    }
  }
  \new Staff {
    \override Voice.TextScript.fret-diagram-details.finger-code =
      #'below-string
    \clef "treble_8"
    <c e g c' e'>1^\markup {

```

```

    \fret-diagram-terse "x;3-3;2-2;o;1-1;o;"
  }
  <d a d' f'>1^\markup {
    \fret-diagram-terse "x;x;o;2-2;3-3;1-1;"
  }
}
>>

```



Other fret diagram properties must be adjusted using `\override` when using the `\fret-diagram-terse` markup.


Only one indication per string can be included in a `\fret-diagram-terse` markup. To have multiple indications per string use a fret diagram or `\fret-diagram-verbose` markup.

The `\fret-diagram-verbose` markup string is in the format of a Scheme list. Each element of the list indicates an item to be placed on the fret diagram.

```

<<
  \new ChordNames {
    \chordmode {
      c1 d:m
    }
  }
  \new Staff {
    \clef "treble_8"
    <c e g c' e'>1^\markup {
      \fret-diagram-verbose #'(
        (mute 6)
        (place-fret 5 3)
        (place-fret 4 2)
        (open 3)
        (place-fret 2 1)
        (open 1)
      )
    }
    <d a d' f'>1^\markup {
      \fret-diagram-verbose #'(
        (mute 6)
        (mute 5)
        (open 4)
        (place-fret 3 2)
        (place-fret 2 3)
        (place-fret 1 1)
      )
    }
  }
}
>>

```



Fingering indications and barrés can be included in a `\fret-diagram-verbose` markup string. Unique to the `\fret-diagram-verbose` interface is a capo indication that can be placed on the fret diagram. The capo indication is a thick bar that covers all strings. The fret with the capo will be the lowest fret in the fret diagram.

Fingering indication dots can be colored as well as parenthesized; the parenthesis's color can also be altered independently.


Markups can be placed into the dots as well.

```
<<
  \new ChordNames {
    \chordmode {
      f1 g c c b
    }
  }
  \new Staff {
    \clef "treble_8"
    \override Voice.TextScript
      .fret-diagram-details.finger-code = #'below-string
    <f, c f a c' f'>1^\markup {
      \fret-diagram-verbose #'(
        (place-fret 6 1)
        (place-fret 5 3)
        (place-fret 4 3)
        (place-fret 3 2)
        (place-fret 2 1)
        (place-fret 1 1)
        (barre 6 1 1)
      )
    }
    <g, b, d g b g'>1^\markup {
      \fret-diagram-verbose #'(
        (place-fret 6 3 2)
        (place-fret 5 2 1)
        (open 4)
        (open 3)
        (open 2)
        (place-fret 1 3 3)
      )
    }
    <c g c' e' g'>1^\markup {
      \fret-diagram-verbose #'(
        (capo 3)
        (mute 6)
        (place-fret 4 5 1)
        (place-fret 3 5 2)
      )
    }
  }
```

```

        (place-fret 2 5 3)
    )
}
\override Voice.TextScript.size = 1.4
<c g c' e' g'>1^\markup {
  \fret-diagram-verbose #'(
    (place-fret 6 3 1 red parenthesized default-paren-color)
    (place-fret 5 3 1 inverted)
    (place-fret 4 5 2 blue parenthesized)
    (place-fret 3 5 3 blue)
    (place-fret 2 5 4 blue)
    (place-fret 1 3 1 inverted)
  )
}
\override Voice.TextScript.size = 1.5
<b, fis b dis' fis'>1^\markup
  \override #'(fret-diagram-details . ((finger-code . in-dot)))
  \fret-diagram-verbose #`(
    (place-fret 5 2 1)
    (place-fret 4 4 "fis" red)
    (place-fret 3 4 "b" red)
    (place-fret
      2 4
      ,#{ \markup
        \concat {
          \vcenter "d"
          \fontsize #-5
          \musicglyph "accidentals.sharp"} #}
      red)
    (place-fret 1 2 1)
  )
}
>>

```



All other fret diagram properties must be adjusted using `\override` when using the `\fret-diagram-verbose` markup.

The graphical layout of a fret diagram can be customized according to user preference through the properties of the `fret-diagram-interface`. Details are found at Section “fret-diagram-interface” in *Internals Reference*; see Section “Fret diagrams explained and developed” in *Snippets* for an exhaustive example. For a fret diagram markup, the interface properties belong to `Voice.TextScript`.


Selected snippets

Changing fret orientations

Fret diagrams can be oriented in three ways. By default the top string or fret in the different orientations will be aligned.

```
\include "predefined-guitar-fretboards.ly"

<<
\chords {
  c1
  c1
  c1
}
\new FretBoards \chordmode {
  c1
  \override FretBoard.fret-diagram-details.orientation =
    #'landscape
  c1
  \override FretBoard.fret-diagram-details.orientation =
    #'opposing-landscape
  c1
}
\new Voice {
  c'1
  c'1
  c'
}
>>
```



Customizing markup fret diagrams

Fret diagram properties can be modified by setting the `fret-diagram-details` property. For markup fret diagrams, overrides can be applied to the `Voice.TextScript` object or directly to the markup.

```
<<
\chords { c1 | c | c | d }

\new Voice = "mel" {
  \textLengthOn
  % Set global properties of fret diagram
  \override TextScript.size = 1.2
  \override TextScript.fret-diagram-details.finger-code = #'in-dot
  \override TextScript.fret-diagram-details.dot-color = #'white

  %% C major for guitar, no barre, using defaults
```

```

    % terse style
c'1~\markup { \fret-diagram-terse "x;3-3;2-2;o;1-1;o;" }

%% C major for guitar, barred on third fret
% verbose style
% size 1.0
% roman fret label, finger labels below string, straight barre
c'1~\markup {
  % standard size
  \override #'(size . 1.0) {
    \override #'(fret-diagram-details . (
      (number-type . roman-lower)
      (finger-code . in-dot)
      (barre-type . straight))) {
      \fret-diagram-verbose #'((mute 6)
        (place-fret 5 3 1)
        (place-fret 4 5 2)
        (place-fret 3 5 3)
        (place-fret 2 5 4)
        (place-fret 1 3 1)
        (barre 5 1 3))
    }
  }
}

%% C major for guitar, barred on third fret
% verbose style
% landscape orientation, arabic numbers, M for mute string
% no barre, fret label down or left, small mute label font
c'1~\markup {
  \override #'(fret-diagram-details . (
    (finger-code . below-string)
    (number-type . arabic)
    (label-dir . -1)
    (mute-string . "M")
    (orientation . landscape)
    (barre-type . none)
    (xo-font-magnification . 0.4)
    (xo-padding . 0.3))) {
    \fret-diagram-verbose #'((mute 6)
      (place-fret 5 3 1)
      (place-fret 4 5 2)
      (place-fret 3 5 3)
      (place-fret 2 5 4)
      (place-fret 1 3 1)
      (barre 5 1 3))
    }
  }
}

%% simple D chord
% terse style
% larger dots, centered dots, fewer frets


```



```

% label below string
d'1^\markup {
  \override #'(fret-diagram-details . (
    (finger-code . below-string)
    (dot-radius . 0.35)
    (dot-position . 0.5)
    (fret-count . 3))) {
    \fret-diagram-terse "x;x;o;2-1;3-2;2-3;"
  }
}
>>

```



See also

Notation Reference: Section A.1.6 [Instrument-specific markup], page 862.

Snippets: Section “Fretted string instruments” in *Snippets*.

Internals Reference: Section “fret-diagram-interface” in *Internals Reference*.


12.1.6 Predefined fret diagrams

Fret diagrams can be displayed using the FretBoards context. By default, the FretBoards context will display fret diagrams that are stored in a lookup table:

```

\include "predefined-guitar-fretboards.ly"
\new FretBoards {
  \chordmode {
    c1 d
  }
}

```



The default predefined fret diagrams are contained in the file `predefined-guitar-fretboards.ly`. Fret diagrams are stored based on the pitches of a chord and the value of `stringTunings` that is currently in use. `predefined-guitar-fretboards.ly` contains predefined fret diagrams only for guitar-tuning. Predefined fret diagrams can be added for other instruments or other tunings by following the examples found in `predefined-guitar-fretboards.ly`.

Fret diagrams for the ukulele are contained in the file `predefined-ukulele-fretboards.ly`.

```

\include "predefined-ukulele-fretboards.ly"


myChords = \chordmode { a1 a:m a:aug }

\new ChordNames {
  \myChords
}

\new FretBoards {
  \set Staff.stringTunings = #ukulele-tuning
  \myChords
}

A   Am  A+

```



Fret diagrams for the mandolin are contained in the file `predefined-mandolin-fretboards.ly`.

```

\include "predefined-mandolin-fretboards.ly"


myChords = \chordmode { c1 c:m7.5- c:aug }

\new ChordNames {
  \myChords
}

\new FretBoards {
  \set Staff.stringTunings = #mandolin-tuning
  \myChords
}

C   C∅  C+

```



Chord pitches can be entered either as simultaneous music or using chord mode (see Section 15.1.1 [Chord mode overview], page 507).

```

\include "predefined-guitar-fretboards.ly"

\new FretBoards {
  \chordmode { c1 }
  <c' e' g'>1
}

x   o   o   x   o   o
3 2  1  3 2  1

```


It is common that both chord names and fret diagrams are displayed together. This is achieved by putting a `ChordNames` context in parallel with a `FretBoards` context and giving both contexts the same music.

```

\include "predefined-guitar-fretboards.ly"
mychords = \chordmode {
  c1 f g
}

<<
  \new ChordNames {
    \mychords
  }
  \new FretBoards {
    \mychords
  }
>>

```



Predefined fret diagrams are transposable, as long as a diagram for the transposed chord is stored in the fret diagram table.


```

\include "predefined-guitar-fretboards.ly"
mychords = \chordmode {
  c1 f g
}

mychordlist = {
  \mychords
  \transpose c e { \mychords }
}

<<
  \new ChordNames {
    \mychordlist
  }
  \new FretBoards {
    \mychordlist
  }
>>

```



The predefined fret diagram table for guitar contains eight chords (major, minor, augmented, diminished, dominant seventh, major seventh, minor seventh, dominant ninth) for each of 17 keys.

The predefined fret diagram table for ukulele contains these chords plus an additional three chords (major sixth, suspended second, and suspended fourth).


See Section B.4 [Predefined fretboard diagrams], page 892, for a complete list of the predefined fret diagrams. If there is no entry in the table for a chord, the FretBoards engraver calculates a fret diagram using the automatic fret diagram functionality, see Section 12.1.7 [Automatic fret diagrams], page 477.

```

\include "predefined-guitar-fretboards.ly"
mychords = \chordmode {
  c1 c:maj9
}

<<
  \new ChordNames {
    \mychords
  }
  \new FretBoards {
    \mychords
  }
>>

```



Fret diagrams can be added to the fret diagram table. To add a diagram, you must specify the hash table for the diagram, the chord for the diagram, the tuning to be used, and a definition for the diagram. Normally, the hash table will be *default-fret-table*. The diagram definition can be either a *\fret-diagram-terse* definition string or a *\fret-diagram-verbose* marking list.

```


\include "predefined-guitar-fretboards.ly"

\storePredefinedDiagram #default-fret-table
  \chordmode { c:maj9 }
  #guitar-tuning
  "x;3-2;o;o;o;o;"

mychords = \chordmode {
  c1 c:maj9
}

<<
  \new ChordNames {
    \mychords
  }
  \new FretBoards {
    \mychords
  }
>>

```



Different fret diagrams for the same chord name can be stored using different octaves of pitches. The different octave should be at least two octaves above or below the default octave, because the octaves above and below the default octave are used for transposing fretboards.

```


\include "predefined-guitar-fretboards.ly"

\storePredefinedDiagram #default-fret-table
    \chordmode { c'' }
    #guitar-tuning
    #(offset-fret 2
        (chord-shape 'bes guitar-tuning))

mychords = \chordmode {
    c1 c''
}

<<
    \new ChordNames {
        \mychords
    }
    \new FretBoards {
        \mychords
    }
>>

```



In addition to fret diagrams, LilyPond stores an internal list of chord shapes. The chord shapes are fret diagrams that can be shifted along the neck to different positions to provide different chords. Chord shapes can be added to the internal list and then used to define predefined fret diagrams. Because they can be moved to various positions on the neck, chord shapes will normally not contain any open strings. Like fret diagrams, chord shapes can be entered as either `\fret-diagram-terse` strings or `\fret-diagram-verbose` marking lists.

```

\include "predefined-guitar-fretboards.ly"

% Add a new chord shape

\addChordShape #'powerf #guitar-tuning "1-1;3-3;3-4;x;x;x;"

% add some new chords based on the power chord shape

\storePredefinedDiagram #default-fret-table
    \chordmode { f'' }
    #guitar-tuning
    #(chord-shape 'powerf guitar-tuning)
\storePredefinedDiagram #default-fret-table
    \chordmode { g'' }
    #guitar-tuning
    #(offset-fret 2
        (chord-shape 'powerf guitar-tuning))


mychords = \chordmode {
    f1 f'' g g''
}

```

```

}

<<
  \new ChordNames {
    \mychords
  }
  \new FretBoards {
    \mychords
  }
>>



```

The graphical layout of a fret diagram can be customized according to user preference through the properties of the `fret-diagram-interface`. Details are found at Section “fret-diagram-interface” in *Internals Reference*; see Section “Fret diagrams explained and developed” in *Snippets* for an exhaustive example. For a predefined fret diagram, the interface properties belong to `FretBoards.FretBoard`.

Selected snippets

Customizing fretboard fret diagrams

Fret diagram properties can be modified by setting the `fret-diagram-details` property. For `FretBoard` fret diagrams, overrides are applied to the `FretBoards.FretBoard` object. Like `Voice`, `FretBoards` is a bottom-level context, and therefore can be omitted in property overrides.

```

\include "predefined-guitar-fretboards.ly"

\storePredefinedDiagram #default-fret-table \chordmode { c' }
                        #guitar-tuning
                        "x;1-1-(;3-2;3-3;3-4;1-1-);"

% shorthand
oo = #(define-music-function
      (grob-path value)
      (list? scheme?)
      #{ \once \override $grob-path = #value #})


<<
  \new ChordNames {
    \chordmode { c1 | c | c | d | bes }
  }
  \new FretBoards {
    % Set global properties of fret diagram
    \override FretBoards.FretBoard.size = 1.2
    \override FretBoard.fret-diagram-details.finger-code = #'in-dot
    \override FretBoard.fret-diagram-details.dot-color = #'white
    \chordmode {
      c
      \oo FretBoard.size #1.0
    }
  }
>>

```

```

\oo FretBoard.fret-diagram-details.barre-type #'straight
\oo FretBoard.fret-diagram-details.dot-color #'black
\oo FretBoard.fret-diagram-details.finger-code #'below-string
c'
\oo FretBoard.fret-diagram-details.barre-type #'none
\oo FretBoard.fret-diagram-details.number-type #'arabic
\oo FretBoard.fret-diagram-details.orientation #'landscape
\oo FretBoard.fret-diagram-details.mute-string "M"
\oo FretBoard.fret-diagram-details.label-dir #LEFT
\oo FretBoard.fret-diagram-details.dot-color #'black
c'
\oo FretBoard.fret-diagram-details.finger-code #'below-string
\oo FretBoard.fret-diagram-details.dot-radius #0.35
\oo FretBoard.fret-diagram-details.dot-position #0.5
\oo FretBoard.fret-diagram-details.fret-count #3
d
\oo FretBoard.fret-diagram-details.barre-type #'straight
\oo FretBoard.fret-diagram-details.finger-code #'none
\oo FretBoard.fret-diagram-details.dot-radius #0.25
\oo FretBoard.fret-diagram-details.dot-color #'black
\oo FretBoard.fret-diagram-details.string-overhang #0.
\oo FretBoard.fret-diagram-details.barre-thickness #2.
bes
}
}
\new Voice {
  c'1 | c' | c' | d' | bes
}
>>

```



Setting up predefined fretboards for other instruments

Predefined fret diagrams can be added for new instruments in addition to the standard diagrams used for guitar. This file shows how this is done by defining a new string tuning and a few predefined fretboards for the Venezuelan *cuatro*.

This file also shows how fingerings can be included in the chords used as reference points for the chord lookup, and displayed in the fret diagram and the TabStaff, but not the music.

These fretboards are not transposable because they contain string information. This is planned to be corrected in the future.

```

% Add fretboards for the cuatro.
%
% Note: This section could be put into a separate file
%       `predefined-cuatro-fretboards.ly`
%       and be \included into each of your compositions.

```

```

cuatroTuning = #`((ly:make-pitch 0 6 0)
                ,(ly:make-pitch 1 3 SHARP)
                ,(ly:make-pitch 1 1 0)
                ,(ly:make-pitch 0 5 0))

dSix = { <a\4 b\1 d\3 fis\2> }
dMajor = { <a\4 d\1 d\3 fis \2> }
aMajSeven = { <a\4 cis\1 e\3 g\2> }
dMajSeven = { <a\4 c\1 d\3 fis\2> }
gMajor = { <b\4 b\1 d\3 g\2> }

\storePredefinedDiagram #default-fret-table \dSix
                        #cuatroTuning
                        "o;o;o;o;"
\storePredefinedDiagram #default-fret-table \dMajor
                        #cuatroTuning
                        "o;o;o;3-3;"
\storePredefinedDiagram #default-fret-table \aMajSeven
                        #cuatroTuning
                        "o;2-2;1-1;2-3;"
\storePredefinedDiagram #default-fret-table \dMajSeven
                        #cuatroTuning
                        "o;o;o;1-1;"
\storePredefinedDiagram #default-fret-table \gMajor
                        #cuatroTuning
                        "2-2;o;1-1;o;"

% End of potential include file `predefined-cuatro-fretboards.ly`.

#(set-global-staff-size 16)

primerosNames = \chordmode {
  d:6 d a:maj7 d:maj7
  g
}
primeros = {
  \dSix \dMajor \aMajSeven \dMajSeven
  \gMajor
}

\score {
  <<
    \new ChordNames {
      \set chordChanges = ##t
      \primerosNames
    }

    \new Staff {
      \new Voice \with {
        \remove "New_fingering_engraver"

```



```

    }
    \relative c'' {
      \primeros
    }
  }

  \new FretBoards {
    \set Staff.stringTunings = #cuatroTuning
    % \override FretBoard
    % #'(fret-diagram-details string-count) = 4
    \override FretBoard.fret-diagram-details.finger-code = #'in-dot
    \primeros
  }

  \new TabStaff \relative c'' {
    \set TabStaff.stringTunings = #cuatroTuning
    \primeros
  }

  >>

  \layout {
    \context {
      \Score
      \override SpacingSpanner.base-shortest-duration =
        \musicLength 16
    }
  }
  \midi { }
}

```

The image displays five chords and their corresponding fretboard diagrams for a four-string instrument. The chords are D⁶, D, A^Δ, D^Δ, and G. The notation shows the chords on a treble clef staff in C major. Below each chord is a fretboard diagram. The fretboard diagrams show fingerings: D⁶ (0, 3, 2, 1), D (0, 0, 2, 0), A^Δ (0, 0, 1, 0), D^Δ (0, 0, 0, 0), and G (0, 0, 0, 2).

Chord changes for fretboards

Fretboards can be set to display only when the chord changes, or at the beginning of a new line.


```

\include "predefined-guitar-fretboards.ly"

myChords = \chordmode {
  c1 c1 \break
  \set chordChanges = ##t
  c1 c1 \break
  c1 c1
}

```

```
<<
\new ChordNames { \myChords }
\new FretBoards { \myChords }
\new Staff { \myChords }
>>
```



Fretboards alternate tables

Alternate fretboard tables can be created. These would be used in order to have alternate fretboards for a given chord. In order to use an alternate fretboard table, the table must first be created. Fretboards are then added to the table.

The created fretboard table can be blank, or it can be copied from an existing table. The table to be used in displaying predefined fretboards is selected by the property `\predefinedDiagramTable`.

```
\include "predefined-guitar-fretboards.ly"

% Make a blank new fretboard table.
\define custom-fretboard-table-one
(make-fretboard-table)

% Make a new fretboard table as a copy of `default-fret-table`.
\define custom-fretboard-table-two
(make-fretboard-table default-fret-table)

% Add a chord to `custom-fretboard-table-one`.
\storePredefinedDiagram #custom-fretboard-table-one
\chordmode {c}
#guitar-tuning
"3-(;3;5;5;5;3-);"

% Add a chord to `custom-fretboard-table-two`.
```

```

\storePredefinedDiagram #custom-fretboard-table-two
\chordmode {c}
#guitar-tuning
"x;3;5;5;5;o;"

<<
\chords {
  c1 | d1 |
  c1 | d1 |
  c1 | d1 |
}
\new FretBoards {
  \chordmode {
    \set predefinedDiagramTable = #default-fret-table
    c1 | d1 |
    \set predefinedDiagramTable = #custom-fretboard-table-one
    c1 | d1 |
    \set predefinedDiagramTable = #custom-fretboard-table-two
    c1 | d1 |
  }
}
\new Staff {
  \clef "treble_8"
  <<
    \chordmode {
      c1 | d1 |
      c1 | d1 |
      c1 | d1 |
    }
    {
      s1_\markup "Default table" | s1 |
      s1_\markup \column { "New table" "from empty" } | s1 |
      s1_\markup \column { "New table" "from default" } | s1 |
    }
  >>
}
>>

```

8

Default table New table from empty New table from default

See also

Notation Reference: Section 12.1.4 [Custom tablatures], page 452, Section 12.1.7 [Automatic fret diagrams], page 477, Section 15.1.1 [Chord mode overview], page 507, Section B.4 [Predefined fretboard diagrams], page 892.

Installed Files: `ly/predefined-guitar-fretboards.ly`,
`ly/predefined-guitar-ninth-fretboards.ly`,
`ly/predefined-ukulele-fretboards.ly`,
`ly/predefined-mandolin-fretboards.ly`.


Snippets: Section “Fretted string instruments” in *Snippets*.

Internals Reference: Section “fret-diagram-interface” in *Internals Reference*.

12.1.7 Automatic fret diagrams

Fret diagrams can be automatically created from entered notes using the `FretBoards` context. If no predefined diagram is available for the entered notes in the active `stringTunings`, this context calculates strings and frets that can be used to play the notes.

```
<<
  \new ChordNames {
    \chordmode {
      f1 g
    }
  }
  \new FretBoards {
    <f, c f a c' f'>1
    <g, \6 b, d g b g'>1
  }
  \new Staff {
    \clef "treble_8"
    <f, c f a c' f'>1
    <g, b, d g b g'>1
  }
>>
```



As no predefined diagrams are loaded by default, automatic calculation of fret diagrams is the default behavior. Once default diagrams are loaded, automatic calculation can be enabled and disabled with predefined commands:


```
\storePredefinedDiagram #default-fret-table
                                <c e g c' e'>
                                #guitar-tuning
                                "x;3-1-(;5-2;5-3;5-4;3-1-1-);"
```

```
<<
  \new ChordNames {
    \chordmode {
      c1 c c
    }
  }
  \new FretBoards {
    <c e g c' e'>1
  }
```

```

\predefinedFretboardsOff
<c e g c' e'>1
\predefinedFretboardsOn
<c e g c' e'>1
}
\new Staff {
  \clef "treble_8"
  <c e g c' e'>1
  <c e g c' e'>1
  <c e g c' e'>1
}
>>

```




Sometimes the fretboard calculator will be unable to find an acceptable diagram. This can often be remedied by manually assigning a note to a string. In many cases, only one note need be manually placed on a string; the rest of the notes will then be placed appropriately by the FretBoards context.

Fingerings can be added to FretBoard fret diagrams.

```

<<
\new ChordNames {
  \chordmode {
    c1 d:m
  }
}
\new FretBoards {
  <c-3 e-2 g c'-1 e'>1
  <d a-2 d'-3 f'-1>1
}
\new Staff {
  \clef "treble_8"
  <c e g c' e'>1
  <d a d' f'>1
}
>>

```




The minimum fret to be used in calculating strings and frets for the FretBoard context can be set with the `minimumFret` property.

```

<<
  \new ChordNames {
    \chordmode {
      d1:m d:m
    }
  }
  \new FretBoards {
    <d a d' f'>1
    \set FretBoards.minimumFret = 5
    <d a d' f'>1
  }
  \new Staff {
    \clef "treble_8"
    <d a d' f'>1
    <d a d' f'>1
  }
>>

```



The strings and frets for the FretBoards context depend on the `stringTunings` property, which has the same meaning as in the `TabStaff` context. See Section 12.1.4 [Custom tablatures], page 452, for information on the `stringTunings` property.

The graphical layout of a fret diagram can be customized according to user preference through the properties of the `fret-diagram-interface`. Details are found at Section “fret-diagram-interface” in *Internals Reference*; see Section “Fret diagrams explained and developed” in *Snippets* for an exhaustive example. For a FretBoards fret diagram, the interface properties belong to `FretBoards.FretBoard`.

Predefined commands

`\predefinedFretboardsOff`, `\predefinedFretboardsOn`.

See also

Notation Reference: Section 12.1.4 [Custom tablatures], page 452.

Snippets: Section “Fretted string instruments” in *Snippets*.

Internals Reference: Section “fret-diagram-interface” in *Internals Reference*.

Known issues and warnings

Automatic fretboard calculations do not work properly for instruments with non-monotonic tunings.

12.1.8 Right-hand fingerings

Right-hand fingerings *p-i-m-a* must be entered using `\rightHandFinger` followed by a number.

Note: If the number is entered in Scheme notation, remember to append a space before following it with a closing > or similar.

```
\clef "treble_8"
c4\rightHandFinger 1
e\rightHandFinger 2
g\rightHandFinger 3
c'\rightHandFinger 4
<c\rightHandFinger 1 e\rightHandFinger 2
g\rightHandFinger 3 c'\rightHandFinger 4 >1
```



For convenience, `\rightHandFinger` may be abbreviated to something shorter, for example `\RH`, by adding the appropriate definition at the source file's top level:

```
RH = \rightHandFinger \etc
```

Most behaviors of right-hand fingerings (namely, the `StrokeFinger` object) may be set in the same way as ordinary fingerings: see Section 7.1.2 [Fingering instructions], page 281.

Selected snippets

Placement of right-hand fingerings

It is possible to exercise greater control over the placement of right-hand fingerings by setting a specific property, as demonstrated in the following example.

```
#(define RH rightHandFinger)


\relative c {
  \clef "treble_8"

  \set strokeFingerOrientations = #'(up down)
  <c\RH 1 e\RH 2 g\RH 3 c\RH 4 >4

  \set strokeFingerOrientations = #'(up right down)
  <c\RH 1 e\RH 2 g\RH 3 c\RH 4 >4

  \set strokeFingerOrientations = #'(left)
  <c\RH 1 e\RH 2 g\RH 3 c\RH 4 >2

  \set strokeFingerOrientations = #'(right)
  c\RH 1
}
```




Fingerings, string indications, and right-hand fingerings

This example combines left-hand fingering, string indications, and right-hand fingering.

```
#(define RH rightHandFinger)

\relative c {
  \clef "treble_8"
  <c-3\5\RH 1 >4
  <e-2\4\RH 2 >4
  <g-0\3\RH 3 >4
  <c-1\2\RH 4 >4
}
```



See also

Notation Reference: Section 7.1.2 [Fingering instructions], page 281.

Snippets: Section “Fretted string instruments” in *Snippets*.

Internals Reference: Section “StrokeFinger” in *Internals Reference*.

12.2 Guitar

Most of the notational issues associated with guitar music are covered sufficiently in the general fretted strings section, but there are a few more worth covering here. Occasionally users want to create songbook-type documents having only lyrics with chord indications above them. Since LilyPond is a music typesetter, it is not recommended for documents that have no music notation in them. A better alternative is a word processor, text editor, or, for experienced users, a typesetter like GuitarTeX.

12.2.1 Indicating position and barring

This example demonstrates how to include guitar position and barring indications using a barré line.

```
\relative {
  \clef "treble_8"
  b,16 d g b e
  \once \override TextSpanner.bound-details.left.text =
    \markup {"XII" \hspace #0.4 }
  \once \override TextSpanner.bound-details.right.text =
    \markup \draw-line #'(0 . -.5)
  \once \override TextSpanner.bound-details.right.padding = -0.65
  \once \override TextSpanner.dash-fraction = 0.4
  \once \override TextSpanner.dash-period = 1.3
  g16\startTextSpan
  b16 e g e b g\stopTextSpan
  e16 b g d
}
```




See also

Snippets: Section “Fretted string instruments” in *Snippets*, Section “Expressive marks” in *Snippets*.

Special note heads can be used to indicate dampened notes or harmonics. Harmonics are normally further explained with a text markup.

```
\relative {
  \clef "treble_8"
  \override NoteHead.style = #'harmonic-mixed
  d'8~\markup { \italic \fontsize #-2 "harm. 12" } <g b>4
}
```




```
music = \relative c' {
  \omit StringNumber

  <a \deadNote cis a'>4
    <b\3 \deadNote dis b'>
    <c\3 \deadNote e\2 c'>
    \deadNotesOn
    \tuplet 3/2 { g8 b e }
    \deadNotesOff

  <a, c e>1
}

\new StaffGroup <<
  \new Staff {
    \clef "treble_8"
    \music
  }
  \new TabStaff {
    \music
  }
}
```



Another playing technique (especially used on electric guitars) is called *palm mute*. The string is hereby partly muted by the palm of the striking hand (hence the name). LilyPond supports the notation of palm mute-style notes by changing the note head to a triangle shape.

```

\relative c, {
  \clef "G_8"
  \palmMuteOn
  e8~\markup { \musicglyph "noteheads.s2do" = palm mute }
  <e b' e> e
  \palmMuteOff
  e e \palmMute e e e |
  e8 \palmMute { e e e } e e e e |
  <\palmMute e b' e>8 \palmMute { e e e } <\palmMute e b' e>2
}

```



See also

Snippets: Section “Fretted string instruments” in *Snippets*.

Notation Reference: Section 1.4.1 [Special note heads], page 43, Section B.9 [Note head styles], page 920.

12.2.3 Indicating power chords

Power chords and their symbols can be engraved in chord mode or as chord constructs. As an exception, the fifth is specified in these chord names, whereas it is usually left out in other chords (e.g., major or minor triads).

```

ChordsAndSymbols = {
  \chordmode {
    e,,1:5
    a,,5.8
    \set TabStaff.restrainOpenStrings = ##t
    \set minimumFret = 8
    c,:5
    f,:5.8
  }
  \set minimumFret = 2
  \set restrainOpenStrings = ##f
  <a, e> <a cis' e'>
}

```

```

    <g d' g'>
  }
  \score {
    <<
      \new ChordNames {
        \ChordsAndSymbols
      }
      \new Staff {
        \clef "treble_8"
        \ChordsAndSymbols
      }
      \new TabStaff {
        \ChordsAndSymbols
      }
    >>
  }

```

Chord	String 1 (Treble)	String 2	String 3	String 4	String 5 (Bass)
E ⁵	8	8	8	8	0
A ⁵	8	8	8	8	0
C ⁵	8	8	8	8	0
F ⁵	8	8	8	8	0
A ⁵	8	8	8	8	0
A	8	8	8	8	0
G ⁵	8	8	8	8	0

See also

Music Glossary: Section “power chord” in *Music Glossary*.

Notation Reference: Section 15.1.3 [Extended and altered chords], page 509, Section 15.2.1 [Printing chord names], page 512.

Snippets: Section “Fretted string instruments” in *Snippets*.

12.3 Banjo

12.3.1 Banjo tablatures

LilyPond has basic support for the five-string banjo. When making tablatures for five-string banjo, use the banjo tablature format function to get correct fret numbers for the fifth string:


```

music = {
  g8 d' g'\5 a b g e d' |
  g4 d''8\5 b' a'\2 g'\5 e'\2 d' |
  g4
}

<<
  \new Staff \with { \omit StringNumber }
  { \clef "treble_8" \music }
  \new TabStaff \with {
    tablatureFormat = #fret-number-tablature-format-banjo
    stringTunings = #banjo-open-g-tuning
  }
  { \music }

```

>>



A number of common tunings for the five-string banjo are predefined: `banjo-open-g-tuning` (gDGBD), `banjo-c-tuning` (gCGBD), `banjo-modal-tuning` (gDGCD), `banjo-open-d-tuning` (aDF#AD), `banjo-open-dm-tuning` (aDFAD), `banjo-double-c-tuning` (gCGCD) and `banjo-double-d-tuning` (aDGDE).

These may be converted to four-string tunings using the `four-string-banjo` function:

```
\set TabStaff.stringTunings = #(four-string-banjo banjo-c-tuning)
```

See also

Installed Files: `ly/string-tunings-init.ly`.

Snippets: Section “Fretted string instruments” in *Snippets*.

12.4 Lute

12.4.1 Lute tablatures


LilyPond supports tablature for lute.

To get additional bass strings use `additionalBassStrings`, where the pitches of those strings are set. They will be printed below lowest line as: a, /a, //a, ///a, 4, 5, etc.

`fret-letter-tablature-format` for `tablatureFormat` should be used, probably also `fretLabels` for further customizing.

```
m = { f'4 d' a f d a, g, fis, e, d, c, \bar "|" }

\score {
  <<
    \new Staff { \clef bass \cadenzaOn \m }
    \new TabStaff \m
  >>
  \layout {
    \context {
      \Score
      tablatureFormat = #fret-letter-tablature-format
    }
    \context {
      \TabStaff
      stringTunings = \stringTuning <a, d f a d' f'>
      additionalBassStrings = \stringTuning <c, d, e, fis, g,>
      fretLabels = #("a" "b" "r" "d" "e" "f" "g" "h" "i" "k")
    }
  }
}
```



Known issues and warnings

Using `FretBoards` with `additionalBassStrings` is not supported and will yield unsatisfying results.

13 Percussion

13.1 Common notation for percussion

Rhythmic music is primarily used for percussion and drum notation, but it can also be used to show the rhythms of melodies.

13.1.1 References for percussion

- Some percussion may be notated on a rhythmic staff; this is discussed in Section 2.3.8 [Showing melody rhythms], page 98, and Section 6.1.1 [Instantiating new staves], page 241.
- MIDI output is discussed in a separate section; please see Chapter 24 [Creating MIDI output], page 651.

See also


Notation Reference: Section 2.3.8 [Showing melody rhythms], page 98, Section 6.1.1 [Instantiating new staves], page 241, Chapter 24 [Creating MIDI output], page 651.

Snippets: Section “Percussion” in *Snippets*.

13.1.2 Basic percussion notation


Percussion notes may be entered in `\drummode` mode, which is similar to the standard mode for entering notes. The simplest way to enter percussion notes is to use the `\drums` command, which creates the correct context and entry mode for percussion:

```
\drums {
  hihat4 hh bassdrum bd
}
```



This is shorthand for:

```
\new DrumStaff \drummode {
  hihat4 hh bassdrum bd
}
```



Each piece of percussion has a full name and an abbreviated name, and both can be used in input files. The full list of percussion note names may be found in Section B.15 [Percussion notes], page 930.

Note that the normal notation of pitches (such as `cis4`) in a `DrumStaff` context will cause an error message. Percussion clefs are added automatically to a `DrumStaff` context but they can also be set explicitly. Other clefs may be used as well.

```
\drums {
  \clef percussion
  bd4 4 4 4
  \clef treble
  hh4 4 4 4
}
```



There are a few issues concerning MIDI support for percussion instruments; for details please see Chapter 24 [Creating MIDI output], page 651.

See also

Notation Reference: Chapter 24 [Creating MIDI output], page 651, Section B.15 [Percussion notes], page 930.

Installed Files: `ly/drumpitch-init.ly`.

Snippets: Section “Percussion” in *Snippets*.

13.1.3 Drum rolls

Drum rolls are indicated with three slashes across the stem. For quarter notes or longer the three slashes are shown explicitly, eighth notes are shown with two slashes (the beam being the third), and drum rolls shorter than eighths have one stem slash to supplement the beams. This is achieved with the tremolo notation, as described in Section 4.2.2 [Tremolo repeats], page 211.

```
\drums {
  \time 2/4
  sn16 8 16 8 8:32 ~
  8 8 4:32 ~
  4 8 16 16
  4 r4
}
```



Sticking can be indicated by placing a markup for "R" or "L" above or below notes, as discussed in Section 36.1 [Direction and placement], page 772. The `staff-padding` property may be overridden to achieve a pleasing baseline.

```
\drums {
  \repeat unfold 2 {
    sn16^"L" 16^"R" 16^"L" 16^"L" 16^"R" 16^"L" 16^"R" 16^"R"
    \stemUp
    sn16_"L" 16_"R" 16_"L" 16_"L" 16_"R" 16_"L" 16_"R" 16_"R"
  }
}
```



See also

Notation Reference: Section 4.2.2 [Tremolo repeats], page 211.

Snippets: Section “Percussion” in *Snippets*.

13.1.4 Pitched percussion

Certain pitched percussion instruments (e.g., xylophone, vibraphone, and timpani) are written using normal staves. This is covered in other sections of the manual.

See also

Notation Reference: Chapter 24 [Creating MIDI output], page 651.

Snippets: Section “Percussion” in *Snippets*.

13.1.5 Percussion staves


A percussion part for more than one instrument typically uses a multi-line staff where each position in the staff refers to one piece of percussion. To typeset the music, the notes must be interpreted in `DrumStaff` and `DrumVoice` context.

```
up = \drummode {
  crashcymbal4 hihat8 halfopenhihat hh hh hh openhihat
}
down = \drummode {
  bassdrum4 snare8 bd r bd sn4
}
\new DrumStaff <<
  \new DrumVoice { \voiceOne \up }
  \new DrumVoice { \voiceTwo \down }
>>
```



The above example shows verbose polyphonic notation. The short polyphonic notation, described in Section “I’m hearing voices” in *Learning Manual*, can also be used. For example,


```
\new DrumStaff <<
  \drummode {
    bd4 sn4 bd4 sn4
    << {
      \*16 hh16
    } \ \ {
      bd4 sn4 bd4 sn4
    } >>
  }
>>
```




There are also other layout possibilities. To use these, set the property `drumStyleTable` in context `DrumVoice`. The following variables have been predefined:

`drums-style`

This is the default. It typesets a typical drum kit on a five-line staff:






The drum scheme supports six different toms. When there are fewer toms, simply select the toms that produce the desired result. For example, to get toms on the three middle lines you use tommh, tomml, and tomfh.


agostini-drums-style

Invented by the French percussionist Dante Agostini in 1965, this notation is commonly employed in France but also elsewhere.




weinberg-drums-style

Based on the work of Norman Weinberg, published in his *Guidelines for Drumset Notation*.




timbales-style


This typesets timbales on a two line staff:

**congas-style**


This typesets congas on a two line staff:

**bongos-style**

This typesets bongos on a two line staff:

**percussion-style**

To typeset all kinds of simple percussion on one-line staves:



Custom percussion styles may also be defined, as explained in Section 13.1.6 [Custom percussion staves], page 491.

See also

Learning Manual: Section “I’m hearing voices” in *Learning Manual*.

Notation Reference: Section 13.1.6 [Custom percussion staves], page 491.

Installed Files: ly/drumpitch-init.ly.

Snippets: Section “Percussion” in *Snippets*.

13.1.6 Custom percussion staves

Custom percussion styles may be defined, to which the `drumStyleTable` property may then be set. Existing notations may be redefined as an association list where each entry has to be comprised of four items: a name, the note head style (or ‘()’ to indicate the default), an articulation sign if needed (or #f if not), and the note head’s position on the staff. That list must then be converted into a Scheme hash table, using the `alist->hash-table` function.

The entry for an articulation can either be a script name symbol or a pair, with the first element the script name symbol and the second a forced-direction indicator for the script.

[In the following example, note the use of the quasi-quotation shorthand (‘~’) at the beginning of the Scheme expression instead of the standard quotation shorthand (‘’), which enables the unquote shorthand (‘,’) to evaluate the element it precedes.]

```

#(define mydrums `(
  (bassdrum      ()      #f      -1)
  (snare         ()      #f      0)
  (hihat         cross   #f      1)
  (halfopenhihat cross   halfopen 1)
  (pedalhihat    xcircle stopped 2)
  (splashhihat   xcircle (open . ,DOWN) 2)
  (lowtom        diamond #f      3)))

up = \drummode { hh8 hh hhho hhho hhp4 hhs }
down = \drummode { bd4 sn bd toml8 toml }

\new DrumStaff \with { drumStyleTable = #(alist->hash-table mydrums) }
<<
  \new DrumVoice { \voiceOne \up }
  \new DrumVoice { \voiceTwo \down }
>>

```



New names may also be added to these custom notations through the `drumPitchNames` variable, that may be redefined as an association list (or augmented by appending a new list to its existing value, as demonstrated below), but also through its individual entries. This also makes it possible to define aliases: alternate input shorthand for some notations.


```

drumPitchNames =
  #(append
    '((leftsnap . sidestick)
      (rightsnap . ridecymbal))
    drumPitchNames)

drumPitchNames.ls = #'sidestick
drumPitchNames.rs = #'ridecymbal

\drums {
  leftsnap4. rightsnap8 leftsnap4 rightsnap
  ls8 rs ls rs ls4 rs
}

```



In a similar manner, the `drumPitchTable` property associates a specific pitch (meaning a different instrument sound, as provided by available MIDI sound fonts) to each notation. That property needs to be defined as a hash table, which is again converted from an association list (stored by default as the `midiDrumPitches` variable). Redefining these associations is achieved as explained above, either by defining an entire association list or through individual entries. The following example demonstrates how to create a whole notation set with its own input syntax, custom notations and corresponding MIDI output.

```

drumPitchNames.dbass      = #'dbass
drumPitchNames.dba        = #'dbass % 'db is in use already
drumPitchNames.dbassmute  = #'dbassmute
drumPitchNames.dbm        = #'dbassmute
drumPitchNames.do         = #'dopen
drumPitchNames.dopenmute  = #'dopenmute
drumPitchNames.dom        = #'dopenmute
drumPitchNames.dslap      = #'dslap
drumPitchNames.ds         = #'dslap
drumPitchNames.dslapmute  = #'dslapmute
drumPitchNames.dsm        = #'dslapmute

#(define djembe-style
  '((dbass      ()   #f      -2)
    (dbassmute  ()   stopped -2)
    (dopen      ()   #f      0)
    (dopenmute  ()   stopped 0)
    (dslap      ()   #f      2)
    (dslapmute  ()   stopped 2)))

midiDrumPitches.dbass      = g
midiDrumPitches.dbassmute  = fis
midiDrumPitches.dopen      = a
midiDrumPitches.dopenmute  = gis
midiDrumPitches.dslap      = b
midiDrumPitches.dslapmute  = ais

test = \drummode { dba4 do ds dbm dom dsm }

\score {
  \new DrumStaff \with {
    \override StaffSymbol.line-count = 3
    instrumentName = "Djembe "
    drumStyleTable = #(alist->hash-table djembe-style)
    drumPitchTable = #(alist->hash-table midiDrumPitches)
  } {
    \time 3/4
    \test
  }
  \layout {}
  \midi {}
}

```



See also

Installed Files: `ly/drumpitch-init.ly`.


Snippets: Section “Percussion” in *Snippets*.

Internals Reference: Section “DrumStaff” in *Internals Reference*, Section “DrumVoice” in *Internals Reference*.

13.1.7 Ghost notes

Also known as dead, muted, silenced or false notes; ghost notes can be created using the `\parenthesize` command, see Section 7.1.8 [Parentheses], page 295.

```
\new DrumStaff <<
  \new DrumVoice = "1" { s1 }
  \new DrumVoice = "2" { s1 }
  \drummode {
    <<
    {
      hh8[ 8] <hh sn> hh16
      \parenthesize sn hh
      \parenthesize sn hh8 <hh sn> hh
    } \\
    {
      bd4 r4 bd8 8 r8 bd
    }
  }
  >>
}
```



See also

Notation Reference: Section 7.1.8 [Parentheses], page 295.

Snippets: Section “Percussion” in *Snippets*.

14 Wind instruments

Moderato assai

Flauto I,II

Flauto III

Gr.Fl.

p *mf* *sf* *mf*

This section includes elements of music notation that arise when writing specifically for wind instruments.

14.1 Common notation for wind instruments

This section discusses notation common to most wind instruments.

14.1.1 References for wind instruments

Many notation issues for wind instruments pertain to breathing and tonguing:

- Breathing can be specified by rests or Section 3.2.3 [Breath marks], page 175.
- Legato playing is indicated by Section 3.2.1 [Slurs], page 170.
- Different types of tonguings, ranging from legato to non-legato to staccato are usually shown by articulation marks, sometimes combined with slurs, see Section 3.1.1 [Articulations and ornamentations], page 155, and Section B.13 [List of articulations], page 927.
- Flutter tonguing is usually indicated by placing a tremolo mark and a text markup on the note. See Section 4.2.2 [Tremolo repeats], page 211.

Other aspects of musical notation that can apply to wind instruments:

- Many wind instruments are transposing instruments, see Section 1.3.4 [Instrument transpositions], page 30.
- Slide glissandi are characteristic of the trombone, but other winds may perform keyed or valved glissandi. See Section 3.3.1 [Glissando], page 176.
- Harmonic series glissandi, which are possible on all brass instruments but common for French Horns, are usually written out as Section 2.6.1 [Grace notes], page 147.
- Pitch inflections at the end of a note are discussed in Section 3.2.4 [Falls and doits], page 176.
- Key slaps or valve slaps are often shown by the cross style of Section 1.4.1 [Special note heads], page 43.
- Woodwinds can overblow low notes to sound harmonics. These are shown by the flageolet articulation. See Section B.13 [List of articulations], page 927.
- The use of brass mutes is usually indicated by a text markup, but where there are many rapid changes it is better to use the stopped and open articulations. See Section 3.1.1 [Articulations and ornamentations], page 155, and Section B.13 [List of articulations], page 927.
- Stopped horns are indicated by the stopped articulation. See Section 3.1.1 [Articulations and ornamentations], page 155.

See also

Notation Reference: Section 3.2.3 [Breath marks], page 175, Section 3.2.1 [Slurs], page 170, Section 3.1.1 [Articulations and ornamentations], page 155, Section B.13 [List of articulations], page 927, Section 4.2.2 [Tremolo repeats], page 211, Section 1.3.4 [Instrument transpositions], page 30, Section 3.3.1 [Glissando], page 176, Section 2.6.1 [Grace notes], page 147, Section 3.2.4 [Falls and doits], page 176, Section 1.4.1 [Special note heads], page 43.

Snippets: Section “Wind instruments” in *Snippets*.

14.1.2 Fingerings

All wind instruments other than the trombone require the use of several fingers to produce each pitch. Some fingering examples are shown in the snippets below.

Woodwind diagrams can be produced and are described in Section 14.3.1 [Woodwind diagrams], page 500.


Selected snippets

Fingering symbols for wind instruments

Special symbols can be achieved by combining existing glyphs, which is useful for wind instruments.

```
lineup =
  \tweak outside-staff-padding #0
  \tweak staff-padding #0
  \tweak padding #0.2
  \tweak parent-alignment-X #CENTER
  \tweak self-alignment-X #CENTER
  \etc

\relative c' {
  g\open
  g\lineup ^\markup \combine
    \musicglyph "scripts.open"
    \musicglyph "scripts.tenuto"
  g\lineup ^\markup \combine
    \musicglyph "scripts.open"
    \musicglyph "scripts.stopped"
  g\stopped
}
```



Recorder fingering chart

The following example demonstrates how fingering charts for wind instruments can be realized.

% range chart for paetzold contrabass recorder

```
centermarkup = {
  \once \override TextScript.self-alignment-X = #CENTER
  \once \override TextScript.X-offset = #(lambda (g)
    (+ (ly:self-alignment-interface::centered-on-x-parent g)
```

```

        (ly:self-alignment-interface::x-aligned-on-self g)))
    }

    \new Staff \with {
      \remove "Time_signature_engraver"
      \omit Stem
      \omit Flag
      \consists "Horizontal_bracket_engraver"
    } {
      \clef bass
      \set Score.timing = ##f

      f,1*1/4 \glissando

      \clef violin
      gis'1*1/4

      a'4^\markup "1)"

      \centermarkup
      \once \override TextScript.padding = 2
      bes'1*1/4_\markup \override #'(baseline-skip . 1.7) \column {
        \fontsize #-5
        \slashed-digit #0 \finger 1 \finger 2
        \finger 3 \finger 4 \finger 5 \finger 6 \finger 7 }

      b'1*1/4

      c''4^\markup "1)"


      cis''1*1/4

      deh''1*1/4

      \centermarkup
      \once \override TextScript.padding = 2
      \once \override Staff.HorizontalBracket.direction = #UP
      e''1*1/4_\markup \override #'(baseline-skip . 1.7) \column {
        \fontsize #-5
        \slashed-digit #0 \finger 1 \finger 2
        \finger 4 \finger 5 } \startGroup

      f''1*1/4^\markup "2)" \stopGroup
    }

```

See also

Notation Reference: Section 14.3.1 [Woodwind diagrams], page 500.

Snippets: Section “Wind instruments” in *Snippets*.

14.2 Bagpipes

This section discusses notation common bagpipes.

14.2.1 Bagpipe definitions

LilyPond contains special definitions for Scottish, Highland Bagpipe music; to use them, add

```
\include "bagpipe.ly"
```

to the top of your input file. This lets you add the special grace notes common to bagpipe music with short commands. For example, you could write `\taor` instead of

```
\grace { \small G32[ d G e] }
```

`bagpipe.ly` also contains pitch definitions for the bagpipe notes in the appropriate octaves, so you do not need to worry about `\relative` or `\transpose`.

```
\include "bagpipe.ly"
{ \grg G4 \grg a \grg b \grg c \grg d \grg e \grg f \grA g A }
```



Bagpipe music nominally uses the key of D Major (even though that isn’t really true). However, since that is the only key that can be used, the key signature is normally not written out. To set this up correctly, always start your music with `\hideKeySignature`. If you for some reason want to show the key signature, you can use `\showKeySignature` instead.

Some modern music use cross-fingering on c and f to flatten those notes. This can be indicated by c-flat or f-flat. Similarly, the *Piobaireachd* high g can be written g-flat when it occurs in light music.

See also

Snippets: Section “Wind instruments” in *Snippets*.

14.2.2 Bagpipe example

This is what the well known tune Amazing Grace looks like in bagpipe notation.

```

\include "bagpipe.ly"
\layout {
  indent = 0.0\cm
  \context { \Score \remove Bar_number_engraver }
}

\header {
  title = "Amazing Grace"
  meter = "Hymn"
  arranger = "Trad. arr."
}

{
  \hideKeySignature
  \time 3/4
  \grg \partial 4 a8. d16
  \slurd d2 \grg f8[ e32 d16.]
  \grg f2 \grg f8 e
  \thrwd d2 \grg b4
  \grG a2 \grg a8. d16
  \slurd d2 \grg f8[ e32 d16.]
  \grg f2 \grg e8. f16
  \dblA A2 \grg A4
  \grg A2 f8. A16
  \grg A2 \hdbl f8[ e32 d16.]
  \grg f2 \grg f8 e
  \thrwd d2 \grg b4
  \grG a2 \grg a8. d16
  \slurd d2 \grg f8[ e32 d16.]
  \grg f2 e4
  \thrwd d2.
  \slurd d2
  \bar "|."
}

```

Amazing Grace

Hymn

Trad. arr.



See also

Snippets: Section “Wind instruments” in *Snippets*.

14.3 Woodwinds

This section discusses notation specifically for woodwind instruments.


14.3.1 Woodwind diagrams

Woodwind diagrams can be used to indicate the fingering to be used for specific notes and are available for the following instruments:

- piccolo
- flute
- oboe
- clarinet
- bass clarinet
- saxophone
- bassoon
- contrabassoon

Woodwind diagrams are created as markups:

```
c''1^\markup {
  \woodwind-diagram #'piccolo #'((lh . (gis))
                                   (cc . (one three))
                                   (rh . (ees)))
}
```




Keys can be open, partially-covered, ring-depressed, or fully covered. The angle of partially-covered keys can be specified:

```
\markup \override #'(baseline-skip . 22) \column {
  \override #'(baseline-skip . 2.5) \fill-line {
    ""
    \raise #1.2 \center-column { "one" "quarter" }
    \raise #1.2 \center-column { "one" "half" }
    \raise #1.2 \center-column { "three" "quarter" }
    "ring"
    "full"
    \raise #1.2 \center-column { "one half," "vertical" }
    ""
  }
  \fill-line {
    ""
```

```

\woodwind-diagram #'flute #'((cc . (one1q))
                        (lh . ()))
                        (rh . ()))
\woodwind-diagram #'flute #'((cc . (one1h))
                        (lh . ()))
                        (rh . ()))
\woodwind-diagram #'flute #'((cc . (one3q))
                        (lh . ()))
                        (rh . ()))
\woodwind-diagram #'flute #'((cc . (oneR))
                        (lh . ()))
                        (rh . ()))
\woodwind-diagram #'flute #'((cc . (oneF two))
                        (lh . ()))
                        (rh . ()))
\override #'(woodwind-diagram-details . ((fill-angle . 90)))
\woodwind-diagram #'flute #'((cc . (one1h))
                        (lh . ()))
                        (rh . ()))
""
}
}

```



Trills are indicated as shaded keys, or in non-graphical mode, as either circled (the default) or shaded text:

```


\markup {
  \override #'(baseline-skip . 20)
  \override #'(line-width . 50)
  \column {
    \fill-line {
      ""
      "standard"
      "circled"
      "shaded"
      ""
    }
  }
  \fill-line {
    ""
    \woodwind-diagram #'bass-clarinet
                        #'((cc . (threeT four))
                          (lh . ()))
                          (rh . (b fis)))
  }
}

```

```

\override #'(graphical . #f)
\woodwind-diagram #'bass-clarinet
      #'((cc . (threeT four))
        (lh . ()))
      (rh . (b fisT)))
\override #'(graphical . #f)
\override #'(woodwind-diagram-details
  . ((text-trill-circled . #f)))
\woodwind-diagram #'bass-clarinet
      #'((cc . (threeT four))
        (lh . ()))
      (rh . (b fisT)))
""
}
}
}

```



A variety of trills can be displayed:

```


\markup {
  \override #'(baseline-skip . 22)
  \column {
    \override #'(baseline-skip . 2.5) \fill-line {
      ""
      \center-column { "one quarter" "to ring" }
      \center-column { "ring" "to shut" }
      \center-column { "ring" "to open" }
      \center-column { "open" "to shut" }
      \center-column { "one quarter to" "three quarters" }
      ""
    }
  }
  \fill-line {
    ""
    \woodwind-diagram #'flute #'((cc . (one1qTR))
      (lh . ()))
      (rh . ()))
    \woodwind-diagram #'flute #'((cc . (oneTR))
      (lh . ()))
      (rh . ()))
    \woodwind-diagram #'flute #'((cc . (oneRT))
      (lh . ()))
      (rh . ()))
    \woodwind-diagram #'flute #'((cc . (oneT))

```

```

                                (lh . ())
                                (rh . ()))
\woodwind-diagram #'flute #'((cc . (one1qT3q))
                                (lh . ())
                                (rh . ()))
""
}
}
}
}

```



The list of all possible keys and settings for a given instrument can be displayed on the console using `$(print-keys-verbose 'flute)` or in the log file using `$(print-keys-verbose 'flute (current-error-port))`, although they will not show up in the music output.

Creating new diagrams is possible, although this will require Scheme ability and may not be accessible to all users. The patterns for the diagrams are in files `scm/define-woodwind-diagrams.scm` and `scm/display-woodwind-diagrams.scm`.

Selected snippets

Woodwind diagrams listing

The following music shows all of the woodwind diagrams currently defined in LilyPond.

```

\relative c' {
  \textLength0n
  c1^\markup \center-column { "tin whistle"
    " "
    \woodwind-diagram #'tin-whistle #'() }
  c1^\markup \center-column { "piccolo"
    " "
    \woodwind-diagram #'piccolo #'() }
  c1^\markup \center-column { "flute"
    " "
    \woodwind-diagram #'flute #'() }
  c1^\markup \center-column { "oboe"
    " "
    \woodwind-diagram #'oboe #'() }
  c1^\markup \center-column { "clarinet"
    " "
    \woodwind-diagram #'clarinet #'() }
  \break

  c1^\markup \center-column { "bass clarinet"
    " "

```

```

\woodwind-diagram #'bass-clarinet #'() }
c1~\markup \center-column { "saxophone"
" "

\woodwind-diagram #'saxophone #'() }
c1~\markup \center-column { "bassoon"
" "


\woodwind-diagram #'bassoon #'() }
c1~\markup \center-column { "contrabassoon"
" "

\woodwind-diagram #'contrabassoon #'() }

}

\paper {
  system-system-spacing.padding = 5
}

```



Graphical and text woodwind diagrams


In many cases, the keys other than the central column can be displayed by key name as well as by graphical means.

```

\relative c'' {
  \textLengthOn
  c1^\markup
    \woodwind-diagram #'piccolo
      #'((cc . (one three))
        (lh . (gis))
        (rh . (ees)))

  c^\markup
    \override #'(graphical . #f)
    \woodwind-diagram #'piccolo
      #'((cc . (one three))
        (lh . (gis))
        (rh . (ees)))
}

```



Changing the size of woodwind diagrams


The size and thickness of woodwind diagrams can be changed.

```

\relative c'' {
  \textLengthOn
  c1^\markup
    \woodwind-diagram #'piccolo #'()

  c^\markup \override #'(size . 1.5)
    \woodwind-diagram #'piccolo #'()
  c^\markup \override #'(thickness . 0.15)
    \woodwind-diagram #'piccolo #'()
}

```

Woodwind diagrams key lists

The snippet below produces a list of all possible keys and key settings for woodwind diagrams as defined in `scm/define-woodwind-diagrams.scm`. The list gets written to `stderr` but is not shown in the music. If output to `stdout` is wanted instead, omit the code `(current-error-port)` from the commands.

```
#(print-keys-verbose 'piccolo (current-error-port))
#(print-keys-verbose 'flute (current-error-port))
#(print-keys-verbose 'flute-b-extension (current-error-port))
#(print-keys-verbose 'tin-whistle (current-error-port))
#(print-keys-verbose 'oboe (current-error-port))
#(print-keys-verbose 'clarinet (current-error-port))
#(print-keys-verbose 'bass-clarinet (current-error-port))
#(print-keys-verbose 'low-bass-clarinet (current-error-port))
#(print-keys-verbose 'saxophone (current-error-port))
#(print-keys-verbose 'soprano-saxophone (current-error-port))
#(print-keys-verbose 'alto-saxophone (current-error-port))
#(print-keys-verbose 'tenor-saxophone (current-error-port))
#(print-keys-verbose 'baritone-saxophone (current-error-port))
#(print-keys-verbose 'bassoon (current-error-port))
#(print-keys-verbose 'contrabassoon (current-error-port))
```

```
\score {c''1}
```



See also

Installed Files: `scm/define-woodwind-diagrams.scm`,
`scm/display-woodwind-diagrams.scm`.

Snippets: Section “Wind instruments” in *Snippets*.

Internals Reference: Section “TextScript” in *Internals Reference*, Section “instrument-specific-markup-interface” in *Internals Reference*.

15 Chord notation

1. Fair is the sun-shine, Fair-er the moon-light
2. Fair are the meadows, Fair-er the wood-land,

And all the stars in heav'n above;
Robed in the flowers of blooming spring;

Chords can be entered either as normal notes or in chord mode and displayed using a variety of traditional European chord naming conventions. Chord names and figured bass notation can also be displayed.

15.1 Chord mode

Chord mode is used to enter chords using an indicator of the chord structure, rather than the chord pitches.

15.1.1 Chord mode overview

Chords can be entered as simultaneous music, as discussed in Section 5.1.1 [Chorded notes], page 215.


Chords can also be entered in “chord mode”, which is an input mode that focuses on the structures of chords in traditional European music, rather than on specific pitches. This is convenient for those who are familiar with using chord names to describe chords. More information on different input modes can be found at Chapter 19 [Input modes], page 587.

```
\chordmode { c1 g a g c }
```

Chords entered using chord mode are music elements, and can be transposed just like chords entered using simultaneous music. `\chordmode` is absolute, as `\relative` has no effect on chordmode blocks. However, in `\chordmode` the absolute pitches are one octave higher than in note mode.

Chord mode and note mode can be mixed in sequential music:

```
\relative {
  <c' e g>2 <g b d>
  \chordmode { c2 f }
  <c e g>2 <g' b d>
  \chordmode { f2 g }
}
```



See also

Music Glossary: Section “chord” in *Music Glossary*.

Notation Reference: Section 5.1.1 [Chorded notes], page 215, Chapter 19 [Input modes], page 587.

Snippets: Section “Chord notation” in *Snippets*.

Known issues and warnings

Predefined shorthands for articulations and ornaments cannot be used on notes in chord mode, see Section 3.1.1 [Articulations and ornamentations], page 155.

15.1.2 Common chords

Major triads are entered by including the root and an optional duration:

```
\chordmode { c2 f4 g }
```




Minor, augmented, and diminished triads are entered by placing : and a quality modifier string after the duration:

```
\chordmode { c2:m f4:aug g:dim }
```



Seventh chords can be created:

```
\chordmode { c1:7 c:m7 c:maj7 c:dim7 c:aug7 }
```




The table below shows the actions of the quality modifiers on triads and seventh chords. The default seventh step added to chords is a minor or flatted seventh, which makes the dominant seventh the basic seventh chord. All alterations are relative to the dominant seventh. A more complete table of modifier usage is found at Section B.2 [Common chord modifiers], page 888.

Modifier	Action	Example

None

The default action; produces a major triad.



m, m7

The minor chord. This modifier lowers the 3rd.




dim, dim7

The diminished chord. This modifier lowers the 3rd, 5th and (if present) the 7th step.




aug

The augmented chord. This modifier raises the 5th step.



maj, maj7

The major 7th chord. This modifier adds a raised 7th step. The 7 following maj is optional. Do NOT use this modifier to create a major triad.



See also

Notation Reference: Section B.2 [Common chord modifiers], page 888, Section 15.1.3 [Extended and altered chords], page 509.

Snippets: Section “Chord notation” in *Snippets*.

Known issues and warnings


Only one quality modifier should be used per chord, typically on the highest step present in the chord. Chords with more than quality modifier will be parsed without an error or warning, but the results are unpredictable. Chords that cannot be achieved with a single quality modifier should be altered by individual pitches, as described in Section 15.1.3 [Extended and altered chords], page 509.

15.1.3 Extended and altered chords

Chord structures of arbitrary complexity can be created in chord mode. The modifier string can be used to extend a chord, add or remove chord steps, raise or lower chord steps, and add a bass note or create an inversion.

The first number following the `:` is taken to be the extent of the chord. The chord is constructed by sequentially adding thirds to the root until the specified number has been reached. Note that the seventh step added as part of an extended chord will be the minor or flatted seventh, not the major seventh. If the extent is not a third (e.g., 6), thirds are added up to the highest third below the extent, and then the step of the extent is added. The largest possible value for the extent is 13. Any larger value is interpreted as 13.


```
\chordmode {
  c1:2 c:3 c:4 c:5
  c1:6 c:7 c:8 c:9
  c1:10 c:11 c:12 c:13
  c1:14
}
```



As a special exception, `c:5` produces a ‘power chord’ only consisting of root and fifth.

Since an unaltered 11 does not sound good when combined with an unaltered 13, the 11 is removed from a `:13` major chord (unless it is added explicitly).

```
\chordmode {
  c1:13 c:13.11 c:m13
}
```



Individual steps can be added to a chord. Additions follow the extent and are prefixed by a dot (.). The basic seventh step added to a chord is the minor or flatted seventh, rather than the major seventh.

```
\chordmode {
  c1:3.5.6 c:3.7.8 c:3.6.13
}
```



Added steps can be as high as desired.

```
\chordmode {
  c4:3.5.15 c:3.5.20 c:3.5.25 c:3.5.30
}
```



Added chord steps can be altered by suffixing a - or + sign to the number. To alter a step that is automatically included as part of the basic chord structure, add it as an altered step.

```
\chordmode {
  c1:7+ c:5+.3- c:3-.5-.7-
}
```



Following any steps to be added, a series of steps to be removed is introduced in a modifier string with a prefix of `^`. If more than one step is to be removed, the steps to be removed are separated by `.` following the initial `^`.

```
\chordmode {
  c1^3 c:7^5 c:9^3 c:9^3.5 c:13.11^3.7 c:m13^11
}
```




The modifier `sus` can be added to the modifier string to create suspended chords. This removes the 3rd step from the chord. Append either 2 or 4 to add the 2nd or 4th step to the chord. When `sus` is followed by either a 2nd or 4th step, it is equivalent to `^3`, otherwise to `sus4`, namely 5.4.

```
\chordmode {
  c1:sus c:sus2 c:sus4 c:5.4
}
```




Added bass notes (putting a pitch other than the root on the bottom of the chord) can be specified by appending `/pitch` to the chord.

```
\chordmode {
  c'1 c'/e c'/f
}
```



If the added pitch is already part of the chord, this may be used to print chord inversions, in which case the pitch is not added but merely moved to the bottom of the chord. It may however be treated as an added note (and thus printed twice), by using the syntax `/+pitch`.

```
\chordmode {
  c'1 c'/g c'/+e
}
```



Automatic chord inversions and voicings are demonstrated in Section 15.1.4 [Chord inversions and specific voicings], page 512.

Chord modifiers that can be used to produce a variety of standard chords are shown in Section B.2 [Common chord modifiers], page 888.

See also

Notation Reference: Section 15.1.4 [Chord inversions and specific voicings], page 512, Section B.2 [Common chord modifiers], page 888.

Snippets: Section “Chord notation” in *Snippets*.

Known issues and warnings

Later entries for a given step override earlier entries. The following simply produces the augmented chord, since 5+ is interpreted last.


```
\chordmode { c1:3.5.5-.5+ }
```



15.1.4 Chord inversions and specific voicings

In addition to chord modifiers and added bass notes, various functions may be used to automatically print chords in a specific inversion or voicing – for example the so-called ‘drop 2’ voicing commonly used in jazz music.

```
\chordmode {
  \dropNote 2 {
    c2:maj7 d:m7
  }
  \invertChords 1 d1:maj7
}
```



Unlike added bass notes shown in Section 15.1.3 [Extended and altered chords], page 509, this only affects the way chords are printed on a staff, and not chord names written with letters. Furthermore, these functions may be used not only in chord mode but also with `<...>` chords constructs explained in Section 5.1.1 [Chorded notes], page 215.

See also

Notation Reference: Section 15.1.3 [Extended and altered chords], page 509, Section 5.1.1 [Chorded notes], page 215.

Snippets: Section “Chord notation” in *Snippets*.

15.2 Displaying chords

Chords can be displayed by name, in addition to the standard display as notes on a staff.

15.2.1 Printing chord names

Chord names are printed in the ChordNames context:

```
\new ChordNames {
  \chordmode {
    c2 f4. g8
  }
}
```


C F G

Chords can be entered as simultaneous notes or through the use of chord mode. The displayed chord name will be the same, regardless of the mode of entry, unless there are inversions or added bass notes:

```

chordmusic = \relative {
  <c' e g>2 <f bes c>
  <f c' e g>1
  \chordmode {
    c2 f:sus4 c1:/f
  }
}
<<
  \new ChordNames {
    \chordmusic
  }
  {
    \chordmusic
  }
>>

```



When passed to a ChordNames context, rests (including multi-measure rests) cause the text “N.C.” (*No Chord*) to be displayed.

```

myChords = \chordmode {
  c1
  r1
  g1
  R1
  c1
}
<<
  \new ChordNames \myChords
  \new Staff \myChords
>>

```




It is also possible to display “N.C.” with a bass note by forcing the chord to be a single note identical to the bass.

```

myChords = \chordmode {
  c1
  b1:1/b
  a,1
}
<<
  \new ChordNames \myChords
  \new Staff \myChords
>>

```

`\chords { ... }` is a shortcut notation for `\new ChordNames \chordmode { ... }`.

```
\chords {
  c2 f4.:m g8:maj7
}
```

C Fm G^Δ

```
\new ChordNames {
  \chordmode {
    c2 f4.:m g8:maj7
  }
}
```

C Fm G^Δ


Selected snippets

Showing chords at changes

By default, every chord entered is printed. This behavior can be modified so that chord names are printed only at the start of lines or when the chord changes.

```
harmonies = \chordmode {
  c'1:m c:m \break
  c'1:m c:m d
}


<<
\new ChordNames {
  \set chordChanges = ##t
  \harmonies
}
\new Staff {
  \harmonies
}
>>
```



Simple lead sheet

When put together, chord names, a melody, and lyrics form a lead sheet.


```
<<
\chords { c2 g:sus4 f e }
\new Staff \relative c'' {
  a4 e c8 e r4
  b2 c4( d)
}
\addlyrics { One day this shall be free __ }
>>
```



Customizing the no-chord symbol

By default, rests in a ChordNames context cause the text “N.C.” to be printed. This markup can be customized by setting the noChordSymbol context property.

```
<<
\chords {
  R1
  \set noChordSymbol = "----"
  R1
  \set noChordSymbol = \markup \italic "Ssh!"
  R1
}
{
  R1*3
}
>>
```



See also

Music Glossary: Section “chord” in *Music Glossary*.

Notation Reference: Section 5.2.6 [Writing music in parallel], page 237.

Snippets: Section “Chord notation” in *Snippets*.

Internals Reference: Section “ChordNames” in *Internals Reference*, Section “ChordName” in *Internals Reference*, Section “Chord_name_engraver” in *Internals Reference*, Section “Volta_engraver” in *Internals Reference*, Section “Bar_engraver” in *Internals Reference*.

Known issues and warnings

Chords containing inversions or altered bass notes are not named properly if entered using simultaneous music.

15.2.2 Customizing chord names


There is no unique system for naming chords. Different musical traditions use different names for the same set of chords. There are also different symbols displayed for a given chord name. The names and symbols displayed for chord names are customizable.

The basic chord name layout is a system for Jazz music proposed by Klaus Ignatzek (see Section “Literature list” in *Essay*). (Other chord naming systems may be implemented through Scheme functions, see Section “Chord names alternative” in *Snippets* for an example.) A list of common jazz chords notations can be found in Section B.1 [Chord name chart], page 888.

The default naming system may be tweaked easily in a number of ways. To begin with, predefined commands allow the display of different languages for the root pitch. These include `\germanChords`, `\italianChords`, `\frenchChords`, and `\englishChords`.

A special case is `\semiGermanChords`, which is intended for educational purposes in German-speaking countries while addressing an international audience. It displays letter B with a flat for German pitch B; everything else is identical to `\germanChords`.

default	E/D	Cm	B/B	B [#] /B [#]	B ^b /B ^b	B ^{bb} /B ^{bb}
German	E/d	Cm	H/h	H [#] /his	B/b	H ^{bb} /heses
semi-German	E/d	Cm	H/h	H [#] /his	B ^b /b	H ^{bb} /heses
Italian	Mi/Re	Do m	Si/Si	Si [#] /Si [#]	Si ^b /Si ^b	Si ^{bb} /Si ^{bb}
French	Mi/Ré	Do m	Si/Si	Si [#] /Si [#]	Si ^b /Si ^b	Si ^{bb} /Si ^{bb}
English	E/D	Cm	B/B	B [#] /B [#]	B ^b /B ^b	B ^{bb} /B ^{bb}



German songbooks may indicate minor chords as lowercase letters, without any ‘m’ suffix. This can be obtained by setting the `chordNameLowercaseMinor` property:

```
\chords {
  \set chordNameLowercaseMinor = ##t
  c2 d:m e:m f
}
```

C d e F

The chord name display can also be tuned by adjusting the following properties.

`chordRootNamer`

The default setup is to print the chord name as a letter for the root with an optional alteration. The transformation from pitch to letter is done by this function. Special note names (for example, the German ‘H’ for a B-chord) can be produced by storing a different function in this property.

`majorSevenSymbol`

This property holds the markup object that identifies a major 7 chord, to be printed right after the chord root. Predefined values are `whiteTriangleMarkup` (the default) and `blackTriangleMarkup`.

`additionalPitchPrefix`

If the chord name contains additional pitches, they normally have the prefix ‘add’, which is LilyPond’s default. This prefix can be changed or suppressed.

```
\new ChordNames {
  <c e g d'>    % add9
  \set additionalPitchPrefix = ""
  <c e g d'>    % add9
}
```

C^{add9} C^9

chordNoteNamer

If a chord name contains additional pitches other than the root (e.g., an added bass note), the function assigned to this property is used to print them. If not set or set to '()', use the function assigned to chordRootNamer instead.

As an example, the function chord-name:german-lowercase-name-markup is used by \germanChords to print bass notes in lower case.

chordNameSeparator

Different parts of a chord name are normally separated by a small amount of horizontal space. By setting chordNameSeparator, you can use any desired markup as a separator. This does not affect the separator between a chord and its bass note; to customize that, use slashChordSeparator.

```
\chords {
  c4:7.9- c:7.9-/g
  \set chordNameSeparator = \markup { "/" }
  \break
  c4:7.9- c:7.9-/g
}
```

$C^{7\flat9}$ $C^{7\flat9}/G$

$C^{7/b9}$ $C^{7/b9}/G$

slashChordSeparator

Chords can be played over a bass note other than the conventional root of the chord. These are known as “inversions” or “slash chords”, because the default way of notating them is with a forward slash between the main chord and the bass note. Therefore the value of slashChordSeparator defaults to a forward slash, but you can change it to other markup.

```
\chords {
  c4:7.9- c:7.9-/g
  \set slashChordSeparator = \markup { " over " }
  \break
  c4:7.9- c:7.9-/g
}
```

$C^{7\flat9}$ $C^{7\flat9}/G$

$C^{7\flat9}$ $C^{7\flat9}$ over G

chordNameExceptions

This property is a list of pairs. The first item in each pair is a set of pitches used to identify the steps present in the chord. The second item is a markup that follows the chordRootNamer output to create the chord name.

minorChordModifier

Minor chords are often denoted via an ‘m’ suffix to the right of the root of the chord (this is LilyPond’s default). However, some idioms prefer other suffixes, such as a minus sign.

```
\chords {
  c4:min f:min7
  \set minorChordModifier = \markup { "-" }
  \break
  c4:min f:min7
}
```

Cm Fm⁷

C- F-⁷

chordPrefixSpacer

The modifier for minor chords as determined by `minorChordModifier` is by default printed immediately to the right of the chord root. Some whitespace can be placed between the root and the modifier by setting `chordPrefixSpacer` (used, for example, in `\italianChords`). No whitespace is inserted if the root is altered.

Predefined commands

`\whiteTriangleMarkup`, `\blackTriangleMarkup`, `\germanChords`, `\semiGermanChords`,
`\italianChords`, `\frenchChords`, `\englishChords`.

Selected snippets***Chord name exceptions***

The property `chordNameExceptions` stores a list of chord name exceptions to handle cases either not covered or handled incorrectly.

The default chord names used by LilyPond follow the rules as given in Klaus Ignatzek’s book “Die Jazzmethode für Klavier 1”; the algorithm to convert chords to chord names can be found in file `scm/chord-ignatzek-names.scm`. Additional rules are given as chord exceptions and stored in the variable `ignatzekExceptions`, as set up in file `ly/chord-modifiers-init.ly`.

This snippet modifies these exceptions in three steps.

1. Set up some music with chords and associated markup. By convention, the root (i.e., the lowest note) of each chord should have pitch `c`.
2. Call Scheme function `sequential-music-to-chord-exceptions` to create a new list of exceptions, then concatenate it with the existing ones. Since `ignatzekExceptions` is set up with this function’s second parameter set to `#t` (to ignore the root of the chords), we have to do the same.
3. Register the new exception list.

```
% Step 1: Define music with chords and markup for maj9 and 6(add9).
```

```
chExceptionMusic = {
  <c e g b d'>-\markup { \super "maj9" }
  <c e g a d'>-\markup { \super "6(add9)" }
}
```

```
% Step 2: Create extended exception list.
```

```
chExceptions =
```

```

#(append (sequential-music-to-chord-exceptions chExceptionMusic #t)
          ignatzekExceptions)

theMusic = \chordmode {
  g1:maj9 g1:6.9
  % Step 3: Register extended exception list.
  \set chordNameExceptions = #chExceptions
  g1:maj9 g1:6.9
}

<<
  \new ChordNames \theMusic
  \new Voice \theMusic
>>

\layout {
  line-width = 10\cm
  ragged-right = ##f
}

```



Chord name *major7*

The layout of the major 7 can be tuned with the `majorSevenSymbol` context property.

```

\chords {
  c:7+
  \set majorSevenSymbol = \markup { j7 }
  c:7+
}

```

$C^{\Delta} C^{j7}$

Adding bar lines to *ChordNames* context

To add bar line indications in the *ChordNames* context, add the `Bar_engraver`.

```

\new ChordNames \with {
  \override BarLine.bar-extent = #'(-1 . 3)
  \consists "Bar_engraver"
}

\chordmode {
  f1:maj7 f:7 bes:7
}

```

$F^{\Delta} \mid F^7 \mid B\flat^7 \mid$


Volta below chords

By adding the `Volta_engraver` to the relevant staff, volte can be put below chords.

```

\score {
  <<
    \chords { c1 c1 }
    \new Staff \with { \consists "Volta_engraver" }
    {
      \repeat volta 2 { c'1 \alternative { c' } }
    }
  >>
  \layout {
    \context {
      \Score
      \remove "Volta_engraver"
    }
  }
}

```



Changing chord separator

The separator between different parts of a chord name can be set to any markup.

```

\chords {
  c:7sus4
  \set chordNameSeparator = \markup { \typewriter | }
  c:7sus4
}

```

C⁷ sus4 **C**⁷ | sus4

See also

Notation Reference: Section B.1 [Chord name chart], page 888, Section B.2 [Common chord modifiers], page 888.

Essay on automated music engraving: Section “Literature list” in *Essay*.

Installed Files: `scm/chords-ignatzek-names.scm`, `scm/chord-entry.scm`, `ly/chord-modifiers-init.ly`.

Snippets: Section “Chord notation” in *Snippets*.

Known issues and warnings


Chord names are determined from both the pitches that are present in the chord and the information on the chord structure that may have been entered in `\chordmode`. If the simultaneous pitches method of entering chords is used, undesired names result from inversions or bass notes.

```

myChords = \relative c' {
  \chordmode { c1 c/g c/f }
  <c e g>1 <g c e> <f c' e g>
}
<<
  \new ChordNames { \myChords }
  \new Staff { \myChords }


```

>>



15.2.3 Chord grids

In some European countries, particularly France, jazz musicians use so-called ‘chord grids’, which notate chords visually by placing them in squares.




Although they are omitted in the rest of this section for brevity, it is recommended to use the following `\paper` settings for chord grids:

```
\paper {
  indent = 0
  ragged-right = ##f
}
```

`indent = 0` ensures that the first line is not indented as it would normally be (see Section 26.5.3 [`\paper` variables for shifts and indents], page 676). `ragged-right = ##f` is necessary for single-line grids to ensure they span the whole page; see Section 26.5.1 [`\paper` variables for widths and margins], page 674.


In order to create a chord grid, instantiate a `ChordGrid` context.

```
\new ChordGrid \chordmode { c1 d1:m e1:7 f1:7+ }
```





Each square is automatically subdivided.

```
\new ChordGrid \chordmode {
  c1
  d2 c2
  e2. c4
}
```



Chords spanning a complete measure are centered within their square. Chords lasting half a measure take half the square, and those lasting a quarter of a measure take a quarter of the square. This summary picture shows the default rules for subdividing the square:



The `\medianChordGridStyle` changes the default display of squares with particular measure divisions to use the style recommended by Philippe Baudoin in his book *Jazz, mode d'emploi* (“Jazz, user instructions”).

```
\layout {
  \context {
    \ChordGrid
    \medianChordGridStyle
  }
}
```

Default style	<code>\medianChordGridStyle</code>


In chord grids, rests cause the `noChordSymbol` to be printed, just like in a regular `ChordNames` context (see Section 15.2.1 [Printing chord names], page 512).

```
\new ChordGrid \chordmode { c1 r2 c2 R1 }
```

C	N.C. C	N.C.

Skips cause blank space. They can occupy part of a square.

```
\new ChordGrid \chordmode { c1 s2 c2 s1 }
```



Selected snippets

Customizing the chord grid style

Custom divisions of chord squares can be defined through the `measure-division-lines-alist` and `measure-division-chord-placement-alist` properties of `ChordSquare`. These are both alists. Their keys are measure divisions, namely lists which give the fraction of the measure that each chord (or rest, or skip) represents. More precisely, a measure division alist is made of positive, exact numbers adding up to 1, for example: `'(1/2 1/4 1/4)`. The exactness requirement means that, e.g., `1/2` is valid but not `0.5`.

The values in `measure-division-lines-alist` are lists of lines, which are represented as `(x1 y1 x2 y2)`. The line starts at the point `(x1 . y1)` and ends at `(x2 . y2)`. Coordinates are expressed in the `[-1, 1]` scale relative to the extent of the square.


The values in `measure-division-chord-placement-alist` are lists of `(x . y)` pairs giving the placement of the respective chords.

This example defines a peculiar chord grid style that has a rule for measures divided in three equal parts.

```
\paper {
  \line-width = 10\cm
  \ragged-right = ##f
}

\new ChordGrid \with {
  \override ChordSquare.measure-division-lines-alist =
    #'(((1) . ()))
    ((1/3 1/3 1/3) . ((-1 -0.4 0 1) (0 -1 1 0.4))))
  \override ChordSquare.measure-division-chord-placement-alist =
    #'(((1) . ((0 . 0)))
    ((1/3 1/3 1/3) . ((-0.7 . 0.5) (0 . 0) (0.7 . -0.5))))
}

\chordmode {
  \time 3/4
  c2.
  c4 c4 c4
}
```



See also

Music Glossary: Section “chord grid” in *Music Glossary*.

Internals Reference: Section “ChordGrid” in *Internals Reference*, Section “ChordGrid-Score” in *Internals Reference*, Section “GridChordName” in *Internals Reference*, Section “ChordSquare” in *Internals Reference*, Section “Grid_chord_name_engraver” in *Internals Reference*, Section “Chord_square_engraver” in *Internals Reference*.

15.3 Figured bass

Adagio

Violino I.

Violino II.

Violone,
e Cembalo.

The image shows a musical score for a piece titled "Adagio". It features three staves: Violino I, Violino II, and Violone, e Cembalo. The Violone, e Cembalo part includes figured bass notation. The figures are as follows:

First system: 6 # 6 6 6 6 #

Second system: 5 6 6 5 5 6 6 5 #

Third system: 6 # 6 6 5 4 6 6 5 6 6 5 6 5 3 7 6 5 9 8 3

Figured bass notation can be displayed.

15.3.1 Introduction to figured bass

LilyPond has support for figured bass, also called *thorough bass* or *basso continuo*.

```

<<
  \new Voice { \clef bass dis4 c d ais g fis}
  \new FiguredBass {
    \figuremode {
      <6>4 <7\+>8 <6+ [_!]> <6>4 <6 5 [3+]> |
      <_>4 <6 5/>4
    }
  }
>>

```



The support for figured bass consists of two parts: there is an input mode, introduced by `\figuremode`, that accepts entry of bass figures, and there is a context named `FiguredBass` that takes care of displaying `BassFigure` objects. Figured bass can also be displayed in `Staff` contexts.

`\figures { ... }` is a shortcut notation for `\new FiguredBass \figuremode { ... }`.

Although the support for figured bass may superficially resemble chord support, it is much simpler. `\figuremode` mode simply stores the figures and the `FiguredBass` context prints them as entered. There is no conversion to pitches.

See also

Music Glossary: Section “figured bass” in *Music Glossary*.

Snippets: Section “Chord notation” in *Snippets*.

15.3.2 Entering figured bass

`\figuremode` is used to switch the input mode to figure mode. See Chapter 19 [Input modes], page 587, for more information on different input modes.

In figure mode, a group of bass figures is delimited by ‘<’ and ‘>’. The duration is entered after the ‘>’.

```

\new FiguredBass {
  \figuremode {
    <6 4>2
  }
}

```

6
4

Accidentals (including naturals) may be used for modifying scale steps. These are entered by appending ‘+’ (for sharps), ‘-’ (for flats) or ‘!’ (for naturals) after the number. For double accidentals the modifier is applied twice. For the modification of the third step the number is often omitted, which can be achieved by using ‘_’ instead of a number.

```
\figures {
  <7! 6+ 4-> <5++> <3--> <_+> <7 _!>
}
```

```
♭7 *5 ♭3 # 7
#6
♭4
```

If used without accidental, ‘_’ creates an empty figure which nevertheless takes up space. This can be used for controlling the stacking of bass figures.

```
<<
{
  \clef bass
  g2 c4
}
\figures {
  <_ 5 4>4 <8 _ 3>8 <7>
}
>>
```



Augmented and diminished steps can be indicated.

```
\figures {
  <6\+ 5/> <7/> <7 _\+>
}
```

```
+6 7 7
5 + +
```

A backward slash through a figure is also available.

```
\figures {
  <5> <5\\>
}
```

```
5 5
```

For some figures, special backward slash glyphs are provided.

```
\figures {
  <8 6\\> <9 7\\> <9\\ 7>
}
```

```
8 9 9
6 7 7
```

Brackets can be added around accidentals, figures, and consecutive groups of figures.

```
\figures {
  <9[-] 8 [7-] 5 [4[!] 2+]>
}
```

```
[♭]9
8
[♭]7
5
[[♭]4]
#2
```

Any text markup can be inserted as a figure.

```
\figures {
  <\markup { \fontsize #-5 \number 6 \teeny \super (1) } 5>
}
```

6⁽¹⁾
5

Continuation lines can be used to indicate repeated figures.

```
<<
{
  \clef bass
  e4 d c b,
  e4 d c b,
}
\figures {
  \bassFigureExtendersOn
  <6 4>4 <6 3> <7 3> <7 3>
  \bassFigureExtendersOff
  <6 4>4 <6 3> <7 3> <7 3>
}
>>
```



In this case, the extender lines replace existing figures, unless the continuation lines have been explicitly terminated with \!.

```
<<
\figures {
  \bassFigureExtendersOn
  <6 4>4 <6 4> <6\! 4\!> <6 4>
}
{
  \clef bass
  d4 d c c
}
>>
```



The table below summarizes the figure modifiers available.

modifier	purpose	example
+, -, !	accidentals	$\sharp 7$ *5 $\flat 3$ $\sharp 6$ $\flat 4$
\+, /	augmented and diminished steps	*6 7 5

`\\` raised by a semitone

`6 7 9`

`\!` end of continuation line



Predefined commands

`\bassFigureExtendersOn`, `\bassFigureExtendersOff`.

Selected snippets

Changing the positions of figured bass alterations

Accidentals and plus signs can appear before or after the numbers, depending on the `figuredBassAlterationDirection` and `figuredBassPlusDirection` properties.

If plus signs appear after the number, specially designed glyphs are provided for some figures.

```

#(set-global-staff-size 26)

```

```

\figures {
  <5\+> <5+ 4\+> <6 4- 2\+> r
  \set figuredBassAlterationDirection = #RIGHT
  <5\+> <5+ 4\+> <6 4- 2\+> r
  \set figuredBassPlusDirection = #RIGHT
  <5\+> <5+ 4\+> <6 4- 2\+> r
  \set figuredBassAlterationDirection = #LEFT
  <5\+> <5+ 4\+> <6 4- 2\+> r
}

```

$\begin{matrix} +5 & \sharp 5 & 6 \\ & +4 & \flat 4 \\ & & +2 \end{matrix}$
 $\begin{matrix} +5 & 5\sharp & 6 \\ & +4 & 4\flat \\ & & +2 \end{matrix}$
 $\begin{matrix} 5^+ & 5\sharp & 6 \\ & 4^+ & 4\flat \\ & & 2^+ \end{matrix}$
 $\begin{matrix} 5^+ & \sharp 5 & 6 \\ & 4^+ & \flat 4 \\ & & 2^+ \end{matrix}$

Adjusting figured bass alteration glyphs

In figured bass, specially designed glyphs for `6\\`, `7\\`, and `9\\` are used by default. Similarly, specially designed glyphs for symbols `2\+`, `4\+`, and `5\+` are used by default if plus signs appear after the number.

To change that, pass an alist to `figuredBassPlusStrokedAlist` and set the glyph in question to `#f` (or omit it).

```

#(set-global-staff-size 26)

```

```

\figures {
  \set figuredBassPlusDirection = #RIGHT
  <6\\> <7\\> <9\\> r
  <2\+> <4\+> <5\+> r

  \set figuredBassPlusStrokedAlist =
    #'((2 . "figbass.twoplus")
      ;; (4 . "figbass.fourplus")
      ;; (5 . "figbass.fiveplus")
      (6 . "figbass.sixstroked")
      ;; (7 . "figbass.sevenstroked")
    )

```



```

        ;; (9 . "figbass.ninestroked")
    )
    <6\\> <7\\> <9\\> r
    <2\+> <4\+> <5\+> r
}

    6   7   9           2+ 4+ 5+           6   7   9           2+ 4+ 5+

```

See also

Snippets: Section “Chord notation” in *Snippets*.

Internals Reference: Section “BassFigure” in *Internals Reference*, Section “BassFigure-Alignment” in *Internals Reference*, Section “BassFigureLine” in *Internals Reference*, Section “BassFigureBracket” in *Internals Reference*, Section “BassFigureContinuation” in *Internals Reference*, Section “FiguredBass” in *Internals Reference*.

15.3.3 Displaying figured bass

Figured bass can be displayed using the FiguredBass context, or in most staff contexts.

When displayed in a FiguredBass context, the vertical location of the figures is independent of the notes on the staff.

```

<<
  \relative {
    c' '4 c'8 r8 c,4 c'
  }
  \new FiguredBass {
    \figuremode {
      <4>4 <10 6>8 s8
      <6 4>4 <6 4>
    }
  }
}
>>

```



In the example above, the FiguredBass context must be explicitly instantiated to avoid creating a second (empty) staff.

Figured bass can also be added to Staff contexts directly. In this case, the vertical position of the figures is adjusted automatically.

```

<<
  \new Staff = "myStaff"
  \figuremode {
    <4>4 <10 6>8 s8
    <6 4>4 <6 4>
  }
  %% Put notes on same Staff as figures
  \context Staff = "myStaff" {
    \clef bass
    c4 c'8 r8 c4 c'
  }
}

```

>>



When added in a `Staff` context, figured bass can be displayed above or below the staff.

```
<<
  \new Staff = "myStaff"
  \figuremode {
    <4>4 <10 6>8 s8
    \bassFigureStaffAlignmentDown
    <6 4>4 <6 4>
  }
  %% Put notes on same Staff as figures
  \context Staff = "myStaff" {
    \clef bass
    c4 c'8 r8 c4 c'
  }
>>
```




The horizontal alignment of numbers in a figured bass stack that have more than a single digit can be controlled with the context property `figuredBassLargeNumberAlignment`.

```
<<
  \new Voice {
    \clef bass
    r2 d | d d | a2
  }
  \new FiguredBass \figuremode {
    s2 <10+ 8> |
    \set figuredBassLargeNumberAlignment = #RIGHT
    <11 9>2
    \set figuredBassLargeNumberAlignment = #LEFT
    <10+ 9>2 |
    <_+>2
  }
>>
```



The vertical distance of figured bass elements can be controlled with subproperties `minimum-distance` and `padding` of `staff-staff-spacing`.

```
<<
{ \clef bass g,2 c, }
\figures {
  \once \override BassFigureLine
                                .staff-staff-spacing.minimum-distance = 3
  <7 _-> <7- _->
}
>>
```



Predefined commands

\bassFigureStaffAlignmentDown, \bassFigureStaffAlignmentUp,
\bassFigureStaffAlignmentNeutral.

See also

Snippets: Section “Chord notation” in *Snippets*.

Internals Reference: Section “BassFigure” in *Internals Reference*, Section “BassFigure-Alignment” in *Internals Reference*, Section “BassFigureLine” in *Internals Reference*, Section “BassFigureBracket” in *Internals Reference*, Section “BassFigureContinuation” in *Internals Reference*, Section “FiguredBass” in *Internals Reference*.


Known issues and warnings

To ensure that continuation lines work properly, it is safest to use the same rhythm in the figure line as in the bass line.

```
<<
{
  \clef bass
  \*4 { f16. g32 } f8. es16 d8 es
}
\figures {
  \bassFigureExtendersOn
  % The extenders are correct here,
  % with the same rhythm as the bass.
  \*4 { <6 4->16. <6 4->32 }
  <5>8. r16 <6>8 <6\! 5->
}
>>

<<
{
  \clef bass
  \*4 { f16. g32 } f8. es16 d8 es
}
\figures {
  \bassFigureExtendersOn
  % The extenders are incorrect here,
  % even though the timing is the same.
  <6 4->4 <6 4->4
}
```

<5>8. r16 <6>8 <6\! 5->
}
>>



16 Contemporary music

From the beginning of the 20th Century there has been a massive expansion of compositional style and technique. New harmonic and rhythmic developments, an expansion of the pitch spectrum and the development of a wide range of new instrumental techniques have been accompanied by a parallel evolution and expansion of musical notation. The purpose of this section is to provide references and information relevant to working with these new notational techniques.

16.1 Pitch and harmony in contemporary music

This section highlights issues that are relevant to notating pitch and harmony in contemporary music.

16.1.1 References for pitch and harmony in contemporary music

- Standard quarter tone notation is addressed in Section 1.1.5 [Note names in other languages], page 10.
- Non-standard key signatures are addressed in Section 1.3.2 [Key signature], page 24.
- Contemporary practices in displaying accidentals are addressed in Section 1.3.5 [Automatic accidentals], page 31.

16.1.2 Microtonal notation

16.1.3 Contemporary key signatures and harmony

16.2 Contemporary approaches to rhythm

This section highlights issues that are relevant to the notation of rhythm in contemporary music.

16.2.1 References for contemporary approaches to rhythm

- Complex time signatures are addressed in Section 2.3.2 [Time signature], page 79.
- Basic polymetric notation is addressed in Section 2.3.6 [Polymetric notation], page 93.
- Feathered beams are addressed in Section 2.4.4 [Feathered beams], page 118.
- Mensurstriche bar lines (bar lines between staves only) are addressed in Section 6.1.2 [Grouping staves], page 243.

16.2.2 Tuplets in contemporary music

16.2.3 Contemporary time signatures

16.2.4 Extended polymetric notation

16.2.5 Beams in contemporary music

16.2.6 Bar lines in contemporary music

16.3 Graphical notation

Rhythmic items may be continued by a duration line, which gets represented by a `DurationLine` grob. Possible styles are 'beam', 'line', 'dashed-line', 'dotted-line', 'zigzag', 'trill' and 'none'. The duration line may end with a hook (beam-style only) or an arrow.

```

\layout {
  \context {
    \Voice
    \consists Duration_line_engraver
    \omit Stem
    \omit Flag
    \omit Beam
    \override NoteHead.duration-log = 2
  }
}

{
  a'1\~ s2 r
  \once \override DurationLine.style = #'line
  a'1\~ s2 r
  \once \override DurationLine.style = #'dashed-line
  \once \override DurationLine.dash-period = 2
  a'1\~ s2 r
  \once \override DurationLine.style = #'dotted-line
  \once \override DurationLine.dash-period = 1
  \once \override DurationLine.bound-details.right.padding = 1
  a'1\~ s2 r
  \once \override DurationLine.thickness = 2
  \once \override DurationLine.style = #'zigzag
  a'1\~ s2 r
  \once \override DurationLine.style = #'trill
  a'1\~ s2 r
  \once \override DurationLine.style = #'none
  a'1\~ s2 r
  \once \override DurationLine.bound-details.right.end-style = #'arrow
  a'1\~ s2 r
  \override DurationLine.bound-details.right.end-style = #'hook
  a'1\~ s2 r
  \override DurationLine.details.hook-direction = #DOWN
  a'1\~ s2 r
  \bar "|"
}

```



DurationLine may avoid mid-line items from BreakAlignGroup.

```


\layout {
  \context {
    \Voice
    \consists "Duration_line_engraver"
  }
}

```

```

<<
  \new Staff {
    g'1\- s \clef "alto" g'
  }
  \new Staff {
    \override DurationLine.bound-details
      .right.end-on-break-align-group = ##t
    g'1\- s \clef "alto" g' \bar "|."
  }
>>

```



16.4 Contemporary scoring techniques

16.5 New instrumental techniques

16.6 Further reading and scores of interest

This section suggests books, musical examples and other resources useful in studying contemporary musical notation.

16.6.1 Books and articles on contemporary musical notation

- *Music Notation in the Twentieth Century: A Practical Guidebook* by Kurt Stone [W. W. Norton, 1980]
- *Music Notation: A Manual of Modern Practice* by Gardner Read [Taplinger, 1979]
- *Instrumentation and Orchestration* by Alfred Blatter [Schirmer, 2nd ed. 1997]

16.6.2 Scores and musical examples

17 Ancient notation

Sál- ve, Re- gí- na, máter mi-se- ri cór- di- ae : Ad te cla- má mus, éx-
 su- les, fí li- i Hévae. Ad te suspi- rá- mus, ge- mén tes et flén- tes in
 hac la cri- márum vál- le. E- ia er go, Advo- cá- ta nóstra, illos tú-
 os mi se ri- cór- des ó- cu- los ad nos con- vér- te. Et Jé- sum, be- ne-
 díc- tum frúctum vén tris tú- i, nó- bis post hoc ex sí- li- um os- tén-
 de. O clé mens : O pí- a : O dúl- cis Vírgo Ma- rí- a.

Support for ancient notation includes features for mensural notation, Gregorian chant notation, and Kievan square notation. These features can be accessed either by modifying style properties of graphical objects such as note heads and rests, or by using one of the predefined contexts for these styles.

Many graphical objects, such as note heads and flags, accidentals, time signatures, and rests, provide a style property, which can be changed to emulate several different styles of ancient notation. See

- Section 17.3.4 [Mensural note heads], page 543,
- Section 17.3.7 [Mensural accidentals and key signatures], page 545,
- Section 17.3.6 [Mensural rests], page 545,
- Section 17.3.2 [Mensural clefs], page 542,
- Section 17.4.2 [Gregorian clefs], page 554,
- Section 17.3.5 [Mensural flags], page 544,
- Section 17.3.3 [Mensural time signatures], page 543.

Some notational concepts are introduced specifically for ancient notation,

- Section 17.2.3 [Custodes], page 540,
- Section 17.4.4 [Divisiones], page 555,
- Section 17.2.2 [Ligatures], page 539.

See also

Music Glossary: Section “custos” in *Music Glossary*, Section “ligature” in *Music Glossary*, Section “mensural notation” in *Music Glossary*.

Notation Reference: Section 17.3.4 [Mensural note heads], page 543, Section 17.3.7 [Mensural accidentals and key signatures], page 545, Section 17.3.6 [Mensural rests], page 545, Section 17.4.2 [Gregorian clefs], page 554, Section 17.3.5 [Mensural flags], page 544, Section 17.3.3 [Mensural time signatures], page 543, Section 17.2.3 [Custodes], page 540, Section 17.4.4 [Divisiones], page 555, Section 17.2.2 [Ligatures], page 539.

17.1 Overview of the supported styles

Three styles are available for typesetting Gregorian chant:

- *Editio Vaticana* is a complete style for Gregorian chant, following the appearance of the Solesmes editions, the official chant books of the Vatican since 1904. LilyPond has support for all the notational signs used in this style, including ligatures, *custodes*, and special signs such as the quilisma and the oriscus.
- The *Editio Medicaea* style offers certain features used in the Medicaea (or Ratisbona) editions which were used prior to the Solesmes editions. The most significant differences from the *Vaticana* style are the clefs, which have downward-slanted strokes, and the note heads, which are square and regular.
- The *Hufnagel* (“horseshoe nail”) or *Gothic* style mimics the writing style in chant manuscripts from Germany and Central Europe during the middle ages. It is named after the basic note shape (the *virga*), which looks like a small nail.

Three styles emulate the appearance of late-medieval and Renaissance manuscripts and prints of mensural music:

- The *Mensural* style most closely resembles the writing style used in late-medieval and early Renaissance manuscripts, with its small and narrow, diamond-shaped note heads and its rests which approach a hand-drawn style.
- The *Neomensural* style is a modernized and stylized version of the former: the note heads are broader and the rests are made up of straight lines. This style is particularly suited, e.g., for incipits of transcribed pieces of mensural music.
- The *Petrucchi* style is named after Ottaviano Petrucci (1466-1539), the first printer to use movable type for music (in his *Harmonice musices odhecaton*, 1501). The style uses larger note heads than the other mensural styles.

Baroque and *classical* are not complete styles but differ from the default style only in some details: certain note heads (Baroque) and the quarter rest (classical).

Only the mensural style has alternatives for all aspects of the notation. Thus, there are no rests or flags in the Gregorian styles, since these signs are not used in plainchant notation, and the Petrucci style has no flags or accidentals of its own.

Each element of the notation can be changed independently of the others, so that one can use mensural flags, Petrucci note heads, classical rests and Vaticana clefs in the same piece, if one wishes.

See also

Music Glossary: Section “mensural notation” in *Music Glossary*, Section “flag” in *Music Glossary*.

17.2 Ancient notation – common features

17.2.1 Predefined contexts

For Gregorian chant and mensural notation, there are predefined voice, staff, and score contexts available, which set all the various notation signs to values suitable for these styles. If one is satisfied with these defaults, one can proceed directly with note entry without worrying about the details on how to customize a context. See one of the predefined contexts `VaticanaScore`, `VaticanaVoice`, `VaticanaStaff`, `MensuralVoice`, `MensuralStaff`, `PetrucchiStaff`, `PetrucchiVoice`, `KievanVoice`, and `KievanStaff`.

See also

Music Glossary: Section “mensural notation” in *Music Glossary*.

Notation Reference: Section 17.4.1 [Gregorian chant contexts], page 554, Section 17.3.1 [Mensural contexts], page 541, Section 17.5.1 [Kievan contexts], page 563.

17.2.2 Ligatures

A ligature is a graphical symbol that represents at least two distinct notes. Ligatures originally appeared in the manuscripts of Gregorian chant notation to denote ascending or descending sequences of notes on the same syllable. They are also used in mensural notation.

Ligatures are entered by *enclosing* them in `\[` and `\]`. Some ligature styles may need additional input syntax specific for this particular type of ligature. By default, the `LigatureBracket` engraver just puts a square bracket above the ligature.

```
\relative {
  \[ g' c, a' f d' \]
  a g f
  \[ e f a g \]
}
```



Three other ligature styles are available: ‘Vaticana’ for Gregorian chant, ‘Mensural’ for mensural music (only white mensural ligatures are supported for mensural music, and with certain limitations), and ‘Kievan’ for Kievan melismata. To use any of these styles, the default `Ligature_bracket_engraver` has to be replaced with one of the specialized ligature engravers in the `Voice` context. For more information, see Section 17.3.10 [White mensural ligatures], page 548, Section 17.4.7 [Gregorian square neume ligatures], page 557, and Section 17.5.6 [Kievan melismata], page 565.

See also

Music Glossary: Section “ligature” in *Music Glossary*.

Notation Reference: Section 17.3.10 [White mensural ligatures], page 548, Section 17.4.7 [Gregorian square neume ligatures], page 557.

Known issues and warnings

Spacing required for ligatures is not currently implemented and, as a result, there may end up being too much space between them. Line breaking may also be unsatisfactory.

Lyrics might not align as expected when using ligatures.

Accidentals must not be printed within a ligature, but instead be collected and printed in front of it.

The syntax still uses the deprecated “infix” style `\[ music expr \]`. For consistency reasons, it will eventually be changed to “postfix” style `note\[ ... note\]`.

17.2.3 Custodes

A *custos* (plural: *custodes*; Latin word for “guard”) is a symbol that appears at the end of a staff. It anticipates the pitch of the first note of the following line, thus helping the performer to manage line breaks during performance.

Custodes were frequently used in music notation until the seventeenth century. Nowadays, they have survived only in a few particular forms of musical notation such as contemporary editions of Gregorian chant like the *Editio Vaticana*. There are different custos glyphs used in different flavors of notational style.


For typesetting custodes, just put a `Custos_engraver` into the `Staff` context when declaring the `\layout` block, and change the style of the custos with an `\override` if desired, as shown in the following example:

```
\score {
  \relative {
    a'1
    \break
    g
  }
  \layout {
    \context {
      \Staff
      \consists Custos_engraver
      \override Custos.style = #'mensural
    }
  }
}
```



The custos glyph is selected by the style property. The styles supported are *vaticana*, *medicaea*, *hufnagel*, and *mensural*.

```
\new Lyrics \lyricmode {
  \markup { \column {
    \typewriter "vaticana "
    \line { " " \musicglyph "custodes.vaticana.u0" }
  } }
  \markup { \column {
    \typewriter "medicaea "
    \line { " " \musicglyph "custodes.medicaea.u0" }
  } }
  \markup { \column {
```




See also

Music Glossary: Section “mensural notation” in *Music Glossary*.

17.3.2 Mensural clefs

Mensural clefs are supported using the `\clef` command. Some of the clefs use the same glyph, but differ only with respect to the line they are printed on. In such cases, a trailing number in the name is used to enumerate these clefs, numbered from the lowest to the highest line.


```
\new MensuralStaff {
  \clef "mensural-c1" c'1
}
```



```
\new MensuralStaff {
  \override NoteHead.style = #'blackmensural
  \clef "blackmensural-c2" c'1
}
```



```
\new MensuralStaff {
  \override NoteHead.style = #'neomensural
  \clef "neomensural-c3" c'1
}
```



```
\new PetrucciStaff {
  \clef "petrucci-c4" c'1
}
```



It is possible to manually force a clef glyph to be typeset on an arbitrary line, see Section 1.3.1 [Clef], page 19. For the complete range of possible clefs, see Section B.11 [Clef styles], page 921.

See also

Music Glossary: Section “mensural notation” in *Music Glossary*, Section “clef” in *Music Glossary*.

Notation Reference: Section 17.4.2 [Gregorian clefs], page 554, Section 1.3.1 [Clef], page 19.

Installed Files: `scm/parser-clef.scm`.

Snippets: Section “Pitches” in *Snippets*.

Internals Reference: Section “Clef_engraver” in *Internals Reference*, Section “Clef” in *Internals Reference*, Section “ClefModifier” in *Internals Reference*, Section “clef-interface” in *Internals Reference*.

Known issues and warnings

The Mensural g clef is mapped to the Petrucci g clef.

17.3.3 Mensural time signatures

There is limited support for mensuration signs (which are similar to but not exactly the same as time signatures). The glyphs are hard-wired to particular time fractions. In other words, to get a particular mensuration sign with the `\time n/m` command, n and m have to be chosen according to the following table.

<code>\time 4/4</code>	<code>\time 2/2</code>	<code>\time 6/4</code>	<code>\time 6/8</code>
			
<code>\time 3/2</code>	<code>\time 3/4</code>	<code>\time 9/4</code>	<code>\time 9/8</code>
			
<code>\time 4/8</code>	<code>\time 2/4</code>		
			

Use the style property of grob TimeSignature to select ancient time signatures. Supported styles are `neomensural` and `mensural`. The above table uses the `neomensural` style. The following examples show the differences in style:

default	numbered	mensural	neomensural	single-number
				

See Section 2.3.2 [Time signature], page 79, for a general introduction to the use of time signatures.

See also

Music Glossary: Section “mensural notation” in *Music Glossary*.

Notation Reference: Section 2.3.2 [Time signature], page 79.

Known issues and warnings

Ratios of note durations cannot change with the time signature, as those are not constant. For example, the ratio of 1 breve = 3 semibreves (*tempus perfectum*) can be made by hand, by setting

```
breveTP = #(ly:make-duration -1 0 3/2)
...
{ c\breveTP f1 }
```

This sets `breveTP` to $3/2$ times $2 = 3$ times a whole note.

The `mensural68alt` and `neomensural68alt` symbols (alternate symbols for 6/8) are not addressable with `\time`. Use `\markup {\musicglyph "timesig.mensural68alt" }` instead.

17.3.4 Mensural note heads

For ancient notation, a note head style other than the default style may be chosen. This is accomplished by setting the style property of the NoteHead object to `baroque`, `neomensural`, `mensural`, `petrucci`, `blackpetrucci` or `semipetrucci`.

The baroque style differs from the default style by:

- Providing a maxima note head, and
- Using a square shape for `\breve` note heads.

The `neomensural`, `mensural`, and `petrucci` styles differ from the baroque style by:

- Using rhomboidal heads for semibreves and all smaller durations, and


- Centering the stems on the note heads.

The `blackpetrucci` style produces note heads usable in black mensural notation or coloratio sections in white mensural notation. Because note head style does not influence flag count, in this style a semiminima should be notated as `a8*2`, not `a4`, otherwise it will look like a minima. The multiplier can be different if coloratio is used, e.g., to notate triplets.

Use `semipetrucci` style to draw half-colored note heads (breves, longas and maximas).

The following example demonstrates the `petrucci` style:

```
\compressEmptyMeasures
\autoBeamOff
\override NoteHead.style = #'petrucci
a'\maxima a'\longa a'\breve a'1 a'2 a'4 a'8 a'16 a'
\override NoteHead.style = #'semipetrucci
a'\breve*5/6
\override NoteHead.style = #'blackpetrucci
a'8*4/3 a'
\override NoteHead.style = #'petrucci
a'\longa
```



Section B.9 [Note head styles], page 920, gives an overview of all available note head styles.

See also


Music Glossary: Section “mensural notation” in *Music Glossary*, Section “note head” in *Music Glossary*.

Notation Reference: Section B.9 [Note head styles], page 920.

17.3.5 Mensural flags

Use the style property of grob `Flag` to select ancient flags. Besides the default flag style, only the mensural style is supported.

```
\relative c' {
  \override Flag.style = #'mensural
  \override Stem.thickness = 1.0
  \override NoteHead.style = #'mensural
  \autoBeamOff
  c8 d e f c16 d e f c32 d e f s8
  c'8 d e f c16 d e f c32 d e f
}
```



Note that the innermost flare of each mensural flag is vertically aligned with a staff line.

There is no particular flag style for neo-mensural or Petrucci notation. There are no flags in Gregorian chant notation.

See also

Music Glossary: Section “mensural notation” in *Music Glossary*, Section “flag” in *Music Glossary*.

Known issues and warnings


Vertically aligning each flag with a staff line assumes that stems always end either exactly on or exactly in the middle of two staff lines. This may not always be true when using advanced layout features of classical notation (which however are typically out of scope for mensural notation).

17.3.6 Mensural rests

Use the `style` property of grob `Rest` to select ancient rests. Supported ancient styles are `neomensural`, and `mensural`.

The following example demonstrates these styles:

```
\compressEmptyMeasures
\override Rest.style = #'mensural
r\longa^"mensural" r\breve r1 r2 r4 r8 r16 s \break
\override Rest.style = #'neomensural
r\longa^"neomensural" r\breve r1 r2 r4 r8 r16
```



There are no 32nd and 64th rests specifically for the mensural or neo-mensural styles. Rests from the default style are used.

See also

Music Glossary: Section “mensural notation” in *Music Glossary*.

Notation Reference: Section 2.2.1 [Rests], page 67.

Snippets: Section “Ancient notation” in *Snippets*.

Known issues and warnings

The glyph for the maxima rest in mensural style is actually a perfect longa rest; use two (or three) longa rests to print a maxima rest. Longa rests are not grouped automatically, so have to be done manually by using pitched rests.

17.3.7 Mensural accidentals and key signatures

The `mensural` style provides a sharp and a flat sign different from the default style. Mensural notation rarely used a natural sign: instead the appropriate sharp or flat is used. For example, a B natural in the key of F major would be indicated with a sharp. However, if specifically called for, the natural sign is taken from the `vaticana` style.

mensural

♭ ✕

The way to use this style is covered in Section 1.3.6 [Alternate accidental glyphs], page 39. It is the default in the `MensuralStaff` context.

See also

Music Glossary: Section “mensural notation” in *Music Glossary*, Section “Pitch names” in *Music Glossary*, Section “accidental” in *Music Glossary*, Section “key signature” in *Music Glossary*.

Notation Reference: Chapter 1 [Pitches], page 3, Section 1.1.3 [Accidentals], page 8, Section 1.3.5 [Automatic accidentals], page 31, Section 1.3.6 [Alternate accidental glyphs], page 39, Section B.10 [Accidental glyph sets], page 920, Section 1.3.2 [Key signature], page 24.

Internals Reference: Section “KeySignature” in *Internals Reference*.

17.3.8 Annotational accidentals (*musica ficta*)

In European music from before about 1600, singers were expected to chromatically alter notes at their own initiative according to certain rules. This is called *musica ficta*. In modern transcriptions, these accidentals are usually printed over the note.


Support for such suggested accidentals is included, and can be switched on by setting `suggestAccidentals` to `##t`.

```
\relative {
  fis' gis
  \set suggestAccidentals = ##t
  ais bis
}
```



This will treat *every* subsequent accidental as *musica ficta* until it is unset with `\set suggestAccidentals = ##f`. A more practical way is to use `\once \set suggestAccidentals = ##t`, which can even be defined as a convenient shorthand:

```
ficta = { \once \set suggestAccidentals = ##t }
\score { \relative
  \new MensuralVoice {
    \once \set suggestAccidentals = ##t
    bes'4 a2 g2 \ficta fis8 \ficta e! fis2 g1
  }
}
```



See also

Internals Reference: Section “Accidental_engraver” in *Internals Reference*, Section “AccidentalSuggestion” in *Internals Reference*.

17.3.9 Historical overview of ligatures

Early polyphony used modal rhythm and encoded the meter by ligatures (as they existed in Gregorian neume notation, see Section 17.4.7 [Gregorian square neume ligatures], page 557), breaking the flow of notes *not by feet*, but after each metric stress, i.e., the last note of a ligature was stressed, the preceding ones were not. The most common ligatures had two or three notes (*ligatura binaria/ternaria*: binary/ternary ligature), corresponding to the stress distribution

of the common meters iamb (short-long), trochee (long-short), dactyl (long-short-short), and anapaest (short-short-long). (Note that long-short is the quantitative concept; stress is the qualitative counterpart of long.)

When modal rhythm was abandoned and note shapes started to encode length, ligatures were not abandoned but (interpreting the meter strictly quantitatively) read as breves followed by a final longa. The pes () indicates an ascending ligature, and the climacus () a descending one.

New shapes were introduced to encode other length sequences, preferably independently of context, so that ligatures of arbitrary length became possible. Shapes for binary brevis-brevis ligatures might have been taken from the first two notes of the existing ternary ligatures (meaning brevis-brevis-longa): the torculus () and the modified scandici () start the same way; the shape  is thus usable as an ascending binary brevis-brevis ligature. Climacus must have been abandoned, as it is indistinguishable from the sequence   of non-ligated notes, so only the porrectus () remained to use its start as the descending form: the oblique parallelogram  is referred to as a *flexa*; it always denotes *two* notes (at the starting and ending pitches), not a scale of all pitches between the two.

Binary ligatures starting with a longa were crafted by tweaking the existing brevis-brevis or brevis-longa shapes. For the descending shapes longa-breve () and longa-longa () the initial stem was removed; for the ascending shapes longa-breve () and longa-longa () a right downward stem was added to the first note.

The pes shape was difficult to draw with void heads if the penultimate pitch was close (the same holds for the porrectus), so such final notes were replaced by virgae (for example,  and , perhaps inspired by the scandicus). Nevertheless, the original shape remained in use for quite a long time, even though it looks like a divisi, and at end of sections it may be impossible to tell which one is meant.

Binary ligatures for semibreve pairs like , , and  were also introduced, denoted by an upward left stem.

The following table summarizes the customary binary ligatures.

Lengths	S S	B B	L B	B L	L L
Ascending					
Descending	 				


Maximae were easy to introduce into ligatures, because they post-date the era of modal rhythm, so they do not have to comply with old customs: they can appear anywhere within a ligature in their customary form, with or without a downward right stem. In the middle of a ligature, breves and longae were also written in their customary shape (stems of longae point always downwards), except when a pair of two brevis shaped noteheads is merged to form a flexa (which can be compulsory only at the end, but frequently used in the middle too). Rarely initial breves got a left stem even in an ascending configuration, or final longae got a right stem even in descending configurations.

Gregorian neume ligatures could not have been abandoned, since plainchant notation remained in use (some manuscripts contain plainchant and mensural notation side by side). Evolution of mensural ligatures must have been influenced by that – that may be the cause of using almost exclusively breves in the middle of a ligature; that the flexa shape is mostly used when the second note is lower than its neighbors, is probably also a heritage of neumes.

The table above is a quite practical cheat sheet for reading *any* mensural ligature: the first and last notes should be decoded from this table, the rest can be read roughly as is (for “exact” rules see Section 17.3.11 [Reading white mensural ligatures], page 550). The flexa shape poses some practical difficulties: pitches can be hard to decide whether on a line or in a neighboring

space; also notes could be dotted (such a dot appears above or below the next note), and it may be hard to decide whether a dot above a flexa belongs to the first note of the flexa or the preceding one:

```
\new PetrucciVoice {
  \relative {
    \[ b'\breve. a\breve g\breve \]
    \[ b\breve. a\breve. g\breve \]
    \[ b\breve a\breve. g\breve \]
  }
}
```



17.3.10 White mensural ligatures

There is limited support for white mensural ligatures.

To engrave white mensural ligatures, replace the `Ligature_bracket_engraver` with the `Mensural_ligature_engraver` in the `Voice` context's layout block:

```
\layout {
  \context {
    \Voice
    \remove Ligature_bracket_engraver
    \consists Mensural_ligature_engraver
  }
}
```


In the following, we use a `PetrucchiStaff` context, which does this replacement, among other settings, approximating the mensural typesetting of Ottaviano Petrucci's *Harmonices Musices Odhecaton* (Venice, 1501). The accompanying voice context is called `PetrucchiVoice`.

There is no additional input language to describe the shape of a white mensural ligature; instead, the shape is determined solely from the pitches and durations of the enclosed notes. While this approach may take a new user a while to get accustomed to, it has the great advantage that the full musical information of the ligature is known internally. This is not only required for correct MIDI output, but also allows for automatic transcription of the ligatures.

By default optional stems and flexae are not drawn, and final ascending longae are drawn as virgae. To draw alternatives, some tweaks are provided: An optional flexa can be requested by setting the `ligature-flexa` property of the *second* note head. The width of a flexa can be set by the note head property `flexa-width`.

For example,

```
\new PetrucciStaff \relative {
  \[ c'\maxima g \]
  \[ d'\longa
    \tweak ligature-flexa ##t
    \tweak flexa-width #3.2 c\breve f e
    \tweak flexa-width #4.3 d \]
  \[ c\maxima d\longa \]
  \[ e1 a, g\breve \]
}
```



After replacing `Mensural_ligature_engraver` with `Ligature_bracket_engraver`, the same music looks as follows:




Optional stems can be requested by the following properties:

- `left-down-stem` for downward left stem for an initial breve;
- `right-down-stem` for downward right stem for a maxima or a longa (which is by default stemless in descending start/end circumstances);
- `right-up-stem` for upward right stem for a final maxima/longa.


Here is an example that demonstrates these tweaks.

```
\new PetrucciStaff \relative {
  \clef "petrucci-c4"
  \[ \tweak left-down-stem ##t a\breve b
    \tweak right-down-stem ##t g\longa \]
  \[ \tweak right-down-stem ##t b\maxima
    \tweak right-up-stem ##t g\longa \]
}
```



Without tweaking, the same ligatures look as follows:

```
\new PetrucciStaff \relative {
  \clef "petrucci-c4"
  \[ a\breve b g\longa \]
  \[ b\maxima g\longa \]
}
```



Pes-style final ascending longa can be drawn by `ligature-pes`:

```
\layout {
  \context {
    \Score
    \override SpacingSpanner.base-shortest-duration =
      #(ly:make-moment 16 1)
  }
}
\new PetrucciStaff {
  \clef "petrucci-c4"
  \[ d\breve \tweak ligature-pes ##t a\longa \]
  \[ e \tweak ligature-pes ##t b \]
  \[ c\breve d c \tweak ligature-pes ##t c'\longa \]
  \[ f\breve d \tweak ligature-pes ##t a\longa \]
}
```



In the last case LilyPond draws the breves as flexa, otherwise the initial note would collide with the final one. Without tweaking these ligatures look like

```
\layout {
  \context {
    \Score
    \override SpacingSpanner.base-shortest-duration =
      #(ly:make-moment 16 1)
  }
}
\new PetrucciStaff {
  \clef "petrucci-c4"
  \[ d\breve a\longa \]
  \[ e b \]
  \[ c\breve d c c'\longa \]
  \[ f\breve d a\longa \]
}
```



See also

Music Glossary: Section “ligature” in *Music Glossary*.

Notation Reference: Section 17.4.7 [Gregorian square neume ligatures], page 557, Section 17.2.2 [Ligatures], page 539.

Known issues and warnings

Horizontal spacing of ligatures may be poor.

Accidentals may collide with previous notes.

17.3.11 Reading white mensural ligatures


Ligatures are read from left to right and (if, very rarely, two notes appear vertically aligned) bottom up. First the ligature is to be parsed into notes (a flexa shape denotes two notes, any note may be dotted (see above) or colored), and each stem is to be assigned to a note: a final or downward middle stem belongs to the preceding note, or, if two vertically aligned notes precede the stem, to the lower of those (so is a right stem of that note), while an initial or upward middle stem belongs to the next note (so is a left stem – upward middle stems are extremely rare).

Then each note is assigned a length as follows:

1. (rule of maxima) if the shape of the note is maxima, then the length is `\maxima`, otherwise
2. (rule of pes) if the note is aligned above the previous note, then the length is `\longa`, otherwise
3. (rule of stems) if the note has a stem, then the length is `semibreve` (1) for an upward left stem, `\breve` for a downward left stem, and `\longa` for a right stem; otherwise
4. (appendix to the stem rule) if the previous note has an upward left stem, then the length is `semibreve` (1), otherwise
5. (rule of descending start) if the note is the first one, and is higher than the next note, then the length is `\longa`, otherwise
6. (rule of descending end) if the note is the final one, and lower than the penultimate note, and of breve shape, then the length is `\longa`, otherwise

7. the length is `\breve`.

(Note that lengths shorter than the semibreve cannot be ligated.) Some examples showing which rule applies on which note:



Besides these rules, there are some restrictions/conventions:

- A. successive notes must not have the same pitch.
- B. vertically aligned notes can occur only at the end of a ligature.
- C. a ligature contains at least two notes (occasionally one may encounter  looking like a unary ligature, but it probably fixes scribal mistakes, correcting a breve to semibreve by adding the stem).
- D. semibreves can appear only at the beginning and just one pair of them (some English manuscripts have ligatures with four or six semibreves).
- E. flexae are descending (however, ascending flexae are ubiquitous in manuscripts not respecting this convention).
- F. non-final flexae are turning, i.e., descending flexae are followed by a higher, ascending ones by a lower note.
- G. second note of a flexa must not be a longa; in other words, a flexa must not have a right stem.
- H. middle notes are breves; this is actually an explicit rule of Tinctoris, does not exactly match praxis, but can be refined in several steps:
 - I. middle longae and maximae occur in ligatures consisting only of longae and maximae;
 - J. middle longae are higher than the previous note;
 - K. middle longae are lower than the next note.

There is also a tendency that maximae in a mixed (not all maxima) ligature have a right stem, except for descending starts and ends.

Some examples showing these restrictions in action:


- In Obrecht's *Missa Salve diva parens*, the same four-note motif is written in decreasing lengths; while (dotted) maximae or breves can form a four-note ligature, longae and semibreves cannot (restrictions K and D).

```
\layout {
  \context {
    \Score
    \override SpacingSpanner.base-shortest-duration =
      #(ly:make-moment 16 1)
  }
}
\new PetrucciStaff {
  \clef "petrucci-c3"
  \[ a\maxima. b c' b \]
  \[ a\longa. b \] \[ c' b \]
```

```

\[[ a\breve. b c' b \]
\[[ a1. b \] \[[ c' \tweak ligature-flexa ##t b \]
}

```



- The Amen in a Credo by Vaqueras is a long melisma; the one in the tenor part is written mostly in ligatures, broken by restrictions D, J, and K (while ignoring H and I):

```

\layout {
  \context {
    \Score
    \override SpacingSpanner.base-shortest-duration =
      #(ly:make-moment 16 1)
  }
}
\new PetrucciStaff {
  \clef "petrucci-c5"
  \[[ f1 g \] \[[ e\longa g a \] d\breve
  \[[ e1 \tweak ligature-flexa ##t d f\breve g\longa a b \]
  c'1 \[[ a\breve. g\longa \] \[[ f e \] \[[ d1 e \]
}

```




Observing restriction H would result in

```

\layout {
  \context {
    \Score
    \override SpacingSpanner.base-shortest-duration =
      #(ly:make-moment 16 1)
  }
}
\new PetrucciStaff {
  \clef "petrucci-c5"
  \[[ f1 g \] \[[ e\longa g \] \[[ a d\breve \]
  \[[ e1 \tweak ligature-flexa ##t d f\breve g\longa \] \[[ a b \]
  c'1 \[[ a\breve. g\longa \] \[[ f e \] \[[ d1 e \]
}

```



while ignoring all restrictions results in

```


\layout {
  \context {
    \Score
    \override SpacingSpanner.base-shortest-duration =
      #(ly:make-moment 16 1)
  }
}

```

```

}
\new PetrucciStaff {
  \clef "petrucci-c5"
  \[ f1 g e\longa g a d\breve
    e1 \tweak ligature-flexa ##t d f\breve g\longa a b \]
  c'1 \[ a\breve. g\longa f e d1 e \]
}

```



Rule 6 presents a conundrum: how to draw a final brevis if the penultimate note has a right stem (which is extremely rare because of restriction K)? The easy answer is “stop the ligature after the stem”, but there are examples when  is to be read as longa-brevis (note that a final longa could always be disambiguated by adding a right stem).

An alternative interpretation is to read this stem as a right stem of the last note, and indeed there is a piece in Trent 89, fol 97, where  is to be read as three breves.

LilyPond draws both a `\breve` and a `\longa` as a brevis head when descending final notes, and allows tweaking right-down-stem to disambiguate the latter:

```

\layout {
  \context {
    \Score
    \override SpacingSpanner.base-shortest-duration =
      #(ly:make-moment 16 1)
  }
}
\new PetrucciStaff {
  \clef "petrucci-c5"
  \[ \tweak right-down-stem ##t g\longa d\breve \]
  \[ a\breve \tweak right-down-stem ##t c'\maxima b\longa \]
  \[ a\longa b \tweak right-down-stem ##t a \]
}

```



(All examples are real; in fact the middle one was originally written as , and the stem is a later addition.)

17.4 Typesetting Gregorian chant

When typesetting a piece in Gregorian chant notation, the `Vaticana_ligature_engraver` automatically selects the proper note heads, so there is no need to explicitly set the note head style. Still, the note head style can be set, e.g., to `vaticana.punctum` to produce punctum neumes. Similarly, the `Mensural_ligature_engraver` automatically assembles mensural ligatures.

See also

Music Glossary: Section “ligature” in *Music Glossary*.


Notation Reference: Section 17.3.10 [White mensural ligatures], page 548, Section 17.2.2 [Ligatures], page 539.

17.4.1 Gregorian chant contexts

The predefined contexts `VaticanaScore`, `VaticanaVoice`, `VaticanaStaff`, and `VaticanaLyrics` can be used to engrave a piece of Gregorian chant in the style of the *Editio Vaticana*. These contexts initialize all relevant context and grob properties to proper values; you can immediately go ahead entering the chant, as the following excerpt demonstrates.

```
\new VaticanaScore {
  <<
    \new VaticanaVoice = "cantus" {
      \[ c'\melisma c' \flexa a \]
      \[ a \flexa \deminutum g\melismaEnd \]
      f \divisioMinima
      \[ f\melisma \pes a c' c' \pes d'\melismaEnd \]
      c' \divisioMinima \break
      \[ c'\melisma c' \flexa a \]
      \[ a \flexa \deminutum g\melismaEnd \] f \divisioMinima
    }
    \new VaticanaLyrics \lyricsto "cantus" {
      San -- ctus, San -- ctus, San -- ctus
    }
  >>
}

\layout {
  indent = 0
  ragged-last = ##t
}



San ctus, Sanctus,





San ctus


```

17.4.2 Gregorian clefs

The following table shows all Gregorian clefs that are supported via the `\clef` command. Some of the clefs use the same glyph, but differ only with respect to the line they are printed on. In such cases, a trailing number in the name is used to enumerate these clefs, numbered from the lowest to the highest line. Still, you can manually force a clef glyph to be typeset on an arbitrary line, as described in Section 1.3.1 [Clef], page 19. The note printed to the right side of each clef in the example column denotes the `c'` with respect to that clef.

Description	Supported Clefs	Example
Editio Vaticana style do clef	<code>vaticana-do1</code> , <code>vaticana-do2</code> , <code>vaticana-do3</code>	
Editio Vaticana style fa clef	<code>vaticana-fa1</code> , <code>vaticana-fa2</code>	
Editio Medicaea style do clef	<code>medicaea-do1</code> , <code>medicaea-do2</code> , <code>medicaea-do3</code>	

Editio Medicaea style fa clef	medicaea-fa1, medicaea-fa2	
Hufnagel style do clef	hufnagel-do1, hufnagel-do2, hufnagel-do3	
Hufnagel style fa clef	hufnagel-fa1, hufnagel-fa2	
Hufnagel style combined do/fa clef	hufnagel-do-fa	

See also


Music Glossary: Section “clef” in *Music Glossary*.

Notation Reference: Section 1.3.1 [Clef], page 19.

17.4.3 Gregorian accidentals and key signatures

Accidentals for the three different Gregorian styles are available:

vaticana medicaea hufnagel



As shown, not all accidentals are supported by each style. When trying to access an unsupported accidental, LilyPond will switch to a different style.

How to switch between styles is covered in Section 1.3.6 [Alternate accidental glyphs], page 39.

See also

Music Glossary: Section “accidental” in *Music Glossary*, Section “key signature” in *Music Glossary*.

Notation Reference: Chapter 1 [Pitches], page 3, Section 1.1.3 [Accidentals], page 8, Section 1.3.5 [Automatic accidentals], page 31, Section 1.3.6 [Alternate accidental glyphs], page 39, Section 1.3.2 [Key signature], page 24.

Internals Reference: Section “KeySignature” in *Internals Reference*.

17.4.4 Divisiones

There are no rests in Gregorian chant notation; instead, it uses divisiones.

A *divisio* (plural: *divisiones*; Latin word for ‘division’) is a staff-context symbol indicating the phrase and section structure of Gregorian music. The musical meaning of *divisio minima*, *divisio maior*, and *divisio maxima* can be characterized as short, medium, and long pause. The *finalis* sign not only marks the end of a chant, but is also frequently used within a single antiphonal/responsorial chant to mark the end of each section.

Some editions use *virgula* or *caesura* instead of *divisio minima*; the predefined staff contexts for Gregorian chant configure \caesura to produce an ancient caesura mark.



Predefined commands

`\virgula`, `\caesura`, `\divisioMinima`, `\divisioMaior`, `\divisioMaxima`, `\finalis`.

See also

Music Glossary: Section “caesura” in *Music Glossary*, Section “divisio” in *Music Glossary*.






Notation Reference: Section 3.2.3 [Breath marks], page 175.

17.4.5 Gregorian articulation signs

In addition to the standard articulation signs described in section Section 3.1.1 [Articulations and ornamentations], page 155, articulation signs specifically designed for use with notation in *Editio Vaticana* style are provided.

```
\new VaticanaScore {
  \new VaticanaVoice {
    \override Script.padding = -0.1
    a\ictus_"ictus " \break
    a\circulus_"circulus " \break
    a\semicirculus_"semicirculus " \break
    a\accentus_"accentus " \break
    \[ a_"episema" \epistemInitium \pes b
      \flexa a b \epistemFinis \flexa a \]
  }
}
```

```
\layout {
  indent = 0
  ragged-last = ##t
}
```



See also

Notation Reference: Section 3.1.1 [Articulations and ornamentations], page 155.

Snippets: Section “Ancient notation” in *Snippets*.

Internals Reference: Section “Episema” in *Internals Reference*, Section “EpisemaEvent” in *Internals Reference*, Section “Episema_engraver” in *Internals Reference*, Section “Script” in *Internals Reference*, Section “ScriptEvent” in *Internals Reference*, Section “Script_engraver” in *Internals Reference*.

Known issues and warnings

Some articulations are vertically placed too closely to the corresponding note heads.

17.4.6 Augmentum dots (*morae*)

Augmentum dots, also called *morae*, are added with the music function `\augmentum`. Note that `\augmentum` is implemented as a unary music function rather than as head prefix. It applies to the immediately following music expression only. That is, `\augmentum \virga c` will have no visible effect. Instead, say `\virga \augmentum c` or `\augmentum {\virga c}`. Also note that you can say `\augmentum {a g}` as a shortcut for `\augmentum a \augmentum g`.

```
\new VaticanaScore {
  \new VaticanaVoice {
    \[ \augmentum a \flexa \augmentum g \]
    \augmentum g
  }
}
```



See also

Notation Reference: Section 3.2.3 [Breath marks], page 175.

Internals Reference: Section “Divisio” in *Internals Reference*.

Snippets: Section “Ancient notation” in *Snippets*.

17.4.7 Gregorian square neume ligatures

There is limited support for Gregorian square neumes notation (following the style of the Editio Vaticana). Core ligatures can already be typeset, but essential issues for serious typesetting are still lacking, such as (among others) horizontal alignment of multiple ligatures, lyrics alignment, and proper handling of accidentals.

Note heads can be *modified* and/or *joined*.

- The shape of the note head can be modified by *prefixing* the note name with any of the following commands: `\virga`, `\strophæ`, `\inclinatum`, `\auctum`, `\descendens`, `\ascendens`, `\oriscus`, `\quilisma`, `\deminutum`, `\cavum`, `\linea`.
- Ligatures, properly speaking (i.e., notes joined together), are produced by placing one of the joining commands `\pes` or `\flexa`, for upwards and downwards movement, respectively, *between* the notes to be joined.

An alternative to `\pes` and `\flexa` (which internally do exactly the same) is the command `\~`.

A note name without any qualifiers will produce a *punctum*. All other neumes, including the single-note neumes with a different shape such as the *virga*, are in principle considered as ligatures and should therefore be placed between `\[...]`.

Single-note neumes

- The *punctum* is the basic note shape (in the *Vaticana* style: a square with some curvature for typographical finesse). In addition to the regular *punctum*, there is also the oblique *punctum inclinatum*, produced with the prefix `\inclinatum`. The regular *punctum* can be modified with `\cavum`, which produces a hollow note, and `\linea`, which draws vertical lines on either side of the note.
- The *virga* has a descending stem on the right side. It is produced by the modifier `\virga`.

Ligatures

Unlike most other neumes notation systems, the typographical appearance of ligatures is not directly dictated by the input commands, but follows certain conventions dependent on musical meaning. For example, a three-note ligature with the musical shape low-high-low, such as `\[ a \pes b \flexa g \]` (or `\[ a \~ b \~ g \]`), produces a Torculus consisting of three Punctum heads, while the shape high-low-high, such as `\[ a \flexa g \pes b \]` (or `\[ a \~ g \~ b \]`), produces a Porrectus with a curved flexa shape and only a single Punctum head. There is no command to explicitly typeset the curved flexa shape; the decision of when to typeset a curved flexa shape is based on the musical input. The idea of this approach is to separate the musical aspects of the input from the notation style of the output. This way, the same input can be reused to typeset the same music in a different style of Gregorian chant notation.

Liquescent neumes

Another main category of notes in Gregorian chant is the so-called liquescent neumes. They are used under certain circumstances at the end of a syllable which ends in a ‘liquescent’ letter, i.e., the sounding consonants that can hold a tone (the nasals, l, r, v, j, and their diphthong equivalents). Thus, the liquescent neumes are never used alone (although some of them can be produced), and they always fall at the end of a ligature.

Liquescent neumes are represented graphically in two different, more or less interchangeable ways: with a smaller note or by ‘twisting’ the main note upwards or downwards. The first is produced by making a regular pes or flexa and modifying the shape of the second note: `\[ a \pes \deminutum b \]`, the second by modifying the shape of a single-note neume with `\auctum` and one of the direction markers `\descendens` or `\ascendens`, e.g., `\[ \auctum \descendens a \]`.

Special signs

A third category of signs is made up of a small number of signs with a special meaning (which, incidentally, in most cases is only vaguely known): the *quilisma*, the *oriscus*, and the *strophicus*. These are all produced by prefixing a note name with the corresponding modifier, `\quilisma`, `\oriscus`, or `\strophica`.

Virtually, within the ligature delimiters `\[` and `\]`, any number of heads may be accumulated to form a single ligature, and head prefixes like `\pes`, `\flexa`, `\virga`, `\inclinatum`, etc., may be mixed in as desired. The use of the set of rules that underlies the construction of the ligatures in the above table is accordingly extrapolated. This way, infinitely many different ligatures can be created.

Note that the use of these signs in the music itself follows certain rules, which are not checked by LilyPond. E.g., the *quilisma* is always the middle note of an ascending ligature, and usually falls on a half-tone step, but it is perfectly possible, although incorrect, to make a single-note quilisma.

In addition to the note signs, LilyPond also defines the commands `\versus`, `\responsum`, `\ij`, `\iij`, `\IJ`, and `\IIJ`, that will produce the corresponding characters, e.g., for use in lyrics, as section markers, etc. These commands use special Unicode characters and will only work if a font is used which supports them.

The following table shows a limited, but still representative pool of Gregorian ligatures, together with the code fragments that produce the ligatures. The table is based on the extended neumes table of the 2nd volume of the Antiphonale Romanum (*Liber Hymnarius*), published 1983 by the monks of Solesmes. The first column gives the name of the ligature, with the main form in boldface and the liquescent forms in italics. The third column shows the code fragment that produces this ligature, using g, a, and b as example pitches.

Single-note neumes

Basic and <i>Liquescent</i> forms	Output	LilyPond code
Punctum	▪	<code>\[b \]</code>
	◻	<code>\[\cavum b \]</code>
	▣	<code>\[\linea b \]</code>
<i>Punctum Auctum Ascendens</i>	⌞	<code>\[\auctum \ascendens b \]</code>
<i>Punctum Auctum Descendens</i>	⌟	<code>\[\auctum \descendens b \]</code>
Punctum inclinatum	◆	<code>\[\inclinatum b \]</code>
<i>Punctum Inclinatum Auctum</i>	⌞	<code>\[\inclinatum \auctum b \]</code>
<i>Punctum Inclinatum Parvum</i>	◊	<code>\[\inclinatum \deminutum b \]</code>
Virga	┘	<code>\[\virga b' \]</code>

Two-note ligatures

Clivis vel Flexa	⌞	<code>\[b \flexa g \]</code> <code>(\[b \~ g \])</code>
<i>Clivis Aucta Descendens</i>	⌟	<code>\[b \flexa \auctum \descendens g \]</code>
<i>Clivis Aucta Ascendens</i>	⌞	<code>\[b \flexa \auctum \ascendens g \]</code>
<i>Cephalicus</i>	⌞	<code>\[b \flexa \deminutum g \]</code>
Podatus/Pes	⌞	<code>\[g \pes b \]</code> <code>(\[g \~ b \])</code>

<i>Pes Auctus Descendens</i>		<code>\[g \pes \auctum \descendens b \]</code>
<i>Pes Auctus Ascendens</i>		<code>\[g \pes \auctum \ascendens b \]</code>
<i>Epiphonus</i>		<code>\[g \pes \deminutum b \]</code>
<i>Pes Initio Debilis</i>		<code>\[\deminutum g \pes b \]</code>
<i>Pes Auctus Descendens Initio Debilis</i>		<code>\[\deminutum g \pes \auctum \descendens b \]</code>

Multi-note ligatures

Torculus		<code>\[a \pes b \flexa g \]</code> <code>(\[a \~ b \~ g \])</code>
<i>Torculus Auctus Descendens</i>		<code>\[a \pes b \flexa \auctum \descendens g \]</code>
<i>Torculus Deminutus</i>		<code>\[a \pes b \flexa \deminutum g \]</code>
<i>Torculus Initio Debilis</i>		<code>\[\deminutum a \pes b \flexa g \]</code>
<i>Torculus Auctus Descendens Initio Debilis</i>		<code>\[\deminutum a \pes b \flexa \auctum \descendens g \]</code>
<i>Torculus Deminutus Initio Debilis</i>		<code>\[\deminutum a \pes b \flexa \deminutum g \]</code>
Porrectus		<code>\[a \flexa g \pes b \]</code> <code>(\[a \~ g \~ b \])</code>
<i>Porrectus Auctus Descendens</i>		<code>\[a \flexa g \pes \auctum \descendens b \]</code>
<i>Porrectus Deminutus</i>		<code>\[a \flexa g \pes \deminutum b \]</code>

Climacus

$$\backslash[\backslash virga\ b\ \backslash inclinatum\ a\ \backslash inclinatum\ g\ \backslash]$$
Climacus Auctus

$$\backslash[\backslash virga\ b\ \backslash inclinatum\ a\ \backslash inclinatum\ \backslash auctum\ g\ \backslash]$$
Climacus Deminutus

$$\backslash[\backslash virga\ b\ \backslash inclinatum\ a\ \backslash inclinatum\ \backslash deminutum\ g\ \backslash]$$
Scandicus

$$\backslash[g\ \backslash pes\ a\ \backslash virga\ b\ \backslash]$$
Scandicus Auctus Descendens

$$\backslash[g\ \backslash pes\ a\ \backslash pes\ \backslash auctum\ \backslash descendens\ b\ \backslash]$$
Scandicus Deminutus

$$\backslash[g\ \backslash pes\ a\ \backslash pes\ \backslash deminutum\ b\ \backslash]$$

Special signs

Quilisma		<code>\[g \pes \quilisma a \pes b \]</code>
<i>Quilisma Pes Auctus Descendens</i>		<code>\[g \quilisma a \pes \auctum \descendens b \]</code>
Oriscus		<code>\[\oriscus b \]</code>
<i>Pes Quassus</i>		<code>\[\oriscus g \pes \virga b \]</code>
<i>Pes Quassus Auctus Descendens</i>		<code>\[\oriscus g \pes \auctum \descendens b \]</code>
Salicus		<code>\[g \oriscus a \pes \virga b \]</code>
<i>Salicus Auctus Descendens</i>		<code>\[g \oriscus a \pes \auctum \descendens b \]</code>
(Apo)stropha		<code>\[\stropha b \]</code>
<i>Stropha Aucta</i>		<code>\[\stropha \auctum b \]</code>
Bistropha		<code>\[\stropha b \stropha b \]</code>
Tristropha		<code>\[\stropha b \stropha b \stropha b \]</code>
<i>Trigonus</i>		<code>\[\stropha b \stropha b \stropha a \]</code>

Predefined commands

The following head prefixes are supported: `\virga`, `\stropha`, `\inclinatum`, `\auctum`, `\descendens`, `\ascendens`, `\oriscus`, `\quilisma`, `\deminutum`, `\cavum`, `\linea`.

Head prefixes can be accumulated, though restrictions apply. For example, either `\descendens` or `\ascendens` can be applied to a head, but not both to the same head.

Two adjacent heads can be tied together with the `\pes` and `\flexa` infix commands for a rising and falling line of melody, respectively. An alternative to these commands is using `\~`.

Use the unary music function `\augmentum` to add augmentum dots.

See also

Music Glossary: Section “ligature” in *Music Glossary*.

Notation Reference: Section 17.4.7 [Gregorian square neume ligatures], page 557, Section 17.3.10 [White mensural ligatures], page 548, Section 17.2.2 [Ligatures], page 539.

Known issues and warnings

When an `\augmentum` dot appears at the end of the last staff within a ligature, it is sometimes vertically placed wrong. As a workaround, add an additional skip note (e.g., `s8`) as last note of the staff.

`\augmentum` should be implemented as a head prefix rather than a unary music function, such that `\augmentum` can be intermixed with head prefixes in arbitrary order.

17.5 Typesetting Kievan square notation

17.5.1 Kievan contexts

As with Mensural and Gregorian notation, the predefined `KievanVoice` and `KievanStaff` contexts can be used to engrave a piece in square notation. These contexts initialize all relevant context properties and grob properties to proper values, so you can immediately go ahead entering the chant:

```
% Font settings for Cyrillic
\paper {
  property-defaults.fonts.serif = "Linux Libertine O,serif"
}

\score {
  <<
    \new KievanVoice = "melody" \relative c' {
      c4 c c c c2 b\longa \fine
    }
    \new Lyrics \lyricsto "melody" {
      Го -- спо -- ди по -- ми -- луй.
    }
  >>
}
```



Господи помилуй.

See also

Music Glossary: Section “Kievan notation” in *Music Glossary*.

Known issues and warnings

LilyPond supports Kievan notation of the Synodal style, as used in the corpus of chant books printed by the Russian Holy Synod in the 1910’s and recently reprinted by the Moscow Patriarchate Publishing House. LilyPond does not support the older (less common) forms of Kievan notation that were used in Galicia to notate Rusyn plainchant.

17.5.2 Kievan clefs

There is only one clef used in Kievan notation (the Tse-fa-ut Clef). It is used to indicate the position of c:

```
\clef "kievan-do"
\kievanOn
c'
```



See also

Music Glossary: Section “Kievan notation” in *Music Glossary*, Section “clef” in *Music Glossary*.

Notation Reference: Section 1.3.1 [Clef], page 19.

17.5.3 Kievan notes

For Kievan square notation, the appropriate note head style needs to be chosen and the flags and stems need to be turned off. This is accomplished by calling the `\kievanOn` function, which sets the appropriate properties of the note head, stems, and flags. Once Kievan note heads are not needed, these properties can be reverted by calling the `\kievanOff` function.

The Kievan final note, which usually comes at the end of a piece of music, may be selected by setting the duration to `\longa`. The Kievan recitative mark, used to indicate the chanting of several syllables on one note, may be selected by setting the duration to `\breve`. The following example demonstrates the various Kievan note heads:

```
\cadenzaOn
\kievanOn
b'1 b'2 b'4 b'8 b'\breve b'\longa
\kievanOff
b'2
```



See also

Music Glossary: Section “Kievan notation” in *Music Glossary*, Section “note head” in *Music Glossary*.

Notation Reference: Section B.9 [Note head styles], page 920.

Known issues and warnings

LilyPond automatically determines if the stem up or stem down form of a note is drawn. When setting chant in square notation, however, it is customary to have the stems point in the same direction within a single melisma. This can be done manually by setting the `direction` property of the `Stem` object.

17.5.4 Kievan accidentals

The kievan style provides a sharp and a flat sign different from the default style. There is no natural sign in Kievan notation. The sharp sign is not used in Synodal music but may occur in earlier manuscripts. It has been included primarily for the sake of compatibility.

```
\clef "kievan-do"
\set Staff.alterationGlyphs =
  #alteration-kievan-glyph-name-alist
bes' dis'
```



See also

Music Glossary: Section “Kievan notation” in *Music Glossary*, Section “accidental” in *Music Glossary*.

Notation Reference: Section 1.1.3 [Accidentals], page 8, Section 1.3.5 [Automatic accidentals], page 31, Section 1.3.6 [Alternate accidental glyphs], page 39, Section B.8 [The Emmentaler font], page 905.

17.5.5 Kievan bar lines

In a `KievanStaff`, there are no measures, but the `\caesura` command creates a phrase bar line, and the `\section` and `\fine` commands create a special section bar line.

```
\new KievanStaff {
  c'4 4 4 4 4 4 \caesura % \bar "."
  d'4 4 4 4 4 4 \section % \bar "k"
  e'4 4 4 4 4 4 \fine
}
```



See also

Notation Reference: Section 2.5 [Bars], page 120, Section B.8 [The Emmentaler font], page 905.

17.5.6 Kievan melismata

Notes within a Kievan melisma are usually placed close to each other and the melismata separated by whitespace. This is done to allow the chanter to quickly identify the melodic structures of *Znamenny chant*. In LilyPond, melismata are treated as ligatures and the spacing is implemented by the `Kievan_ligature_engraver`.

When the `KievanVoice` and `KievanStaff` contexts are used, the `Kievan_ligature_engraver` is enabled by default. In other contexts, it can be invoked by replacing the `Ligature_bracket_engraver` with the `Kievan_ligature_engraver` in the layout block:

```
\layout {
  \context {
    \Voice
    \remove Ligature_bracket_engraver
    \consists Kievan_ligature_engraver
  }
}
```

The spacing between the notes within a Kievan ligature can be controlled by setting the padding property of the `KievanLigature`.

The following example demonstrates the use of Kievan ligatures:

```
% Font settings for Cyrillic
\paper {
  property-defaults.fonts.serif = "Linux Libertine O,serif"
}

\score {
  <<
    \new KievianVoice = "melody" \relative c' {
      e2 \[ e4( d4 ) \] \[ c4( d e d) \] e1 \fine
    }
    \new Lyrics \lyricsto "melody" {
      Га -- ври -- и -- лу
    }
  >>
}
```



See also

Music Glossary: Section “ligature” in *Music Glossary*.

Notation Reference: Section 17.3.10 [White mensural ligatures], page 548, Section 17.4.7 [Gregorian square neume ligatures], page 557, Section 17.2.2 [Ligatures], page 539.

Known issues and warnings

Horizontal spacing of ligatures is poor.

17.6 Working with ancient music – scenarios and solutions

Working with ancient music frequently involves particular tasks which differ considerably from the modern notation for which LilyPond is designed. In the rest of this section, a number of typical scenarios are outlined, with suggestions of solutions. These involve:

- how to make incipits (i.e., prefatory material to indicate what the original has looked like) to modern transcriptions of mensural music;
- how to achieve the *Mensurstriche* layout frequently used for modern transcriptions of polyphonic music;
- how to transcribe Gregorian chant in modern notation;
- how to generate both ancient and modern notation from the same source.

17.6.1 Incipits

It is customary when transcribing mensural music into modern notation to place an indication of how the initial rests and note or notes of the original version appeared – including the original clefs. This is called an *incipit*. The `\incipit` command uses the indent of the main staff to set the width occupied by the incipit together with the instrument name, and `incipit-width` to set the width of the incipit staff. An optional argument indicates how much the incipit should be shifted to the left.

```

\score {
  \new Staff <<
    \new Voice = Tenor {
      \set Staff.instrumentName = "Tenor"
      \override Staff.InstrumentName.self-alignment-X = #RIGHT
      \incipit #1 { \clef "mensural-c4" \key f \major r\breve r1 c'1 }
      \clef "treble_8"
      \key f \major
      R1 r2 c'2 |
      a4. c'8
    }
    \new Lyrics \lyricsto Tenor { Cyn -- thia your }
  >>
  \layout
  {
    indent = 5\cm
    incipit-width = 3\cm
  }
}

```



By default, LilyPond uses a ‘MensuralStaff’ context for typesetting an incipit. Other contexts can be used by directly writing `\incipit \new contexttype ...`; in this case a ‘MensuralStaff’ wrapper is only used when it can contain the specified context.

Known issues and warnings

Note that `instrumentName` must be set in the music for the incipit to be produced. If no instrument name is required then use `\set Staff.instrumentName = ""`.

17.6.2 Mensurstriche layout

Mensurstriche (‘mensuration lines’) is the accepted term for bar lines that are drawn between the staves of a system but not through the staves themselves. It is a common way to preserve the rhythmic appearance of the original, i.e., not having to break syncopated notes at bar lines, while still providing the orientation aids that bar lines give.

Mensurstriche, bar lines between but not through staves, can be printed by setting `measureBarType` to `"-span|"` and using a grouping context that allows span bars, such as `StaffGroup`.

```

\layout {
  \context {
    \Staff
    measureBarType = "-span|"
  }
}

music = \fixed c'' {
  c1
  d2 \section e2
  f1 \fine
}


```

```

}

\new StaffGroup <<
  \new Staff \music
  \new Staff \music
>>

```



17.6.3 Transcribing Gregorian chant

Gregorian chant can be transcribed into modern notation with a number of simple tweaks.

Stems. The `GregorianTranscriptionVoice` context does not create stems. You can extend this behavior to other contexts by removing `Stem_engraver`:

```

\layout {
  ...
  \context {
    \Voice
    \remove Stem_engraver
  }
}

```

Timing. For unmetered chant, there are several alternatives.

The `Time_signature_engraver` can be removed from the `Staff` context without any negative side effects. The alternative, to make it transparent, will leave an empty space in the score, since the invisible signature will still take up space.

In many cases, `\set Score.timing = ##f` will give good results. An alternative is to use `\cadenzaOn` and `\cadenzaOff`.

The predefined staff contexts for ancient music do not create measure bar lines. You can extend this behavior to all other contexts with `\set Score.measureBarType = #'()` or to particular staves with `\set Staff.measureBarType = #'()`.

The predefined staff contexts for ancient music allow line breaks without bar lines. You can extend this behavior to all other contexts with `\set Score.forbidBreakBetweenBarLines = ##f` or to particular staves with `\set Staff.forbidBreakBetweenBarLines = ##f`.

A common type of transcription is recitativic chant where the repeated notes are indicated with a single breve. The text to the recitation tone can be dealt with in two different ways: either set as a single, left-aligned syllable:

```

chant = \relative {
  \clef "G_8"
  c'\breve c4 b4 a c2 c4 \divisioMaior
  c'\breve c4 c f, f \finalis
}

words = \lyricmode {
  \tweak self-alignment-X #LEFT "Noctem quietam et"
  fi -- nem per -- fec -- tum
  \tweak self-alignment-X #LEFT "concedat nobis Dominus"
}


```

```

    om -- ni -- po -- tens.
}

\score {
  \new GregorianTranscriptionStaff <<
    \new GregorianTranscriptionVoice = "melody" {
      \chant
    }
    \new GregorianTranscriptionLyrics = "one" {
      \lyricsto "melody" \words
    }
  >>
}

```



This works fine, as long as the text doesn't span a line break. If that is the case, an alternative is to add hidden notes to the score, as below.

In some transcription styles, stems are used occasionally, for example to indicate the transition from a single-tone recitative to a fixed melodic gesture. In these cases, one can use the `Stem_engraver` and manually `\omit Stem` and `\undo \omit Stem`.

```

chant = \relative {
  \clef "G_8"
  \omit Stem
  \omit Flag
  c'\breve*1/16 \hide NoteHead c8 c c c c
  \undo \hide NoteHead
  \undo \omit Stem \stemUp c4 b4 a
  \omit Stem c2 c4 \divisioMaior
  c\breve*1/16 \hide NoteHead c8 c c c c c c
  \undo \hide NoteHead c4 c f, f \finalis
}

verba = \lyricmode {
  No -- ctem qui -- e -- tam et fi -- nem per -- fec -- tum
  con -- ce -- dat no -- bis Do -- mi -- nus om -- ni -- po -- tens.
}

\score {
  \new GregorianTranscriptionStaff <<
    \new GregorianTranscriptionVoice = "melody" {
      \chant
    }
    \new GregorianTranscriptionLyrics = "one" {
      \lyricsto "melody" \verba
    }
  >>
}

```



```

    }
  >>
  \layout {
    \context {
      \GregorianTranscriptionVoice
      \consists Stem_engraver
    }
  }
}

```



Another common situation is transcription of neumatic or melismatic chants, i.e., chants with a varying number of notes to each syllable. In this case, one would want to set the syllable groups clearly apart, usually also the subdivisions of a longer melisma. One way to achieve this is to use a fixed `\time`, e.g., `1/4`, and let each syllable or note group fill one of these measures, with the help of tuplets or shorter durations. If the bar lines and all other rhythmical indications are made transparent, and the space around the bar lines is increased, this will give a fairly good representation in modern notation of the original.

To avoid that syllables of different width (such as “-ri” and “-rum”) spread the syllable note groups unevenly apart, the `X-extent` property of the `LyricText` object may be set to a fixed value. Another, more cumbersome way would be to add the syllables as `\markup` elements. If further adjustments are necessary, this can be easily done with `s ‘notes’`.

```

spiritus = \relative {
  \time 1/4
  d'4 \tuplet 3/2 { f8 a g } g a a4 g f8 e
  d4 f8 g g8 d f g a g f4 g8 a a4 s
  \tuplet 3/2 { g8 f d } e f g a g4
}

spirLyr = \lyricmode {
  \override Lyrics.LyricText.X-extent = #'(0 . 3)
  Spi -- ri -- _ _ tus _ Do -- mi -- ni _
  re -- ple -- _ vit _ or -- _ bem _ ter -- ra -- _ rum,
  al -- _ _ le -- _ lu -- _ ia.
}

\score {
  \new GregorianTranscriptionStaff <<
    \new GregorianTranscriptionVoice = "chant" {
      \spiritus
    }
    \new GregorianTranscriptionLyrics = "one" {
      \lyricsto "chant" \spirLyr
    }
  >>
}

```

```

\layout {
  \context {
    \GregorianTranscriptionStaff
    measureBarType = ""
    \override BarLine.X-extent = #'(-1 . 1)
    \hide TupletNumber
    \hide TupletBracket
  }
}

```



17.6.4 Ancient and modern from one source

Using tags to produce mensural and modern music from the same source

Using tags it is possible to produce both mensural and modern notation from the same music. In this snippet, a function `\menrest` is introduced, allowing mensural rests to be pitched as in the original, but with modern rests in the standard staff position.

Tags can also be used where other differences are needed: for example using “whole measure rests” (`R1`, `R\breve`, etc.) in modern music, but normal rests (`r1`, `r\breve`, etc.) in the mensural version. Converting mensural music to its modern equivalent is usually referred to as *transcription*.

The call `c4.\Be c8 c\Am` is the same as `c4.[ c8 c]`. However, it suppresses warnings if it starts on a note that can’t hold a beam but needs it anyway due to the use of `Completion_heads_engraver`.

[Note that the custos sticks out into the right margin and might be cut off if the LilyPond output gets cropped tightly. The use of `\with-true-dimensions` below avoids this.]

```

\layout {
  line-width = 150\mm
}

menrest = #(define-music-function (note) (ly:music?)
  #{
    \tag #'mens $(make-music 'RestEvent note)
    \tag #'mod $(make-music 'RestEvent note 'pitch '())
  #})

Be = \tag #'mod
  #(begin
    (ly:expect-warning (G_ "stem does not fit in beam"))
    (ly:expect-warning (G_ "beam was started here"))
    (make-span-event 'BeamEvent START))

Am = \tag #'mod ]

```

```

MenStyle = {
  \override Score.BarNumber.transparent = ##t
  \override Stem.neutral-direction = #up
  \omit Slur
  \omit Beam
}

finalis = \section

Music = \relative c'' {
  \key f \major
  g1 d'2 \menrest bes4 bes a2 \menrest r4 g4 fis4. fis8 fis4 fis \break
  g e f4.([ g8] a4[ g8 f] g2.\Be fis8 e\Am fis2) g\breve \finalis
}

MenLyr = \lyricmode {
  So farre, deere life, deare life,
  from thy bright beames ab- en- ted,
}
ModLyr = \lyricmode {
  So far, dear life, dear life,
  from your bright beams ab -- sen -- ted, --
}

\score {
  \keepWithTag #'mens {
    <<
    \new PetrucciStaff {
      \new PetrucciVoice = "Cantus" {
        \clef "petrucci-c1" \time 4/4 \MenStyle \Music
      }
    }
    \new Lyrics \lyricsto "Cantus" \MenLyr
  } >>
}
\layout {
  \context {
    \PetrucciVoice
    % No longer necessary starting with version 2.25.23.
    \override Flag.style = #'mensural
  }
}

\markup\vspace #1

\score {
  \keepWithTag #'mod {
    \new ChoirStaff <<
    \new Staff {
      \new Voice = "Sop" \with {

```

```

\remove "Note_heads_engraver"
\consists "Completion_heads_engraver"
\remove "Rest_engraver"
\consists "Completion_rest_engraver"
} \shiftDurations 1 0 { \time 2/4 \autoBeamOff \Music }
}
\new Lyrics \lyricsto "Sop" \ModLyr
>>
}
}

```



So farre, deere life, deare life, from thy bright



beames ab-fen- ted,



So far, dear life, dear life, from your bright



beams ab-sen - - - ted,___

18 World music

The purpose of this section is to highlight musical notation issues that are relevant to traditions outside the Western tradition.

18.1 Common notation for non-Western music

This section discusses how to enter and print music scores that do not belong to the Western classical tradition, also referred to as *Common Practice Period*.

18.1.1 Extending notation and tuning systems

Standard classical notation (also known as *Common Practice Period* notation) is commonly used in all sorts of music, not limited to ‘classical’ Western music. This notation is discussed in Section 1.1 [Writing pitches], page 3, and the various note names that may be used are explained in Section 1.1.5 [Note names in other languages], page 10.

Some types of non-Western music and folk/traditional music often employ alternative or extended tuning systems that do not fit easily into standard, classical notation.

Standard notation is still used but with pitch differences being implicit. For example, *Arabic music* is notated with semi and quarter tone accidentals but with precise pitch alterations being determined by context. In the case of *Arabic music*, the init file `arabic.ly` provides a suitable set of macros and definitions that extend the standard notation using Italian note names. For more details see Section 18.2 [Arabic music], page 574.

Other types of music require extended or unique notations, for example, *Turkish classical music* (also known as Ottoman classical music) employs melodic forms known as *makamlar* where intervals are based on 1/9 divisions of the whole tone. Standard, Western staff notes are still used, but with special accidentals uniquely defined in the files `turkish-makam.ly`. For more information on Turkish classical music and *makamlar* see Section 18.3 [Turkish classical music], page 580.

Other, related init files are also available; `hel-arabic.ly` and `makam.ly`.

To locate these init files on your system, see Section “Other sources of information” in *Learning Manual*.

See also

Music Glossary: Section “Common Practice Period” in *Music Glossary*, Section “makamlar” in *Music Glossary*.

Learning Manual: Section “Other sources of information” in *Learning Manual*.

Notation Reference: Section 1.1 [Writing pitches], page 3, Section 1.1.5 [Note names in other languages], page 10, Section 18.2 [Arabic music], page 574, Section 18.3 [Turkish classical music], page 580, Section 18.4 [Persian classical music], page 582.

18.2 Arabic music

This section highlights issues that are relevant to notating Arabic music.

18.2.1 References for Arabic music

Arabic music so far has been mainly an oral tradition. When music is transcribed, it is usually in a sketch format, on which performers are expected to improvise significantly. Increasingly, Western notation, with a few variations, is adopted in order to communicate and preserve Arabic music.

Some elements of Western musical notation such as the transcription of chords or independent parts, are not required to typeset the more traditional Arabic pieces. There are however some

different issues, such as the need to indicate medium intervals that are somewhere between a semi-tone and a tone, in addition to the minor and major intervals that are used in Western music. There is also the need to group and indicate a large number of different maqams (modes) that are part of Arabic music.

In general, Arabic music notation does not attempt to precisely indicate microtonal elements that are present in musical practice.

Several issues that are relevant to Arabic music are covered elsewhere:

- Note names and accidentals (including quarter tones) can be tailored as discussed in Section 18.1 [Common notation for non-Western music], page 574.
- Additional key signatures can also be tailored as described in Section 1.3.2 [Key signature], page 24.
- Complex time signatures may require that notes be grouped manually as described in Section 2.4.3 [Manual beams], page 114.
- *Takasim* which are rhythmically free improvisations may be written down omitting bar lines as described in Section 2.3.5 [Unmetered music], page 91.

See also

Notation Reference: Section 18.1 [Common notation for non-Western music], page 574, Section 1.3.2 [Key signature], page 24, Section 2.4.3 [Manual beams], page 114.

Snippets: Section “World music” in *Snippets*.

18.2.2 Arabic note names

Traditional Arabic note names (like ‘rast’, ‘dukah’, ‘sukah’, etc.) can be quite long and so may not always be suitable for the purpose of music writing.

Include the file `arabic.ly` to write Arabic sheet music. The following example demonstrates how to write a ‘rast’ scale:

```
\include "arabic.ly"
\relative {
  \key do \rast
  do' re misb fa | sol la sisb do | sib la sol fa | misb re do
}
```



The file `arabic.ly` sets the note language to Italian (or Solfege), since that is the modern standard in Arabic music and is widely adopted among Arabic musicians. If you prefer to write sheet music in another language, simply change the language to your preferred language directly after including the file `arabic.ly`. This is a ‘rast’ scale with English note names:

```
\include "arabic.ly"
\language "english"
\relative {
  \key c \rast
  c' d eqf f | g a bqf c | bf a g f | eqf d c
}
```



“Rast” is a heptatonic scale that uses quarter tone intervals and is considered the most important and central scale of the “Arabic Maqamat”. For the full list of supported Arabic scales, see Section 18.2.3 [Arabic key signatures], page 576.

The use of standard Western notation to notate non-Western music is discussed in Section 18.1 [Common notation for non-Western music], page 574. Also see Section 1.1.5 [Note names in other languages], page 10.

The symbol for semi-flat does not match the symbol which is used in Arabic notation. The `\dwn` symbol defined in `arabic.ly` may be used preceding a flat symbol as a work around if it is important to use the specific Arabic semi-flat symbol. The appearance of the semi-flat symbol in the key signature cannot be altered by using this method.

```
\include "arabic.ly"
\relative {
  \set Staff.extraNatural = ##f
  dod' dob dosd \dwn dob dobsb dodsd do do
}
```



See also

Notation Reference: Section 1.1.5 [Note names in other languages], page 10, Section 18.1 [Common notation for non-Western music], page 574, Section 22.1 [Including LilyPond files], page 625.

Installed Files: `ly/arabic.ly`

Snippets: Section “World music” in *Snippets*.

18.2.3 Arabic key signatures

In addition to the minor and major key signatures, LilyPond provides the most common Arabic key signatures in the file `arabic.ly`. With that being said LilyPond is not aiming at providing a full suite of all possible maqams. It rather defines the most common ones that are frequently used and offers key signatures by grouping maqams together. In general, a maqam uses the key signature of its family, or a neighboring family, and varying accidentals are marked throughout the music. When forming key signatures neighboring maqam families are grouped together. For example, maqam *saba* seldom occurs outside of the context of maqam *bayati* and adds only a single alteration. Although both maqams come from different *maqam families* they are inside the same key signature *group*. Arabic maqams only allow for limited modulations, due to the nature of Arabic musical instruments.

Here is an example of the key signature for a “maqam muhayer” piece of music:

```
\key re \bayati
```

Here *re* is the default pitch of the muhayer maqam, and *bayati* is the name of the base maqam in the group.

While the key signature indicates the group, it is common for the title to indicate the more specific maqam, so in this example, the name of “maqam muhayer” should also appear in the title.

Other maqams in the same *bayati* group, as shown in the table below (e.g., *bayati*, *hussaini*, *saba*, and *ushaq*) can be indicated in the same way. These are all variations of the base and most common maqam in the group, which is *bayati*. They usually differ from the base maqam in their upper tetrachords, or certain flow details that do not change their fundamental nature, as siblings.

The other maqam in the same group (*nawa*) is related to *bayati* by modulation and is shown in the table in parentheses for those that are modulations of their base maqam. *Nawa*, for example, can be indicated as follows:

```
\key sol \bayati
```

In Arabic music, the same term, for example *bayati*, that is used to indicate a maqam family, is also a maqam that is usually the most important in the family so can also be thought of as a *base maqam*.

Here is the grouping that maps the more common maqams to key signatures as defined in the file `arabic.ly`:

maqam group	key	finalis	Other maqams in group (finalis)
ajam	major	sib	jaharka (fa)
bayati	bayati	re	hussaini, muhayer, saba, ushaq, nawa (sol)
hijaz	hijaz	re	zanjaran (do)
hijaz kar	hijaz_kar	do	shahnaz, shad arban (sol)
huzam	huzam	misb	-
iraq	iraq	sisb	-
kurd	kurd	re	hijazkar kurd (do)
nahawand	minor	do	busalik (re), farah faza (sol)
nakriz	nakriz	do	nawa athar, hisar (re)
rast	rast	do	mahur, yakah (sol)
sikah	sikah	misb	-

In case you are missing a specific maqam, you can define it yourself in your sheet music before using it. The following example defines and then uses the *zanjaran* maqam.

```
\include "arabic.ly"

% For example on do: do reb mi fa sol la sib do
% reb and sib are FLAT
% You can also use SHARP, SEMI-FLAT, SEMI-SHARP
zanjaran = #` (
  (0 . ,NATURAL)
  (1 . ,FLAT)
  (2 . ,NATURAL)
  (3 . ,NATURAL)
  (4 . ,NATURAL)
  (5 . ,NATURAL)
  (6 . ,FLAT)
)

\relative {
  \key do \zanjaran
  do' reb mi fa sol la sib do
}
```



For special cases, rare maqams are defined in the `hel-arabic.ly` file. Please refer to the file included with LilyPond for a full list of the provided maqams.

Selected snippets

Non-traditional key signatures

The commonly used `\key` command sets the `keyAlterations` property, in the `Staff` context.

To create non-standard key signatures, set this property directly. The format of this command is a list:

```
\set Staff.keyAlterations =
  #`(((octave . step) . alter) ((octave . step) . alter) ...)
```

where, for each element in the list, *octave* specifies the octave (0 being the octave from middle C to the B above), *step* specifies the note within the octave (0 means C and 6 means B), and *alter* is one of SHARP, FLAT, DOUBLE-SHARP, etc., preceded by a comma.

Alternatively, you can use the more concise format (*step . alter*) for each item in the list if the same alterations are used in all octaves.

For microtonal scales where a “sharp” is not 100 cents, *alter* refers to the alteration as a proportion of a 200-cent whole tone.

```
\include "arabic.ly"

\relative do' {
  \set Staff.keyAlterations = #`((0 . ,SEMI-FLAT)
                                (1 . ,SEMI-FLAT)
                                (2 . ,FLAT)
                                (5 . ,FLAT)
                                (6 . ,SEMI-FLAT))

  % \set Staff.extraNatural = ##f
  re reb \down reb resd
  dod dob dosd \down dob |
  dobsb dodsd do do |
}
```



See also

Music Glossary: Section “maqam” in *Music Glossary*, Section “bayati” in *Music Glossary*, Section “rast” in *Music Glossary*, Section “sikah” in *Music Glossary*, Section “iraq” in *Music Glossary*, Section “kurd” in *Music Glossary*.

Learning Manual: Section “Pitches and key signatures” in *Learning Manual*.

Notation Reference: Section 1.3.2 [Key signature], page 24.

Installed Files: `ly/arabic.ly` `ly/hel-arabic.ly`

Snippets: Section “World music” in *Snippets*, Section “Pitches” in *Snippets*.

Internals Reference: Section “KeySignature” in *Internals Reference*.

18.2.4 Arabic time signatures

Some Arabic and Turkish music classical forms such as *Semai* use unusual time signatures such as 10/8. This may lead to an automatic grouping of notes that is quite different from existing typeset music, where notes may not be grouped on the beat, but in a manner that is difficult to match by adjusting automatic beaming. The alternative is to switch off automatic beaming and beam the notes manually. Even if a match to existing typeset music is not required, it may still be desirable to adjust the automatic beaming behavior and/or use complex time signatures.


Selected snippets

Arabic improvisation

For improvisations or *taqasim* which are temporarily free, the time signature can be omitted and `\cadenzaOn` can be used. Adjusting the accidental style might be required, since the absence of bar lines causes the accidental to be marked only once. Here is an example of what could be the start of a *hijaz* improvisation.

```
\include "arabic.ly"

\relative sol' {
  \key re \kurd
  \accidentalStyle forget
  \cadenzaOn
  sol4 sol sol sol fad mib sol1 fad8 mib re4. r8 mib1 fad sol
}
```



See also

Music Glossary: Section “semai” in *Music Glossary*, Section “taqasim” in *Music Glossary*.

Notation Reference: Section 2.4.3 [Manual beams], page 114, Section 2.4.1 [Automatic beams], page 101, Section 2.3.5 [Unmetered music], page 91, Section 1.3.5 [Automatic accidentals], page 31, Section 2.4.2 [Setting automatic beam behavior], page 104, Section 2.3.2 [Time signature], page 79.

Installed Files: `ly/arabic.ly`

Snippets: Section “World music” in *Snippets*.

18.2.5 Arabic music example

Here is a template that also uses the start of a Turkish *Semai* that is familiar in Arabic music education in order to illustrate some of the peculiarities of Arabic music notation, such as medium intervals and unusual modes that are discussed in this section.

```
\include "arabic.ly"
\score {
  \header {
    title = "Semai Muhayer"
    composer = "Jamil Bek"
  }
  \relative {
    \set Staff.extraNatural = ##f
    \set Staff.autoBeaming = ##f
    \key re \bayati
    \time 10/8

    re'4 re'8 re16 [misb re do] sisb [la sisb do] re4 r8
    re16 [misb do re] sisb [do] la [sisb sol8] la [sisb] do [re] misb
    fa4 fa16 [misb] misb8. [re16] re8 [misb] re [do] sisb
    do4 sisb8 misb16 [re do sisb] la [do sisb la] la4 r8
  }
}
```

}



See also

Installed Files: `ly/arabic.ly`

Snippets: Section “World music” in *Snippets*.

18.2.6 Further reading for Arabic music

There are some variations in the details of how maqams are grouped, despite agreement of grouping maqams related through common lower tetra chords or by modulation. There are also some inconsistencies, even within the same texts, on how key signatures for a particular maqam should be specified. However, it is common to use a key signature per ‘group’ of maqams instead of individual key signatures for each maqam separately.

- *The music of the Arabs* by Habib Hassan Touma [Amadeus Press, 1996], contains a discussion of maqams and their method of groupings.
- There are also some web sites that explain maqams and even provide audio examples:
 - <https://www.maqamworld.com/>
 - <https://www.turath.org/>
- Method books by the following authors for the oud (the Arabic lute) contain examples of mainly Turkish and Arabic compositions.
 - Charbel Rouhana
 - George Farah
 - Ibrahim Ali Darwish Al-masri

18.3 Turkish classical music

This section highlights issues that are relevant to notating Turkish classical music.

18.3.1 References for Turkish classical music

Turkish classical music developed in the Ottoman Empire at roughly the same time as classical music in Europe, and has continued on into the 20th and 21st centuries as a vibrant and distinct tradition with its own compositional forms, theory and performance styles. Among its striking features is the use of microtonal intervals based on ‘commas’ of $1/9$ of a tone, from which are constructed the melodic forms known as *makam* (plural *makamlar*) are constructed.

Some issues relevant to Turkish classical music are covered elsewhere. Special note names and accidentals are explained in Section 18.1 [Common notation for non-Western music], page 574.

18.3.2 Turkish note names

Pitches in Turkish classical music traditionally have unique names and the basis of pitch on $1/9$ -tone divisions means that makamlar employ a completely different set of intervals compared to Western scales and modes:

From a modern, notational point of view it is convenient to use standard, Western staff notes (c, d, e, etc.) but with custom accidentals that raise or lower notes by intervals of $1/9$, $4/9$, $5/9$ or $8/9$ of a tone.

These custom accidentals are defined in the file `turkish-makam.ly`.

For a more general explanation of non-Western music notation, see Section 18.1 [Common notation for non-Western music], page 574.

See also

Music Glossary: Section “makam” in *Music Glossary*, Section “makamlar” in *Music Glossary*.

Notation Reference: Section 18.1 [Common notation for non-Western music], page 574.

18.3.3 Turkish key signatures

LilyPond supports over 200 makam key signature definitions – well beyond what is used in Turkish classical music – with each makam having its own specific tonic / finalis pitch (known as ‘karar’ in Turkish).

It is important to be aware of the finalis of each makam. Here is an example where *g* is the default tonic and *rast* is the name of the makam.

```
\key g \rast
```

The correct accidentals, koma flat (*b1*) and koma sharp (*f4*), (both in relation to the tonic *g*), will be displayed automatically.

Selected snippets

Turkish Makam example

This template uses the start of a well-known Turkish *Saz Semai* that is familiar in the repertoire in order to illustrate some of the elements of Turkish music notation.

```
#(set-default-paper-size "a6" 'landscape)

\include "turkish-makam.ly"

\header {
  title = "Hüseyin Saz Semaisi"
  composer = "Lavtacı Andon"
  tagline = ##f
}

\relative {
  \set Staff.extraNatural = ##f
  \set Staff.autoBeaming = ##f

  \key a \huseyni
  \time 10/8

  a'4 g'16[ fb] e8.[ d16] d[ c d e] c[ d c8] bfc |
  a16[ bfc a8] bfc c16[ d c8] d16[ e d8] e4 fb8 |
  d4 a'8 a16[ g fb e] fb8[ g] a8.[ b16] a16[ g] |
  g4 g16[ fb] fb8.[ e16] e[ g fb e] e4 r8 |
}

\layout {
  indent = 0
}
```

Hüseyin Saz Semaisi

Lavtacı Andon



18.3.4 Further reading for Turkish music

- *Türk Musikisi Nazariyati ve Usulleri: Kudum Velveleleri* by İsmail Hakkı Özkan [(Kültür serisi, 41) (Turkish) Paperback – 1986]
contains information about the theory of makams and usul.
- *Music of the Ottoman Court* by Walter Feldman [VWB Hardback – 1996]
contains information about the history of Ottoman court music.
- *Turkish Music Makam Guide* by Murat Aydemir [Pan Paperback – 2010]
contains information in English regarding Turkish makam including two CDs.

18.4 Persian classical music

This section highlights issues that are relevant to notating Persian classical music.

18.4.1 Persian music notation

The notation for Persian classical music commonly uses two accidentals for microtones, *sori* and *koron*. Invented by Ali-Naqi Vaziri around 1935, they indicate raising and lowering a pitch by (approximately) a quarter tone, respectively.

sori	koron
♯	♭

The file `persian.ly`¹ provides support for *koron* and *sori*; they can be obtained by appending ‘k’ (*koron*) and ‘o’ (*sori*) to the English note symbols.

LilyPond supports tunings for all major Persian modes in all keys, sufficient to notate the *gushehs* (central nuclear melodies) of all *dastgahs* (musical modal systems).

The note immediately following a *koron* is sometimes² lowered by about 20 cents. This is not notated but considered part of the tuning. However, for getting better MIDI support you can make a sound flat by appending ‘v’ to the note name (‘*vlat*’). This note should actually also get a strong vibrato, and the vibrato and low tuning are perceptually integrated (*serialism*). This is just for MIDI and has no effect on the notation itself.

There are no further tuning issues in Persian music. Since the music is monophonic, the difference between just intonation (for example) and equal temperament is merely academic – there are no chords where out-of-tune intervals would be noticeable.

The following suffixes to English note names are provided.

¹ There exists another, older support file for Persian classical music also called `persian.ly` (written by Kees van den Doel) that no longer works with the current LilyPond version; while note names are compatible, the selection of key signatures is not.

² If the interval defined by the note before the *koron* and after the *koron* is a minor third. The same is true for the note below the finalis in the ‘Esfahan’ *dastgah* according to some (but not all) Persian musicians.

ff	double-flat
f	flat
k	koron (about quarter flat, -3/10 of whole tone, 60 cents)
o	sori (about quarter sharp, 2/10 of whole tone, 40 cents)
s	sharp
x	double-sharp
v	20 cent flat-tuned note (“vlat”, not notated)
fv	flat, tuned 20 cents down (notated as a normal flat)
sv	sharp, tuned 20 cents down (notated as a normal sharp; does never occur in traditional Persian music)

18.4.2 Persian tunings

Dastgahs can have many tunings; it has become common to name tunings after representative dastgahs featuring them. The following Persian tunings are provided to be used as the second argument of the `\key` command. Note that in practice not all tunings are used in all keys.

<code>\shur</code>	‘Shur’ gushehs with natural 5th degree
<code>\shurk</code>	‘Shur’ gushehs with koron 5th degree
<code>\esfahan</code>	
<code>\mokhalefsegah</code>	
<code>\chahargah</code>	
<code>\mahur</code>	the same as <code>\major</code> but used in a completely different context
<code>\delkashMahur</code>	

In dastgah ‘Shur’, the 5th degree can either be natural or koron, so two tunings are provided (\shur, \shurk). Secondary dastgahs ‘Dashti’, ‘Abuata’, and ‘Bayat-e-tork’ use \shur, the derived dastgah ‘Afshari’ uses \shurk. ‘Nava’ on G is like ‘Shur’ on D (a 4th apart). The tuning of ‘Segah’ is \shurk. Other tunings are \esfahan (‘Homayoun’ on C is like ‘Esfahan’ on G, a 5th apart), \chahargah, and \mokhalefsegah. For dastgahs ‘Mahur’ and ‘Rast-panjgah’ the same tuning \mahur can be used.

All the various modulatory gushehs in all dastgahs can be notated with these tunings, with the exception of ‘Delkash’ in ‘Mahur’, but traditionally the peculiar accidentals there are notated explicitly (however, `persian.ly` also defines a tuning `\delkashMahur`).

As an example, Chahargah in D can be input with the following.

```
\include "persian.ly"
```

```
\relative c' {
  \key d \chahargah
  bk'8 a gs fo r g ak g |
  fs ek d c d ef16 d c4 |
}
```



18.4.3 Persian key signatures

By default, the order of accidentals in Persian key signatures is flats followed by korons, then sharps followed by soris (then double flats, then double sharps).

An alternative key order, similar to the one used in `turkish-makam.ly`, can be selected. Here, the order is flats or korons (or double flats), then sharps or soris (or double sharps). In other words, korons and soris are handled equal to flats and sharps, respectively.

```

\include "persian.ly"

{
  \key b \chahargah b'1 |
  \set Staff.keyAlterationOrder = \persianAltKeyAlterationOrder
  \key b \chahargah b'1 |
}

```



18.4.4 Further reading on Persian music

- *Traditional Persian Art Music* by Dariush Tala'i [Bibliotheca Persica, Costa Mesa CA, 2000]
The provided Persian tunings closely follow this book.
- *The Dastgah Concept in Persian Music* by Hormoz Farhat [Cambridge University Press, Cambridge, 1990]
- *Le répertoire-modèle de la musique iranienne* by Jean During (in French) [Sourush, Tehran, 1995]

This book contains measurements of the intervals in actual practice, consistent with the tunings of `persian.ly`.

- *Armoni-e Musiqi-e Iran* by Ali-Naqi Vaziri (in Persian) [1935]
- *Scales and Modes Around the World* by Herman Rechberger [Fennica Gehrman, 2018, ISBN 978-952-5489-07-1]

General input and output

19 Input modes

The way in which the notation contained within an input file is interpreted is determined by the current input mode. In general, there are two ways of specifying the mode: a long form, e.g. `\chordmode`, and a short form, e.g. `\chords`. The long form is typically used when supplying input to a variable or when entering input directly into an explicitly created context. The short form implicitly creates a context of the correct type for the input and passes the input directly to it. It is useful in simple situations when there is no requirement to explicitly create the receiving context.

Chord mode

This is activated with the `\chordmode` command, and causes input to be interpreted with the syntax of chord notation, see Chapter 15 [Chord notation], page 507. Music in chord mode is rendered as chords on a staff when entered into a `Staff` context, as chord names when entered into a `ChordNames` context or as fretboards when entered into a `FretBoards` context.

Chord mode is also activated with the `\chords` command. This also causes the following input to be interpreted with the syntax of chord notation but in addition it implicitly creates a new `ChordNames` context and renders the input into it as chord names, see Section 15.2.1 [Printing chord names], page 512.

Drum mode

This is activated with the `\drummode` command, and causes input to be interpreted with the syntax of drum notation, see Section 13.1.2 [Basic percussion notation], page 487. Music in drum mode is rendered as percussion notes when entered into a `DrumStaff` context.

Drum mode is also activated with the `\drums` command. This also causes the following input to be interpreted with the syntax of drum notation but in addition it implicitly creates a new `DrumStaff` context and renders the input into it as percussion notes, see Section 13.1.2 [Basic percussion notation], page 487.

Figure mode

This is activated with the `\figuremode` command, and causes input to be interpreted with the syntax of figured bass, see Section 15.3.2 [Entering figured bass], page 526. Music in figure mode is rendered as figured bass when entered into a `FiguredBass` context or a `Staff` context.

Figure mode is also activated with the `\figures` command. This also causes the following input to be interpreted with the figured bass syntax but in addition it implicitly creates a new `FiguredBass` context and renders the input into it as figured bass, see Section 15.3.1 [Introduction to figured bass], page 525.

Fret and tab modes

There are no special input modes for entering fret and tab symbols.

To create tab diagrams, enter notes or chords in note mode and render them in a `TabStaff` context, see Section 12.1.3 [Default tablatures], page 433.

To create fret diagrams above a staff, enter notes or chords in either note mode or chord mode and render them in a `FretBoards` context, see Section 12.1.7 [Automatic fret diagrams], page 477. Alternatively, fret diagrams can be entered as markup above the notes using the `\fret-diagram` command, see Section 12.1.5 [Fret diagram markups], page 455.

Lyrics mode

This is activated with the `\lyricmode` command, and causes input to be interpreted as lyric syllables with optional durations and associated lyric modifiers, see Chapter 9 [Vocal music], page 345. Input in lyric mode is rendered as lyric syllables when entered into a `Lyrics` context.

Lyric mode is also activated with the `\lyrics` command. This also causes the following input to be interpreted as lyric syllables but in addition it implicitly creates a new Lyrics context and renders the input into it as lyric syllables.

Lyric mode is also activated with the `\addlyrics` command. This also implicitly creates a new Lyrics context and in addition it adds an implicit `\lyricsto` command which associates the following lyrics with the preceding music, see Section 9.1.4 [Automatic syllable durations], page 349.

Markup mode

This is activated with the `\markup` command, and causes input to be interpreted with the syntax of markup, see Section A.1 [Text markup commands], page 807.

Note mode

This is the default mode or it may be activated with the `\notemode` command. Input is interpreted as pitches, durations, markup, etc and typeset as musical notation on a staff.


It is not normally necessary to specify note mode explicitly, but it may be useful to do so in certain situations, for example if you are in lyric mode, chord mode or any other mode and want to insert something that only can be done with note mode syntax.


```
% This ...

<<
  \chords { g1:m }
  { f'1 }
  \lyrics { foo1 }
  \drums { sn1 }
  \figures { <6 4>1 }
>>

% ... is equivalent to

<<
  \new ChordNames \chordmode { g1:m }
  \new Voice \notemode { f'1 }
  \new Lyrics \lyricmode { foo1 }
  \new DrumStaff \drummode { sn1 }
  \new FiguredBass \figuremode { <6 4>1 }
>>
```





20 Input structure

The main format of input for LilyPond are text files. By convention, these files end with `.ly`.

20.1 Structure of a score

A `\score` block must contain a single music expression delimited by curly brackets.¹

```
\score {
  ...
}
```


Note: There must be **only one** outer music expression in a `\score` block, and it **must** be surrounded by curly brackets.

This single music expression may be of any size, and may contain other music expressions to any complexity. All of these examples are music expressions:

```
{ c'4 c' c' c' }
{
  { c'4 c' c' c' }
  { d'4 d' d' d' }
}
```



```
<<
  \new Staff { c'4 c' c' c' }
  \new Staff { d'4 d' d' d' }
>>
```



```
{
  \new GrandStaff <<
    \new StaffGroup <<
      \new Staff { \flute }
      \new Staff { \oboe }
    >>
    \new StaffGroup <<
      \new Staff { \violinI }
      \new Staff { \violinII }
    >>
  >>
}
```

¹ Note that there also exists a markup command called `\score`, see [Scores within markup], page 858.

Comments are one exception to this general rule. (For others, see Section 20.5 [File structure], page 594.) Both single-line comments and comments delimited by `{ ... }` may be placed anywhere within an input file. They may be placed inside or outside a `\score` block, and inside or outside the single music expression within a `\score` block.

Remember that even in a file containing only a `\score` block, it is implicitly enclosed in a `\book` block. A `\book` block in a source file produces at least one output file, and by default the name of the output file produced is derived from the name of the input file, so `fandangofoforelephants.ly` will produce `fandangofoforelephants.pdf`.

(For more details about `\book` blocks, see Section 20.2 [Multiple scores in a book], page 591, Section 20.3 [Multiple output files from one input file], page 593, Section 20.5 [File structure], page 594.)

See also

Learning Manual: Section “Working on input files” in *Learning Manual*, Section “Music expressions explained” in *Learning Manual*, Section “A score is a (single) compound musical expression” in *Learning Manual*.

20.2 Multiple scores in a book

A document may contain multiple pieces of music and text. Examples of these are an etude book, or an orchestral part with multiple movements. Each movement is entered with a `\score` block,

```
\score {
  ...music...
}
```

and texts are entered with a `\markup` block,

```
\markup {
  ...text...
}
```

All the movements and texts which appear in the same `.ly` file will normally be typeset in the form of a single output file.

```
\score {
  ...
}
\markup {
  ...
}
\score {
  ...
}
```

One important exception is within `lilypond-book` documents, where you explicitly have to add a `\book` block, otherwise only the first `\score` or `\markup` will appear in the output.

The header for each piece of music can be put inside the `\score` block. The piece name from the header will be printed before each movement. The title for the entire book can be put inside the `\book`, but if it is not present, the `\header` which is at the top of the file is inserted.

```
\header {
  title = "Eight miniatures"
  composer = "Igor Stravinsky"
}
\score {
```

```

    \header { piece = "Romanze" }
    ...
}
\markup {
    ...text of second verse...
}
\markup {
    ...text of third verse...
}
\score {
    \header { piece = "Menuetto" }
    ...
}

```

Pieces of music may be grouped into book parts using `\bookpart` blocks. Book parts are separated by a page break, and can start with a title, like the book itself, by specifying a `\header` block.

```

\bookpart {
  \header {
    title = "Book title"
    subtitle = "First part"
  }
  \score { ... }
  ...
}
\bookpart {
  \header {
    subtitle = "Second part"
  }
  \score { ... }
  ...
}

```

Variables defined within a `\book` or `\bookpart` block are local to that book or bookpart; books and bookparts have their own ‘scope’. In contrast, a `\score` does not accept assignments and has no scope of its own.

If you want to use multiple files to set up your music with variables that should be ‘local’ to single files, this can be done with the following structure:

```

% movement1.ly
bookpartI = \bookpart {
  variable = { ... }
  \score { ... use \variable ... }
}

% movement2.ly
bookpartII = \bookpart {
  variable = { ... }
  \score { ... use \variable ... }
}

% main.ly
\include "movement1.ly"
\include "movement2.ly"

```

```

\book {
  \bookpart { \bookpartI }
  \bookpart { \bookpartII }
}

```

The values of variable in both bookparts are not related to one another. You cannot reference the variables outside of the book or bookpart that they are defined in.

`\layout`, `\paper`, and `\midi` blocks at the outer level of a `\book` or `\bookpart` establish local defaults for scores at that level, similar to how this happens at the top level of a document.

20.3 Multiple output files from one input file

LilyPond creates one output file for each `\book` block. If there is no explicit `\book` block in the input file, LilyPond implicitly treats the whole file as a single `\book` block, see Section 20.5 [File structure], page 594.

By default, LilyPond names the output file using the input file name and, if necessary, suffixes it with an increasing number – i.e., if an output file with the same name has already been created during the run. The default behavior is to append a version number suffix for each name that may clash, so

```

\book {
  \score { ... }
  \paper { ... }
}
\book {
  \score { ... }
  \paper { ... }
}
\book {
  \score { ... }
  \paper { ... }
}

```

in source file `eightminiatures.ly` produces

```

eightminiatures.pdf
eightminiatures-1.pdf
eightminiatures-2.pdf

```

as output files.

20.4 Output file names

It is possible to override both the output file name and the suffix appended to the basic file name in `\paper` blocks.

```

\paper {
  output-filename = "my_special_output"
}

\book {
  \paper {
    output-suffix = "menuetto"
  }
  ...
}
\book {

```



```

\paper {
  output-suffix = "scherzo"
}
...
}

```

The result are two output files named `my_special_output-menuetto.pdf` and `my_special_output-scherzo.pdf`. Be careful to select values for `output-filename` and `output-suffix` that are valid for file names on your operating system!

If this output file name already exists (this can happen, for example, if both `output-filename` and `output-suffix` are set in the global `\paper` block and not in any `\book` blocks), LilyPond appends an additional suffix with an increasing number.

Note that predefined `\paper` variables (see Section 26.1 [The `\paper` block], page 669) must be placed before the `output-filename` and `output-suffix` assignments, for example

```

bigMargin = \paper { top-margin = 10\cm }

\book {
  \paper {
    \bigMargin % must come first
    output-filename = "foo"
  }
}

```

20.5 File structure

A `.ly` file may contain any number of top-level expressions, where a top-level expression is one of the following:

- An output definition, such as `\paper`, `\midi`, and `\layout`. Such a definition at the top-level changes the default book-wide settings. If more than one such definition of the same type is entered at the top level the definitions are combined, but in conflicting situations the later definitions take precedence. For details of how this affects the `\layout` block see Section 27.1 [The `\layout` block], page 681.
- A direct Scheme expression, such as `#(set-default-paper-size "a7" 'landscape)` or `#(ly:set-option 'point-and-click #f)` .
- A `\header` block. This sets the global (i.e., the top of file) header block. This is the block containing the default settings of titling fields like `composer`, `title`, etc., for all books within the file (see Section 21.1.1 [Titles explained], page 597).
- A `\score` block. This score will be collected with other top-level scores, and combined as a single `\book`. This behavior can be changed by setting the variable `toplevel-score-handler` at top level. (The default handler is defined in the file `../scm/lily-library.scm` and set in the file `../ly/declarations-init.ly`.)
- A `\book` block logically combines multiple movements (i.e., multiple `\score` blocks) in one document. If there are a number of `\scores`, one output file will be created for each `\book` block, in which all corresponding movements are concatenated. The only reason to explicitly specify `\book` blocks in a `.ly` file is if you wish to create multiple output files from a single input file. One exception is within `lilypond-book` documents, where you explicitly have to add a `\book` block if you want more than a single `\score` or `\markup` in the same example. This behavior can be changed by setting the variable `toplevel-book-handler` at top level. The default handler is defined in the init file `../scm/lily.scm`.
- A `\bookpart` block. A book may be divided into several parts, using `\bookpart` blocks, in order to ease the page breaking, or to use different `\paper` settings in different parts.

- A compound music expression, such as

```
{ c'4 d' e'2 }
```

This will add the piece in a `\score` and format it in a single book together with all other top-level `\scores` and music expressions. In other words, a file containing only the above music expression will be translated into

```
\book {
  \score {
    \new Staff {
      \new Voice {
        { c'4 d' e'2 }
      }
    }
    \layout { }
  }
  \paper { }
  \header { }
}
```

This behavior can be changed by setting the variable `toplevel-music-handler` at top level. The default handler is defined in the init file `../scm/lily.scm`.

- A markup text, a verse for example

```
\markup {
  2. The first line verse two.
}
```

Markup texts are rendered above, between or below the scores or music expressions, wherever they appear.

- A variable or a nested structure of Scheme association lists (alists).

```
foo = { c4 d e d }      % normal variable
"Horn 3" = { c4 d e d } % quoted variable
verse.1 = { c4 d e d }  % nested alist
```

Variables can be used later on in the file by prepending them with a backslash.

```
\foo
\ "Horn 3"
\verse.1
```

The name of a variable should not contain (ASCII) numbers, multiple adjacent underscores, multiple adjacent dashes, or space characters. All other characters Unicode provides are allowed, for example Latin, Greek, Chinese, or Cyrillic. Non-adjacent single underscores and dashes are allowed, too. In other words, variable names like `HornIII` or `Скрипка-II` work.

Any combination of characters is allowed if the variable name is enclosed in double quotation marks (not that you actually should use such a name).² Examples: `"foo bar"`, `"a-b-c"`, `"Horn 3"`.

Nested alists provide a means to partially circumvent the abovementioned restriction of variable names not containing a number. A nested alist is a valid variable name followed by one or more sets of a dot and a key. In `mus.violin.1 = { a1 }` we have a variable called `mus`, which has an alist with a key called `violin`, which in turn has a key called `1`, which is eventually assigned the value `{ a1 }`. In `"1.2"."3.4".5` the variable name is `"1.2"` and the

² For this case the standard LilyPond rules for strings apply: backslashes and double quotation marks within the doublequotes need to be escaped with backslashes.

keys are "3.4" and 5 – such rather illegible constructs might be useful for programmatically generated variable names.

Neither a variable name nor a key in a nested alist is allowed to be a note name. If necessary, enclose those in double quotation marks, or better, change the offending name or key.

For technical reasons, accessing nested alists might fail under some circumstances. In particular, they cannot be accessed at top-level (i.e., outside of a music block). If lilypond aborts with the error ‘bad expression type’, replace the nested alist with a normal or quoted variable.

The following example shows three things that may be entered at top level.

```
\layout {
  % Don't justify the output
  ragged-right = ##t
}

\header {
  title = "Do-re-mi"
}

{ c'4 d' e2 }
```

At any point in a file, any of the following lexical instructions can be entered:

- \version
- \include
- \sourcefilename
- \sourcefileline
- A single-line comment, introduced by a leading % sign.
- A multi-line comment delimited by %{ ... %}.

Whitespace between items in the input stream is generally ignored, and may be freely omitted or extended to enhance readability. However, whitespace should always be used in the following circumstances to avoid errors:

- Around every opening and closing curly bracket.
- After every command or variable, i.e., every item that begins with a \ sign.
- After every item that is to be interpreted as a Scheme expression, i.e., every item that begins with a # sign.
- To separate all elements of a Scheme expression.
- In lyricmode before and after \set and \override commands.

See also

Learning Manual: Section “How LilyPond input files work” in *Learning Manual*.

Notation Reference: Section 21.1.1 [Titles explained], page 597, Section 27.1 [The \layout block], page 681.

21 Titles and headers

Almost all printed music includes a title and the composer's name; some pieces include a lot more information.

21.1 Creating titles, headers, and footers

21.1.1 Titles explained

Each `\book` block in a single input file produces a separate output file, see Section 20.5 [File structure], page 594. Within each output file three types of titling areas are provided: *book titles* at the beginning of each book, *bookpart titles* at the beginning of each bookpart, and *score titles* at the beginning of each score.

Values of titling fields such as `title` and `composer` are set in `\header` blocks. (For the syntax of `\header` blocks and a complete list of the fields available by default, see Section 21.1.2 [Default layout of bookpart and score titles], page 600). Book titles, bookpart titles, and score titles can all contain the same fields, although by default the fields in score titles are limited to `piece` and `opus`.

`\header` blocks may be placed in four different places to form a descending hierarchy.

- At the top of the input file, before all `\book`, `\bookpart`, and `\score` blocks.
- Within a `\book` block but outside all the `\bookpart` and `\score` blocks within that book.
- Within a `\bookpart` block but outside all `\score` blocks within that bookpart.
- Within a `\score` block.

The values of the fields filter down this hierarchy, with the values set higher in the hierarchy persisting unless they are overridden by a value set lower in the hierarchy.

- A book title is derived from fields set at the top of the input file, modified by fields set in the `\book` block. The resulting fields are used to print the book title for that book, providing that there is other material that generates a page at the start of the book, before the first bookpart. A single `\pageBreak` suffices.
- A bookpart title is derived from fields set at the top of the input file, modified by fields set in the `\book` block, and further modified by fields set in the `\bookpart` block. The resulting values are used to print the bookpart title for that bookpart.
- A score title is derived from fields set at the top of the input file, modified by fields set in the `\book` block, further modified by fields set in the `\bookpart` block and finally modified by fields set in the `\score` block. The resulting values are used to print the score title for that score. Note, though, that only `piece` and `opus` fields are printed by default in score titles unless the `\paper` variable `print-all-headers` is set to `#t`.

It is not necessary to provide `\header` blocks in all four places: any or even all of them may be omitted. Similarly, simple input files may omit the `\book` and `\bookpart` blocks, leaving them to be created implicitly.

If the book has only a single score, the `\header` block should normally be placed at the top of the file so that just a bookpart title is produced, making all the titling fields available for use.

If the book has multiple scores a number of different arrangements of `\header` blocks are possible, corresponding to the various types of musical publications. For example, if the publication contains several pieces by the same composer, a `\header` block placed at the top of the file specifying the book title and the composer with `\header` blocks in each `\score` block specifying the piece and/or opus would be most suitable, as here:

```

\header {
  title = "SUITE I."
  composer = "J. S. Bach."
}

\score {
  \header {
    piece = "Prélude."
  }
  \new Staff \relative {
    \clef bass
    \key g \major
    \*2 { g,16( d' b') a b d, b' d, } |
    \*2 { g,16( e' c') b c e, c' e, } |
  }
}

\score {
  \header {
    piece = "Allemande."
  }
  \new Staff \relative {
    \clef bass
    \key g \major
    \partial 16 b16 |
    <g, d' b'~>4 b'16 a( g fis) g( d e fis) g( a b c) |
    d16( b g fis) g( e d c) b(c d e) fis( g a b) |
  }
}

```

SUITE I.

J. S. Bach.

Prélude.



Allemande.



More complicated arrangements are possible. For example, text fields from the `\header` block in a book can be displayed in all score titles, with some fields overridden and some manually suppressed:

```

\book {
  \paper {
    print-all-headers = ##t
  }
  \header {
    title = "DAS WOHLTEMPERIRTE CLAVIER"
    subtitle = "TEIL I"
    % Do not display the default LilyPond footer for this book
    tagline = ##f
  }
  \markup { \vspace #1 }
  \score {
    \header {
      title = "PRAELUDIUM I"
      opus = "BWV 846"
      % Do not display the subtitle for this score
      subtitle = ##f
    }
    \new PianoStaff <<
      \new Staff { s1 }
      \new Staff { \clef "bass" s1 }
    >>
  }
  \score {
    \header {
      title = "FUGA I"
      subsubtitle = "A 4 VOICI"
      opus = "BWV 846"
      % Do not display the subtitle for this score
      subtitle = ##f
    }
    \new PianoStaff <<
      \new Staff { s1 }
      \new Staff { \clef "bass" s1 }
    >>
  }
}


```

DAS WOHLTEMPERIRTE CLAVIER

TEIL I

PRAELUDIUM I


BWV 846



FUGA I

A 4 VOCI

BWV 846



See also

Notation Reference: Section 20.5 [File structure], page 594, Section 21.1.2 [Default layout of bookpart and score titles], page 600, Section 21.2.2 [Custom layout for titles], page 605.

21.1.2 Default layout of bookpart and score titles

The next example demonstrates all printed `\header` variables. Note that the vertical spacing between the various header elements in the default layout is optimized for single-line entries. If you need multi-line elements, say, a two-line composer entry, try to append `\vspace` to the field if necessary to adjust the vertical spacing. An alternative is to define your own, custom layout, see Section 21.2.2 [Custom layout for titles], page 605.

```
\book {
  \header {
    % The following fields are centered
    dedication = "Dedication"
    title = "Title"
    subtitle = "Subtitle"
    subsubtitle = "Subsubtitle"

    % The following fields are evenly spread on one line;
    % the field "instrument" also appears on following pages
    instrument = \markup \with-color #green "Instrument"
    poet = "Poet"
    composer = "Composer"
```

```


    % The following fields are placed at opposite ends
    % of the same line
    meter = "Meter"
    arranger = "Arranger"

    % The following fields are centered at the bottom
    tagline = "The tagline goes at the bottom of the last page"
    copyright = "The copyright goes at the bottom of the first page"
}
\score {
  \header {
    % The following fields are placed at opposite ends
    % of the same line
    piece = "Piece 1"
    opus = "Opus 1"
  }
  { s1 }
}
\score {
  \header {
    % The following fields are placed at opposite ends
    % of the same line
    piece = "Piece 2 on the same page"
    opus = "Opus 2"
  }
  { s1 }
}
\pageBreak
\score {
  \header {
    % The following fields are placed at opposite ends
    % of the same line
    piece = "Piece 3 on a new page"
    opus = "Opus 3"
  }
  { s1 }
}
}


```


Dedication
Title
 Subtitle
 Subsubtitle

Poet	Instrument	Composer
Meter		Arranger
Piece 1		Opus 1




Piece 2 on the same page	Opus 2



The copyright goes at the bottom of the first page

2

Piece 3 on a new page	Opus 3



The tagline goes at the bottom of the last page

Note that

- the instrument name is repeated on every page,
- only piece and opus are printed in a `\score` when the paper variable `print-all-headers` is set to `#f` (the default),
- text fields left unset in a `\header` block produce no output so that the space is not wasted,
- the default settings for `scoreTitleMarkup` place the piece and opus text fields at opposite ends of the same line.

To change the default layout, see Section 21.2.2 [Custom layout for titles], page 605.

If a `\book` block starts immediately with a `\bookpart` block, no book title gets printed, as there is no page on which to print it. If a book title is required, begin the `\book` block with some markup material or a `\pageBreak` command.

Use the `breakbefore` variable inside a `\header` block that is itself in a `\score` block, to make the higher-level `\header` block titles appear on the first page on their own, with the music (defined in the `\score` block) starting on the next page.

```
\book {
  \header {
    title = "This is my Title"
    subtitle = "This is my Subtitle"
    copyright = "This is the bottom of the first page"
  }
  \score {
    \header {
      piece = "This is the Music"
      breakbefore = ##t
    }
    \*4 { e' ' e' ' e' ' e' ' }
  }
}
```

This is my Title

This is my Subtitle

This is the bottom of the first page

2

This is the Music



See also

Learning Manual: Section “How LilyPond input files work” in *Learning Manual*.

Notation Reference: Section 21.2.2 [Custom layout for titles], page 605, Section 20.5 [File structure], page 594.

Installed Files: `ly/titling-init.ly`.

21.1.3 Default layout of headers and footers

Headers and *footers* are lines of text appearing at the top and bottom of pages, separate from the main text of a book. They are controlled by the following `\paper` variables:

- `oddHeaderMarkup`
- `evenHeaderMarkup`
- `oddFooterMarkup`
- `evenFooterMarkup`

These markup variables are defined in `ly/titling-init.ly` and do the following by default.

- Page numbers are automatically placed on the top far left (if even) or top far right (if odd), starting from the second page.
- The instrument header field is placed in the center of every page, starting from the second page.
- The copyright header field is centered on the bottom of the first page.
- The tagline header field is centered on the bottom of the last page, and below the copyright field if there is only a single page.

The following shows an example how to change the tag line.

```
\book {
  \header {
    tagline = "... music notation for Everyone"
  }
  \score {
    \relative {
      c'4 d e f
    }
  }
}
```



... music notation for Everyone

Set tagline to `#f` if you don't want a tag line.

See also

Notation Reference: Section 21.2.3 [Custom layout for headers and footers], page 608.

21.2 Custom titles, headers, and footers


21.2.1 Custom text formatting for titles

Standard `\markup` commands can be used to customize any header, footer, or title text within the `\header` block.

```
\score {
  \header {
    piece = \markup { \fontsize #4 \bold "PRAELUDIUM I" }
    opus = \markup { \italic "BWV 846" }
  }
  { s1 }
```

PRAELUDIUM I

BWV 846



See also

Notation Reference: Section 8.2 [Formatting text], page 319.

21.2.2 Custom layout for titles

`\markup` commands in the `\header` block are useful for simple text formatting, but they do not allow precise control over the placement of titles. To customize the placement of the text fields, change either or both of the following `\paper` variables:

- `bookTitleMarkup`
- `scoreTitleMarkup`

See Section 21.1.2 [Default layout of bookpart and score titles], page 600, for the placement of titles when using the default values of these `\markup` variables.

The default setting for `scoreTitleMarkup` defined in `ly/titling-init.ly` is as follows.


```
scoreTitleMarkup = \markup \column {
  \if \should-print-all-headers { \bookTitleMarkup \hspace #1 }
  \fill-line {
    \fromproperty #'header:piece
    \fromproperty #'header:opus
  }
}
```

This places the `piece` and `opus` text fields at opposite ends of the same line.

```
\score {
  \header {
    piece = "PRAELUDIUM I"
    opus = "BWV 846"
  }
  { s1 }
```

PRAELUDIUM I

BWV 846



The next example redefines `scoreTitleMarkup` so that the piece text field is centered, using a large, bold font.

```
\book {
  \paper {
    indent = 0\mm
    scoreTitleMarkup = \markup {
      \fill-line {
        \null
        \fontsize #4 \bold \fromproperty #'header:piece
        \fromproperty #'header:opus
      }
    }
  }
  \header { tagline = ##f }
  \score {
    \header {
      piece = "PRAELUDIUM I"
      opus = "BWV 846"
    }
    { s1 }
  }
}
```



Text fields not normally effective in score `\header` blocks can be printed in the score title area if `print-all-headers` is placed inside the `\paper` block. A disadvantage of using this method is that text fields intended specifically for the bookpart title area need to be manually suppressed in every `\score` block. See Section 21.1.1 [Titles explained], page 597.


To avoid this, add the desired text field to the `scoreTitleMarkup` definition. In the following example, the composer text field (normally associated with `bookTitleMarkup`) is added to `scoreTitleMarkup`, allowing each score to list a different composer.

```
\book {
  \paper {
    indent = 0\mm
    scoreTitleMarkup = \markup {
      \fill-line {
        \null
        \fontsize #4 \bold \fromproperty #'header:piece
        \fromproperty #'header:composer
      }
    }
  }
  \header { tagline = ##f }
  \score {
```

```

\header {
  piece = "MENUET"
  composer = "Christian Petzold"
}
{ s1 }
}
\score {
  \header {
    piece = "RONDEAU"
    composer = "François Couperin"
  }
  { s1 }
}
}

```



It is also possible to create your own custom text fields and refer to them in the markup definition.

```

\book {
  \paper {
    indent = 0\mm
    scoreTitleMarkup = \markup {
      \fill-line {
        \null
        \override #`(direction . ,UP)
        \dir-column {
          \center-align \fontsize #-1 \bold
          \fromproperty #'header:mycustomtext %% User-defined field
          \center-align \fontsize #4 \bold
          \fromproperty #'header:piece
        }
        \fromproperty #'header:opus
      }
    }
  }
}
\header { tagline = ##f }
\score {
  \header {
    piece = "FUGA I"
    mycustomtext = "A 4 VOCI" %% User-defined field
    opus = "BWV 846"
  }
}

```

```

    }
    { s1 }
  }
}

```



See also

Notation Reference: Section 21.1.1 [Titles explained], page 597.

21.2.3 Custom layout for headers and footers

`\markup` commands in the `\header` block are useful for simple text formatting, but they do not allow precise control over the placement of headers and footers. To customize the placement of the text fields, use one or more of the following `\paper` variables.

- `oddHeaderMarkup`
- `evenHeaderMarkup`
- `oddFooterMarkup`
- `evenFooterMarkup`

The `\markup` command `\if` can be used to add markup conditionally to header and footer text defined within the `\paper` block, using the following syntax within `\markup`:

```
\if condition argument
```

The *condition* is tested each time the markup is interpreted. The resulting markup is *argument* if the condition is true, but empty if false. Typical conditions include tests for page numbers (first page, last page, specific page, ...). To test for the condition being false, replace `\if` with `\unless`.

The following example centers page numbers at the bottom of every page. First, the default settings for `oddHeaderMarkup` and `evenHeaderMarkup` are removed by assigning `#f`. Then, `oddFooterMarkup` is redefined with the page number centered. Finally, `evenFooterMarkup` is given the same layout by defining it as `\oddFooterMarkup`:

```

\book {
  \paper {
    print-page-number = ##t
    print-first-page-number = ##t
    oddHeaderMarkup = ##f
    evenHeaderMarkup = ##f
    oddFooterMarkup = \markup {
      \fill-line {
        \if \should-print-page-number
          \fromproperty #'page:page-number-string
      }
    }
    evenFooterMarkup = \oddFooterMarkup
  }
}
\score {
  \new Staff { s1 \break s1 \break s1 }
}

```



Here is a list of all predefined procedures available for use with `\if` and `\unless`.

Syntax

```
\on-first-page
\on-last-page
\on-first-page-of-part
\on-last-page-of-part
\on-page n
\single-page
\should-print-page-numbers-global
\should-print-page-number
\should-print-all-headers
```

Condition tested

```
First page in the book?
Last page in the book?
First page in the book part?
Last page in the book part?
On page number n?
Does the book fit on just one page?
Print page numbers in the book?1
Print the number of the current page?
Is print-all-headers true?
```

See also

Notation Reference: Section 21.1.1 [Titles explained], page 597, Section 21.1.2 [Default layout of bookpart and score titles], page 600, Section A.1.5 [Conditional markup], page 862.

Installed Files: `../ly/titling-init.ly`.

21.3 Creating output file metadata

In addition to being shown in the printed output, `\header` variables are also used to set metadata for output files. For example, with PDF files, this metadata could be displayed by PDF readers as the properties of the PDF file. For each type of output file, only the `\header` definitions of blocks that define separate files of that type, and blocks higher in the block hierarchy, will be consulted. Therefore, for PDF files, only the `\book` level and the top level `\header` definitions affect the document-wide PDF metadata, whereas for MIDI files, all headers above or at the `\score` level are used.

For example, setting the `title` property of the header block to ‘Symphony I’ will also give this title to the PDF document, and use it as the sequence name of the MIDI file.

```
\header {
```

¹ `\should-print-page-numbers-global` can differ from `\should-print-page-number` for the first page in the book, depending on the `print-first-page-number` setting of the `\paper` block.


```

    title = "Symphony I"
}

```

If you want to set the title of the printed output to one value, but have the title property of the PDF to have a different value, you can use `pdftitle`, as below.

```

\header {
  title = "Symphony I"
  pdftitle = "Symphony I by Beethoven"
}

```

The variables `title`, `subject`, `keywords`, `subtitle`, `composer`, `arranger`, `poet`, `author` and `copyright` all set PDF properties and can all be prefixed with ‘pdf’ to set a PDF property to a value different from the printed output.

The PDF property `Creator` is automatically set to ‘LilyPond’ plus the current LilyPond version, and `CreationDate` and `ModDate` are both set to the current date and time. `ModDate` can be overridden by setting the header variable `moddate` (or `pdfmoddate`) to a valid PDF date string.

The `title` variable sets also the sequence name for MIDI. The `midititle` variable can be used to set the sequence name independently of the value used for typeset output.

21.4 Creating footnotes

Footnotes may be used in many different situations. In all cases, a ‘footnote mark’ is placed as a reference in text or music, and the corresponding ‘footnote text’ appears at the bottom of the same page, separated from the music by a horizontal line. The appearance of this separator can be changed by setting the paper variable `footnote-separator-markup`, see Section 26.6.4 [`\paper` variables concerning headers and markups], page 679.

Footnotes within music expressions and footnotes in stand-alone text outside music expressions are created in different ways.

21.4.1 Footnotes in music expressions

Music footnotes overview

Footnotes in music expressions fall into two categories:

Event-based footnotes

are attached to a particular event. Examples for such events are single notes, articulations (like fingering indications, accents, dynamics), and post-events (like slurs and manual beams). The general form for event-based footnotes is as follows:

```
[direction] \footnote [mark] offset footnote music
```

Time-based footnotes

are bound to a particular point of time in a musical context. Some commands like `\time` and `\clef` don’t actually use events for creating objects like time signatures and clefs. Neither does a chord create an event of its own: its stem or flag is created at the end of a time step (nominally through one of the note events inside). Exactly which of a chord’s multiple note events will be deemed the root cause of a stem or flag is undefined. So for annotating those, time-based footnotes are preferable as well.

A time-based footnote allows such layout objects to be annotated without referring to an event. The general form for time-based footnotes is:

```
\footnote [mark] offset footnote [Context].GrobName
```

The elements for both forms are:

- direction* If (and only if) the `\footnote` is being applied to a post-event or articulation, it must be preceded with a direction indicator (`'-`, `'_'`, `'^'`) in order to attach *music* (with a footnote mark) to the preceding note or rest.
- mark* is a markup or string specifying the footnote mark which is used for marking both the reference point and the footnote itself at the bottom of the page. It may be omitted (or equivalently replaced with `\default`) in which case a number in sequence will be generated automatically. By default, such numerical sequences restart on each page containing a footnote. Footnotes may be numbered consecutively across page breaks by setting the variable `reset-footnotes-on-new-page` to `#f`, see Section 26.6.4 [`\paper` variables concerning headers and markups], page 679.
- offset* is a number pair such as `'#'(2 . 1)'` specifying the X and Y offsets in units of staff spaces from the boundary of the object where the mark should be placed. Positive values of the offsets are taken from the right/top edge, negative values from the left/bottom edge and zero implies the mark is centered on the edge.
- Context* is the context in which the grob being footnoted is created. It may be omitted if the grob is in a bottom context, e.g., a Voice context.
- GrobName* specifies a type of grob to mark (like `'Flag'`). If it is specified, the footnote is not attached to a music expression in particular, but rather to all grobs of the type specified which occur at that moment of musical time.
- footnote* is the markup or string specifying the footnote text to use at the bottom of the page.
- music* is the music event or post-event or articulation that is being annotated.

Event-based footnotes

A footnote may be attached to a layout object directly caused by the event corresponding to *music* with the syntax:


```
\footnote [mark] offset footnote music
```

```

\book {
  \header { tagline = ##f }
  \markup "event-based footnotes"
  \markup \null
  \relative c'' {
    \footnote #'(-1 . 3) "A note." a4
    a4
    \footnote #'(2 . 2) "A rest." r4
    a4
  }
}

```

event-based footnotes



¹A note.
²A rest.

If a chord is marked with an event-based footnote, each chord note gets a separate but identical footnote, which is undesired normally. However, it is possible to create footnotes for individual notes inside of a chord.

```

\book {
  \header { tagline = ##f }
  \markup "event-based footnotes"
  \markup \null
  \relative c'' {
    \footnote #'(1 . 3) "A chord." <a-3 c-5>2
    <a-3 \footnote #'(3 . 0.5) "A note in a chord." c-5>4
  }
}

```

event-based footnotes



¹A chord.
²A chord.
³A note in a chord.

If the footnote is to be attached to a post-event or articulation the `\footnote` command *must* be preceded by a direction indicator (`'`, `'_`, `'^`), and followed by the post-event or articulation to be annotated as the *music* argument. In this form the `\footnote` can be considered to be simply a copy of its last argument with a footnote mark attached to it. The syntax is:

```
direction \footnote [mark] offset footnote music
```

```

\book {
  \header { tagline = ##f }
  \markup "event-based footnotes"
  \markup \null
  \relative {
    a'4_\footnote #'(0 . -1) "A slur forced down." (
    b8^\footnote #'(1 . 0.5) "A manual beam forced up." [
    b8 ]
    c4 )
    c-\footnote #'(1 . 1) "Tenuto." --
  }
}

```

event-based footnotes



-
- ¹A slur forced down.
²A manual beam forced up.
³Tenuto.

Time-based footnotes

If the layout object being footmarked is *indirectly* caused by an event (like an *Accidental* or *Stem* caused by a *NoteHead* event), the *GrobName* of the layout object is required after the footnote text instead of *music*:

```

\book {
  \header { tagline = ##f }
  \markup "time-based footnotes"
  \markup \null
  \relative c'' {
    \footnote #'(-1 . -3) "A flat." Accidental
    aes4 c
    \footnote #'(-1 . 0.5) "Another flat." Accidental
    ees
    \footnote #'(1 . -2) "A stem." Stem
    aes
  }
}

```

time-based footnotes




-
- ¹A flat.
²Another flat.
³A stem.

Note, however, that when a *GrobName* is specified, a footnote is attached to all grobs of that type at the current time step:

```
\book {
  \header { tagline = ##f }
  \markup "time-based footnotes"
  \markup \null
  \markup \null
  \relative c' {
    \footnote #'(-1 . 3) "A flat." Accidental
    <ees ges bes>4
    \footnote #'(2 . 0.5) "Articulation." Script
    c'->-.
  }
}
```

time-based footnotes



-
- ¹A flat.
 - ²A flat.
 - ³A flat.
 - ⁴Articulation.
 - ⁵Articulation.

A note inside of a chord can be given an individual (event-based) footnote. A ‘NoteHead’ is the only grob directly caused from a chord note, so an event-based footnote command is *only* suitable for adding a footnote to the ‘NoteHead’ within a chord. All other chord note grobs are indirectly caused. The `\footnote` command itself offers no syntax for specifying *both* a particular grob type *as well as* a particular event to attach to. However, one can use a time-based `\footnote` command for specifying the grob type, and then prefix this command with `\single` in order to have it applied to just the following event:

```

\book {
  \header { tagline = ##f }
  \markup "time-based footnotes"
  \markup \null
  \relative c'' {
    < \footnote #'(1 . -2) "An A." a
      \single \footnote #'(-1 . -1) "A sharp." Accidental
      cis
      \single \footnote #'(0.5 . 0.5) "A flat." Accidental
      ees fis
    >2
  }
}

```

time-based footnotes



¹A flat.
²A sharp.
³An A.

Note: When footnotes are attached to several musical elements at the same musical moment, as they are in the example above, the footnotes are numbered from the higher to the lower elements as they appear in the printed output, not in the order in which they are written in the input stream.

Layout objects like clefs and key change signatures are mostly caused as a consequence of changed properties rather than actual events. Others, like bar lines and bar numbers, are a direct consequence of timing. For this reason, footnotes on such objects have to be based on their musical timing. Time-based footnotes are also preferable when marking features like stems and beams on *chords*: while such per-chord features are nominally assigned to *one* event inside the chord, relying on a particular choice would be imprudent.

The layout object in question must always be explicitly specified for time-based footnotes, and the appropriate context must be specified if the grob is created in a context other than the bottom context.

```

\book {
  \header { tagline = ##f }
  \markup "time-based footnotes"
  \relative c'' {
    r1 |
    \footnote #'(-0.5 . -1) "Meter change." Staff.TimeSignature
    \time 3/4
    \footnote #'(1 . -1) "Chord stem." Stem
    <c e g>4 q q
    \footnote #'(-0.5 . 2) "Bar line." Staff.BarLine
    q q
  }
}

```

```

\footnote #'(0.5 . -1) "Key change." Staff.KeySignature
\key c \minor
q
}
}

```

time-based footnotes



¹Meter change.

²Chord stem.

³Bar line.

⁴Key change.


Custom marks can be used as alternatives to numerical marks, and the annotation line joining the marked object to the mark can be suppressed:

```

\book {
  \header { tagline = ##f }
  \markup "footnotes with custom marks"
  \markup \null
  \relative c' {
    \footnote "*" #'(0.5 . -2) \markup { \italic "* The first note" }
    a'4 b8
    \footnote \markup { \super "$" } #'(0.5 . 1)
    \markup { \super "$" \italic " The second note." } e
    c4
    \once \override Score.Footnote.annotation-line = ##f
    b-\footnote \markup \tiny "+" #'(0.1 . 0.1)
    \markup { \super "+" \italic " Editorial." } \p
  }
}

```

footnotes with custom marks



* *The first note*

\$ *The second note.*

+ *Editorial.*

More examples of custom marks are shown in Section 21.4.2 [Footnotes in stand-alone text], page 616.

21.4.2 Footnotes in stand-alone text

These are for use in markup outside of music expressions. They do not have a line drawn to their point of reference: their marks simply follow the referenced markup. Marks can be inserted automatically, in which case they are numerical. Alternatively, custom marks can be provided manually.

Footnotes to stand-alone text with automatic and custom marks are created in different ways.

Footnotes in stand-alone text with automatic marks

The syntax of a footnote in stand-alone text with automatic marks is

```
\markup { ... \auto-footnote text footnote ... }
```

The elements are:

text the markup or string to be marked,

footnote the markup or string specifying the footnote text to use at the bottom of the page.

For example:

```
\book {
  \header { tagline = ##f }
  \markup {
    "A simple"
    \auto-footnote "tune" \italic " By me."
    "is shown below. It is a"
    \auto-footnote "recent" \italic " Aug 2012."
    "composition."
  }
  \relative {
    a'4 b8 e c4 d
  }
}
```

A simple tune¹ is shown below. It is a recent² composition.



¹ *By me.*

² *Aug 2012.*

Footnotes in stand-alone text with custom marks

The syntax of a footnote in stand-alone text with custom marks is

```
\markup { ... \footnote mark footnote ... }
```

The elements are:

mark is a markup or string specifying the footnote mark which is used for marking the reference point. Note that this mark is *not* inserted automatically before the footnote itself.

footnote is the markup or string specifying the footnote text to use at the bottom of the page, preceded by the *mark*.

Any easy to type character such as ‘*’ or ‘+’ may be used as a mark, as shown in Section 21.4.1 [Footnotes in music expressions], page 610. Alternatively, ASCII aliases may be used (see Section 22.4.3 [ASCII aliases], page 645):

```
\book {
  \paper { #(include-special-characters) }
  \header { tagline = ##f }
  \markup {
    "A simple tune"
    \footnote "*" \italic "* By me."
    "is shown below. It is a recent"
    \footnote \super &dagger; \concat {
      \super &dagger; \italic " Aug 2012."
    }
    "composition."
  }
  \relative {
    a'4 b8 e c4 d
  }
}
```

A simple tune * is shown below. It is a recent [†] composition.



* *By me.*

[†] *Aug 2012.*

Unicode character codes may also be used to specify marks (see Section 22.4.2 [Unicode], page 645):

```
\book {
  \header { tagline = ##f }
  \markup {
    "A simple tune"
    \footnote \super \char##x00a7 \concat {
      \super \char##x00a7 \italic " By me."
    }
    "is shown below. It is a recent"
    \footnote \super \char##x00b6 \concat {
      \super \char##x00b6 \italic " Aug 2012."
    }
    "composition."
  }
  \relative {
```

```

      a'4 b8 e c4 d
    }
  }

```

A simple tune § is shown below. It is a recent ¶ composition.



§ *By me.*
 ¶ *Aug 2012.*

See also

Learning Manual: Section “Objects and interfaces” in *Learning Manual*.

Notation Reference: Section 22.4.3 [ASCII aliases], page 645, Section 7.2.2 [Balloon help], page 299, Section B.12 [List of special characters], page 925, Section 8.1.5 [Text marks], page 313, Section 8.1.2 [Text scripts], page 309, Section 22.4.2 [Unicode], page 645.

Internals Reference: Section “FootnoteEvent” in *Internals Reference*, Section “Footnote” in *Internals Reference*, Section “Footnote-engraver” in *Internals Reference*.

Known issues and warnings

Multiple footnotes for the same page can only be stacked, one above the other; they cannot be printed on the same line.

Footnote marks may collide with staves, \markup objects, other footnote marks and annotation lines.

21.5 Creating in-notes

In-notes function like footnotes in that they serve to annotate music, but are different in that they are typeset either above or below the system to which the grob being annotated belongs.

To create an in-note, set the footnote property of the Footnote grob to #f. The distance between two in-notes can be controlled with the paper variable in-note-padding, the distance between the in-note and its associated system by in-note-system-padding. If you want in-notes positioned below its associated system, set paper variable in-note-direction to DOWN.

```

music = { a4 b8 e c4 d }

\book {
  \relative c'' {
    \override Score.Footnote.footnote = ##f

    \*5 \music
    \footnote #'(1 . 1) "An in-note." NoteHead
    <>-> \*4 \music
  }
}

```

```

\footnote "" #'(0 . 0) "An in-note without number." NoteHead
<>-> \*2 \music
\footnote "" #'(0 . 0) "Another numberless in-note." NoteHead
<>-> \music
}

\paper {
  in-note-system-padding = 5
  in-note-padding = 2
  tagline = ##f
}
}

```



¹An in-note.



An in-note without number.
Another numberless in-note.




21.6 Reference to page numbers

A particular place of a score can be marked using the `\label` command, either at top level or inside music. This label can then be referred to in a markup, to get the number of the page where the marked point is placed, using the `\page-ref` markup command.

```

\header { tagline = ##f }
\book {
  \label #'firstScore
  \score {
    {
      c'1
      \pageBreak \mark A \label #'markA
      c'1
    }
  }
}
\markup { The first score begins on page \page-ref #'firstScore "0" "?" }
\markup { Mark A is on page \page-ref #'markA "0" "?" }
}

```



The first score begins on page 1
Mark A is on page 2

The `\page-ref` markup command takes three arguments:

1. the label, a Scheme symbol, for example `#'firstScore`;
2. a markup that will be used as a gauge to estimate the dimensions of the markup;
3. a markup that will be used in place of the page number if the label is not known.

The reason why a gauge is needed is that, at the time markups are interpreted, the page breaking has not yet occurred, so the page numbers are not yet known. To work around this issue, the actual markup interpretation is delayed to a later time; however, the dimensions of the markup have to be known before, so a gauge is used to decide these dimensions. If the book has between 10 and 99 pages, it may be “00”, i.e., a two digit number.

If the size of the final text is different from the gauge, it could be useful to configure the horizontal alignment relative to the gauge with the property `x-align`. The default is right-aligned.

```
\markup {
  \box
    \page-ref #'foo "???" "?" " right-aligned (default)"
}
\markup {
  \box
    \override #`(x-align . ,LEFT)
    \page-ref #'foo "???" "?" " left-aligned"
}
\markup {
  \box
    \override #'(x-align . -2.5)
    \page-ref #'foo "???" "?" " left outside"
}
```

☐? right-aligned (default)

☐? left-aligned

?☐ left outside

In the example the gauge ‘???’ is wider than the replacement text ‘?’. The replacement is used because the label `#'foo` does not exist. The property `x-align` can be set with any numbers. The predefined symbols `LEFT`, `CENTER` or `RIGHT` can also be used to set the alignment to left, center or right relative to the gauge.

Predefined commands

`\label`, `\page-ref`.

21.7 Table of contents

A table of contents is included using the `\markuplist \table-of-contents` command. The elements which should appear in the table of contents are entered with the `\tocItem` command, which may be used either at top level, or inside a music expression.

```
\markuplist \table-of-contents
\pageBreak

\tocItem \markup "First score"
\score {
  {
    c'4 % ...
    \tocItem \markup "Some particular point in the first score"
    d'4 % ...
  }
}

\tocItem \markup "Second score"
\score {
  {
    e'4 % ...
    \tocItem actI \markup "Act I"
    f'4 % ...
    \tocItem actI.sceneI \markup "Scene 1"
    g'4 % ...
    \tocItem actI.sceneI.recitativo \markup "Recit."
    a'4 % ...
  }
}
```

Optionally, a label can be associated with a particular item, or a hierarchical list of existing labels, finishing with that item's label. That latter case allows to mark the item as a 'child' of the preceding labeled items, thus making the score's structure apparent in the table of contents.

Markups used for formatting the table of contents are defined in the `\paper` block. There are three 'predefined' markups already available;

- `tocTitleMarkup`

Used for formatting the title of the table of contents.

```
tocTitleMarkup = \markup \huge \column {
  \fill-line { \null "Table of Contents" \null }
  \null
}
```

- `tocItemMarkup`

Used for formatting the elements within the table of contents.

```
tocItemMarkup = \markup \fill-line {
  \fromproperty #'toc:text \fromproperty #'toc:page
}
```

- `tocFormatMarkup`

How the table's top level entries will be formatted (if there are several hierarchical levels). This is actually a procedure, as explained in Section "Markup construction in Scheme" in *Extending*.

```
tocFormatMarkup = #make-bold-markup
```

- `tocIndentMarkup`

Used to define how the outline's hierarchy will be made apparent. This markup is printed zero, one or several times depending on the level of each entry.

```
tocIndentMarkup = \markup \hspace #4
```

Any of these variables can be changed.

Here is an example translating the table of contents' title into French:

```
\paper {
  tocTitleMarkup = \markup \huge \column {
    \fill-line { \null "Table des matières" \null }
    \hspace #1
  }
}
```

Here is an example changing the font size of the elements in the table of contents:

```
tocItemMarkup = \markup \large \fill-line {
  \fromproperty #'toc:text \fromproperty #'toc:page
}
```

Note how the element text and page numbers are referred to in the `tocItemMarkup` definition.

The `\tocItemWithDotsMarkup` command can be included within the `tocItemMarkup` to fill the line, between a table of contents item and its corresponding page number, with dots:

```
\header { tagline = ##f }
\paper {
  tocItemMarkup = \tocItemWithDotsMarkup
}

\book {
  \markuplist \table-of-contents
  \tocItem \markup { Allegro }
  \tocItem \markup { Largo }
  \markup \null
}
```

Table of Contents

Allegro	1
Largo	1

In addition to the built-in outline mechanism, custom commands can also be defined to build a more personalized table of contents with different markups. In the following example, a new style is defined for entering act and scenes in the table of contents of an opera:

A new markup variable (called `tocActMarkup`) is defined in the `\paper` block:

```
\paper {
  tocActMarkup = \markup \large \column {
    \hspace #1
    \fill-line { \null \italic \fromproperty #'toc:text \null }
  }
}
```

```

    \hspace #1
  }
}

```

A custom music function (`tocAct`) is then created – which uses the new `tocActMarkup` markup definition, and allows to specify a label for each act.

```

tocAct =
  #(define-music-function (label text) (symbol? markup?)
    (add-toc-item! 'tocActMarkup text label))

```

Using these custom definitions and modifying some of the existing definitions, the source file could then be written as follows:

Table of Contents

Atto Primo

Coro. Viva il nostro Alcide	1
Cesare. Presti omai l'Egizia terra	1
<i>Recit.</i> Curio, Cesare venne, e vide, e vinse. . .	1

Atto Secondo

Sinfonia	1
Cleopatra. V'adoro, pupille, saette d'Amore . .	1

The previous example also demonstrates how to use the `\fill-with-pattern` markup command within the context of a table of contents.

See also

Installed Files: `ly/toc-init.ly`.

Predefined commands

`\table-of-contents`, `\tocItem`, `tocItemMarkup`, `tocTitleMarkup`, `tocFormatMarkup`, `tocIndentMarkup`.

22 Working with input files

22.1 Including LilyPond files

A large project may be split up into separate files. To refer to another file, use

```
\include "otherfile.ly"
```

The line `\include "otherfile.ly"` is equivalent to pasting the contents of `otherfile.ly` into the current file at the place where the `\include` appears. For example, in a large project you might write separate files for each instrument part and create a “full score” file which brings together the individual instrument files. Normally the included file will define a number of variables which then become available for use in the full score file. Tagged sections can be marked in included files to assist in making them usable in different places in a score, see Section 22.2 [Different editions from one source], page 626.

Files in the current working directory may be referenced by specifying just the file name after the `\include` command. Files in other locations may be included by giving either a full path reference or a relative path reference (but use the UNIX forward slash, `/`, rather than the DOS/Windows back slash, `\`, as the directory separator.) For example, if `stuff.ly` is located one directory higher than the current working directory, use

```
\include "../stuff.ly"
```

or if the included orchestral parts files are all located in a subdirectory called `parts` within the current directory, use

```
\include "parts/VI.ly"
\include "parts/VII.ly"
... etc
```

Files which are to be included can also contain `\include` statements of their own. These second-level `\include` statements are then interpreted relatively to the path of the file containing that command, which is convenient for multiple files located in the same subdirectory. For example, a general library, ‘libA’, may itself use subfiles which are `\included` by the entry file of that library, like this:

```
libA/
  libA.ly
  A1.ly
  A2.ly
  ...
```

then the entry file, `libA.ly`, will contain

```
\include "A1.ly"
\include "A2.ly"
...
```

Any `.ly` file can then include the entire library simply with

```
\include "~/libA/libA.ly"
```

However, that behavior can be changed globally by passing the command-line option `-drelative-includes=#f`, or by adding `#{ly:set-option 'relative-includes #f}` at the top of the main input file. In that case, each file will be included relatively to the location of the main file, regardless of where its `\include` statement is located. Complex file structures, that require to `\include` *both* files relative to the main directory and files relative to some other directory, may even be devised by setting `relative-includes` to `#f` or `#t` at appropriate places in the files.

Files can also be included from a directory in a search path specified as an option when invoking LilyPond from the command line. The included files are then specified using just their

file name. For example, to compile `main.ly` which includes files located in a subdirectory called `parts` by this method, change to the directory containing `main.ly` and enter

```
lilypond --include=parts main.ly
and in main.ly write
\include "VI.ly"
\include "VII.ly"
... etc
```

Files which are to be included in many scores may be placed in the LilyPond directory `../ly`. (The location of this directory is installation-dependent – see Section “Other sources of information” in *Learning Manual*). These files can then be included simply by naming them on an `\include` statement. This is how the language-dependent files like `english.ly` are included.

LilyPond includes a number of files by default when you start the program. These includes are not apparent to the user, but the files may be identified by running `lilypond --verbose` from the command line. This will display a list of paths and files that LilyPond uses, along with much other information. Alternatively, the more important of these files are discussed in Section “Other sources of information” in *Learning Manual*. These files may be edited, but changes to them will be lost on installing a new version of LilyPond.

Some simple examples of using `\include` are shown in Section “Scores and parts” in *Learning Manual*.

See also

Learning Manual: Section “Other sources of information” in *Learning Manual*, Section “Scores and parts” in *Learning Manual*.

Known issues and warnings

If an included file is given a name which is the same as one in LilyPond’s installation files, LilyPond’s file from the installation files takes precedence.

22.2 Different editions from one source

Several methods can be used to generate different versions of a score from the same music source. Variables are perhaps the most useful for combining lengthy sections of music and/or annotation. Tags are more useful for selecting one section from several alternative shorter sections of music, and can also be used for splicing pieces of music together at different points.

Whichever method is used, separating the notation from the structure of the score will make it easier to change the structure while leaving the notation untouched.

22.2.1 Using variables

If sections of the music are defined in variables they can be reused in different parts of the score, see Section “Organizing pieces with variables” in *Learning Manual*. For example, an *a cappella* vocal score frequently includes a piano reduction of the parts for rehearsal purposes which is identical to the vocal music, so the music need be entered only once. Music from two variables may be combined on one staff, see Section 5.2.5 [Automatic part combining], page 232. Here is an example:

```

sopranoMusic = \relative { a'4 b c b8( a) }
altoMusic = \relative { e'4 e e f }
tenorMusic = \relative { c'4 b e d8( c) }
bassMusic = \relative { a4 gis a d, }
allLyrics = \lyricmode { King of glo -- ry }
<<
  \new Staff = "Soprano" \sopranoMusic
  \new Lyrics \allLyrics
  \new Staff = "Alto" \altoMusic
  \new Lyrics \allLyrics
  \new Staff = "Tenor" {
    \clef "treble_8"
    \tenorMusic
  }
  \new Lyrics \allLyrics
  \new Staff = "Bass" {
    \clef "bass"
    \bassMusic
  }
  \new Lyrics \allLyrics
  \new PianoStaff <<
    \new Staff = "RH" {
      \partCombine \sopranoMusic \altoMusic
    }
    \new Staff = "LH" {
      \clef "bass"
      \partCombine \tenorMusic \bassMusic
    }
  }
>>
>>

```

The image displays a musical score for the hymn "King of glo-ry". It consists of five staves. The first four staves are vocal parts: Soprano (treble clef), Alto (treble clef), Tenor (treble clef with an 8va line), and Bass (bass clef). The fifth staff is the Piano accompaniment, shown as a grand staff with both treble and bass clefs. The lyrics "King of glo-ry" are written below each vocal staff. The music is in common time (C) and features a simple melody with some grace notes and a final flourish in the piano part.

Separate scores showing just the vocal parts or just the piano part can be produced by changing just the structural statements, leaving the musical notation unchanged.

For lengthy scores, the variable definitions may be placed in separate files which are then included, see Section 22.1 [Including LilyPond files], page 625.

22.2.2 Using tags

The `\tag` command marks a music expression with a name.

```
\tag #'foo { ... }
```

Expressions tagged in this way can be conveniently manipulated as a whole.

Keeping and removing tagged music

The command `\keepWithTag` selects tagged music. On the other hand, `\removeWithTag` filters out tagged music.

Filter	Result
Tagged music preceded by <code>\keepWithTag #'name</code> or <code>\keepWithTag #'(name1 name2...)</code>	Untagged music and music tagged with any of the given tag names is included; music tagged with any other tag name is excluded.
Tagged music preceded by <code>\removeWithTag #'name</code> or <code>\removeWithTag #'(name1 name2...)</code>	Untagged music and music not tagged with any of the given tag names is included; music tagged with any of the given tag names is excluded.
Tagged music not preceded by either <code>\keepWithTag</code> or <code>\removeWithTag</code>	All tagged and untagged music is included.

The arguments of the `\tag`, `\keepWithTag`, and `\removeWithTag` commands should be a symbol or a list of symbols such as `#'score` or `#'(violinI violinII)`, followed by a music expression. If *and only if* the symbols are valid LilyPond identifiers (alphabetic characters only, no numbers, underscores, or dashes, and different from any note names), the `#'` prefix may be omitted and, as a shorthand, a list of symbols can use the comma separator. For example, `\tag #'(violinI violinII)` can be written as `\tag violinI,violinII`. The same applies to the arguments of `\keepWithTag` and `\removeWithTag`.


Tagging commands are music functions, thus they cannot be used to filter items that are not music expressions, such as `\book` or `\score` blocks.

In the following example, we see two versions of a piece of music, one showing trills with the usual notation, and one with trills explicitly expanded.

```
music = \relative {
  g'8. c32 d
  \tag #'trills { d8.\trill }
  \tag #'expand { \*3 { e32 d } }
  c32 d
}

\score {
  \keepWithTag #'trills \music
}
\score {
  \keepWithTag #'expand \music
}
```


}



Alternatively, it is sometimes easier to exclude sections of music.

```
music = \relative {
  g'8. c32 d
  \tag #'trills { d8.\trill }
  \tag #'expand { \*3 { e32 d } }
  c32 d
}
```

```
\score {
  \removeWithTag #'expand \music
}
\score {
  \removeWithTag #'trills \music
}
```



If tags mark alternatives that have non-zero duration, the alternatives are often conceptually simultaneous. In this case it is best to put the alternatives in a simultaneous music expression so that the music expression has the same duration no matter which tags are retained. This is especially important if you are using tags in combination with commands like `\cueDuring`.

```
outputTypeTag = "isScore"
```

```
firstInstrument = \relative c' {
  <<
    \tag #'isPart {
      \cueDuring "quoteSecondInstrument" #UP { r2 } }
    \tag #'isScore { r2 }
  >>
  e4 f |
  g4 a b c |
}
```

```
secondInstrument= \relative c'' {
  c4 c r2 |
  \cueDuring "quoteFirstInstrument" #DOWN { r2 }
```

```

    c4 c |
}

\addQuote quoteFirstInstrument \firstInstrument
\addQuote quoteSecondInstrument \secondInstrument

\new Staff {
    \keepWithTag \outputTypeTag \firstInstrument
}

\new Staff {
    \keepWithTag \outputTypeTag \secondInstrument
}

```



Tagged filtering can be applied to articulations, texts, etc., by prepending

```
-\tag #'your-tag
```

to an articulation. For example, the following defines a note with a conditional fingering indication and a note with a conditional annotation.

```

c1-\tag #'finger ^4
c1-\tag #'warn ^"Watch!"

```

Multiple tags may be placed on expressions with multiple `\tag` entries, or by combining multiple tags into one symbol list.

```

music = \relative c'' {
    \tag AA \tag AB { a4 a a a }
    \tag BB,both { b4 b b b }
}

<<
    \keepWithTag AA \music
    \keepWithTag BB \music
    \keepWithTag AB \music
>>

```



Multiple `\removeWithTag` filters may be applied to a single music expression to remove several differently named tagged sections. Alternatively, you can use a single `\removeWithTag` with a list of tags.

```
music = \relative c'' {
  \tag AA { a4 a a a }
  \tag BB { b4 b b b }
  \tag CC { c4 c c c }
  \tag DD { d4 d d d }
}

\new Voice {
  \removeWithTag BB \removeWithTag CC \music
  \removeWithTag BB,CC \music
}
```



Using two or more `\keepWithTag` filters on a single music expression causes *all* of the tagged sections to be removed, which is certainly not what you want: the first filter removes everything except the one named, and any subsequent filter removes the rest. Instead, use one `\keepWithTag` command with a list of multiple tags to remove all tagged sections that are not specified in that list. As an example, the following code prints music tagged with *violinI* and *violinII* but not tagged with *viola* or *cello*.

```
music = \relative c'' {
  \tag violinI { a4 a a a }
  \tag violinII { b4 b b b }
  \tag viola { c4 c c c }
  \tag cello { d4 d d d }
}

\new Staff {
  \keepWithTag violinI,violinII \music
}
```



Using tag groups

While `\keepWithTag` is convenient when dealing with *one* set of alternatives, the removal of music tagged with unrelated tags is problematic when using them for more than one purpose. In that case tags can be grouped with `\tagGroup`. The following code

```
\tagGroup violinI,violinII,viola,cello
```

puts the four tags into a single tag group. As a result, code like

```
\keepWithTag violinI ...
```

now only shows music tagged from *violinI*'s tag group; any music tagged with one of the other tags in the group is removed, as the following example demonstrates.

```

\tagGroup violinI,violinII
\tagGroup original,arranged

music = \relative {
  \tag violinI { c''4^"violinI" c c c }
  \tag violinII { a2 a }
  \tag original { e8 e e2. }
  \tag arranged { d'2 d4 d }
  \tag other { f^"other" f f f }
  R1^"untagged"
}

\new Voice {
  \keepWithTag violinI \music
}

```



Note that individual tags cannot be members of more than one tag group.

It is possible to modify tag groups. There is an alternative way of defining them using `\tagGroupRef` to be able to reference the tag group later for modification. The call

```
tg = \tagGroupRef violinI,violinII
```

is essentially the same as

```

tg = #'(violinI violinII)
\tagGroup \tg

```

There are different possibilities to change existing tag groups.

- To undo the effects of every call of `\tagGroup` or `\tagGroupRef` you can just use `\resetTagGroups`.

```

\tagGroup tagI,tagII


music = \relative {
  \tag tagI { c''4^"tagI" c c c }
  \tag tagII { a2^"tagII" a }
  \tag otherI { d4^"otherI" d d d }
  \tag otherII { f,4^"otherII" g a c }
}

\new Voice {
  \keepWithTag tagI \music
}

\resetTagGroups

\new Voice {
  \keepWithTag tagI \music
}

```



- If you want to reset one specific tag group you have to use `\resetTagGroup` with a given tag group specified by all of its tags. It is handy to use `\tagGroupRef` for the definition of the tag group.

```

tgI = \tagGroupRef tagI,tagII
tgII = \tagGroupRef otherI,otherII


music = \relative {
  \tag tagI { c''4^"tagI" c c c }
  \tag tagII { a2^"tagII" a }
  \tag otherI { d4^"otherI" d d d }
  \tag otherII { f,4^"otherII" g a c }
  \tag test { c8^"test" a g f e2 }
}

% 'otherI', 'otherII' and 'test' are not in the same group
% as 'tagI' so they stay untouched.
\new Voice {
  \keepWithTag tagI \music
}

\resetTagGroup \tgI

% now only 'otherI' and 'otherII' are in a tag group,
% so '\keepWithTag tagI' filters 'tagII' and 'test'.
\new Voice {
  \keepWithTag tagI \music
}

```



- Another way of modifying an existing tag group is to add or remove single tags with the commands `\addToTagGroup` and `\removeFromTagGroup`.

```

tgI = \tagGroupRef tagI,tagII
tgII = \tagGroupRef otherI,otherII

music = \relative {
  \tag tagI { c''4^"tagI" c c c }
  \tag tagII { a2^"tagII" a }
}

```



```

\tag otherI { d4~"otherI" d d d }
\tag otherII { f,4~"otherII" g a c }
\tag test { c8~"test" a g f e2 }
}

% 'otherI', 'otherII' and 'test' are not in the same group
% as 'tagI' so they stay untouched.
\new Voice {
  \keepWithTag tagI \music
}


\addToTagGroup \tgI test

% now 'tagI', 'tagII' and 'test' are in the same group
% so 'tagII' and 'test' are removed.
\new Voice {
  \keepWithTag tagI \music
}

\removeFromTagGroup \tgII otherII
\addToTagGroup \tgI otherII

% now 'otherII' is removed from 'tgII' and
% added to 'tgI' so only 'otherI' is in its
% own tag group and is not filtered.
\new Voice {
  \keepWithTag tagI \music
}

```



Prepending and appending to tagged music

Sometimes you want to splice some music at a particular place in an existing music expression. You can use `\pushToTag` and `\appendToTag` to add material at the front and end of various music constructs, respectively. The supported places are

sequential and simultaneous music

If you tag an entire `{...}` or `<...>` construct, you can add music expressions at its front or back.

chords

If you tag a chord `<...>`, you can either add notes at its front or back, or articulations for the whole chord.

notes and rests

If you tag a note (also inside of a chord) or a rest, you can add articulations to the front or back of its existing articulations. Note that to add other notes, you have to put the note inside of a chord and tag the *chord* instead.

Also note that you cannot tag a single articulation and add to it since it isn't inherently a list. Instead, tag the note.

Both commands get a tag, the material to splice in at every occurrence of the tag, and the tagged expression.

```
music = { \tag #'here { \tag #'here <<c'>> } }

{
  \pushToTag #'here c'
  \pushToTag #'here e'
  \pushToTag #'here g' \music
  \appendToTag #'here c'
  \appendToTag #'here e'
  \appendToTag #'here g' \music
}
```



Replace tagged music

It is possible to replace tagged music with other music.

```
music = { c' \tag #'here { d' } e' }

{
  \music
  \replaceWithTag #'here c' \music
}
```



Keep in mind that the tag is gone after the replacement, so you can only replace it once. Filtering is also not possible after replacement.

```
music = { c' \tag #'here { d' } e' }

{
  \removeWithTag #'here % does nothing because tag is replaced
  \replaceWithTag #'here c'
  \music
}
```



Tagging within markups

The `\tag` command can also be used within `\markup`. LilyPond provides markup commands `\keep-with-tag`, `\remove-with-tag`, `\push-to-tag`, `\append-to-tag` and `\replace-with-tag` in analogy to the corresponding commands for music expressions.

```
test = \markup {
  \tag #'AA a
  \tag #'BB b
  \tag #'CC c
}

\markup { \keep-with-tag #'BB \test }
\markup { \remove-with-tag #'BB \test }
\markup { \push-to-tag #'CC pre \test }
\markup { \append-to-tag #'CC post \test }
\markup { \replace-with-tag #'CC sub \test }
```

b

a c

a b pre c

a b c post

a b sub

Music commands like `\keepWithTag` and `\removeWithTag` filter tags in `\markup` parts in the related music, too.

```
music = \relative {
  c'4~\markup { \tag #'one first \tag #'two second part } c c c
}

{
  \keepWithTag #'one \music
  \removeWithTag #'one \music
}
```




It is also possible to push and append something to the `\markup` of musical objects. However, we cannot use `\pushToTag`, `\appendToTag` or `\replaceWithTag` because they only insert some music, so we need commands like `\pushToTagMarkup`, `\appendToTagMarkup` or `\replaceWithTagMarkup` to insert markup.

```

music = \relative {
  c'4^\markup { \tag #'part part } c c c
}

{
  \pushToTagMarkup #'part "great" \music
  \appendToTagMarkup #'part \markup { is also great } \music
  \replaceWithTagMarkup #'part \markup { cool substitution } \music
}

```



The filtering of tags also works for music embedded within `\score` blocks in markup commands.

```

music = \relative {
  c'2^\markup { \tag #'first first \tag #'second second } c
  \tag #'first { d d }
  \tag #'second { f f }
}

\markup {
  \keep-with-tag #'first \score { \music }
  \remove-with-tag #'first \score { \music }
}

```



Tagging lists of markup need special attention. While the filter functions work as expected, commands like `\push-to-tag`, `\append-to-tag` and `\replace-with-tag` do not.

```

\markup {
  \remove-with-tag #'test { a \tag #'test { b c } d }
}
\markup {
  \push-to-tag #'test "twice" { a \tag #'test { b c } d }
}
\markup {
  \replace-with-tag #'test "twice" { a \tag #'test { b c } d }
}

```

a d

a twice b twice c d

a twice twice d

The reason for this behavior is that LilyPond resolves

```
\tag #'test { b c }
```

internally to

```
\tag #'test b
\tag #'test c
```

and thus the given text is inserted twice. For tagging a list to insert or append something before or after the whole list the command `\tag-list` should be used.

```
\markup {
  \push-to-tag #'test "once" { a \tag-list #'test { b c } d }
}
```

a once b c d

See also

Learning Manual: Section “Organizing pieces with variables” in *Learning Manual*.

Notation Reference: Section 5.2.5 [Automatic part combining], page 232, Section 22.1 [Including LilyPond files], page 625.

Known issues and warnings

Calling `\relative` on a music expression obtained by filtering music through `\keepWithTag` or `\removeWithTag` might cause the octave relations to change, as only the pitches actually remaining in the filtered expression are considered. Applying `\relative` first, before `\keepWithTag` or `\removeWithTag`, avoids this danger as `\relative` then acts on all the pitches as input.

Even when using tag groups, commands like `\keepWithTag` are not commutative. Code like

```
\keepWithTag violinI,original \someMusic
```

does not produce the same output as

```
\keepWithTag violinI \keepWithTag original \someMusic
```

22.2.3 Using global settings

Global settings can be included from a separate file:

```
lilypond -dinclude-settings=MY_SETTINGS.ly MY_SCORE.ly
```

Groups of settings such as page size, font or type face can be stored in separate files and loaded with several `-dinclude-settings` options. This allows different editions from the same score as well as standard settings to be applied to many scores, simply by specifying the proper settings file.

This technique also works well with the use of style sheets, as discussed in Section “Style sheets” in *Learning Manual*.

See also

Learning Manual: Section “Organizing pieces with variables” in *Learning Manual*, Section “Style sheets” in *Learning Manual*.

Notation Reference: Section 22.1 [Including LilyPond files], page 625.

22.3 Using music functions

Where tweaks need to be reused with different music expressions, it is often convenient to make the tweak part of a *music function*. In this section, we discuss only *substitution* functions, where the object is to substitute a variable into a piece of LilyPond input code. Other more complex functions are described in Section “Music functions” in *Extending*.

22.3.1 Substitution function syntax

Making a function that substitutes a variable into LilyPond code is easy. The general form of these functions is

```
function =
#(define-music-function
  (arg1 arg2 ...)
  (type1? type2? ...)
  #{
    ...music...
  #})
```

where

<i>argN</i>	The <i>n</i> th argument.
<i>typeN?</i>	A Scheme <i>type predicate</i> for which <i>argN</i> must return #t.
<i>...music...</i>	Normal LilyPond input, using '\$' (in places where only LilyPond constructs are allowed) or '#' (to use it as a Scheme value or music function argument or music inside of music lists) to reference arguments (e.g., '#arg1').

The list of type predicates is required. Some of the most common type predicates used in music functions are:

```
boolean?
cheap-list? (use instead of 'list?' for faster processing)
ly:duration?
ly:music?
ly:pitch?
markup?
number?
pair?
string?
symbol?
```

For a list of available type predicates, see Section B.25 [Predefined type predicates], page 972. User-defined type predicates are also allowed.

See also

Notation Reference: Section B.25 [Predefined type predicates], page 972.

Extending LilyPond: Section “Music functions” in *Extending*.

Installed Files: `lily/music-scheme.cc`, `scm/c++.scm`, `scm/lily.scm`.

22.3.2 Substitution function examples

This section introduces some substitution function examples. These are not intended to be exhaustive, but rather to demonstrate some of the possibilities of simple substitution functions.

In the first example, a function is defined that simplifies setting the padding of a TextScript grob:

```

padText =
#(define-music-function
  (padding)
  (number?)
  #{
    \once \override TextScript.padding = #padding
  #})

\relative {
  c' '4^"piu mosso" b a b
  \padText 1.8
  c4^"piu mosso" b a b
  \padText 2.6
  c4^"piu mosso" b a b
}

```



In addition to numbers, we can use music expressions such as notes for arguments to music functions:

```

custosNote =
#(define-music-function
  (note)
  (ly:music?)
  #{
    \tweak NoteHead.stencil #ly:text-interface::print
    \tweak NoteHead.text
      \markup \musicglyph "custodes.mensural.u0"
    \tweak Stem.stencil ##f
    #note
  #})

\relative { c'4 d e f \custosNote g }

```



Both of those functions are simple single expressions where only the last element of a function call or override is missing. For those particular function definitions, there is a simpler alternative syntax, namely just writing out the constant part of the expression and replacing its final missing element with `\etc`:

```

padText =
  \once \override TextScript.padding = \etc

\relative {
  c' '4^"piu mosso" b a b
  \padText 1.8
  c4^"piu mosso" b a b
  \padText 2.6
}

```

```
c4^"piu mosso" b a b
}
```



```
custosNote =
  \tweak NoteHead.stencil #ly:text-interface::print
  \tweak NoteHead.text
    \markup \musicglyph "custodes.mensural.u0"
  \tweak Stem.stencil ##f
  \etc
```


```
\relative { c'4 d e f \custosNote g }
```



Substitution functions with multiple arguments can be defined:

```
tempoPadded =
#(define-music-function
  (padding tempotext)
  (number? markup?)
  #{
    \once \override Score.MetronomeMark.padding = #padding
    \tempo \markup { \bold #tempotext }
  #})
```

```
\relative {
  \tempo \markup { "Low tempo" }
  c'4 d e f g1
  \tempoPadded 4.0 "High tempo"
  g4 f e d c1
}
```



22.3.3 How to prevent sharing of music expressions

When writing music functions, it is important to abide by a rule: the same music expressions must not be shared in several places. As an example, here is a problematic function:

```
simpleAccompaniment =
#(define-music-function
  (bass-1 bass-2 chord) (ly:music? ly:music? ly:music?)
  #{
    #bass-1 #chord #bass-2 #chord
  #})
```



```
{
  \clef bass
  \simpleAccompaniment c g, <e g>
  \simpleAccompaniment d g, <f g>
}
```



The problem with this function becomes clear if the result is transposed:

```
simpleAccompaniment =
#(define-music-function
  (bass-1 bass-2 chord) (ly:music? ly:music? ly:music?)
  #{
    #bass-1 #chord #bass-2 #chord
  #})

\transpose c e {
  \clef bass
  \simpleAccompaniment c g, <e g>
  \simpleAccompaniment d g, <f g>
}
```



While the bass notes are correct, the chord is not transposed properly – in fact, it is being transposed twice. The reason for this is that the music expression *chord* was used twice in the result of the function, without copying it. Functions such as `\transpose` modify the music object directly (in the case of `\transpose`, the pitches are changed). If the same music object is reused, modifications made in one place where it is used affect both places, since they hold the same object. In this case, `\transpose` encounters the object twice and transposes it twice.

One way to fix this function is to use ‘\$’ instead of ‘#’ to reference the variables, which makes a copy. The difference between ‘#’ and ‘\$’ is detailed in Section “LilyPond Scheme syntax” in *Extending*.

```
simpleAccompaniment =
#(define-music-function
  (bass-1 bass-2 chord) (ly:music? ly:music? ly:music?)
  #{
    $bass-1 $chord $bass-2 $chord
  #})

\transpose c e {
  \clef bass
  \simpleAccompaniment c g, <e g>
  \simpleAccompaniment d g, <f g>
}
```




22.3.4 Substitution functions and relative octave entry

When `\relative` is applied to a music expression, it traverses it searching for pitched notes, and modifies the pitches in the order they are found, changing the octave of each pitch according to its octave marks (‘`'`’ and ‘`,`’) and the previous pitch. When writing substitution functions, this may lead to the situation that a music expression is ‘relativized’ in a surprising way because the output of the function uses the parameters several times and/or in a different order. Consider this function and how its output reacts to `\relative`:


```
simpleAccompaniment =
#(define-music-function
  (bass-1 bass-2 chord) (ly:music? ly:music? ly:music?)
  #{
    $bass-1 $chord $bass-2 $chord
  #})

\relative {
  \clef bass
  \simpleAccompaniment c g <e' g>
  \simpleAccompaniment d g, <f' g>
}
```



In this example, the output is the same as that of

```
\relative {
  \clef bass
  c <e' g> g <e' g>
  d <f' g> g, <f' g>
}
```



However, this is not the desired output when using the `\simpleAccompaniment` function. The pitch `g`, is relative to the first note of the chord that precedes it, `<e' g>`, although it comes after `c` in the input. Clearly, the pitches should be made relative according to the order in which they are input when using the function, not in the order they appear in the output of the function. This can be achieved using the `make-relative` Scheme macro. Its arguments are: a list of variables, a reference expression, and a main music expression. The reference expression is intended to be a mock-up of how the variables were entered in the input. Most of the time, it can be a simple expression made with `#{ ... #}` containing the variables in order. Beware *not* to make copies in the reference expression (in particular, use ‘`#`’, not ‘`$`’). The example above can be fixed using `make-relative` in this way:

```

simpleAccompaniment =
#(define-music-function
  (bass-1 bass-2 chord) (ly:music? ly:music? ly:music?)
  (make-relative
    (bass-1 bass-2 chord)
    #{ #bass-1 #bass-2 #chord #}
    #{ $bass-1 $chord $bass-2 $chord #}))

\relative {
  \clef bass
  \simpleAccompaniment c g <e' g>
  \simpleAccompaniment d g, <f' g>
}

```



22.4 Special characters

22.4.1 Text encoding

LilyPond uses the character repertoire defined by the Unicode consortium and ISO/IEC 10646. This defines a unique name and code point for the character sets used in virtually all modern languages and many others too. Unicode can be implemented using several different encodings. LilyPond uses the UTF-8 encoding (UTF stands for Unicode Transformation Format) which represents all common Latin characters in one byte, and represents other characters using a variable length format of up to four bytes.

The actual appearance of the characters is determined by the glyphs defined in the particular fonts available – a font defines the mapping of a subset of the Unicode code points to glyphs. LilyPond uses the Pango library to layout and render multi-lingual texts.

LilyPond does not perform any input encoding conversions. This means that any text, be it title, lyric text, or musical instruction containing non-ASCII characters, must be encoded in UTF-8. The easiest way to enter such text is by using a Unicode-aware editor and saving the file with UTF-8 encoding. Most popular modern editors have UTF-8 support, for example, vim, Emacs, jEdit, and Gedit do. All MS Windows systems later than NT use Unicode as their native character encoding, so even Notepad can edit and save a file in UTF-8 format. A more functional alternative for Windows is BabelPad.

If a LilyPond input file containing a non-ASCII character is not saved in UTF-8 format the error message

```
FT_Get_Glyph_Name () error: invalid argument
```

will be generated.

Here is an example showing Cyrillic, Hebrew and Portuguese text:



22.4.2 Unicode


To enter a single character for which the Unicode code point is known but which is not available in the editor being used, use either `\char ##xhhhh` or `\char #dddd` within a `\markup` block, where `hhhh` is the hexadecimal code for the character required and `dddd` is the corresponding decimal value. Leading zeroes may be omitted, but it is usual to specify all four characters in the hexadecimal representation. (Note that the UTF-8 encoding of the code point should *not* be used after `\char`, as UTF-8 encodings contain extra bits indicating the number of octets.) Unicode code charts and a character name index giving the code point in hexadecimal for any character can be found on the Unicode Consortium website, <https://www.unicode.org/>.

For example, `\char ##x03BE` and `\char #958` would both enter the Unicode U+03BE character, which has the Unicode name “Greek Small Letter Xi”.

Any Unicode code point may be entered in this way and if all special characters are entered in this format it is not necessary to save the input file in UTF-8 format. Of course, a font containing all such encoded characters must be installed and available to LilyPond.

The following example shows Unicode hexadecimal values being entered in four places – in a text mark, as articulation text, in lyrics and as stand-alone text below the score:

```
\score {
  \relative {
    c'1
    \textMark \markup { \char ##x03A8 }
    c1_\markup { \tiny { \char ##x03B1 " to " \char ##x03C9 } }
  }
  \addlyrics { 0 \markup { \concat { Ph \char ##x0153 be! } } }
}
\markup { "Copyright 2008--2026" \char ##x00A9 }
```



Copyright 2008--2026 ©

To enter the copyright sign in the copyright notice use:

```
\header {
  copyright = \markup { \char ##x00A9 "2008" }
}
```

22.4.3 ASCII aliases

A list of ASCII aliases for special characters can be included:

```
\paper {
  #(include-special-characters)
}

\markup "&flqq; &ndash; &OE;uvre incomplète&hellip; &frqq;"

\score {
  \new Staff { \*9 a'4 }
  \addlyrics {
    This is al -- so wor -- kin'~in ly -- rics: &ndash;_&OE;&hellip;
  }
}
```


```

}

\markup \column {
  "The replacement can be disabled:"
  "&ndash; &OE; &hellip;"
  \override #'(replacement-alist . ()) "&ndash; &OE; &hellip;"
}

```

« – Œuvre incomplète... »



The replacement can be disabled:

– Œ ...

– &OE; …

You can also make your own aliases, either globally:

```

\paper {
  #(add-text-replacements!
    '(("100" . "hundred")
      ("dpi" . "dots per inch")))
}
\markup "A 100 dpi."

```

A hundred dots per inch.

or locally:

```

\markup \replace #'(("100" . "hundred")
  ("dpi" . "dots per inch")) "A 100 dpi."

```

A hundred dots per inch.

The replacement is not necessarily a string; it can be an arbitrary markup. On the syntax level, this requires using Scheme quasi-quoting syntax, with a backtick ‘`’ instead of a quote ‘’ to write the alist.

```

\markup \replace
  #`(("2nd" . ,#{ \markup \concat { 2 \super nd } #})) "2nd time"

```

2nd time

Aliases themselves are not further processed for replacements.

See also

Notation Reference: Section B.12 [List of special characters], page 925.

Installed Files: `ly/text-replacements.ly`.

23 Controlling output

23.1 Extracting fragments of music

It is possible to output one or more fragments of a score. To do so, use the `clip-regions` variable within the `\layout` or `\paper` block to define a list of explicit location of the music to be extracted, then execute `lilypond` with the `-dclip-systems` option.

```
\layout {
  clip-regions
  = #(list (cons (make-rhythmic-location 5 1 2)
                 (make-rhythmic-location 7 3 4)))
}
```

This example extracts a single fragment of the input file starting after a half note duration in fifth measure (5 1 2) and ending after the third quarter note in the seventh measure (7 3 4).

Additional fragments can be extracted by adding more pairs of `make-rhythmic-location` entries to the `clip-regions` list.

If system starts and ends are included, they include extents of the `System` grob, e.g., instrument names.

Grace notes at the end point of the region are not included.

Each music fragment gets written as a separate file. The extracted music is output as if it had been literally ‘cut’ from the original printed score, so if a fragment runs over one or more lines, a separate output file for each line is generated. Assuming that the above example covers two lines in the PDF output of input file `foo.ly`, the output files for the music fragments would be called `foo-from-5.1.2-to-7.3.4-clip.pdf` and `foo-from-5.1.2-to-7.3.4-clip-1.pdf`.

See also

Notation Reference: Section 27.1 [The `\layout` block], page 681.

Application Usage: Section “Command-line usage” in *Application Usage*.

23.2 Skipping corrected music

When entering or copying music, usually only the music near the end (where new notes are being added) is interesting to view and correct. To speed up this correction process, it is possible to skip typesetting of all but the last few measures. This is achieved by defining a special variable at the source file’s top level, as follows:

```
showLastLength = R1*5
\score { ... }
```

In this instance, nothing will be rendered but the last five measures (assuming 4/4 time signature) of every `\score` in the input file. For longer pieces, rendering only a small part is often an order of magnitude quicker than rendering it completely. When working on the beginning of a score that has already been typeset (for example to add a new part), the `showFirstLength` property may be useful as well.

Skipping parts of a score can be controlled in a more fine-grained fashion with the property `Score.skipTypesetting`. When it is set, no typesetting is performed at all. As a property of the `Score` context, it affects all voices and staves; see Section 33.1.2 [Score – the master of all contexts], page 734.

This property is also used to control output to the MIDI file. If some event in the skipped section alters some of its context properties, for example a tempo or instrument change, then that new setting will take effect only at the point in time where `skipTypesetting` is disabled again:

```

\relative c' {
  c4 c c c
  \set Score.skipTypesetting = ##t
  d4 d d d
  \tempo 4 = 80
  e4 e e e
  \set Score.skipTypesetting = ##f
  f4 f f f
}

```



Predefined commands

`showLastLength`, `showFirstLength`.

See also

Notation Reference: Chapter 33 [Interpretation contexts], page 734, Section 33.1.2 [Score – the master of all contexts], page 734.

Internals Reference: Section “Tunable context properties” in *Internals Reference*.

23.3 Alternative output formats

The default output formats for the printed score are Portable Document Format (PDF) and PostScript (PS). Portable Network Graphics (PNG), Scalable Vector Graphics (SVG) and Encapsulated PostScript (EPS) output formats are available through command-line options, see Section “Basic command-line options for LilyPond” in *Application Usage*.

23.3.1 SVG Output

SVG output can optionally contain metadata for graphical objects (grobs) like note heads, rests, etc. This metadata can be standard SVG attributes like `id` and `class`, or non-standard custom attributes. Specify the attributes and their values by overriding a grob’s `output-attributes` property with a Scheme association list (alist). The values can be numbers, strings, or symbols. For example:

```

{
  \once \override NoteHead.output-attributes =
    #'((id . 123)
      (class . "this that")
      (data-whatever . something))
  c
}

```

The input above will produce the following `<g>` (group) tag in the SVG file:

```

<g id="123" class="this that" data-whatever="something">
  ...NoteHead grob SVG elements...
</g>

```

The `<g>` tag contains all of the SVG elements for a given grob. (Some grobs generate multiple SVG elements.) In SVG syntax the `data-` prefix is used for non-standard custom metadata attributes.

23.4 Embedding files in PDF output

Command-line option `-dembed-source-code` makes LilyPond embed all (user) source files needed for compilation in the final output PDF (see Section “Advanced command-line options for LilyPond” in *Application Usage*); a PDF viewer can then extract these attachments for further use.


In a similar vein it is possible to embed arbitrary files in the PDF output with function `ly:note-extra-source-file` (see Section “Scheme functions” in *Internals Reference*).

23.5 Replacing the notation font

Gonville is an alternative set of glyphs to *Feta* – part of the Emmmentaler font – and used in LilyPond. They can be downloaded from:

<http://www.chiark.greenend.org.uk/~sgtatham/gonville/> (<http://www.chiark.greenend.org.uk/~sgtatham/gonville/>)

Here are a few sample bars of music set in Gonville:



Here are a few sample bars of music set in LilyPond’s Feta glyphs:



Installation Instructions

- Download and extract the font files.
- Copy¹ the files

gonville-11.otf

¹ Currently it is necessary to repeat these steps after installing a new LilyPond version. If you are running the `lilypond` binary directly from the build directory, see Section “Replacing the notation fonts in development versions” in *Contributor’s Guide* for more information.


```

gonville-13.otf
gonville-14.otf
gonville-16.otf
gonville-18.otf
gonville-20.otf
gonville-23.otf
gonville-26.otf
gonville-brace.otf

```

to directory `.../share/lilypond/X.Y.Z/fonts/otf`.

- If you have `gonville-*.svg` files, copy them to directory `.../share/lilypond/X.Y.Z/fonts/svg`.

For more information, see Section “Other sources of information” in *Learning Manual*.

Note: `gonville-*.otf` files are for the `ps` and `cairo` backend (for PDF and PostScript outputs, as well as all output formats when using the Cairo backend). `gonville-*.svg` files are for the `svg` backend. For more information, see Section “Advanced command-line options for LilyPond” in *Application Usage*.

The following code changes the notation font to the Gonville font.

```

\paper {
  property-defaults.fonts.music = "gonville"
}

```

For more information, see Section 8.3.5 [Changing fonts], page 340.

See also

Learning Manual: Section “Other sources of information” in *Learning Manual*.

Notation Reference: Section B.8 [The Emmentaler font], page 905, Section 8.3.5 [Changing fonts], page 340.

Known issues and warnings

Gonville cannot be used to typeset ‘Ancient Music’ notation and it is likely newer glyphs in later releases of LilyPond may not exist in the Gonville font family. Please refer to the author’s website for more information on these and other specifics, including licensing of Gonville.

Other notation fonts

If you have other notation fonts like `fontname-*.otf` and `fontname-*.svg`, you can use them in the same way as Gonville.

That is, copy the `fontname-*.otf` files to `.../share/lilypond/X.Y.Z/fonts/otf`. If you have `fontname-*.svg` files, copy them to `.../share/lilypond/X.Y.Z/fonts/svg`.

Note: At the moment, LilyPond expects the font file names to have the following suffixes, all of which must be present in the above installation folder(s) to work properly: `-11`, `-13`, `-14`, `-16`, `-18`, `-20`, `-23`, `-26`, `-brace`. For example, `emmentaler-11.otf`, `emmentaler-20.svg`, etc.

The following code changes the notation font to the *fontname* font.

```

\paper {
  % font file name without suffix and extension
  property-defaults.fonts.music = "fontname"
}

```

24 Creating MIDI output

LilyPond can produce files that conform to the MIDI (Musical Instrument Digital Interface) standard and so allow for the checking of the music output aurally (with the help of an application or device that understands MIDI). Listening to MIDI output may also help in spotting errors such as notes that have been entered incorrectly or are missing accidentals and so on.

MIDI files do not contain sound (like AAC, MP3 or Vorbis files) but require additional software to produce sound from them.

24.1 Supported notation for MIDI

The following musical notation can be used with LilyPond's default capabilities to produce MIDI output;

- Breath marks
- Chords entered as chord names
- Crescendi, decrescendi over multiple notes. The volume is altered linearly between the two extremes
- Dynamic markings from ppppp to fffff, including mp, mf and sf
- Lyrics
- Markers: rehearsal marks, segni, coda marks, and section labels
- Microtones but *not* microtonal chords. A MIDI player that supports pitch bending will also be required.
- Pitches
- Rhythms entered as note durations, including tuplets
- 'Simple' articulations; staccato, staccatissimo, accent, marcato and portato
- Tempo changes using the `\tempo` function, including for fractional metronome values
- Ties
- Tremolos that are *not* entered with a `':[number]'` value

Panning, balance, expression, reverb and chorus effects can also be controlled by setting context properties, see Section 24.8 [Context properties for MIDI effects], page 661.

When combined with the `articulate` script the following, additional musical notation can be output to MIDI;

- Appoggiaturas. These are made to take half the value of the note following (without taking dots into account). For example;

```
\appoggiatura c8 d2.
```

The `c` will take the value of a crotchet.

- Ornaments (i.e., mordents, trills and turns et al.)
- Rallentando, accelerando, ritardando and *a tempo*
- Slurs, including phrasing slurs
- Tenuto

See Section 24.9 [Enhancing MIDI output], page 662.

24.2 Unsupported notation for MIDI

The following items of musical notation cannot be output to MIDI;

- Articulations other than staccato, staccatissimo, accent, marcato and portato
- Crescendi and decrescendi over a *single* note
- Fermata
- Figured bass
- Glissandi
- Falls and doits
- Microtonal chords
- Rhythms entered as annotations, e.g., swing
- Tempo changes without `\tempo` (e.g., entered as annotations)
- Tremolos that *are* entered with a `':[number]` value

24.3 The MIDI block

To create a MIDI output file from a LilyPond input file, insert a `\midi` block, which can be empty, within the `\score` block.¹

```
\score {
  ... music ...
  \layout { }
  \midi { }
}
```

Note: A `\score` block that contains music and a `\midi` block but no `\layout` block produces a MIDI output file only. No notation gets printed.

A `\midi` block at the top level can be used to change MIDI settings globally; however, the generation of an actual MIDI file only happens when a `\midi` block is part of a `\score` block.

Similarly, a `\layout` block at the top level affects layout settings globally but does not influence whether printed output is produced or not.

The default output file extension (`.midi`) can be changed by using the `-dmidi-extension` option with the `lilypond` command:

```
lilypond -dmidi-extension=mid MyFile.ly
```

Alternatively, add the following Scheme expression before the start of either the `\book`, `\bookpart` or `\score` blocks. See Section 20.5 [File structure], page 594.

```
 #(ly:set-option 'midi-extension "mid")
```

See also

Notation Reference: Section 20.5 [File structure], page 594, Section 21.3 [Creating output file metadata], page 609.

Installed Files: `scm/midi.scm`.

¹ Note that there also exists a markup command called `\score` that doesn't produce MIDI output, even if a `\midi` block is present. See [Scores within markup], page 858.

Known issues and warnings

There are fifteen MIDI channels available and one additional channel (#10) for drums. Staves are assigned to channels in sequence, so a score that contains more than fifteen staves will result in the extra staves sharing (but not overwriting) the same MIDI channel. This may be a problem if the sharing staves have conflicting, channel-based, MIDI properties – such as different MIDI instruments – set.

24.4 Controlling MIDI dynamics

It is possible to control the overall MIDI volume, the relative volume of dynamic markings and the relative volume of different instruments.

Dynamic marks translate automatically into volume levels in the available MIDI volume range whereas crescendi and decrescendi vary the volume linearly between their two extremes. It is possible to control the relative volume of dynamic markings, and the overall volume levels of different instruments.

24.4.1 Dynamic marks in MIDI

Only the dynamic markings from *ppppp* to *fffff*, including *mp*, *mf* and *sf* have values assigned to them. This value is then applied to the value of the overall MIDI volume range to obtain the final volume included in the MIDI output for that particular dynamic marking. The default fractions range from 0.25 for *ppppp* to 0.95 for *fffff*. The complete set of dynamic marks and their associated fractions can be found in `ly/midi-init.ly`.

Selected snippets


Creating custom dynamics in MIDI output

The following example shows how to create a dynamic marking, not included in the default list, and assign a specific value to it so that it affects MIDI output.

The dynamic mark `\rfz` gets value 0.9.

```
#(define (myDynamics dynamic)
  (if (equal? dynamic "rfz")
      0.9
      (default-dynamic-absolute-volume dynamic)))

\score {
  \new Staff {
    \set Staff.midiInstrument = "cello"
    \set Score.dynamicAbsoluteVolumeFunction = #myDynamics
    \new Voice {
      \relative {
        a'4\pp b c-\rfz
      }
    }
  }
  \layout {}
  \midi {}
}
```



Installed Files: `ly/script-init.ly scm/midi.scm`.

Snippets: Section “MIDI” in *Snippets*.

Internals Reference: Section “Dynamic_performer” in *Internals Reference*.

24.4.2 Setting MIDI volume

The minimum and maximum overall volume of MIDI dynamic markings is controlled by setting the properties `midiMinimumVolume` and `midiMaximumVolume` at the Score level. These properties have an effect only at the start of a voice and on dynamic marks. The fraction corresponding to each dynamic mark is modified with this formula

$$\text{midiMinimumVolume} + (\text{midiMaximumVolume} - \text{midiMinimumVolume}) * \text{fraction}$$

In the following example the dynamic range of the overall MIDI volume is limited to the range 0.2–0.5.

```
\score {
  <<
    \new Staff {
      \set Staff.midiInstrument = "flute"
      ... music ...
    }
    \new Staff {
      \set Staff.midiInstrument = "clarinet"
      ... music ...
    }
  >>
  \midi {
    \context {
      \Score
      midiMinimumVolume = 0.2
      midiMaximumVolume = 0.5
    }
  }
}
```

Simple MIDI instrument equalization can be achieved by setting `midiMinimumVolume` and `midiMaximumVolume` properties within the Staff context.

```
\score {
  \new Staff {
    \set Staff.midiInstrument = "flute"
    \set Staff.midiMinimumVolume = 0.7
    \set Staff.midiMaximumVolume = 0.9
    ... music ...
  }
  \midi { }
}
```

For scores with multiple staves and multiple MIDI instruments, the relative volumes of each instrument can be set individually;

```
\score {
  <<
    \new Staff {
      \set Staff.midiInstrument = "flute"
      \set Staff.midiMinimumVolume = 0.7
      \set Staff.midiMaximumVolume = 0.9
```

```

    ... music ...
  }
  \new Staff {
    \set Staff.midiInstrument = "clarinet"
    \set Staff.midiMinimumVolume = 0.3
    \set Staff.midiMaximumVolume = 0.6
    ... music ...
  }
>>
\midi { }
}

```

In this example the volume of the clarinet is reduced relative to the volume of the flute.

If these volumes properties are not set then LilyPond still applies a ‘small degree’ of equalization to certain instruments. See `scm/midi.scm`.

Installed Files: `scm/midi.scm`.

See also

Notation Reference: Chapter 27 [Score layout], page 681.

Internals Reference: Section “Dynamic_performer” in *Internals Reference*.

Selected snippets

Replacing default MIDI instrument equalization

The default MIDI instrument equalizer can be replaced by setting the `instrumentEqualizer` property in the Score context to a user-defined Scheme procedure that uses a MIDI instrument name as its argument along with a pair of fractions indicating the minimum and maximum volumes, respectively, to be applied to that specific instrument.

The following example sets the minimum and maximum volumes for flute and clarinet.

```

#(define my-instrument-equalizer-alist '())

#(set! my-instrument-equalizer-alist
  (append
    '(("flute" . (0.7 . 0.9))
      ("clarinet" . (0.3 . 0.6)))
    my-instrument-equalizer-alist))

#(define (my-instrument-equalizer s)
  (let ((entry (assoc s my-instrument-equalizer-alist)))
    (if entry
      (cdr entry))))

\score {
  <<
    \new Staff {
      \key g \major
      \time 2/2
      \set Score.instrumentEqualizer = #my-instrument-equalizer
      \set Staff.midiInstrument = "flute"
      \new Voice \relative {
        r2 g''\mp g fis~

```

```

        4 g8 fis e2~
        4 d8 cis d2
    }
}
\new Staff {
  \key g \major
  \set Staff.midiInstrument = "clarinet"
  \new Voice \relative {
    b'1\p a2. b8 a
    g2. fis8 e
    fis2 r
  }
}
>>
\layout { }
\midi { }
}

```



Known issues and warnings

Changes in the MIDI volume take place only on starting a note, so crescendi and decrescendi cannot affect the volume of a single note.

24.4.3 Setting MIDI block properties

The `\midi` block can contain context rearrangements, new context definitions or code that sets the values of certain properties.

```

\score {
  ... music ...
  \midi {
    \tempo 4 = 72
  }
}

```

Here the tempo is set to 72 quarter note beats per minute. The tempo mark in the `\midi` block will not appear in the printed score. Although any other `\tempo` indications specified within the `\score` block will also be reflected in the MIDI output.

In a `\midi` block the `\tempo` command is setting properties during the interpretation of the music and in the context of output definitions; so it is interpreted *as if* it were a context modification.

Context definitions follow the same syntax as those in a `\layout` block;

```

\score {
  ... music ...
  \midi {
    \context {
      \Voice
    }
  }
}

```

```

        \remove Dynamic_performer
    }
}

```

This example removes the effect of dynamics from the MIDI output. Note: LilyPond’s translation modules used for sound are called ‘performers’.

See also

Learning Manual: Section “Other sources of information” in *Learning Manual*.

Notation Reference: Chapter 3 [Expressive marks], page 155, Chapter 27 [Score layout], page 681.

Installed Files: `ly/performer-init.ly`.

Snippets: Section “MIDI” in *Snippets*.

Internals Reference: Section “Dynamic_performer” in *Internals Reference*.

Known issues and warnings

Some MIDI players do not always correctly handle tempo changes in the midi output.

Changes to the `midiInstrument`, as well as some MIDI options, at the *beginning* of a staff may appear twice in the MIDI output.

24.5 Using MIDI instruments

MIDI instruments are set using the `midiInstrument` property within a `Staff` context.

```

\score {
  \new Staff {
    \set Staff.midiInstrument = "glockenspiel"
    ... music ...
  }
  \midi { }
}

```

or

```

\score {
  \new Staff \with {midiInstrument = "cello"} {
    ... music ...
  }
  \midi { }
}

```

If the instrument name does not match any of the instruments listed in the ‘MIDI instruments’ section, the acoustic grand instrument will be used instead. See Section B.6 [MIDI instruments], page 899.

See also

Learning Manual: Section “Other sources of information” in *Learning Manual*.

Notation Reference: Section B.6 [MIDI instruments], page 899, Chapter 27 [Score layout], page 681.

Installed Files: `scm/midi.scm`.

Known issues and warnings

Percussion instruments that are notated in a `DrumStaff` context will be output, correctly, to MIDI channel 10 but some pitched, percussion instruments like the xylophone, marimba, vibraphone or timpani, are treated as “normal” instruments so the music for these should be entered in a `Staff` (not `DrumStaff`) context to obtain correct MIDI output. A full list of channel 10 drum-kits entries can be found in `scm/midi.scm`. See Section “Other sources of information” in *Learning Manual*.

24.6 Using repeats with MIDI

Repeats can be represented in the MIDI output by applying the `\unfoldRepeats` command.

```
\score {
  \unfoldRepeats {
    \repeat tremolo 8 { c'32 e' }
    \repeat percent 2 { c''8 d'' }
    \repeat volta 2 { c'4 d' e' f' }
    \alternative {
      \volta 1 { g' a' a' g' }
      \volta 2 { f' e' d' c' }
    }
  }
}
\midi { }
```

In order to restrict the effect of `\unfoldRepeats` to the MIDI output only, while also generating printable scores, it is necessary to make *two* `\score` blocks; one for MIDI (with unfolded repeats) and one for the notation (with volta, tremolo, and percent repeats);

```
\score {
  ... music ...
  \layout { }
}
\score {
  \unfoldRepeats {
    ... music ...
  }
  \midi { }
}
```

When using multiple voices, each of the voices must contain completely unfolded repeats for correct MIDI output.

See also

Notation Reference: Chapter 4 [Repeats], page 188.

24.7 MIDI channel mapping

When generating a MIDI file from a score, LilyPond will automatically assign every note in the score to a MIDI channel, the one on which it should be played when it is sent to a MIDI device. A MIDI channel has a number of controls available to select, for example, the instrument to be used to play the notes on that channel, or to request the MIDI device to apply various effects to the sound produced on the channel. At all times, every control on a MIDI channel can have only a single value assigned to it (which can be modified, however, for example, to switch to another instrument in the middle of a score).

The MIDI standard supports only 16 channels per MIDI device. This limit on the number of channels also limits the number of different instruments which can be played at the same time.

LilyPond creates separate MIDI tracks for each staff, (or discrete instrument or voice, depending on the value of `Score.midiChannelMapping`), and also for each lyrics context. There is no limit to the number of tracks.

To work around the limited number of MIDI channels, LilyPond supports a number of different modes for MIDI channel allocation, selected using the `Score.midiChannelMapping` context property. In each case, if more MIDI channels than the limit are required, the allocated channel numbers wrap around back to 0, possibly causing the incorrect assignment of instruments to some notes. This context property can be set to one of the following values:

`'staff`

Allocate a separate MIDI channel to each staff in the score (this is the default). All notes in all voices contained within each staff will share the MIDI channel of their enclosing staff, and all are encoded in the same MIDI track.

The limit of 16 channels is applied to the total number of staff and lyrics contexts, even though MIDI lyrics do not take up a MIDI channel.

`'instrument`

Allocate a separate MIDI channel to each distinct MIDI instrument specified in the score. This means that all the notes played with the same MIDI instrument will share the same MIDI channel (and track), even if the notes come from different voices or staves.

In this case the lyrics contexts do not count towards the MIDI channel limit of 16 (as they will not be assigned to a MIDI instrument), so this setting may allow a better allocation of MIDI channels when the number of staves and lyrics contexts in a score exceeds 16.

`'voice`

Allocate a separate MIDI channel to each voice in the score that has a unique name among the voices in its enclosing staff. Voices in different staves are always assigned separate MIDI channels, but any two voices contained within the same staff will share the same MIDI channel if they have the same name. Because `midiInstrument` and the several MIDI controls for effects are properties of the staff context, they cannot be set separately for each voice. The first voice will be played with the instrument and effects specified for the staff, and voices with a different name from the first will be assigned the default instrument and effects.

Note: different instruments and/or effects can be assigned to several voices on the same staff by moving the `Staff_performer` from the `Staff` to the `Voice` context, and leaving `midiChannelMapping` to default to `'staff` or set to `'instrument`; see the snippet below.

For example, the default MIDI channel mapping of a score can be changed to the `'instrument` setting as shown:

```
\score {
  ...music...
  \midi {
    \context {
      \Score
      midiChannelMapping = #'instrument
    }
  }
}
```

Selected snippets

Changing MIDI output to one channel per voice

When outputting MIDI, the default behavior is for each staff to represent one MIDI channel, with all the voices on a staff amalgamated. This minimizes the risk of running out of MIDI channels, since there are only 16 available per track.

However, by moving the `Staff_performer` to the `Voice` context, each voice on a staff can have its own MIDI channel, as is demonstrated by the following example: despite being on the same staff, two MIDI channels are created, each with a different `midiInstrument`.

```
\score {
  \new Staff <<
    \new Voice \relative c'' {
      \set midiInstrument = "flute"
      \voiceOne
      \key g \major
      \time 2/2
      r2 g-"Flute" ~
      g fis ~
      fis4 g8 fis e2 ~
      e4 d8 cis d2
    }
    \new Voice \relative c'' {
      \set midiInstrument = "clarinet"
      \voiceTwo
      b1-"Clarinet"
      a2. b8 a
      g2. fis8 e
      fis2 r
    }
  >>
  \layout { }
  \midi {
    \context {
      \Staff
      \remove "Staff_performer"
    }
    \context {
      \Voice
      \consists "Staff_performer"
    }
    \tempo 2 = 72
  }
}
```



24.8 Context properties for MIDI effects

The following context properties can be used to apply various MIDI effects to notes played on the MIDI channel associated with the current staff, MIDI instrument or voice (depending on the value of the `Score.midiChannelMapping` context property and the context in which the `Staff_performer` is located; see Section 24.7 [MIDI channel mapping], page 658).

Changing these context properties will affect all notes played on the channel after the change, however some of the effects may even apply also to notes which are already playing (depending on the implementation of the MIDI output device).

The following context properties are supported:

`Staff.midiPanPosition`

The pan position controls how the sound on a MIDI channel is distributed between left and right stereo outputs. The context property accepts a number between -1.0 (`#LEFT`) and 1.0 (`#RIGHT`); the value -1.0 will put all sound power to the left stereo output (keeping the right output silent), the value 0.0 (`#CENTER`) will distribute the sound evenly between the left and right stereo outputs, and the value 1.0 will move all sound to the right stereo output. Values between -1.0 and 1.0 can be used to obtain mixed distributions between left and right stereo outputs.

`Staff.midiBalance`

The stereo balance of a MIDI channel. Similarly to the pan position, this context property accepts a number between -1.0 (`#LEFT`) and 1.0 (`#RIGHT`). It varies the relative volume sent to the two stereo speakers without affecting the distribution of the stereo signals.

`Staff.midiExpression`

Expression level (as a fraction of the maximum available level) to apply to a MIDI channel. A MIDI device combines the MIDI channel's expression level with a voice's current dynamic level (controlled using constructs such as `\p` or `\ff`) to obtain the total volume of each note within the voice. The expression control could be used, for example, to implement crescendo or decrescendo effects over single sustained notes (not supported automatically by LilyPond).

The expression level ranges from 0.0 (no expression, meaning zero volume) to 1.0 (full expression).

`Staff.midiReverbLevel`

Reverb level (as a fraction of the maximum available level) to apply to a MIDI channel. This property accepts numbers between 0.0 (no reverb) and 1.0 (full effect).

`Staff.midiChorusLevel`

Chorus level (as a fraction of the maximum available level) to apply to a MIDI channel. This property accepts numbers between 0.0 (no chorus effect) and 1.0 (full effect).

Known issues and warnings

As MIDI files do not contain any actual audio data, changes in these context properties translate only to requests for changing MIDI channel controls in the outputted MIDI files. Whether a particular MIDI device (such as a software MIDI player) can actually handle any of these requests in a MIDI file is entirely up to the implementation of the device: a device may choose to ignore some or all of these requests. Also, how a MIDI device will interpret different values for these controls (generally, the MIDI standard fixes the behavior only at the endpoints of the value range available for each control), and whether a change in the value of a control will affect notes already playing on that MIDI channel or not, is also specific to the MIDI device implementation.

When generating MIDI files, LilyPond will simply transform the fractional values within each range linearly into values in a corresponding (7-bit, or 14-bit for MIDI channel controls which support fine resolution) integer range (0-127 or 0-16383, respectively), rounding fractional values towards the nearest integer away from zero. The converted integer values are stored as-is in the generated MIDI file. Please consult the documentation of your MIDI device for information about how the device interprets these values.

24.9 Enhancing MIDI output

The default MIDI output is basic but can be improved by setting MIDI instruments and various `\midi` block properties.

Additional scripts allow to fine-tune the way dynamics, articulations and rhythm are rendered in MIDI: the `articulate` script and the `swing` script.

24.9.1 The `articulate` script

To use the `articulate` script add the appropriate `\include` command at the top of the input file;

```
\include "articulate.ly"
```

The script creates MIDI output into appropriately ‘time-scaled’ notes to match many articulation and tempo indications. Engraved output however, will also be altered to literally match the MIDI output.

```
\score {
  \articulate <<
    ... music ...
  >>
  \midi { }
}
```

The `\articulate` command enables abbreviations (such as trills and turns) to be processed. A full list of supported items can be found in the script itself. See `ly/articulate.ly`.

See also

Learning Manual: Section “Other sources of information” in *Learning Manual*.

Notation Reference: Chapter 27 [Score layout], page 681.

Installed Files: `ly/articulate.ly`.

Note: The `articulate` script may shorten chords, which might not be appropriate for some types of instrument, such as organ music. Notes that do not have any articulations attached to them may also be shortened; so to allow for this, restrict the use of the `\articulate` function to shorter segments of music, or modify the values of the variables defined in the `articulate` script to compensate for the note-shortening behavior.

24.9.2 The `swing` script

The `swing` script provides additional functions allowing for regular durations to be played with an unequal rhythm. The most obvious example is ‘swing’ interpretation commonly found in jazz music where binary eighth notes should be played in a ternary fashion; however additional interpretations are also supported.

This script has to be `\include-d` at the beginning of the input file:

```
\include "swing.ly"
```

Three commands are provided:

- `\tripletFeel` creates a triplet-feel swing. It takes two arguments: the durations that should be affected by it (typically 8 for eighth notes), and then the music expression to which it should be applied.
- `\applySwing` takes an additional argument prior to the music expression: a ‘weight list’ of n number ratios expressing the way regular notes should be played: for example, `\#' (2 1)` indicates that every other note should be played twice as long as the following note (in fact, `\tripletFeel duration {music}` is actually a shortcut for `\applySwing duration \#' (2 1) {music}`). Smoother swung eighths may be obtained with a weight list of `\#' (3 2)`, or other values depending on taste.

That list may include more than two values, which allows for longer and more sophisticated groove patterns; for example, a samba feel for sixteenth notes may be obtained as follows:

```
\score {
  \applySwing 16 \#' (3 2 2 3) {
    ... music ...
  }
  \midi { }
}
```

- `\applySwingWithOffset` adds yet another argument between the ‘weight list’ and the music expression: an offset length. This command should be used when the music expression has to start off-beat, with a partial swing cycle.

Note: As with the articulate script, all swing commands are also rendered in the engraved output, which results in irregular note spacing. This can be avoided by using them only in a `\score` block dedicated to MIDI output, rather than to printed music.

Additional help and information is included in the script file: see `ly/swing.ly`.

See also

Learning Manual: Section “Other sources of information” in *Learning Manual*.

Notation Reference: Chapter 2 [Rhythms], page 52.

Installed Files: `ly/swing.ly`.

Known issues and warnings

- `\repeat` constructs in music (even `\repeat unfold`) are not taken into consideration when determining note timing. This will lead to problems unless the durations of all repeated parts are integer multiples of the swing cycle duration.
- These functions are oblivious to time signatures and measures. That is why offsets need to be supplied by using `\applySwingWithOffset` if music starts off-beat.
- Grace notes are ignored and simply left unaffected; so are tuplets.

25 Extracting musical information

In addition to creating graphical output and MIDI, LilyPond can display musical information as text.

25.1 Displaying LilyPond notation

Displaying a music expression in LilyPond notation can be done with the music function `\displayLilyMusic`. To see the output, you will typically want to call LilyPond using the command line. For example,

```
{
  \displayLilyMusic \transpose c a, { c4 e g a bes }
}
will display
{ a,4 cis4 e4 fis4 g4 }
```

By default, LilyPond will print these messages to the console along with all the other LilyPond compilation messages. To split up these messages and save the results of `\displayLilyMusic`, redirect the output to a file.

```
lilypond file.ly >display.txt
```

Note that LilyPond does not just display the music expression, but also interprets it (since `\displayLilyMusic` returns it in addition to displaying it). Just insert `\displayLilyMusic` into the existing music in order to get information about it.

To interpret and display a music section in the console but, at the same time, remove it from the output file use the `\void` command.

```
{
  \void \displayLilyMusic \transpose c a, { c4 e g a bes }
  c1
}
```

25.2 Displaying Scheme music expressions

See Section “Displaying music expressions” in *Extending*.

25.3 Saving music events to a file

Music events can be saved to a file on a per-staff basis by including a file in your main score.

```
\include "event-listener.ly"
```

This creates file(s) called `FILENAME-STAFFNAME.notes` or `FILENAME-unnamed-staff.notes` for each staff. Note that if you have multiple unnamed staves, the events for all staves are mixed together in the same file. The output looks like this:

```
0.000  note      57      4    p-c 2 12
0.000  dynamic   f
0.250  note      62      4    p-c 7 12
0.500  note      66      8    p-c 9 12
0.625  note      69      8    p-c 14 12
0.750  rest      4
0.750  breathe
```

The syntax is a tab-delimited line, with two fixed fields on each line followed by optional parameters.

```
time  type  ...params...
```

This information can easily be read into other programs such as python scripts, and can be very useful for researchers wishing to perform musical analysis or playback experiments with LilyPond.

Known issues and warnings

Not all lilypond music events are supported by `event-listener.ly`. It is intended to be a well-crafted “proof of concept”. If some events that you want to see are not included, copy `event-listener.ly` into your lilypond directory and modify the file so that it outputs the information you want.

Spacing issues

26 Page layout

The global paper layout is determined by three factors: the page layout, the line breaks, and the spacing. These all influence each other. The choice of spacing determines how densely each system of music is set. This influences where line breaks are chosen, and thus ultimately, how many pages a piece of music takes.

Globally speaking, this procedure happens in four steps: first, flexible distances (‘springs’) are chosen, based on durations. All possible line breaking combinations are tried, and a ‘badness’ score is calculated for each. Then the height of each possible system is estimated. Finally, a page breaking and line breaking combination is chosen so that neither the horizontal nor the vertical spacing is too cramped or stretched.

Two types of blocks can contain layout settings: `\paper {...}` and `\layout {...}`. The `\paper` block contains page layout settings that are expected to be the same for all scores in a book or book part, such as the paper height, or whether to print page numbers, etc. See Chapter 26 [Page layout], page 669. The `\layout` block contains score layout settings, such as the number of systems to use, or the space between staff groups, etc. See Chapter 27 [Score layout], page 681.

26.1 The `\paper` block

`\paper` blocks may be placed in three different places to form a descending hierarchy of `\paper` blocks:

- At the top of the input file, before all `\book`, `\bookpart`, and `\score` blocks.
- Within a `\book` block but outside all the `\bookpart` and `\score` blocks within that book.
- Within a `\bookpart` block but outside all `\score` blocks within that book part.

A `\paper` block cannot be placed within a `\score` block.

The values of the fields filter down this hierarchy, with the values set higher in the hierarchy persisting unless they are overridden by a value set lower in the hierarchy.

Several `\paper` blocks can appear at each of the levels, for example as parts of several `\included` files. If so, the fields at each level are merged, with values encountered last taking precedence if duplicated fields appear.

Settings that can appear in a `\paper` block include:

- the `set-paper-size` Scheme function,
- `\paper` variables used for customizing page layout, and
- markup definitions used for customizing the layout of headers, footers, and titles.

The `set-paper-size` function is discussed in the next section, Section 26.2 [Paper size and automatic scaling], page 670. The `\paper` variables that deal with page layout are discussed in later sections. The markup definitions that deal with headers, footers, and titles are discussed in Section 21.2 [Custom titles, headers, and footers], page 605.

Most `\paper` variables will only work in a `\paper` block. The few that will also work in a `\layout` block are listed in Section 27.1 [The `\layout` block], page 681.

Except when specified otherwise, all `\paper` variables that correspond to distances on the page are measured in millimeters, unless a different unit is specified by the user. For example, the following declaration sets `top-margin` to ten millimeters:

```
\paper {
  top-margin = 10
}
```

To set it to 0.5 inches, use the `\in` unit suffix:

```
\paper {
  top-margin = 0.5\in
}
```

The available unit suffixes are `\mm`, `\cm`, `\in`, `\pt`, and `\bp`. These units are simple values for converting from millimeters; they are defined in `ly/paper-defaults-init.ly`. For the sake of clarity, when using millimeters, the `\mm` is typically included in the code, even though it is not technically necessary.

It is also possible to define `\paper` values using Scheme. The Scheme equivalent of the above example is:

```
\paper {
  #(define top-margin (* 0.5 in))
}
```

Finally, you can also predefine paper variables.

```
bigMargin = \paper { top-margin = 10\cm }

\paper {
  \bigMargin
  indent = 0\mm
}
```

See also

Notation Reference: Section 26.2 [Paper size and automatic scaling], page 670, Section 21.2 [Custom titles, headers, and footers], page 605, Section 27.1 [The `\layout` block], page 681.

Installed Files: `ly/paper-defaults-init.ly`.

26.2 Paper size and automatic scaling

26.2.1 Setting the paper size

‘A4’ is the default value when no explicit paper size is set. However, there are two functions that can be used to change it:

```
set-default-paper-size
  #(set-default-paper-size "quarto")
  which must always be placed at the top-level scope, and

set-paper-size
  \paper {
    #(set-paper-size "tabloid")
  }
  which must always be placed in a \paper block.
```

If the `set-default-paper-size` function is used in the top-level scope, it must come before any `\paper` block. `set-default-paper-size` sets the paper size for all pages, whereas `set-paper-size` only sets the paper size for the pages that the `\paper` block applies to. For example, if the `\paper` block is at the top of the file, then it applies the paper size to all pages. If the `\paper` block is inside a `\book`, then the paper size applies only to that book.

When the `set-paper-size` function is used, it must be placed *before* any other functions used within the same `\paper` block. See Section 26.2.2 [Automatic scaling to paper size], page 671.

Paper sizes are defined in file `scm/paper.scm`; see Section B.5 [Predefined paper sizes], page 897, for a complete list.

Both `set-default-paper-size` and `set-paper-size` also accept a quoted number pair as its argument to set a custom paper size. For example,

```
#(set-default-paper-size '(cons (* 100 mm) (* 50 mm)))
```

sets the paper width and height to 100 mm and 50 mm, respectively.

Possible units are `in` (inches), `cm` (centimeters), `mm` (millimeters), `pt` (points), and `bp` (big points).

If the symbol `'landscape` is added to the paper size function as a second argument, pages are rotated by 90 degrees, and wider line widths are set accordingly.

```
#(set-default-paper-size "a6" 'landscape)
```

Swapping the paper dimensions *without* having the print rotated (like when printing to postcard size, or creating graphics for inclusion rather than a stand-alone document) can be achieved by appending `'landscape` to the name of the paper size itself:

```
#(set-default-paper-size "a6landscape")
```

When the paper size ends with an explicit `'landscape` or `'portrait`, the presence of a `'landscape` symbol *only* affects print orientation, not the paper dimensions used for layout.

See also

Notation Reference: Section 26.2.2 [Automatic scaling to paper size], page 671, Section B.5 [Predefined paper sizes], page 897.

Installed Files: `scm/paper.scm`.

26.2.2 Automatic scaling to paper size

If the paper size is changed with one of the Scheme functions (`set-default-paper-size` or `set-paper-size`), the values of several `\paper` variables are automatically scaled to the new size. To bypass the automatic scaling for a particular variable, set the variable after setting the paper size. Note that the automatic scaling is not triggered by setting the `paper-height` or `paper-width` variables, even though `paper-width` can influence other values (this is separate from scaling and is discussed below). The `set-default-paper-size` and `set-paper-size` functions are described in Section 26.2.1 [Setting the paper size], page 670.

The vertical dimensions affected by automatic scaling are `top-margin` and `bottom-margin` (see Section 26.3 [Fixed vertical spacing `\paper` variables], page 671). The horizontal dimensions affected by automatic scaling are `left-margin`, `right-margin`, `inner-margin`, `outer-margin`, `binding-offset`, `indent`, and `short-indent` (see Section 26.5 [Horizontal spacing `\paper` variables], page 674).

The default values for these dimensions are set in `ly/paper-defaults-init.ly`, using internal variables named `top-margin-default`, `bottom-margin-default`, etc. These are the values that result at the default paper size `a4`. For reference, with `a4` paper the `paper-height` is 297\mm and the `paper-width` is 210\mm.

See also

Notation Reference: Section 26.3 [Fixed vertical spacing `\paper` variables], page 671, Section 26.5 [Horizontal spacing `\paper` variables], page 674.

Installed Files: `ly/paper-defaults-init.ly`, `scm/paper.scm`.

26.3 Fixed vertical spacing `\paper` variables

Note: Some `\paper` dimensions are automatically scaled to the paper size, which may lead to unexpected behavior. See Section 26.2.2 [Automatic scaling to paper size], page 671.

Default values (before scaling) are defined in file `ly/paper-defaults-init.ly`.

`paper-height`

The height of the page, unset by default. Note that the automatic scaling of some vertical dimensions is not affected by this.

`top-margin`

The margin between the top of the page and the top of the printable area. If the paper size is modified, this dimension's default value is scaled accordingly.

`bottom-margin`

The margin between the bottom of the printable area and the bottom of the page. If the paper size is modified, this dimension's default value is scaled accordingly.

`ragged-bottom`

If this is set to `#t`, systems will be set at their natural spacing, neither compressed nor stretched vertically to fit the page.

`ragged-last-bottom`

If this is set to `#f`, then the last page, and the last page in each section created with a `\bookpart` block, will be vertically justified in the same way as the earlier pages.

See also

Notation Reference: Section 26.2.2 [Automatic scaling to paper size], page 671.

Installed Files: `ly/paper-defaults-init.ly`.

Snippets: Section “Spacing” in *Snippets*.

Known issues and warnings

The titles (from the `\header` block) are treated as a system, so `ragged-bottom` and `ragged-last-bottom` will add space between the titles and the first system of the score.

Explicitly defined paper sizes will override any user-defined top or bottom margin settings.

26.4 Flexible vertical spacing `\paper` variables

In most cases, it is preferable for the vertical distances between certain items (such as margins, titles, systems, and separate scores) to be flexible, so that they stretch and compress nicely according to each situation. A number of `\paper` variables (listed below) are available to fine-tune the stretching behavior of these dimensions.

Note that the `\paper` variables discussed in this section do not control the spacing of staves within individual systems. Within-system spacing is controlled by grob properties, with settings typically entered inside a `\score` or `\layout` block, and not inside a `\paper` block. See Section 29.1 [Flexible vertical spacing within systems], page 695.

26.4.1 Structure of flexible vertical spacing alists

Each of the flexible vertical spacing `\paper` variables is an alist (association list) containing four *keys*:

- `basic-distance` – the vertical distance, measured in staff spaces, between the *reference points* of the two items, when no collisions would result, and no stretching or compressing

is in effect. The reference point of a (title or top-level) markup is its highest point, and the reference point of a system is the vertical center of the nearest `StaffSymbol` – even if a non-staff line (such as a `Lyrics` context) is in the way. Values for `basic-distance` that are less than either `padding` or `minimum-distance` are not meaningful, since the resulting distance will never be less than either `padding` or `minimum-distance`.

- `minimum-distance` – the smallest allowable vertical distance, measured in staff spaces, between the reference points of the two items, when compressing is in effect. Values for `minimum-distance` that are less than `padding` are not meaningful, since the resulting distance will never be less than `padding`.
- `padding` – the minimum required amount of unobstructed vertical whitespace between the bounding boxes (or skylines) of the two items, measured in staff spaces.
- `stretchability` – a unitless measure of the dimension’s relative propensity to stretch. If zero, the distance will not stretch (unless collisions would result). When positive, the significance of a particular dimension’s `stretchability` value lies only in its relation to the `stretchability` values of the other dimensions. For example, if one dimension has twice the `stretchability` of another, it will stretch twice as easily. Values should be non-negative and finite. The value `+inf.0` triggers a `programming_error` and is ignored, but `1.0e7` can be used for an almost infinitely stretchable spring. If unset, the default value is set to `basic-distance`. Note that the dimension’s propensity to *compress* cannot be directly set by the user and is equal to $(\text{basic-distance} - \text{minimum-distance})$.

If a page has a ragged bottom, the resulting distance is the largest of:

- `basic-distance`,
- `minimum-distance`, and
- `padding` plus the smallest distance necessary to eliminate collisions.

For multi-page scores with a ragged bottom on the last page, the last page uses the same spacing as the preceding page, provided there is enough space for that.

Specific methods for modifying alists are discussed in Section 35.8 [Modifying alists], page 769. The following example demonstrates the two ways these alists can be modified. The first declaration updates one key value individually, and the second completely redefines the variable:

```
\paper {
  system-system-spacing.basic-distance = 8
  score-system-spacing =
    #'((basic-distance . 12)
      (minimum-distance . 6)
      (padding . 1)
      (stretchability . 12))
}
```

26.4.2 List of flexible vertical spacing `\paper` variables

The names of these variables follow the format *upper-lower-spacing*, where *upper* and *lower* are the items to be spaced. Each distance is measured between the reference points of the two items (see the description of the alist structure above). Note that in these variable names, the term ‘markup’ refers to both *title markups* (`bookTitleMarkup` or `scoreTitleMarkup`) and *top-level markups* (see Section 20.5 [File structure], page 594). All distances are measured in staff spaces.

Default settings are defined in `ly/paper-defaults-init.ly`.

`markup-system-spacing`

the distance between a (title or top-level) markup and the system that follows it.

`score-markup-spacing`
the distance between the last system of a score and the (title or top-level) markup that follows it.

`score-system-spacing`
the distance between the last system of a score and the first system of the score that follows it, when no (title or top-level) markup exists between them.

`system-system-spacing`
the distance between two systems in the same score.

`markup-markup-spacing`
the distance between two (title or top-level) markups.

`last-bottom-spacing`
the distance from the last system or top-level markup on a page to the bottom of the printable area (i.e., the top of the bottom margin).

`top-system-spacing`
the distance from the top of the printable area (i.e., the bottom of the top margin) to the first system on a page, when there is no (title or top-level) markup between the two.

`top-markup-spacing`
the distance from the top of the printable area (i.e., the bottom of the top margin) to the first (title or top-level) markup on a page, when there is no system between the two.

See also

Notation Reference: Section 29.1 [Flexible vertical spacing within systems], page 695.

Installed Files: `ly/paper-defaults-init.ly`.

Snippets: Section “Spacing” in *Snippets*.

26.5 Horizontal spacing `\paper` variables

Note: Some `\paper` dimensions are automatically scaled to the paper size, which may lead to unexpected behavior. See Section 26.2.2 [Automatic scaling to paper size], page 671.

26.5.1 `\paper` variables for widths and margins

Default values (before scaling) that are not listed here are defined in file `ly/paper-defaults-init.ly`.

`paper-width`
The width of the page, unset by default. While `paper-width` has no effect on the automatic scaling of some horizontal dimensions, it does influence the `line-width` variable. If both `paper-width` and `line-width` are set, then `left-margin` and `right-margin` will also be updated. Also see `check-consistency`.

`line-width`
When specified in a `\paper` block this defines the horizontal extent available for the staff lines in unindented systems. If left unspecified, the paper’s `line-width` is determined from $(\text{paper-width} - \text{left-margin} - \text{right-margin})$. If the paper’s `line-width` is specified, and both `left-margin` and `right-margin` are not, then

the margins will be updated to center the systems on the page automatically. Also see `check-consistency`.

`line-widths` for individual scores can be specified in the scores' `\layout` blocks. These values control the width of the lines produced on a score-by-score basis. If `line-width` is not specified for a score, it defaults to the paper's `line-width`. Setting a score's `line-width` has no effect on the paper margins. Staff lines, of a length determined by the score's `line-width`, are left-aligned within the paper area defined by the paper's `line-width`. If the score and paper `line-widths` are equal, the staff lines will extend exactly from the left margin to the right margin, but if the score's `line-width` is greater than the paper's `line-width` the staff lines will run over into the right margin.

`left-margin`

The margin between the left edge of the page and the start of the staff lines in unindented systems. If the paper size is modified, this dimension's default value is scaled accordingly. If `left-margin` is unset, and both `line-width` and `right-margin` are set, then `left-margin` is set to $(\text{paper-width} - \text{line-width} - \text{right-margin})$. If only `line-width` is set, then both margins are set to $((\text{paper-width} - \text{line-width}) / 2)$, and the systems are consequently centered on the page. Also see `check-consistency`.

`right-margin`

The margin between the right edge of the page and the end of the staff lines in non-ragged systems. If the paper size is modified, this dimension's default value is scaled accordingly. If `right-margin` is unset, and both `line-width` and `left-margin` are set, then `right-margin` is set to $(\text{paper-width} - \text{line-width} - \text{left-margin})$. If only `line-width` is set, then both margins are set to $((\text{paper-width} - \text{line-width}) / 2)$, and the systems are consequently centered on the page. Also see `check-consistency`.

`check-consistency`

If this is true (the default value), print a warning if `left-margin`, `line-width`, and `right-margin` do not exactly add up to `paper-width`, and replace each of these (except `paper-width`) with their default values (scaled to the paper size if necessary). If set to `#f`, ignore any inconsistencies and allow systems to run off the edge of the page.

`ragged-right`

If set to `#t`, systems will not fill the line width. Instead, systems end at their natural horizontal length. Default: `#t` for scores with only one system, and `#f` for scores with two or more systems. This variable can also be set in a `\layout` block.

`ragged-last`

If set to `#t`, the last system in the score will not fill the line width. Instead the last system ends at its natural horizontal length. Default: `#f`. This variable can also be set in a `\layout` block.

See also

Notation Reference: Section 26.2.2 [Automatic scaling to paper size], page 671.

Installed Files: `ly/paper-defaults-init.ly`.

Known issues and warnings

Explicitly defined paper sizes will override any user-defined left or right margin settings.

26.5.2 `\paper` variables for two-sided mode

Default values (before scaling) are defined in `ly/paper-defaults-init.ly`.

`two-sided`

If set to `#t`, use `inner-margin`, `outer-margin` and `binding-offset` to determine margins depending on whether the page number is odd or even. This overrides `left-margin` and `right-margin`.

`inner-margin`

The margin all pages have at the inner side if they are part of a book. If the paper size is modified, this dimension's default value is scaled accordingly. Works only with `two-sided` set to `#t`.

`outer-margin`

The margin all pages have at the outer side if they are part of a book. If the paper size is modified, this dimension's default value is scaled accordingly. Works only with `two-sided` set to `#t`.

`binding-offset`

The amount `inner-margin` is increased to make sure nothing will be hidden by the binding. If the paper size is modified, this dimension's default value is scaled accordingly. Works only with `two-sided` set to `#t`.

See also

Notation Reference: Section 26.2.2 [Automatic scaling to paper size], page 671.

Installed Files: `ly/paper-defaults-init.ly`.

26.5.3 `\paper` variables for shifts and indents

Default values (before scaling) that are not listed here are defined in `ly/paper-defaults-init.ly`.

`horizontal-shift`

The amount that all systems (including titles and system separators) are shifted to the right. Default: `0.0\mm`.

`indent`

The level of indentation for the first system in a score. If the paper size is modified, this dimension's default value is scaled accordingly. The space within `line-width` available for the first system is reduced by this amount. `indent` may also be specified in `\layout` blocks to set indents on a score-by-score basis.

`short-indent`

The level of indentation for all systems in a score besides the first system. If the paper size is modified, this dimension's default value is scaled accordingly. The space within `line-width` available for systems other than the first is reduced by this amount. `short-indent` may also be specified in `\layout` blocks to set short indents on a score-by-score basis.

See also

Notation Reference: Section 26.2.2 [Automatic scaling to paper size], page 671.

Installed Files: `ly/paper-defaults-init.ly`.

Snippets: Section “Spacing” in *Snippets*.

26.6 Other `\paper` variables

26.6.1 `\paper` variables for line breaking

`max-systems-per-page`

The maximum number of systems that will be placed on a page. This is currently supported only by the `ly:optimal-breaking` algorithm. Default: unset.

`min-systems-per-page`

The minimum number of systems that will be placed on a page. This may cause pages to be overfilled if it is made too large. This is currently supported only by the `ly:optimal-breaking` algorithm. Default: unset.

`systems-per-page`

The number of systems that should be placed on each page. This is currently supported only by the `ly:optimal-breaking` algorithm. Default: unset.

`system-count`

The number of systems to be used for a score. Default: unset. This variable can also be set in a `\layout` block.

See also

Notation Reference: Section 28.1 [Line breaking], page 687.

26.6.2 `\paper` variables for page breaking

Default values not listed here are defined in `ly/paper-defaults-init.ly`

`page-breaking`

The page breaking algorithm to use. Choices are `ly:minimal-breaking`, `ly:page-turn-breaking`, `ly:one-page-breaking`, `ly:one-line-breaking`, `ly:one-line-auto-height-breaking`, and `ly:optimal-breaking`. Default: `ly:optimal-breaking`.

`page-breaking-system-system-spacing`

Tricks the page breaker into thinking that `system-system-spacing` is set to something different than it really is. For example, if `page-breaking-system-system-spacing.padding` is set to something substantially larger than `system-system-spacing.padding`, then the page breaker will put fewer systems on each page. Default: unset.

`page-count`

The number of pages to be used for a score. Default: unset.

`page-spacing-weight`

When using the `ly:optimal-breaking` algorithm for page breaking, LilyPond has to make trade-offs between horizontal and vertical stretching so that the overall spacing is more acceptable. This parameter controls the relative importance of page (vertical) spacing and line (horizontal) spacing. High values will make page spacing more important. Default: 10.

The following variables are effective only when `page-breaking` is set to `ly:page-turn-breaking`. Page breaks are then chosen to minimize the number of page turns. Since page turns are required on moving from an odd-numbered page to an even-numbered one, a layout in which the last page is odd-numbered will usually be favored. Places where page turns are preferred can be indicated manually by inserting `\allowPageTurn` or automatically by including the `Page_turn_engraver` (see Section 28.2.7 [Optimal page turning], page 693).

If there are insufficient choices available for making suitable page turns, LilyPond may insert a blank page either within a score, between scores (if there are two or more scores), or by ending a score on an even-numbered page. The values of the following three variables may be increased to make these actions less likely.

The values are penalties, i.e., the higher the value the less likely will be the associated action relative to other choices.

`blank-page-penalty`

The penalty for having a blank page in the middle of a score. If `blank-page-penalty` is large and `ly:page-turn-breaking` is selected, then LilyPond will be less likely to insert a page in the middle of a score. Instead, it will space out the music further to fill the blank page and the following one. Default: 5.

`blank-last-page-penalty`

The penalty for ending the score on an even-numbered page. If `blank-last-page-penalty` is large and `ly:page-turn-breaking` is selected, then LilyPond will be less likely to produce a score in which the last page is even-numbered. Instead, it will adjust the spacing in order to use one page more or one page less. Default: 0.

`blank-after-score-penalty`

The penalty for having a blank page after the end of one score and before the next. By default, this is smaller than `blank-page-penalty`, so that blank pages after scores are inserted in preference to blank pages within a score. Default: 2.

See also

Notation Reference: Section 28.2 [Page breaking], page 691, Section 28.2.2 [Optimal page breaking], page 692, Section 28.2.7 [Optimal page turning], page 693, Section 28.2.3 [Minimal page breaking], page 692, Section 28.2.4 [One-page page breaking], page 692, Section 28.2.5 [One-line page breaking], page 693, Section 28.2.6 [One-line-auto-height page breaking], page 693.

Installed Files: `ly/paper-defaults-init.ly`.

26.6.3 \paper variables for page numbering

Default values not listed here are defined in `ly/paper-defaults-init.ly`

`auto-first-page-number`

The page breaking algorithm is affected by the first page number being odd or even. If set to `#t`, the page breaking algorithm will decide whether to start with an odd or even number. This will result in the first page number remaining as is or being increased by one. Default: `#f`.

`first-page-number`

The value of the page number on the first page.

`print-first-page-number`

If set to `#t`, a page number is printed on the first page.

`print-page-number`

If set to `#f`, page numbers are not printed.

`page-number-type`

The type of numerals used for page numbers. Choices include `'arabic`, `'roman-ij-lower`, `'roman-ij-upper`, `'roman-lower`, and `'roman-upper`. Default: `'arabic`.

bookpart-level-page-numbering

If set to `#t`, each book part has its independent sequence of page numbers, starting at `first-page-number` (1 by default).

This may also be used for one book part only. The typical use case is numbering pages of the first book part independently and in roman numerals, as may be wished for an analytical introduction to the work being published.

```
\book {
  \bookpart {
    \paper {
      bookpart-level-page-numbering = ##t
      page-number-type = #'roman-lower
    }
    \markuplist \wordwrap-lines {
      Lorem ipsum dolor sit amet.
    }
  }
  \bookpart {
    ...
  }
}
```

See also

Installed Files: `ly/paper-defaults-init.ly`.

Known issues and warnings

Odd page numbers are always on the right. If you want the music to start on page 1 there must be a blank page on the back of the cover page so that page 1 is on the right-hand side.

26.6.4 \paper variables concerning headers and markups**print-all-headers**

If set to `#t`, this will print all headers for each `\score` in the output. Normally only the piece and opus header variables are printed. For use cases see Chapter 21 [Titles and headers], page 597. Default: `#f`.

reset-footnotes-on-new-page

If set to `#t`, footnote numbers are reset on each page break. For footnotes numbered consecutively across page breaks, set to `#f`. Default: `#t`.

system-separator-markup

A markup object that is inserted between systems, often used for orchestral scores. Default: unset. The `\slashSeparator` markup, defined in `ly/titling-init.ly`, is provided as a sensible default, for example:


```
##(set-default-paper-size "a8")

\book {
  \paper {
    system-separator-markup = \slashSeparator
  }
  \header {
    tagline = ##f
  }
  \score {
```

```

    \relative { c''1 \break c1 \break c1 }
  }
}

```



footnote-separator-markup

A markup object that is inserted above the footnote texts at the bottom of the page.
Default: a centered horizontal line, defined in `ly/paper-defaults-init.ly`.

See also

Installed Files: `ly/titling-init.ly`, `ly/paper-defaults-init.ly`.

Snippets: Section “Spacing” in *Snippets*.

Known issues and warnings

The default page header puts the page number and the instrument field from the `\header` block on a line.

26.6.5 \paper variables for debugging

The variables `debug-beam-scoring`, `debug-slur-scoring` and `debug-tie-scoring` allow to print debugging output for beam, slur and tie scoring. See Section “Debugging scoring algorithms” in *Contributor’s Guide* for a detailed explanation, what these variables do.

27 Score layout

This section discusses score layout options for the `\layout` block.

27.1 The `\layout` block

While the `\paper` block contains settings that relate to the page formatting of the whole document, the `\layout` block contains settings for score-specific layout. To set score layout options globally, enter them in a top-level `\layout` block. To set layout options for an individual score, enter them in a `\layout` block inside the `\score` block, after the music. Settings that can appear in a `\layout` block include:

- the `layout-set-staff-size` Scheme function,
- context modifications in `\context` blocks, and
- `\paper` variables that affect score layout.

The `layout-set-staff-size` function is discussed in the next section, Section 27.2 [Setting the staff size], page 683. Context modifications are discussed in a separate chapter; see Section 33.4 [Modifying context plug-ins], page 743, and Section 33.5 [Changing context default settings], page 744.

The `\paper` variables that can appear in a `\layout` block are as follows.

- `line-width`, `ragged-right` and `ragged-last` (see Section 26.5.1 [`\paper` variables for widths and margins], page 674)
- `indent` and `short-indent` (see Section 26.5.3 [`\paper` variables for shifts and indents], page 676)
- `system-count` (see Section 26.6.1 [`\paper` variables for line breaking], page 677)

The default values of the above variables are taken from the `\paper` block.

Here is an example `\layout` block:

```
\layout {
  indent = 2\cm
  \context {
    \StaffGroup
    \override StaffGroup.staff-staff-spacing.basic-distance = 8
  }
  \context {
    \Voice
    \override TextScript.padding = 1
    \override Glissando.thickness = 3
  }
}
```

Multiple `\layout` blocks can be entered as top-level expressions. This can, for example, be useful if different settings are stored in separate files and included optionally. Internally, when a `\layout` block is evaluated, a copy of the current `\layout` configuration is made, then any changes defined within the block are applied and the result is saved as the new current configuration. From the user's perspective the `\layout` blocks are combined, but in conflicting situations (when the same property is changed in different blocks) the later definitions take precedence.

For example, if this block

```
\layout {
  \context {
    \Voice
```



```

        \override TextScript.color = #magenta
        \override Glissando.thickness = 1.5
    }
}

```

is placed after the one from the preceding example the padding and color overrides for TextScript are combined, but the later thickness override for Glissando replaces (or hides) the earlier one.

`\layout` blocks may be assigned to variables for reuse later, but the way this works is slightly but significantly different from writing them literally.

If a variable is defined like this

```

layoutVariable = \layout {
  \context {
    \Voice
    \override NoteHead.font-size = 4
  }
}

```

it holds the current `\layout` configuration with the `NoteHead.font-size` override added, but this combination is *not* saved as the new current configuration. Be aware that the ‘current configuration’ is read when the variable is defined and not when it is used, so the content of the variable is dependent on its position in the source.

The variable can then be used inside another `\layout` block, for example:

```

\layout {
  \layoutVariable
  \context {
    \Voice
    \override NoteHead.color = #red
  }
}

```

A `\layout` block containing a variable, as in the example above, does *not* copy the current configuration but instead uses the content of `\layoutVariable` as the base configuration for further additions. This means that any changes defined between the definition and the use of the variable are lost.

If `layoutVariable` is defined (or `\included`) immediately before being used, its content is just the current configuration plus the overrides defined within it. So in the example above showing the use of `\layoutVariable` the final `\layout` block would consist of

```

TextScript.padding = 1
TextScript.color = #magenta
Glissando.thickness = 1.5
NoteHead.font-size = 4
NoteHead.color = #red

```

plus the indent and the `StaffGrouper` overrides.

However, if the variable had already been defined before the first `\layout` block the current configuration would now contain only the following.

```

NoteHead.font-size = 4 % written in the variable definition
NoteHead.color = #red  % added after the use of the variable

```

If carefully planned, `\layout` variables can be a valuable tool to structure the layout design of sources, and also to reset the `\layout` configuration to a known state.

See also

Notation Reference: Section 33.5 [Changing context default settings], page 744.

Snippets: Section “Spacing” in *Snippets*.

27.2 Setting the staff size

The default *staff size* is 20 points, which corresponds to a staff height of 7.03 mm (one point is equal to 100/7227 of an inch, or 2540/7227 mm). The staff size may be changed in three ways:

1. To set the staff size globally for all scores in a file, use `set-global-staff-size`.

```
 #(set-global-staff-size 14)
```

The above example sets the global default staff size to 14 pt (4.92 mm) and scales all fonts accordingly.

The function can also be used to set various staff sizes for different `\book` blocks:

```
 #(set-global-staff-size 30)
 \book {
   { c' }
 }
```

```
 #(set-global-staff-size 10)
 \book {
   { c' }
 }
```

2. To set the staff size for a single score within a book, use `layout-set-staff-size` inside that score’s `\layout` block:

```
 \score {
   ...
   \layout {
     #(layout-set-staff-size 14)
   }
 }
```

3. To set the staff size for a single staff within a system, use the `\magnifyStaff` command. For example, traditionally engraved chamber music scores with piano often used 7 mm piano staves while the other staves were typically between 3/5 and 5/7 as large (between 60% and 71%). To achieve the 5/7 proportion, use:

```
 \score {
   <<
     \new Staff \with {
       \magnifyStaff #5/7
     } { ... }
     \new PianoStaff { ... }
   >>
 }
```

If you happen to know which `fontSize` you wish to use, you could use the following form:

```
 \score {
   <<
     \new Staff \with {
       \magnifyStaff #(magstep -3)
     } { ... }
     \new PianoStaff { ... }
   >>
 }
```

```
>>
}
```

To emulate the look of traditional engraving, it is best to avoid reducing the thickness of the staff lines.

Automatic font weight at different sizes

The Emmentaler font provides the set of *Feta* musical glyphs in eight different sizes; each one tuned for a different staff size. The smaller the glyph size, the “heavier” it becomes, so as to match the relatively thicker staff lines. Recommended glyphs sizes are listed in the following table:

font name	staff height (pt)	staff height (mm)	use
feta11	11.22	3.9	pocket scores
feta13	12.60	4.4	
feta14	14.14	5.0	
feta16	15.87	5.6	
feta18	17.82	6.3	song books
feta20	20	7.0	standard parts
feta23	22.45	7.9	
feta26	25.2	8.9	

See also

Notation Reference: Section 7.1.1 [Selecting notation font size], page 277, Section B.8 [The Emmentaler font], page 905.

Snippets: Section “Spacing” in *Snippets*.

Known issues and warnings

When using `\magnifyStaff` only for some staves in a `StaffGroup`, `BarLine` grobs do not align any more, due to the changed `BarLine` properties `thick-thickness`, `hair-thickness` and `kern`.

```
\new StaffGroup
<<
  \new Staff \with { \magnifyStaff #1/2 } { b1 \bar "|." }
  \new Staff { b }
>>
```



You may want to cancel magnifying `BarLine` grobs, mimic them on the other staves or apply intermediate values for every `Staff`.

```
#(define bar-line-props
'((BarLine thick-thickness)
  (BarLine hair-thickness)
  (BarLine kern)))

mus = { b1 \bar "|."}

\markup "Cancel \\magnifyStaff for bar lines:"
```

```

\new StaffGroup
<<
  \new Staff
  \with {
    \magnifyStaff #1/2
    #(revert-props 'magnifyStaff 0 bar-line-props)
  }
  \mus
  \new Staff
  \mus
>>

\markup "Mimic \\magnifyStaff on other staves:"
\new StaffGroup
<<
  \new Staff
  \with { \magnifyStaff #1/2 }
  \mus
  \new Staff
  \with {
    #(scale-props 'magnifyStaff 1/2 #t bar-line-props)
  }
  \mus
>>

\markup "Apply an intermediate value to all staves:"
\new StaffGroup
<<
  \new Staff
  \with {
    \magnifyStaff #1/2
    #(scale-props 'magnifyStaff 3/2 #t bar-line-props)
  }
  \mus
  \new Staff
  \with {
    #(scale-props 'magnifyStaff 3/4 #t bar-line-props)
  }
  \mus
>>

```

Cancel `\magnifyStaff` for bar lines:



Mimic `\magnifyStaff` on other staves:



Apply an intermediate value to all staves:



28 Breaks

28.1 Line breaking

Line breaks are normally determined automatically. They are chosen so that lines look neither cramped nor loose, and consecutive lines have similar density.

To manually force a line break at a bar line, use the `\break` command:

```
\relative c' {
  c4 c c c | \break
  c4 c c c |
}
```




By default, breaks are only allowed at bar lines. There are also a few other factors that can prevent a break from being allowed at a certain bar line:

- a note head or rest continuing over the bar line,
- the presence of an ‘unbreakable’ spanner, such as a beam or a glissando, crossing the bar line.

The `\break` command forces a break in all cases, regardless of the presence of a bar line or any other factor. It is also possible to bypass all these factors using the `\allowBreak` command. In the following example, breaks are allowed everywhere, even in the middle of a measure, and despite the presence of beams.

```
\*56 { c'8 \allowBreak }
```

```
\paper {
  indent = 0
  line-width = 135\mm
}
```



If you find yourself using `\allowBreak` often, you may want to prevent some of the factors mentioned above from disabling breaks.

- `Bar_engraver` forbids breaks between bar lines when `forbidBreakBetweenBarLines` is set to `#t`. To inhibit this, set the property to `#f`.

```

\fixed c' {
  c8 d e f g a b c'
}

\layout {
  \context {
    \Score
    forbidBreakBetweenBarLines = ##f
  }
}

\paper {
  indent = 0
  line-width = 30\mm
}

```



- Note heads and rests extending over bar lines can be made not to suppress breaks by removing the `Forbid_line_break_engraver` from the Voice context.

```

\new Voice \with {
  \remove Forbid_line_break_engraver
} \relative {
  c''2. \tuplet 3/2 { c4 c c } c2.
}

\paper {
  indent = 0
  line-width = 35\mm
}

```



- The presence of beams and other unbreakable spanners over bar lines is ignored if their breakable property is set to `#t`.

```

\relative c'' {
  \override Beam.breakable = ##t
  c2. c8[ c |
  c8 c] c2. |
}

\paper {
  indent = 0
  line-width = 35\mm
}

```



The `\noBreak` command will prevent a line break at the bar line where it is inserted.

Within a score, automatic line breaking is prevented within music lying between `\autoLineBreaksOff` and `\autoLineBreaksOn` commands. If automatic page breaks should also be prevented, the commands `\autoBreaksOff` and `\autoBreaksOn` should be used. Manual breaks are unaffected by these commands. Note that inhibiting automatic line breaks may cause music to run over the right margin if it cannot all be contained within one line.

Automatic line breaks (but not page breaks) may be enabled at single bar lines by using `\once \autoLineBreaksOn` at a bar line. This identifies a permitted rather than a forced line break.

The most basic settings influencing line spacing are `indent` and `line-width`. They are set in the `\layout` block. They control the indentation of the first line of music, and the lengths of the lines.

If `ragged-right` is set to `#t` in the `\layout` block, then systems end at their natural horizontal length, instead of being spread horizontally to fill the whole line. This is useful for short fragments, and for checking how tight the natural spacing is.

The option `ragged-last` is similar to `ragged-right`, but affects only the last line of the piece.

```

\layout {
  indent = 0\mm
  line-width = 150\mm
  ragged-last = ##t
}

```

For line breaks at regular intervals use `\break` separated by skips and repeated with `\repeat`. For example, this would cause the following 28 measures (assuming 4/4 time) to be broken every 4 measures, and only there:

```

<<
  \repeat unfold 7 {
    s1 \noBreak s1 \noBreak
    s1 \noBreak s1 \break
  }
  { the actual music... }
>>

```


Predefined commands

`\break`, `\allowBreak`, `\noBreak`, `\autoBreaksOff`, `\autoBreaksOn`, `\autoLineBreaksOff`, `\autoLineBreaksOn`.

Selected snippets

Using an extra voice for breaks


Often it is easier to manage line and page-breaking information by keeping it separate from the music by introducing an extra voice containing only skips along with the `\break`, `\pageBreak`, and other layout information.

This pattern becomes especially helpful when overriding `line-break-system-details` and the other useful but long properties of the `NonMusicalPaperColumn` grob.

```
music = \relative c'' { c4 c c c }
```

```
\score {
  \new Staff <<
    \new Voice {
      s1*2 \break
      s1*3 \break
      s1*4 \break
      s1*5 \break
    }
    \new Voice {
      \*2 \music
      \*3 \music
      \*4 \music
      \*5 \music
    }
  >>
}
```

```
\paper {
  indent = 0
  line-width = 140\mm
  ragged-right = ##t
}
```



See also

Notation Reference: Section 26.6.1 [`\paper` variables for line breaking], page 677, Section 27.1 [The `\layout` block], page 681.

Snippets: Section “Spacing” in *Snippets*.

Internals Reference: Section “LineBreakEvent” in *Internals Reference*.

Known issues and warnings

Placing `\autoLineBreaksOff` or `\autoBreaksOff` before any music will cause error messages to appear. Always place these commands after some music.

28.2 Page breaking

This section describes the different page breaking methods, and how to modify them.

28.2.1 Manual page breaking

The default page breaking may be overridden by inserting `\pageBreak` or `\noPageBreak` commands. These commands are analogous to `\break` and `\noBreak`. They should be inserted at a bar line. These commands force and forbid a page break from happening at that bar line. Of course, the `\pageBreak` command also forces a line break.

The `\pageBreak` and `\noPageBreak` commands may also be inserted at top-level, between scores and top-level markups.

Within a score, automatic page breaks are prevented within music lying between `\autoPageBreaksOff` and `\autoPageBreaksOn` commands. Manual page breaks are unaffected by these commands.

There are also analogous settings to `ragged-right` and `ragged-last` which have the same effect on vertical spacing. If `ragged-bottom` is set to `#t` the systems will not be justified vertically. When `ragged-last-bottom` is set to `#t`, as it is by default, empty space is allowed at the bottom of the final page (or the final page in each `\bookpart`). See Section 26.3 [Fixed vertical spacing `\paper` variables], page 671.

Page breaks are computed by the page-breaking function. LilyPond provides several algorithms for computing page breaks, including `ly:optimal-breaking`, `ly:page-turn-breaking` and `ly:minimal-breaking`. The default is `ly:optimal-breaking`, but the value can be changed in the `\paper` block:

```
\paper {
  page-breaking = #ly:page-turn-breaking
}
```

When a book has many scores and pages, the page breaking problem may be difficult to solve, requiring large processing time and memory. To ease the page breaking process, `\bookpart` blocks are used to divide the book into several parts: the page breaking occurs separately on each part. Different page breaking functions may also be used in different book parts.

```
\bookpart {
  \header {
    subtitle = "Preface"
  }
  \paper {
    %% In a part consisting mostly of text,
    %% ly:minimal-breaking may be preferred
    page-breaking = #ly:minimal-breaking
  }
  \markup { ... }
```

```

    ...
}
\bookpart {
  %% In this part, consisting of music, the default optimal
  %% page breaking function is used.
  \header {
    subtitle = "First movement"
  }
  \score { ... }
  ...
}

```

Predefined commands

`\pageBreak`, `\noPageBreak`, `\autoPageBreaksOn`, `\autoPageBreaksOff`.

See also

Notation Reference: Section 26.6.2 [`\paper` variables for page breaking], page 677.

Snippets: Section “Spacing” in *Snippets*.

Known issues and warnings

The `\once` prefix is ineffective with `\autoPageBreaksOn` and `\autoPageBreaksOff`. If automatic page breaking is off and is then turned on to permit a page break, it must remain on for a few bars (the precise number of bars depends on the score) before being turned off, else the opportunity to break the page will not be taken.

28.2.2 Optimal page breaking

The `ly:optimal-breaking` function is LilyPond’s default method of determining page breaks. It attempts to find a page breaking that minimizes cramping and stretching, both horizontally and vertically. Unlike `ly:page-turn-breaking`, it has no concept of page turns.

See also

Snippets: Section “Spacing” in *Snippets*.

28.2.3 Minimal page breaking

The `ly:minimal-breaking` function performs minimal computations to calculate the page breaking: it fills a page with as many systems as possible before moving to the next one. Thus, it may be preferred for scores with many pages, where the other page breaking functions could be too slow or memory demanding, or a lot of texts. It is enabled using:

```

\paper {
  page-breaking = #ly:minimal-breaking
}

```

See also

Snippets: Section “Spacing” in *Snippets*.

28.2.4 One-page page breaking

The `ly:one-page-breaking` function is a special-purpose page breaking algorithm that automatically adjusts the page height to fit the music, so that everything fits on a single page. The `paper-height` variable in the `paper` block is ignored, but other settings work as usual. In particular, the spacing between the last system (or top level markup) and the footer can be customized

with `last-bottom-spacing` in the `paper` block. The width of the page is left unmodified by default but can be set with `paper-width` in the `paper` block.

Known issues and warnings

`ly:one-page-breaking` is not currently compatible with `\bookpart`.

28.2.5 One-line page breaking

The `ly:one-line-breaking` function is a special-purpose page breaking algorithm that puts each score on its own page, and on a single line. No titles or margins are typeset; only the score is displayed.

The page width is adjusted so that the longest score fits on one line. In particular, `paper-width`, `line-width` and `indent` variables in the `\paper` block are ignored, although `left-margin` and `right-margin` are still honored. The height of the page is left unmodified.

28.2.6 One-line-auto-height page breaking

The `ly:one-line-auto-height-breaking` function works just like `ly:one-line-breaking` except the page height is automatically modified to fit the height of the music. Specifically, the `paper-height` variable in the `\paper` block is set so that it spans the height of the tallest score plus the top-margin and bottom-margin.

Note that the `top-system-spacing` setting will affect the vertical position of the music. Set it to `#f` in a `paper` block to simply place the music between the top and bottom margins.

28.2.7 Optimal page turning

Often it is necessary to find a page breaking configuration so that there is a rest at the end of every second page. This way, the musician can turn the page without having to miss notes. The `ly:page-turn-breaking` function attempts to find a page breaking minimizing cramping and stretching, but with the additional restriction that it is only allowed to introduce page turns in specified places.

There are two steps to using this page breaking function. First, you must enable it in the `\paper` block, as explained in Section 28.2 [Page breaking], page 691. Then you must tell the function where you would like to allow page breaks.

There are two ways to achieve the second step. First, you can specify each potential page turn manually, by inserting `\allowPageTurn` into your input file at the appropriate places.

If this is too tedious, you can add a `Page_turn_engraver` to a `Staff` or `Voice` context. The `Page_turn_engraver` will scan the context for sections without notes (note that it does not scan for rests; it scans for the absence of notes. This is so that single-staff polyphony with rests in one of the parts does not throw off the `Page_turn_engraver`). When it finds a sufficiently long section without notes, the `Page_turn_engraver` will insert an `\allowPageTurn` at the final bar line in that section, unless there is a ‘special’ bar line (such as a double bar), in which case the `\allowPageTurn` will be inserted at the final ‘special’ bar line in the section.

The `Page_turn_engraver` reads the context property `pageTurnMinimumRestLength` to determine how long a note-free section must be before a page turn is considered. The default value for `pageTurnMinimumRestLength` is 1. If you want to disable page turns, set it to something ‘very large’.

```
\new Staff \with { \consists Page_turn_engraver }
{
  a4 b c d |
  R1 | % a page turn will be allowed here
  a4 b c d |
  \set Staff.pageTurnMinimumRestLength = #5/2
```

```

R1 | % a page turn will not be allowed here
a4 b r2 |
R1*2 | % a page turn will be allowed here
a1
}

```

When using volta repeats, the `Page_turn_engraver` will only allow a page turn during the repeat if there is enough time at the beginning and end of the repeat to turn the page back. If the repeat is too short then the `Page_turn_engraver` can be used to *disable* page turns by setting an appropriate value for the context property `pageTurnMinimumRepeatLength`. In this case the `Page_turn_engraver` will only allow turns in repeats whose duration is longer than the value specified.

The page turning commands, `\pageTurn`, `\noPageTurn` and `\allowPageTurn`, may also be used at top-level, in top-level markups and between scores.

Predefined commands

`\pageTurn`, `\noPageTurn`, `\allowPageTurn`.

See also

Notation Reference: Section 26.6.1 [`\paper` variables for line breaking], page 677.

Snippets: Section “Spacing” in *Snippets*.

Known issues and warnings

Use only one `Page_turn_engraver` per score. If there are more, they will interfere with each other.

See also

Notation Reference: Chapter 29 [Vertical spacing], page 695.

Snippets: Section “Spacing” in *Snippets*.

29 Vertical spacing

Vertical spacing is controlled by three things: the amount of space available (i.e., paper size and margins), the amount of space between systems, and the amount of space between staves inside a system.

29.1 Flexible vertical spacing within systems

Three separate mechanisms control the flexible vertical spacing within systems, one for each of the following categories:

- *ungrouped staves*,
- *grouped staves* (staves within a staff group such as `ChoirStaff`, etc.), and
- *non-staff lines* (such as `Lyrics`, `ChordNames`, etc.).

The height of each system is determined in two steps. First, all of the staves are spaced according to the amount of space available. Then, the non-staff lines are distributed between the staves.

Note that the spacing mechanisms discussed in this section only control the vertical spacing of staves and non-staff lines within individual systems. The vertical spacing between separate systems, scores, markups, and margins is controlled by `\paper` variables, which are discussed in Section 26.4 [Flexible vertical spacing `\paper` variables], page 672.

29.1.1 Within-system spacing properties

The within-system vertical spacing mechanisms are controlled by two sets of grob properties. The first set is associated with the `VerticalAxisGroup` grob, which is created by all staves and non-staff lines. The second set is associated with the `StaffGrouper` grob, which can be created by staff groups, but only if explicitly called. These properties are described individually at the end of this section.

The names of these properties (except for `staff-affinity`) follow the format *item1-item2-spacing*, where *item1* and *item2* are the items to be spaced. Note that *item2* is not necessarily below *item1*; for example, `nonstaff-relatedstaff-spacing` will measure upwards from the non-staff line if `staff-affinity` is UP.


Each distance is measured between the *reference points*¹ of the two items. The reference point for a staff is the vertical center of its `StaffSymbol` (i.e., the middle line if `line-count` is odd; the middle space if `line-count` is even). The reference points for individual non-staff lines are given in the following table:

Non-staff line	Reference point
<code>ChordNames</code>	baseline
<code>NoteNames</code>	baseline
<code>Lyrics</code>	baseline
<code>Dynamics</code>	mid-height of ‘m’
<code>FiguredBass</code>	baseline of topmost element
<code>FretBoards</code>	top line

In the following image, horizontal lines indicate the positions of these reference points:

	<code>ChordNames</code>	<code>NoteNames</code>	<code>Lyrics</code>
baseline	—g—	—g—	—ghjk—

¹ This is a sloppy formulation. For contexts, the positions of grobs along the x-axis are computed by LilyPond’s spacing algorithm (using `PaperColumn` objects and the like for alignment); this means that the only relevant information here is the vertical position. In other words, a reference ‘point’ of a context is the y-coordinate position to which other grobs are aligned to.



Each of the vertical spacing grob properties (except `staff-affinity`) uses the same alist structure as the `\paper` spacing variables discussed in Section 26.4 [Flexible vertical spacing `\paper` variables], page 672. Specific methods for modifying alists are discussed in Section 35.8 [Modifying alists], page 769. Grob properties should be adjusted with an `\override` inside a `\score` or `\layout` block, and not inside a `\paper` block.

The following example demonstrates the two ways these alists can be modified. The first declaration updates one key value individually, and the second completely redefines the property:

```
\new Staff \with {
  \override VerticalAxisGroup
    .default-staff-staff-spacing.basic-distance = 10
} { ... }

\new Staff \with {
  \override VerticalAxisGroup.default-staff-staff-spacing =
    #'((basic-distance . 10)
      (minimum-distance . 9)
      (padding . 1)
      (stretchability . 10))
} { ... }
```

To change any spacing settings globally, put them in the `\layout` block:

```
\layout {
  \context {
    \Staff
    \override VerticalAxisGroup
      .default-staff-staff-spacing
      .basic-distance = 10
  }
}
```

Standard settings for the vertical spacing grob properties are listed in Section “Vertical-AxisGroup” in *Internals Reference* and Section “StaffGrouper” in *Internals Reference*. Default overrides for specific types of non-staff lines are listed in the relevant context descriptions in Section “Contexts” in *Internals Reference*.

Properties of the VerticalAxisGroup grob

`VerticalAxisGroup` properties are typically adjusted with an `\override` at the `Staff` level (or equivalent).

`staff-staff-spacing`

Used to determine the distance between the current staff and the staff just below it in the same system, even if one or more non-staff lines (such as Lyrics) are placed between the two staves. Does not apply to the bottom staff of a system.

Initially, the `staff-staff-spacing` of a `VerticalAxisGroup` is a Scheme function that applies the properties of the `StaffGrouper` if the staff is part of a group, or the `default-staff-staff-spacing` of the staff otherwise. This allows staves to be spaced differently when they are grouped. For uniform spacing regardless of grouping, this function may be replaced by a flexible-spacing alist, using the complete-redefinition form of override shown above. If only some values are specified in an override, missing values will be taken from `default-staff-staff-spacing` (if it has values for them).

`default-staff-staff-spacing`

A flexible-spacing alist defining the `staff-staff-spacing` used for ungrouped staves, unless `staff-staff-spacing` has been explicitly set with an `\override`.

`staff-affinity`

The direction of the staff to use for spacing the current non-staff line. Choices are UP, DOWN, and CENTER. If CENTER, the non-staff line will be placed equidistant between the two nearest staves on either side, unless collisions or other spacing constraints prevent this. Adjacent non-staff lines should have non-increasing staff-affinity from top to bottom, e.g., a non-staff line set to UP should not immediately follow one that is set to DOWN. Non-staff lines at the top of a system should use DOWN; those at the bottom should use UP. Setting `staff-affinity` for a staff causes it to be treated as a non-staff line. Setting `staff-affinity` to `#f` causes a non-staff line to be treated as a staff. Setting `staff-affinity` to UP, CENTER, or DOWN causes a staff to be spaced as a non-staff line.

`nonstaff-relatedstaff-spacing`

The distance between the current non-staff line and the nearest staff in the direction of `staff-affinity`, if there are no non-staff lines between the two, and `staff-affinity` is either UP or DOWN. If `staff-affinity` is CENTER, then `nonstaff-relatedstaff-spacing` is used for the nearest staves on *both* sides, even if other non-staff lines appear between the current one and either of the staves. This means that the placement of a non-staff line depends on both the surrounding staves and the surrounding non-staff lines. Setting the stretchability of one of these types of spacing to a small value will make that spacing dominate. Setting the stretchability to a large value will make that spacing have little effect.

`nonstaff-nonstaff-spacing`

The distance between the current non-staff line and the next non-staff line in the direction of `staff-affinity`, if both are on the same side of the related staff, and `staff-affinity` is either UP or DOWN.

`nonstaff-unrelatedstaff-spacing`

The distance between the current non-staff line and the staff in the opposite direction from `staff-affinity`, if there are no other non-staff lines between the two, and `staff-affinity` is either UP or DOWN. This can be used, for example, to require a minimum amount of padding between a Lyrics line and the staff to which it does not belong.

Properties of the `StaffGrouper` grob

`StaffGrouper` properties are typically adjusted with an `\override` at the `StaffGroup` level (or equivalent).

`staff-staff-spacing`

The distance between consecutive staves within the current staff group. The `staff-staff-spacing` property of an individual staff's `VerticalAxisGroup` grob can be overridden with different spacing settings for that staff.

staffgroup-staff-spacing

The distance between the last staff of the current staff group and the staff just below it in the same system, even if one or more non-staff lines (such as Lyrics) exist between the two staves. Does not apply to the bottom staff of a system. The staff-staff-spacing property of an individual staff's VerticalAxisGroup grob can be overridden with different spacing settings for that staff.

See also

Notation Reference: Section 26.4 [Flexible vertical spacing \paper variables], page 672, Section 35.8 [Modifying alists], page 769.

Installed Files: ly/engraver-init.ly, scm/define-grobs.scm.

Internals Reference: Section “Contexts” in *Internals Reference*, Section “VerticalAxisGroup” in *Internals Reference*, Section “StaffGrouper” in *Internals Reference*.

29.1.2 Spacing of ungrouped staves

Staves (such as Staff, DrumStaff, TabStaff, etc.) are contexts that can contain one or more voice contexts, but cannot contain any other staves.

The following properties affect the spacing of *ungrouped* staves:

- VerticalAxisGroup properties:
 - default-staff-staff-spacing
 - staff-staff-spacing

These grob properties are described individually above; see Section 29.1.1 [Within-system spacing properties], page 695.

Additional properties are involved for staves that are part of a staff group; see Section 29.1.3 [Spacing of grouped staves], page 699.

The following example shows how the default-staff-staff-spacing property can affect the spacing of ungrouped staves. The same overrides applied to staff-staff-spacing would have the same effect, but would also apply in cases where the staves are combined in a group or groups.

```
\layout {
  \context {
    \Staff
    \override VerticalAxisGroup.default-staff-staff-spacing =
      #'((basic-distance . 8)
         (minimum-distance . 7)
         (padding . 1))
  }
}

<<
% The very low note here needs more room than 'basic-distance
% can provide, so the distance between this staff and the next
% is determined by 'padding.
\new Staff { b,2 r | }

% Here, 'basic-distance provides enough room, and there is no
% need to compress the space (towards 'minimum-distance) to make
% room for anything else on the page, so the distance between
% this staff and the next is determined by 'basic-distance.
```

```

\new Staff { \clef bass g2 r | }

% By setting 'padding to a negative value, staves can be made to
% collide. The lowest acceptable value for 'basic-distance is 0.
\new Staff \with {
  \override VerticalAxisGroup.default-staff-staff-spacing =
    #'((basic-distance . 3.5)
      (padding . -10))
} { \clef bass g2 r | }
\new Staff { \clef bass g2 r | }
>>

```



See also

Installed Files: scm/define-grobs.scm.

Snippets: Section “Spacing” in *Snippets*.

Internals Reference: Section “VerticalAxisGroup” in *Internals Reference*.

29.1.3 Spacing of grouped staves

In orchestral and other large scores, it is common to place staves in groups. The space between groups is typically larger than the space between staves of the same group.

Staff-groups (such as *StaffGroup*, *ChoirStaff*, etc.) are contexts that can contain one or more staves simultaneously.

The following properties affect the spacing of staves inside staff groups:

- *VerticalAxisGroup* properties:
 - *staff-staff-spacing*
- *StaffGrouper* properties:
 - *staff-staff-spacing*
 - *staffgroup-staff-spacing*

These grob properties are described individually above; see Section 29.1.1 [Within-system spacing properties], page 695.

The following example shows how properties of the *StaffGrouper* grob can affect the spacing of grouped staves:

```

\layout {
  \context {
    \Score
    \override StaffGrouper.staff-staff-spacing.padding = 0
    \override StaffGrouper.staff-staff-spacing.basic-distance = 1
  }
}


```

```

<<
  \new PianoStaff \with {
    \override StaffGrouper
      .staffgroup-staff-spacing
      .basic-distance = 20
  } <<
    \new Staff { c'1 }
    \new Staff { c'1 }
  >>

  \new StaffGroup <<
    \new Staff { c'1 }
    \new Staff { c'1 }
  >>
>>

```



See also

Installed Files: `scm/define-grobs.scm`.

Snippets: Section “Spacing” in *Snippets*.

Internals Reference: Section “VerticalAxisGroup” in *Internals Reference*, Section “StaffGrouper” in *Internals Reference*.

29.1.4 Spacing of non-staff lines

Non-staff lines (such as Lyrics, ChordNames, etc.) are contexts whose layout objects are engraved like staves (i.e., in horizontal lines within systems). Specifically, non-staff lines are non-staff contexts that contain the Section “Axis_group_engraver” in *Internals Reference*.

The following properties affect the spacing of non-staff lines:


- VerticalAxisGroup properties:
 - `staff-affinity`
 - `nonstaff-relatedstaff-spacing`
 - `nonstaff-nonstaff-spacing`
 - `nonstaff-unrelatedstaff-spacing`

These grob properties are described individually above; see Section 29.1.1 [Within-system spacing properties], page 695.

The following example shows how the `nonstaff-nonstaff-spacing` property can affect the spacing of consecutive non-staff lines. Here, by setting the `stretchability` key to a very high value, the lyrics are able to stretch much more than usual:

```
\layout {
  \context {
    \Lyrics
    \override VerticalAxisGroup
      .nonstaff-nonstaff-spacing
      .stretchability = 1000
  }
}

\new StaffGroup
<<
  \new Staff \with {
    \override VerticalAxisGroup.staff-staff-spacing =
      #'((basic-distance . 30))
  } { c'1 }
  \new Lyrics \with {
    \override VerticalAxisGroup.staff-affinity = #UP
  } \lyricmode { up }
  \new Lyrics \with {
    \override VerticalAxisGroup.staff-affinity = #CENTER
  } \lyricmode { center }
  \new Lyrics \with {
    \override VerticalAxisGroup.staff-affinity = #DOWN
  } \lyricmode { down }
  \new Staff { c'1 }
>>
```



See also

Installed Files: `ly/engraver-init.ly`, `scm/define-grobs.scm`.

Snippets: Section “Spacing” in *Snippets*.

Internals Reference: Section “Contexts” in *Internals Reference*, Section “VerticalAxisGroup” in *Internals Reference*.

29.2 Explicit staff and system positioning

It is possible to approach vertical spacing in a different way (in comparison to what was demonstrated in the previous sections) by using the property `line-break-system-details` of the `NonMusicalPaperColumn` grob. While the flexible vertical spacing mechanisms specify vertical padding, `line-break-system-details` can specify exact vertical positions on the page.

This property contains five different subproperties: `X-offset`, `Y-offset`, `extra-offset`, `alignment-distances`, and `bottom-padding`.

To understand how each of these different subproperties work, we begin by looking at an example that includes no overrides at all. We isolate both line breaking and page breaking information in a dedicated voice, dividing the music into five measures per line. This technique of creating an otherwise empty voice for breaks helps in keeping layout separate from music entry as our example becomes more complicated. Also see Chapter 28 [Breaks], page 687.

```
\book {
  \score {
    <<
      \new Staff <<
        \new Voice {
          s1*5 \break
          s1*5 \break
          s1*5 \break }
        \new Voice { \*15 { c'4 c' c' c' } }
      >>
      \new Staff { \*15 { d'4 d' d' d' } }
    >>
  }
}
```



We now set the vertical and horizontal start points of each system explicitly by using the `Y-offset` and `X-offset` subproperties of `line-break-system-details`.

```

\book {
  \score {
    <<
    \new Staff <<
    \new Voice {
      \once \override
        Score.NonMusicalPaperColumn
          .line-break-system-details.Y-offset = 0
      s1*5 \break
      \once \override
        Score.NonMusicalPaperColumn
          .line-break-system-details.Y-offset = 30
      \once \override
        Score.NonMusicalPaperColumn
          .line-break-system-details.X-offset = 10
      s1*5 \break
      \once \override
        Score.NonMusicalPaperColumn
          .line-break-system-details.Y-offset = 50
      s1*5 \break }
    \new Voice { \*15 { c'4 c' c' c' } }
    >>
    \new Staff { \*15 { d'4 d' d' d' } }
    >>
  }
}

```



In contrast to the absolute positioning available through `Y-offset` and `X-offset`, relative positioning is possible with the `extra-offset` subproperty. Placement is relative to the de-

fault layout or to the absolute positioning created by setting X-offset and Y-offset. The subproperty `extra-offset` accepts a pair consisting of displacements along the X- and Y-axis.

```
\book {
  \score {
    <<
      \new Staff <<
        \new Voice {
          s1*5 \break
          \once \override
            Score.NonMusicalPaperColumn
              .line-break-system-details.extra-offset = #'(5 . 5)
          s1*5 \break
          \once \override
            Score.NonMusicalPaperColumn
              .line-break-system-details.extra-offset = #'(0 . 20)
          s1*5 \break }
        \new Voice { \*15 { c'4 c' c' c' } }
      >>
      \new Staff { \*15 { d'4 d' d' d' } }
    >>
  }
}
```



LilyPond v2.27.3

Now that we have set the vertical start point of each system explicitly, we can also set the vertical distances between staves within each system manually by modifying the `alignment-distances` subproperty. As can be seen, we use an alist to set two different `line-break-system-details` subproperties at the same time.

```

\book {
  \score {
    <<
      \new Staff <<
        \new Voice {
          \once \override
            Score.NonMusicalPaperColumn.line-break-system-details =
              #'((Y-offset . 0)
                (alignment-distances . (10)))
          s1*5 \break
          \once \override
            Score.NonMusicalPaperColumn.line-break-system-details =
              #'((Y-offset . 30)
                (alignment-distances . (15)))
          s1*5 \break
          \once \override
            Score.NonMusicalPaperColumn.line-break-system-details =
              #'((Y-offset . 65)
                (alignment-distances . (20)))
          s1*5 \break }
        \new Voice { \*15 { c'4 c' c' c' } }
      >>
      \new Staff { \*15 { d'4 d' d' d' } }
    >>
  }
}

```




LilyPond v2.27.3

The next example shows how to set vertical positions of multiple staves in a system. Note that `alignment-distances` directly applies to staves, not taking care of grouping with `StaffGroup` or the like. Value `#f` indicates that the default value should be used.


```

\book {
  \score {
    <<
      \new Staff <<
        \new Voice {
          \once \override
            Score.NonMusicalPaperColumn.line-break-system-details =
              #'((Y-offset . 0)
                (alignment-distances . (15 8)))
          s1*5 \break
          \once \override
            Score.NonMusicalPaperColumn.line-break-system-details =
              #'((Y-offset . 35)
                (X-offset . 10)
                (alignment-distances . (#f 8)))
          s1*5 \break
          \once \override
            Score.NonMusicalPaperColumn.line-break-system-details =
              #'((Y-offset . 65)
                (alignment-distances . (8 15)))
          s1*5 \break }
        \new Voice { \*15 { c'4 c' c' c' } }
      >>
      \new StaffGroup <<
        \new Staff { \*15 { d'4 d' d' d' } }
        \new Staff { \*15 { e'4 e' e' e' } }
      >>
    >>
  }
}

```



The last subproperty of `line-break-system-details`, `bottom-padding`, has a similar effect as `last-bottom-spacing`. Note, however, that it doesn't hold a compressible or stretchable spacing dimension but a rigid, fixed padding value from the bottom of the page to the lowest staff. Here is the test snippet without a ragged bottom, showing the default distance.

```
\book {
  \score {
    <<
      \new Staff <<
        \new Voice {
          s1*5 \break
          s1*5 \break
          s1*5 \break }
        \new Voice { \*15 { c'4 c' c' c' } }
      >>
      \new Staff { \*15 { d'4 d' d' d' } }
    >>
  }
  \paper { ragged-last-bottom = ##f }
}
```



LilyPond v2.27.3

Setting `bottom-padding` yields the following result.

```
\book {
  \score {
    <<
      \new Staff <<
        \new Voice {
          s1*5 \break
          s1*5 \break
          \once \override
            Score.NonMusicalPaperColumn.line-break-system-details =
```

```

        #'((bottom-padding . 20))
        s1*5 \break }
        \new Voice { \*15 { c'4 c' c' c' } }
    >>
        \new Staff { \*15 { d'4 d' d' d' } }
    >>
}
\paper { ragged-last-bottom = ##f }
}

```



LilyPond v2.27.3

Some points to consider:

- When using alignment-distances, lyrics and other non-staff lines do not count as a staff.
- The units of the numbers passed to the X-offset, Y-offset, extra-offset, and alignment-distances subproperties are interpreted as multiples of the distance between adjacent staff lines. Positive values move staves and lyrics up, negative values move staves and lyrics down.
- Because the `NonMusicalPaperColumn.line-break-system-details` settings given here allow the positioning of staves and systems anywhere on the page, it is possible to violate paper or margin boundaries or even to print staves or systems on top of one another. Use reasonable values for the subproperties to avoid this.

See also

Snippets: Section “Spacing” in *Snippets*.

29.3 Vertical collision avoidance

Intuitively, there are some objects in musical notation that belong to the staff and there are other objects that should be placed outside the staff. Objects belonging outside the staff include things such as rehearsal marks, text and dynamic markings (from now on, these will be called outside-staff objects). LilyPond’s rule for the vertical placement of outside-staff objects is to place them as close to the staff as possible but not so close that they collide with another object.

LilyPond uses the `outside-staff-priority` property to determine whether a grob is an outside-staff object: if `outside-staff-priority` is a number, the grob is an outside-staff object. In addition, `outside-staff-priority` tells LilyPond in which order the objects should be placed.

First, LilyPond places all the objects that do not belong outside the staff. Then it sorts the outside-staff objects according to their `outside-staff-priority` (in increasing order). One by one, LilyPond takes the outside-staff objects and places them so that they do not collide with any objects that have already been placed. That is, if two outside-staff grobs are competing for the same space, the one with the lower `outside-staff-priority` will be placed closer to the staff.


A listing of defaults for `outside-staff-priority` may be found in Section B.17 [Default values for `outside-staff-priority`], page 936.

```
\relative c'' {
  c4_"Text"\pp
  r2.
  \once \override TextScript.outside-staff-priority = 1
  c4_"Text"\pp % this time the text will be closer to the staff
  r2.
  % by setting outside-staff-priority to a non-number,
  % we disable the automatic collision avoidance
  \once \override TextScript.outside-staff-priority = ##f
  \once \override DynamicLineSpanner.outside-staff-priority = ##f
  c4_"Text"\pp % now they will collide
}
```



The vertical padding around outside-staff objects can be controlled with property `outside-staff-padding`.

```
\relative {
  \once \override TextScript.outside-staff-padding = 0
  a'4-"outside-staff-padding = 0"
  \once \override TextScript.outside-staff-padding = 3
  d-"outside-staff-padding = 3"
  c-"default outside-staff-padding"
  b-"default outside-staff-padding"
  R1
}
```



By default, outside-staff objects are placed so they avoid a horizontal collision with previously-positioned grobs. This can lead to situations in which objects are placed close to each other

horizontally. As shown in the example below, setting `outside-staff-horizontal-padding` increases the horizontal spacing required, and in this case moves the text up to prevent it from getting too close to the ledger lines.

```
\relative {
  c''4^"Word" c c''2
  R1
  \once \override TextScript.outside-staff-horizontal-padding = 1
  c,,4^"Word" c c''2
}
```



See also

Snippets: Section “Spacing” in *Snippets*.

30 Horizontal spacing

30.1 Horizontal spacing overview

The spacing engine translates differences in durations into stretchable distances (‘springs’) of differing lengths. Longer durations get more space, shorter durations get less. The shortest durations get a fixed amount of space (which is controlled by `shortest-duration-space` in the Section “SpacingSpanner” in *Internals Reference* object). The longer the duration, the more space it gets: doubling a duration adds spacing-increment of space to the note.

For example, the following piece contains lots of half, quarter, and 8th notes; the eighth note is followed by 1 note head width (NHW). The quarter note is followed by 2 NHW, the half by 3 NHW, etc.

```
\relative c' {
  c2 c4. c8
  c4. c8 c4. c8
  c8 c c4 c c
}
```



Normally, spacing-increment is set to 1.2 staff space, which is approximately the width of a note head, and `shortest-duration-space` is set to 2.0, meaning that the shortest note gets 2.4 staff space (2.0 times the spacing-increment) of horizontal space. This space is counted from the left edge of the symbol, so the shortest notes are generally followed by one NHW of space.

If one would follow the above procedure exactly, then adding a single 32nd note to a score that uses 8th and 16th notes, would widen up the entire score a lot. The shortest note is no longer a 16th, but a 32nd, thus adding 1 NHW to every note. To prevent this, the shortest duration for spacing is not the shortest note in the score, but rather the one which occurs most frequently.

The most common shortest duration is determined as follows: in every measure, the shortest duration is determined. The most common shortest duration is taken as the basis for the spacing, with the stipulation that this shortest duration should always be equal to or shorter than an 8th note.

These durations may also be customized. If you set the `common-shortest-duration` in Section “SpacingSpanner” in *Internals Reference*, then this sets the base duration for spacing. The maximum duration for this base (normally an 8th), is set through `base-shortest-duration`.

Notes that are even shorter than the common shortest note are followed by a space that is proportional to their duration relative to the common shortest note. So if we were to add only a few 16th notes to the example above, they would be followed by half a NHW:

```
\relative { c''2 c4. c8 | c4. c16[ c] c4. c8 | c8 c c4 c c }
```



As explained in the *Essay on automated music engraving*, stem directions will influence spacing (see Section “Optical spacing” in *Essay*) and can be adjusted using the

stem-spacing-correction property of the Section “NoteSpacing” in *Internals Reference* object (which are generated for every Section “Voice” in *Internals Reference* context).

The StaffSpacing object (generated in Section “Staff” in *Internals Reference* context) contains the same property for controlling the stem/bar line spacing.

The following example shows this; once with the default settings and once with an exaggerated adjustment:



Proportional notation is supported; see Section 30.6 [Proportional notation], page 720.

See also

Essay on automated music engraving: Section “Optical spacing” in *Essay*.

Snippets: Section “Spacing” in *Snippets*.

Internals Reference: Section “SpacingSpanner” in *Internals Reference*, Section “NoteSpacing” in *Internals Reference*, Section “StaffSpacing” in *Internals Reference*, Section “NonMusicalPaperColumn” in *Internals Reference*.

Known issues and warnings

There is no convenient mechanism to manually override spacing. The following workaround may be used to insert extra space into a score, adjusting the padding value as necessary.

```
\override Score.NonMusicalPaperColumn.padding = 10
```

No workaround exists for decreasing the amount of space.

30.2 New spacing section

New sections with different spacing parameters can be started with the newSpacingSection command. This is useful for sections with different notions of ‘long’ and ‘short’ notes. The \newSpacingSection command creates a new SpacingSpanner object at that musical moment.

In the following example the time signature change introduces a new section, and the 16ths notes are automatically spaced slightly wider apart.

```
\relative c' {
  \time 2/4
  c4 c8 c
  c8 c c4 c16[ c c8] c4
  \newSpacingSection
  \time 4/16
  c16[ c c8]
}
```



If the automatic spacing adjustments do not give the required spacing, manual \overrides may be applied to its properties. These must be applied at the same musical moment as the \newSpacingSection command itself and will then affect the spacing of all the following music until the properties are changed in a new spacing section, for example:

```

\relative c' {
  \time 4/16
  c16[ c c8]
  \newSpacingSection
  \override Score.SpacingSpanner.spacing-increment = 2
  c16[ c c8]
  \newSpacingSection
  \revert Score.SpacingSpanner.spacing-increment
  c16[ c c8]
}

```



See also

Snippets: Section “Spacing” in *Snippets*.

Internals Reference: Section “SpacingSpanner” in *Internals Reference*.

30.3 Changing horizontal spacing globally

Horizontal spacing may be altered with the `base-shortest-duration` property. Here we compare the same music; once without altering the property, and then altered. Larger values yield tighter spacing.

```

\score {
  \relative {
    g'4 e e2 | f4 d d2 | c4 d e f | g4 g g2 |
    g4 e e2 | f4 d d2 | c4 e g g | c,1 |
    d4 d d d | d4 e f2 | e4 e e e | e4 f g2 |
    g4 e e2 | f4 d d2 | c4 e g g | c,1 |
  }
}

```



```

\score {
  \relative {
    g'4 e e2 | f4 d d2 | c4 d e f | g4 g g2 |
    g4 e e2 | f4 d d2 | c4 e g g | c,1 |
    d4 d d d | d4 e f2 | e4 e e e | e4 f g2 |
    g4 e e2 | f4 d d2 | c4 e g g | c,1 |
  }
  \layout {

```



```

\context {
  \Score
  \override SpacingSpanner.base-shortest-duration =
    \musicLength 16
}
}
}

```




30.3.1 Uniform stretching of tuplets

By default, spacing in tuplets depends on various non-duration factors (such as accidentals, clef changes, etc). To disregard such symbols and force uniform equal-duration spacing, use `Score.SpacingSpanner.uniform-stretching`. This property can only be changed at the beginning of a score,

```

\score {
  <<
    \new Staff \relative c' {
      \tuplet 5/4 { c8 c c c c } c8 c c c
    }
    \new Staff \relative c' {
      c8 c c c \tuplet 5/4 { c8 c c c c }
    }
  >>
  \layout {
    \context {
      \Score
      \override SpacingSpanner.uniform-stretching = ##t
    }
  }
}


```



30.3.2 Strict note spacing

When `strict-note-spacing` is set, notes are spaced without regard for clefs, bar lines, and grace notes,

```
\override Score.SpacingSpanner.strict-note-spacing = ##t
\new Staff \relative {
  c'18[ c \clef alto c \grace { c16 c } c8 c c] c32[ c] }
```



See also

Snippets: Section “Spacing” in *Snippets*.

30.4 Adjusting horizontal spacing for specific layout objects

In addition to the general-purpose parameters of the default spacing algorithm that apply to all elements of the score or spacing section, several properties serve to operate adjustments on a per-object-type-basis. Examples include adjusting the distance from clefs to time signatures, but not from clefs to notes when there is no time signature, or stretching notes further apart in the presence of a printed text so that it does not overlap with the next note. Tweaking these first requires identifying the type of spacing at play.

30.4.1 Overview of object-specific horizontal spacing tweaks

Layout objects that have a horizontally fixed position are called *items* (as opposed to *spanners*) and, for the purpose of horizontal spacing, are grouped into *columns*. Note heads and rests, forming the main musical material, together with those objects that are logically linked to them – accidentals, articulations, stems, dots, etc. – are all part of ‘musical columns’ (represented by `NoteColumn` grobs). *Prefatory matter*, such as clefs, time signatures and bar lines, is grouped into ‘non-musical columns’ (represented by `NonMusicalPaperColumn` grobs). In the following example, musical items are colored red, while non-musical items are blue.



This example shows that there is an alternation between musical and non-musical columns. The first non-musical column contains a clef and a time signature. The first musical column has a note head with its stem and articulation. The second non-musical column is empty and thus removed during the layout process. The second musical column has a note again. The third non-musical column contains a clef, a bar line and a rehearsal mark, etc.

Within one column, spacing is fixed. On the other hand, the amount of space between consecutive columns is flexible. As we shall see, the methods to adjust spacing within a column and between columns are different.

30.4.2 Spacing between adjacent non-musical items

Within a non-musical column, items are laid out in a specific order. For instance, with the set of items in the picture below, the default order places the breathing sign first, then the clef, then the bar line, the key cancellation and key signature, and finally the time signature (this is controlled by the `BreakAlignment.break-align-orders` property, which may conveniently be changed using `\breakAlignInsert`).

```
\relative {
  \key g \minor
  g'1
  \breathe
  \clef alto
  \time 6/8
  \key a \major
  aes4.
}
```



The distance between two adjacent items from the same non-musical column is controlled by the value of the `space-alist` property of the leftmost one of the two. `space-alist` has the form of an associative list mapping break-align symbols to `(spacing-style . value)` pairs. A breakable item's break-align symbol is given by the value of its `break-align-symbol` property; standard choices are listed in Section “break-alignment-interface” in *Internals Reference*. Spacing styles are listed in Section “break-aligned-interface” in *Internals Reference*. Among the available options, only extra-space and minimum-space are relevant for tweaking the space between non-musical items. The difference is that extra-space measures the padding from the right of the first object to the left of the second object while minimum-space counts from the left of the first object. Thus, a way to move the bar line farther from the clef is:

```
\relative {
  \key g \minor
  g'1
  \override Staff.Clef.space-alist.staff-bar = #'(extra-space . 4)
  \breathe
  \clef alto
  \time 6/8
  \key a \major
  aes4.
}
```



`space-alist` settings, not limited to the two spacing styles described above, are also possible to override the spacing between different columns. However, this kind of spacing is flexible, and does not merely depend on the types of object involved but also their shapes. Methods specific to it are documented in the next section.

Selected snippets

Separating key cancellations from key signature changes

By default, the accidentals used for key cancellations are placed adjacent to those for key signature changes. This behavior can be changed by overriding the `break-align-orders` property of the `BreakAlignment` grob.

If you look up the definition of the `break-alignment-interface` in LilyPond's Internals Reference (https://lilypond.org/doc/v2.24/Documentation/internals/break_002dalignment_002dinterface), you get the following list of available break-align symbols:


```
ambitus
breathing-sign
clef
cue-clef
cue-end-clef
custos
key-cancellation
key-signature
left-edge
signum-repetitionis
staff-bar
staff-ellipsis
time-signature
```

From this list, we find that we want to move `key-cancellation` so that it comes before `staff-bar`. This is accomplished with the `\breakAlignInsert` function.

```
music = { \key es \major d'1 \bar "||"
          \key a \major d'1 }

{ <>^\markup "default"
  \music }

{ <>^\markup "cancellation first"
  \breakAlignInsert key-cancellation before staff-bar
  \music }
```



See also


Notation Reference: Section 36.9.4 [Using the `break-alignable-interface`], page 795.

Extending LilyPond: Section “Association lists (alists)” in *Extending*.

Internals Reference: Section “`Break_align_engraver`” in *Internals Reference*, Section “`BreakAlignGroup`” in *Internals Reference*, Section “`BreakAlignment`” in *Internals Reference*, Section “`break-alignable-interface`” in *Internals Reference*, Section “`break-aligned-interface`” in *Internals Reference*, Section “`break-alignment-interface`” in *Internals Reference*.

30.4.3 Spacing between adjacent columns

Contrary to spacing within one column, spacing between adjacent columns is flexible and stretches or compresses according to the density of music on the line. By default, columns may even overlap in some situations. The following example shows three cases. The second accidental slides behind the bar line, while the third one overlaps with the clef. Also, the tempo marking *Presto* spans several columns. Observe how the first accidental, which remains within the vertical extent of the bar line on its left, is placed further apart.



These spacing rules can be overridden. This is done by modifying the width and height that an object takes in horizontal spacing. The relevant properties are `extra-spacing-width` and `extra-spacing-height`. When unset, an object takes as much space in horizontal spacing as its `X-extent` and `Y-extent` properties allow. These are accurate values of its dimensions. The `extra-spacing-width` and `extra-spacing-height` properties make an object larger or smaller for computation of horizontal spacing between columns only, but preserve its dimensions for other spacing types.

```
{
  \textMark "Default"
  c'2 2 cis'2 2
}

{
  \textMark "Modified X-extent"
  \override NoteHead.X-extent = #'(-2 . 2)
  c'2 2 cis'2 2
}

{
  \textMark "Modified extra-spacing-width"
  \override NoteHead.extra-spacing-width = #'(-2 . 2)
  c'2 2 cis'2 2
}
```



`extra-spacing-width` and `extra-spacing-height` are pairs of numbers, which are added to the dimensions on each axis. For instance, setting `extra-spacing-height` to `'(-2 . 3)` makes

the object three units larger on the top, and two units larger on the bottom (limit lowered by 2). The following example shows how to use `extra-spacing-height` to change the limit after which accidentals no longer overlap with bar lines.

```
music = \relative {
  \time 1/4
  cis8 8 | dis8 8 | eis8 8 | fis8 8 |
  gis8 8 | ais8 8 | bis8 8 | cis8 8 |
}

{
  \music
}

{
  \override Accidental.extra-spacing-height = #'(0 . 1.0)
  \music
}
```



The value `'(+inf.0 . -inf.0)` for `extra-spacing-width` or `extra-spacing-height` removes the object's presence.

```
music = \relative {
  \time 1/4
  cis8 8 | dis8 8 | eis8 8 | fis8 8 |
  gis8 8 | ais8 8 | bis8 8 | cis8 8 |
}

{
  \override Accidental.extra-spacing-height = #'(+inf.0 . -inf.0)
  \music
}
```



Conversely, an `extra-spacing-height` of `'(-inf.0 . +inf.0)` makes the object infinitely high, preventing overlap with another column completely. The below example demonstrates this technique on `Accidental` and `MetronomeMark`. In the case of `MetronomeMark`, it is necessary to set `extra-spacing-width` to `'(0 . 0)` because the default is `'(+inf.0 . -inf.0)`, and even an infinitely high object does not take space if it has no width.

```
{
  \override Score.MetronomeMark.extra-spacing-width =
    #'(0 . 0)
  \override Score.MetronomeMark.extra-spacing-height =
    #'(-inf.0 . +inf.0)
  \override Accidental.extra-spacing-height =
    #'(-inf.0 . +inf.0)
  cis'4 r2.
  \tempo Presto
  fis16 8 16 4 \clef alto cis4 fis4
}
```



See also

Internals Reference: Section “item-interface” in *Internals Reference*, Section “separation-item-interface” in *Internals Reference*.

30.5 Line width

The most basic settings influencing the spacing are `indent` and `line-width`. They are set in the `\layout` block. They control the indentation of the first line of music, and the lengths of the lines.

If `ragged-right` is set to `#t` in the `\layout` block, then systems ends at their natural horizontal length, instead of being spread horizontally to fill the whole line. This is useful for short fragments, and for checking how tight the natural spacing is. The normal default setting is `false`, but if the score has only one system the default value is `true`.

The option `ragged-last` is similar to `ragged-right`, but only affects the last line of the piece. No restrictions are put on that line. The result is similar to formatting text paragraphs. In a paragraph, the last line simply takes its natural horizontal length.

```
\layout {
  indent = 0
  line-width = 150
  ragged-last = ##t
}
```

See also

Snippets: Section “Spacing” in *Snippets*.

30.6 Proportional notation

LilyPond supports proportional notation, a type of horizontal spacing in which each note consumes an amount of horizontal space exactly equivalent to its rhythmic duration. This type of proportional spacing is comparable to horizontal spacing on top of graph paper. Some late 20th- and early 21st-century scores use proportional notation to clarify complex rhythmic relationships, or to facilitate the placement of timelines or other graphics directly in the score.

The following settings for proportional notation are provided, which may be used together or alone:

- `proportionalNotationDuration`

- uniform-stretching
- strict-note-spacing
- `\remove Separating_line_group_engraver`

In the examples that follow, we explore these different proportional notation settings and examine how they interact.

We start with the following one-measure example, which uses classical spacing with ragged-right turned on.

```
\new RhythmicStaff {
  c2 16 16 16 16 \tuplet 5/4 { 16 16 16 16 16 }
}
```




Notice that the half note starting the measure takes up far less than half of the horizontal space of the measure. Likewise, the sixteenth notes and sixteenth-note quintuplets (or twentieth notes) ending the measure together take up far more than half the horizontal space of the measure.

In classical engraving, this spacing may be exactly what we want because we can borrow horizontal space from the half note and conserve horizontal space across the measure as a whole.

On the other hand, if we want to insert a measured timeline or some other graphic above or below our score, we need proportional notation. We turn proportional notation on with the `proportionalNotationDuration` setting.

```
\new RhythmicStaff {
  c2 16 16 16 16 \tuplet 5/4 { 16 16 16 16 16 }
}
\layout {
  \context {
    \Score
    proportionalNotationDuration = #1/20
  }
}
```



The half note at the beginning of the measure and the faster notes in the second half of the measure now occupy equal amounts of horizontal space. We could place a measured timeline or graphic above or below this example.

The `proportionalNotationDuration` setting is a context setting that lives in `Score`. Remember that context settings can appear in one of three locations within our input file – in a `\with` block, in a `\context` block, or directly in the music entry preceded by the `\set` command. As with all context settings, users can pick in which of the three different locations they would like to set `proportionalNotationDuration`.

The `proportionalNotationDuration` setting takes a single argument, which is the reference length to space all music. The value `#1/20` specifies one twentieth of a whole note.

How do we select the right reference duration to pass to `proportionalNotationDuration`? Usually by a process of trial and error, beginning with a duration close to the fastest (or smallest) duration in the piece. Smaller reference durations space music loosely; larger reference durations space music tightly.


```


rhythm = { c2 16 16 16 16 16 \tuplet 5/4 { 16 16 16 16 16 } }

\new RhythmicStaff {
  \set Score.proportionalNotationDuration = #1/8
  % Allow overlapping of note heads.
  \override NoteHead.extra-spacing-width = #'(+inf.0 . -inf.0)
  \rhythm
}

\new RhythmicStaff {
  \set Score.proportionalNotationDuration = #1/16
  \rhythm
}

\new RhythmicStaff {
  \set Score.proportionalNotationDuration = #1/32
  \rhythm
}

```




Note that too large a reference duration – such as the eighth note, above – spaces music too tightly and can cause note head collisions. In general, proportional notation takes up more horizontal space than classical spacing. Proportional spacing provides rhythmic clarity at the expense of horizontal space.

Next we examine how to optimally space overlapping tuplets. We start by examining what happens to our original example, with classical spacing, when we add a second staff with a different type of tuplet.

```


<<
\new RhythmicStaff {
  c2 16 16 16 16 \tuplet 5/4 { 16 16 16 16 16 }
}
\new RhythmicStaff {
  \tuplet 9/8 { c8 8 8 8 8 8 8 8 8 }
}
>>

```




The spacing is bad because the evenly spaced notes of the bottom staff do not stretch uniformly. Classical engravings include very few complex triplets and so classical engraving rules can generate this type of result. Setting `proportionalNotationDuration` fixes this.

```
<<
  \new RhythmicStaff {
    c2 16 16 16 16 \tuplet 5/4 { 16 16 16 16 16 }
  }
  \new RhythmicStaff {
    \tuplet 9/8 { c8 8 8 8 8 8 8 8 8 }
  }
>>
\layout {
  \context {
    \Score
    proportionalNotationDuration = #1/20
  }
}
```



But if we look very carefully we can see that notes of the second half of the 9-tuplet space ever so slightly more widely than the notes of the first half of the 9-tuplet. To ensure uniform stretching, we turn on uniform-stretching, which is a property of `SpacingSpanner`.

```
<<
  \new RhythmicStaff {
    c2 16 16 16 16 \tuplet 5/4 { 16 16 16 16 16 }
  }
  \new RhythmicStaff {
    \tuplet 9/8 { c8 8 8 8 8 8 8 8 8 }
  }
>>
\layout {
  \context {
    \Score
    proportionalNotationDuration = #1/20
    \override SpacingSpanner.uniform-stretching = ##t
  }
}
```



Our two-staff example now spaces exactly, our rhythmic relationships are visually clear, and we can include a measured timeline or graphic if we want.

It is recommended to always set the `SpacingSpanner`’s `uniform-stretching` property to `#t` if you use `proportionalNotationDuration`. Omitting it, for example, causes skips to consume an incorrect amount of horizontal space.


The `SpacingSpanner` is an abstract grob that lives in the `Score` context. As with our settings of `proportionalNotationDuration`, overrides to the `SpacingSpanner` can occur in any of three different places in our input file – in the `Score`’s `\with` block, in a `Score`’s `\context` block, or directly in the note entry.

By default, there is only one `SpacingSpanner` per `Score`. This means that `uniform-stretching` is either turned on for the entire score or turned off for the entire score. We can, however, override this behavior and turn on different spacing features at different places in the score by using the command `\newSpacingSection`. See Section 30.2 [New spacing section], page 712, for more info.

Next we examine the effects of the `Separating_line_group_engraver` and see why proportional scores frequently remove this engraver. The following example shows that there is a small amount of “prefatory” space just before the first note in each system.

```
\paper {
  indent = 0
}
```


```
\new Staff {
  c'1 \break
  c'1
}
```



The amount of this prefatory space stays the same regardless whether a time signature, a key signature, or a clef follows. `Separating_line_group_engraver` is responsible for this space, and removing this engraver reduces the prefatory space to zero.

```
\paper {
  indent = 0
}
```

```
\new Staff \with {
  \remove Separating_line_group_engraver
} {
  c'1 \break
  c'1
}
```




Non-musical elements like time signatures, key signatures, clefs, and accidentals are problematic in proportional notation. None of these elements has rhythmic duration, but all of them consume horizontal space. Different proportional scores approach these problems differently.

It may be possible to avoid spacing problems with key signatures simply by not having any. This is a valid option since most proportional scores are contemporary music. The same may be true of time signatures, especially for those scores that include a measured timeline or other graphic. However, such scores are exceptional, and most proportional scores do include at least some time signatures. Clefs and accidentals are even more essential.

So what strategies exist for spacing non-musical elements in a proportional context? One good option is the `strict-note-spacing` property of `SpacingSpanner`. Compare the two scores below:

```
{
  \set Score.proportionalNotationDuration = #1/16
  c''8 8 8 \clef alto d'2 d'8
}

{
  \set Score.proportionalNotationDuration = #1/16
  \override Score.SpacingSpanner.strict-note-spacing = ##t
  c''8 8 8 \clef alto d'2 d'8
}
```



Both scores are proportional, but the spacing in the first score is too loose because of the clef change. The spacing of the second score remains strict, however, because `strict-note-spacing` is turned on. Turning on this property causes the width of time signatures, key signatures, clefs, and accidentals to play no part in the spacing algorithm.

In addition to the settings given here, there are other settings that frequently appear in proportional scores.

```
\override SpacingSpanner.strict-grace-spacing = ##t
      space grace notes strictly (see [Positioning grace notes with floating space],
      page 150)

\set tupletFullLength = ##t
      extend tuplet brackets to mark both rhythmic start and stop points

\override Beam.breakable = ##t
      permit broken beams (see [Beams across line breaks], page 102)

\override Glissando.breakable = ##t
      permit broken glissandi (see [Making glissandi breakable], page 179)

\remove Forbid_line_break_engraver
      allow line breaks even if a musical element is still active (see Section 28.1 [Line
      breaking], page 687)
```

See also

Notation Reference: Section 30.2 [New spacing section], page 712.

Snippets: Section “Spacing” in *Snippets*.

31 Fitting music onto fewer pages


Sometimes you can end up with one or two staves on a second (or third, or fourth...) page. This is annoying, especially if you look at previous pages and it looks like there is plenty of room left on those.

When investigating layout issues, `annotate-spacing` is an invaluable tool. This command prints the values of various layout spacing variables; for more details see the following section, Section 31.1 [Displaying spacing], page 727.

31.1 Displaying spacing

To graphically display the dimensions of vertical layout variables that may be altered for page formatting, set `annotate-spacing` in the `\paper` block:

```
\book {
  \score { { c4 } }
  \paper { annotate-spacing = ##t }
}
```



All layout dimensions are displayed in staff spaces, regardless of the units specified in the `\paper` or `\layout` block. In the above example, `paper-height` has a value of 59.75 staff spaces, and the `staff-size` is 20 points (the default value). Note that:

$$1 \text{ point} = (25.4/72.27) \text{ mm}$$

$$\begin{aligned} 1 \text{ staff space} &= (\text{staff-size})/4 \text{ pts} \\ &= (\text{staff-size})/4 * (25.4/72.27) \text{ mm} \end{aligned}$$

In this case, one staff space is approximately equal to 1.757mm. Thus the paper-height measurement of 59.75 staff spaces is equivalent to 105 millimeters, the height of a6 paper in landscape orientation. The pairs (a,b) are intervals, where a is the lower edge and b the upper edge of the interval.

See also

Notation Reference: Section 27.2 [Setting the staff size], page 683.

Snippets: Section “Spacing” in *Snippets*.

31.2 Changing spacing

The output of `annotate-spacing` reveals vertical dimensions in great detail. For details about modifying margins and other layout variables, see Chapter 26 [Page layout], page 669.

Other than margins, there are a few other options to save space:

- Force systems to move as close together as possible (to fit as many systems as possible onto a page) while being spaced so that there is no blank space at the bottom of the page.

```
\paper {
  system-system-spacing = #'((basic-distance . 0.1) (padding . 0))
  ragged-last-bottom = ##f
  ragged-bottom = ##f
}
```

- Force the number of systems. This can help in two ways. Just setting a value, even the same value as the number of systems being typeset by default, will sometimes cause more systems to be fitted onto each page, as an estimation step is then bypassed, giving a more accurate fit to each page. Also, forcing an actual reduction in the number of systems may save a further page. For example, if the default layout has 11 systems, the following assignment will force a layout with 10 systems.

```
\paper {
  system-count = 10
}
```

- Force the number of pages. For example, the following assignment will force a layout with 2 pages.

```
\paper {
  page-count = 2
}
```

- Avoid (or reduce) objects that increase the vertical size of a system. For example, volta brackets for alternative repeat endings require extra space. If these endings are spread over two systems, they take up more space than if they were on the same system. As another example, dynamics that ‘stick out’ of a system can be moved closer to the staff:

```
\relative e' {
  e4 c g\ff c
  e4 c g-\tweak X-offset -2.7 \ff c
}
```



- Alter the horizontal spacing via `SpacingSpanner`. For more details, see Section 30.3 [Changing horizontal spacing globally], page 713. The following example illustrates the default spacing:

```
\score {
  \relative {
    g'4 e e2 |
    f4 d d2 |
    c4 d e f |
    g4 g g2 |
    g4 e e2 |
  }
}
```



The next example modifies `common-shortest-duration` from a value of $1/4$ to $1/2$. The quarter note is the most common and shortest duration in this example, so by making this duration longer, a ‘squeezing’ effect occurs:

```
\score {
  \relative {
    g'4 e e2 |
    f4 d d2 |
    c4 d e f |
    g4 g g2 |
    g4 e e2 |
  }
  \layout {
    \context {
      \Score
      \override SpacingSpanner.common-shortest-duration =
        \musicLength 2
    }
  }
}
```



The `common-shortest-duration` property cannot be modified dynamically, so it must always be placed in a `\context` block so that it applies to the whole score.

See also

Notation Reference: Chapter 26 [Page layout], page 669, Section 30.3 [Changing horizontal spacing globally], page 713.

Snippets: Section “Spacing” in *Snippets*.

Changing defaults

32 Tuning output

The purpose of LilyPond’s design is to provide the finest quality output by default. Nevertheless, it may happen that you need to change this default layout. The layout is controlled through a large number of ‘knobs and switches’ collectively called *properties*. A tutorial introduction to accessing and modifying these properties can be found in the Learning Manual, see Section “Tweaking output” in *Learning Manual*. This should be read first. This chapter covers similar ground, but in a style more appropriate to a reference manual.

The definitive description of the controls available for tuning can be found in a separate document: the *Internals Reference*. That manual lists all the variables, functions, and options available in LilyPond.

Internally, LilyPond uses Scheme (a Lisp dialect) to provide infrastructure. Overriding layout decisions in effect accesses the program internals, which requires Scheme input. Scheme elements are introduced in a .ly file with the hash mark ‘#’.¹

¹ Section “Scheme tutorial” in *Extending*, contains a short tutorial on entering numbers, lists, strings, and symbols in Scheme.

33 Interpretation contexts

This section describes what contexts are, and how to modify them.

See also

Learning Manual: Section “Contexts and engravers” in *Learning Manual*.

Installed Files: `ly/engraver-init.ly`, `ly/performer-init.ly`.

Snippets: Section “Contexts and engravers” in *Snippets*.

Internals Reference: Section “Contexts” in *Internals Reference*, Section “Engravers and Performers” in *Internals Reference*.

33.1 Contexts explained

Contexts are arranged hierarchically.

33.1.1 Output definitions – blueprints for contexts

This section explains the relevance of output definitions when working with *contexts*. Examples for actual output definitions are given later (see Section 33.5.1 [Changing all contexts of the same type], page 744).

While music written in a file may refer to context types and names, contexts are created only when the music is actually being interpreted. LilyPond interprets music under control of an *output definition* and may do so for several different output definitions, resulting in different output. The output definition relevant for printing music is specified using `\layout`.

A much simpler output definition used for producing MIDI output is specified using `\midi`. Several other output definitions are used by LilyPond internally, like when using the part combiner (Section 5.2.5 [Automatic part combining], page 232) or creating music quotes (Section 6.3.2 [Quoting other voices], page 265).

Output definitions define the relation between contexts as well as their respective default settings. While most changes are usually made inside of a `\layout` block, MIDI-related settings only have an effect when made within a `\midi` block.

Some settings affect several outputs: for example, if `autoBeaming` is turned off in some context, beams count as melismata for the purpose of matching music to lyrics, see Section 9.1.4 [Automatic syllable durations], page 349. This matching is done both for printed output as well as for MIDI – if changes made to `autoBeaming` within a context definition of a `\layout` block are not repeated in the corresponding `\midi` block, lyrics and music will get out of sync in MIDI output.

See also

Installed Files: `ly/engraver-init.ly`, `ly/performer-init.ly`.

33.1.2 Score – the master of all contexts

This is the top-level notation context.¹ No other context can contain a Score context. This context handles the administration of time signatures. It also makes sure that items such as clefs, time signatures, and key signatures are aligned across staves.

You cannot explicitly instantiate a Score context (since it is not contained in any other context). It is instantiated automatically when an output definition (a `\score` or `\layout` block) is processed.

¹ There exists a context called Global that is even one level higher than Score, and which is the hard-coded entry point for LilyPond. However, this is not meant to be modified; you will need this context only if you are going to implement an engraver in Scheme and can be safely ignored otherwise.

An alias called `Timing` is established by the `Timing_translator` in whatever context it is initialized, and the timing variables are then copied from wherever `Timing` had been previously established. The alias at `Score` level provides a target for initializing `Timing` variables in layout definitions before any `Timing_translator` has been run.

33.1.3 Top-level contexts – staff containers

`StaffGroup`

Connect staves vertically by adding a bracket on the left side. The bar lines of the contained staves are connected vertically, too.

`ChoirStaff`

Identical to `StaffGroup` except that the bar lines of the contained staves are not connected vertically.

`GrandStaff`

Connect staves vertically by adding a brace on the left side. The bar lines of the contained staves are connected vertically, too.

`PianoStaff`

Just like `GrandStaff`, but the staves are only removed together, never separately.

`OneStaff` Provides a common axis for the contained staves, making all of them appear in the same vertical space. This can be useful for typesetting staves of different types in immediate succession or for temporarily changing the character of one staff or overlaying it with a different one. Often used with `\stopStaff` and `\startStaff` for best results.

`VaticanaScore`

Top-level context replacing `Score` for Gregorian chant notated in *Vaticana* style. Compared to `Score`, it changes the staff line color to red, uses packed spacing, and removes bar numbers.

`ChordGridScore`

Top-level context replacing `Score` in chord grid notation. Compared to `Score`, it uses proportional notation, and has a few other settings like removing bar numbers.

`StandaloneRhythmScore`

A `Score`-level context for use by `\markup \rhythm`.

33.1.4 Intermediate-level contexts – staves

`Staff` Handles clefs, bar lines, keys, accidentals. It can contain `Voice` contexts.

`RhythmicStaff`

Like `Staff` but for printing rhythms. Pitches are ignored when engraving; the notes are printed on one line. The MIDI rendition retains pitches unchanged.

`TabStaff` Context for generating tablature. It accepts only `TabVoice` contexts and handles the line spacing, the tablature clef, etc., properly.

`DrumStaff`

Handles typesetting for percussion. Can contain `DrumVoice`.

`VaticanaStaff`

A kind of `Staff` for typesetting Gregorian chant in a notational style approximating *Editio Vaticana*.

`MensuralStaff`

Same as `Staff` context, except that it is accommodated for typesetting a piece in mensural style.

PetrucchiStaff

A kind of Staff approximating the mensural typesetting of Ottaviano Petrucci's *Harmonices Musices Odhecaton* (Venice, 1501).

KievanStaff

Same as Staff context, except that it is accommodated for typesetting a piece in Kievan style.

GregorianTranscriptionStaff

A staff for notating Gregorian chant in modern style.

ChordGrid

Creates chord grid notation. This context is always part of a ChordGridScore context.

StandaloneRhythmStaff

A Staff-level context for use by `\markup \rhythm`.

FretBoards

A context for displaying fret diagrams.

Devnull Silently discard all musical information given to this context.

33.1.5 Bottom-level contexts – voices

Voice-level contexts initialize certain properties and start appropriate engravers. A bottom-level context is one without `\defaultchild`. While it is possible to let it accept/contain subcontexts, they can only be created and entered explicitly.

Voice Corresponds to a voice on a staff. This context handles the conversion of dynamic signs, stems, beams, super- and subscripts, slurs, ties, and rests.
You have to instantiate this explicitly if you require multiple voices on the same staff.

VaticanaVoice

A kind of Voice for typesetting Gregorian chant in a notational style approximating *Editio Vaticana*.

MensuralVoice

Same as Voice context, except that it is accommodated for typesetting a piece in mensural style.

PetrucchiVoice

A kind of Voice approximating the mensural typesetting of Ottaviano Petrucci's *Harmonices Musices Odhecaton* (Venice, 1501).

KievanVoice

Same as Voice context, except that it is accommodated for typesetting a piece in Kievan style.

GregorianTranscriptionVoice

A voice for notating Gregorian chant in modern style.

Lyrics Corresponds to a voice with lyrics. Handles the printing of a single line of lyrics.

VaticanaLyrics

Same as Lyrics context, except that it provides a hyphenation style (a single, flush-left hyphen between two syllables) as used in the notational style of *Editio Vaticana*.

GregorianTranscriptionLyrics

A lyrics context for notating Gregorian chant in modern style.

DrumVoice	A voice on a percussion staff.
FiguredBass	The context in which BassFigure grobs are created from input entered in \figuremode mode.
TabVoice	The voice context used within a TabStaff context. Usually left to be created implicitly.
CueVoice	A voice context used to render notes of a reduced size, intended primarily for adding cue notes to a staff, see Section 6.3.3 [Formatting cue notes], page 268. Usually left to be created implicitly.
ChordNames	Typesets chord names.
NoteNames	Typesets note names.
NullVoice	For aligning lyrics without printing notes.
Devnull	Silently discard all musical information given to this context.
Dynamics	Holds a single line of dynamics centered between the staves surrounding this context.
StandaloneRhythmVoice	A Voice-level context for use by \markup \rhythm.
Bottom	This is a generic bottom-level context, accepted by all intermediate-level contexts. It can be used for situations where the same music should appear, say, in a Staff and a TabStaff context.

33.2 Creating and referencing contexts

LilyPond creates lower-level contexts automatically if a music expression is encountered before a suitable context exists, but this is usually successful only for simple scores or music fragments like the ones in the documentation. For more complex scores it is advisable to specify all contexts explicitly with either the `\new` or `\context` command. The syntax of these two commands is very similar:

```
[\new | \context] Context [= name] [music-expression]
```

where either `\new` or `\context` may be specified. *Context* is the type of context which is to be created, *name* is an optional name to be given to the particular context being created, and *music-expression* is a single music expression that is to be interpreted by the engravers and performers in this context.

The `\new` prefix without a name is commonly used to create scores with many staves:

```
<<
  \new Staff \relative {
    % leave the Voice context to be created implicitly
    c'4 c
  }
  \new Staff \relative {
    d'4 d
  }
>>
```




and to place several voices into one staff:

```
\new Staff <<
  \new Voice \relative {
    \voiceOne c''8 c c4 c c
  }
  \new Voice \relative {
    \voiceTwo g'4 g g g
  }
>>
```



`\new` should always be used to specify unnamed contexts.

The difference between `\new` and `\context` is in the action taken:

- `\new` with or without a name always creates a fresh, distinct context, even if one with the same name already exists:

```
\new Staff <<
  \new Voice = "A" \relative {
    \voiceOne c''8 c c4 c c
  }
  \new Voice = "A" \relative {
    \voiceTwo g'4 g g g
  }
>>
```



- `\context` with a name specified creates a distinct context only if a context of the same type with the same name in the same context hierarchy does not already exist. Otherwise it is taken as a reference to that previously created context, and its music expression is passed to that context for interpretation.

Named contexts may be useful in special cases such as lyrics or figured bass, see Section 9.2.1 [Working with lyrics and variables], page 358, and Section “Vocal ensembles templates” in *Learning Manual* for the former, and Section 15.3.3 [Displaying figured bass], page 530, for the latter. More generally, one application of named contexts is in separating the score layout from the musical content. Either of these two forms is valid:

```

\score {
  <<
    % score layout
    \new Staff <<
      \new Voice = "one" {
        \voiceOne
      }
      \new Voice = "two" {
        \voiceTwo
      }
    >>

    % musical content
    \context Voice = "one" {
      \relative {
        c''4 c c c
      }
    }
    \context Voice = "two" {
      \relative {
        g'8 g g4 g g
      }
    }
  >>
}

```



```

\score {
  <<
    % score layout
    \new Staff <<
      \context Voice = "one" {
        \voiceOne
      }
      \context Voice = "two" {
        \voiceTwo
      }
    >>

    % musical content
    \context Voice = "one" {
      \relative {
        c''4 c c c
      }
    }
    \context Voice = "two" {
      \relative {
        g'8 g g4 g g
      }
    }
  >>
}

```



Alternatively, variables may be employed to similar effect. See Section “Organizing pieces with variables” in *Learning Manual*.

- `\context` with no name matches the first of any previously created contexts of the same type in the same context hierarchy, even one that has been given a name, and its music expression is passed to that context for interpretation. This form is rarely useful. However, `\context` with no name and no music expression is used to set the context in which a Scheme procedure specified with `\applyContext` is executed:

```

\new Staff \relative {
  c'1
  \context Timing
    \applyContext #(lambda (ctx)
                      (newline)
                      (display (ly:context-current-moment ctx)))
  c1
}

```

A context must be named if it is to be referenced later, for example when lyrics are associated with music:

```

\new Voice = "tenor" music
...
\new Lyrics \lyricsto "tenor" lyrics

```

For details of associating lyrics with music, see Section 9.1.4 [Automatic syllable durations], page 349.

The properties of all contexts of a particular type can be modified in a `\layout` block (with a different syntax), see Section 33.5.1 [Changing all contexts of the same type], page 744. This construct also provides a means of keeping layout instructions separate from the musical content. If a single context is to be modified, a `\with` block must be used, see Section 33.5.2 [Changing just one specific context], page 747.

See also

Learning Manual: Section “Organizing pieces with variables” in *Learning Manual*.

Notation Reference: Section 33.5.2 [Changing just one specific context], page 747, Section 9.1.4 [Automatic syllable durations], page 349.

33.3 Keeping contexts alive

Contexts are usually terminated at the first musical moment in which they have nothing to do. So Voice contexts die as soon as they contain no events, Staff contexts die as soon as all the Voice contexts within them contain no events, etc. This can cause difficulties if earlier contexts which have died have to be referenced, for example, when changing staves with `\change` commands, associating lyrics with a voice with `\lyricsto` commands, or when adding further musical events to an earlier context.

There is an exception to this general rule: inside of a `{...}` construct (sequential music), the construct’s notion of the “current context” will descend whenever an element of the sequence

ends in a subcontext of the previous current context. This avoids spurious creation of implicit contexts in a number of situations but means that the first context descended into will be kept alive until the end of the expression.

In contrast, the contexts of a `<<...>>` construct's (simultaneous music) expression are not carried forth, so enclosing a context-creating command in an extra pair of `<<...>>` keeps the context from persisting through all of the enclosing `{...}` sequence.

Any context can be kept alive by ensuring it has something to do at every musical moment. Staff contexts are kept alive by ensuring one of their voices is kept alive. One way of doing this is to add spacer rests to a voice in parallel with the real music. These need to be added to every Voice context which needs to be kept alive. If several voices are to be used sporadically it is safest to keep them all alive rather than attempting to rely on the exceptions mentioned above.

In the following example, both voice A and voice B are kept alive in this way for the duration of the piece:

```
musicA = \relative { d''4 d d d }
musicB = \relative { g'4 g g g }
keepVoicesAlive = {
  <<
    \new Voice = "A" { s1*5 } % keep voice 'A' alive for 5 bars
    \new Voice = "B" { s1*5 } % keep voice 'B' alive for 5 bars
  >>
}

music = {
  \context Voice = "A" {
    \voiceOneStyle \musicA
  }
  \context Voice = "B" {
    \voiceTwoStyle \musicB
  }
  \context Voice = "A" { \musicA }
  \context Voice = "B" { \musicB }
  \context Voice = "A" { \musicA }
}

\score {
  \new Staff <<
    \keepVoicesAlive
    \music
  >>
}
```




The following example shows how a sporadic melody line with lyrics might be written using this approach. In a real situation the melody and accompaniment would consist of several different sections, of course.

```

melody = \relative { a'4 a a a }
accompaniment = \relative { d'4 d d d }
words = \lyricmode { These words fol -- low the mel -- o -- dy }

\score {
  <<
    \new Staff = "music" {
      <<
        \new Voice = "melody" {
          \voiceOne s1*4 % keep voice 'melody' alive for 4 bars
        }
        {
          \new Voice = "accompaniment" {
            \voiceTwo \accompaniment
          }
          <<
            \context Voice = "melody" { \melody }
            \context Voice = "accompaniment" { \accompaniment }
          >>
          \context Voice = "accompaniment" { \accompaniment }
          <<
            \context Voice = "melody" { \melody }
            \context Voice = "accompaniment" { \accompaniment }
          >>
        }
      >>
    }
    \new Lyrics \with { alignAboveContext = "music" }
    \lyricsto "melody" { \words }
  >>
}

```



An alternative way, which may be better in many circumstances, is to keep the melody line alive by simply including spacer notes to line it up correctly with the accompaniment:

```


melody = \relative {
  s1 % skip a bar
  a'4 a a a
  s1 % skip a bar
  a4 a a a
}
accompaniment = \relative {
  d'4 d d d
  d4 d d d
  d4 d d d
  d4 d d d
}
words = \lyricmode { These words fol -- low the mel -- o -- dy }

```

```

\score {
  <<
    \new Staff = "music" {
      <<
        \new Voice = "melody" {
          \voiceOne \melody
        }
        \new Voice = "accompaniment" {
          \voiceTwo \accompaniment
        }
      >>
    }
    \new Lyrics \with { alignAboveContext = "music" }
    \lyricsto "melody" { \words }
  >>
}

```



```

\remove Clef_engraver
} \relative {
  f'2 g2
}
>>

```



In the second staff there are no time signature or clef symbols. This is a rather crude method of making objects disappear since it affects the entire staff. This method also influences the spacing, which may or may not be desirable. More sophisticated methods of blanking objects are shown in Section “Visibility and color of objects” in *Learning Manual*.

Known issues and warnings

The order in which the engravers are specified is the order in which they are called to carry out their processing. Usually the order in which the engravers are specified does not matter, but in a few special cases the order is important, for example where one engraver writes a property and another reads it, or where one engraver creates a grob and another must process it.

The following orderings are important:

- the `Bar_engraver` must normally be first,
- the `New_fingering_engraver` must come before the `Script_column_engraver`,
- the `Timing_translator` must come before the `Bar_number_engraver`.

See also

Installed Files: `ly/engraver-init.ly`.

33.5 Changing context default settings

Context and grob properties can be changed with `\set` and `\override` commands, see Chapter 35 [Modifying properties], page 758. These commands create music events, making the changes take effect at the point in time the music is being processed.

In contrast, this section explains how to change the *default* values of context and grob properties at the time the context is created. There are two ways of doing this. One modifies the default values in all contexts of a particular type, the other modifies the default values in just one particular instance of a context.

33.5.1 Changing all contexts of the same type

The default context settings which are to be used for typesetting in `Score`, `Staff`, `Voice`, and other contexts may be specified in a `\context` block within any `\layout` block.

Settings for MIDI output as opposed to typesetting has to be separately specified in `\midi` blocks (see Section 33.1.1 [Output definitions – blueprints for contexts], page 734).

The `\layout` block should be placed within the `\score` block to which it is to apply, after the music.

```

\layout {
  \context {
    \Voice

```

```

    [context settings for all Voice contexts]
  }
  \context {
    \Staff
    [context settings for all Staff contexts]
  }
}

```


The following types of settings may be specified:

- An `\override` command, but with the context name omitted.

```

\score {
  \relative {
    a'4~"Thicker stems" a a a
    a4 a a\ff a
  }
  \layout {
    \context {
      \Staff
      \override Stem.thickness = 4.0
    }
  }
}

```



- Directly setting a context property.

```

\score {
  \relative {
    a'4~"Smaller font" a a a
    a4 a a\ff a
  }
  \layout {
    \context {
      \Staff
      fontSize = -4
    }
  }
}

```




- A predefined command such as `\dynamicUp` or a music expression like `\accidentalStyle dodecaphonic`.


```

\score {
  \relative {
    a'4^"Dynamics above" a a a
    a4 a a\ff a
  }
  \layout {
    \context {
      \Voice
      \dynamicUp
    }
    \context {
      \Staff
      \accidentalStyle dodecaphonic
    }
  }
}

```



- A user-defined variable containing a `\with` block; for details of the `\with` block, see Section 33.5.2 [Changing just one specific context], page 747.

```

StaffDefaults = \with {
  fontSize = -4
}

\score {
  \new Staff {
    \relative {
      a'4^"Smaller font" a a a
      a4 a a a
    }
  }
  \layout {
    \context {
      \Staff
      \StaffDefaults
    }
  }
}

```



Property-setting commands can be placed in a `\layout` block without being enclosed in a `\context` block. Such settings are equivalent to including the same property-setting commands at the start of every context of the type specified. If no context is specified *every* bottom-level context is affected (see Section 33.1.5 [Bottom-level contexts – voices], page 736). The syntax of a property-setting command in a `\layout` block is the same as the same command written in the music stream.

```

\score {
  \new Staff {
    \relative {
      a'4^"Smaller font" a a a
      a4 a a a
    }
  }
  \layout {
    \accidentalStyle dodecaphonic
    \set fontSize = -4
    \override Voice.Stem.thickness = 4.0
  }
}

```



33.5.2 Changing just one specific context

The context properties of just one specific context instance can be changed in a `\with` block. All other context instances of the same type retain the default settings built into LilyPond and modified by any `\layout` block within scope. The `\with` block must be placed immediately after the `\new context-type` command:

```

\new Staff \with {
  [context settings for this context instance only]
} {
  ...
}

```

Alternatively, if the music is being entered using the short form of the input mode-specifying commands, e.g., `\chords` rather than `\chordmode`, the `\with` command must be placed immediately after the mode-specifying command:

```

\chords \with {
  [context settings for this (implicit) context instance only]
} {
  ...
}

```

as it is the implicit context created by these short forms which should be modified. The same consideration applies to the other input mode-specifying short forms (`\drums`, `\figures`), see Chapter 19 [Input modes], page 587.

Since context modifications specified in `\with` blocks are inside music, they affect *all* outputs (typesetting *and* MIDI) as opposed to changes within an output definition.

The following types of settings may be specified:

- An `\override` command, but with the context name omitted.

```


\score {
  \new Staff {
    \new Voice \with { \override Stem.thickness = 4.0 } {
      \relative {
        a'4^"Thick stems" a a a
        a4 a a a
      }
    }
  }
}

```

```

    }
  }
}

```




- Directly setting a context property.

```

\score {
  <<
    \new Staff {
      \relative {
        a'4^"Default font" a a a
        a4 a a a
      }
    }
    \new Staff \with { fontSize = -4 } {
      \relative {
        a'4^"Smaller font" a a a
        a4 a a a
      }
    }
  >>
}

```




- A predefined command such as `\dynamicUp`.

```

\score {
  <<
    \new Staff {
      \new Voice {
        \relative {
          a'4^"Dynamics below" a a a
          a4 a a\ff a
        }
      }
    }
    \new Staff \with { \accidentalStyle dodecaphonic } {
      \new Voice \with { \dynamicUp } {
        \relative {
          a'4^"Dynamics above" a a a
          a4 a a\ff a
        }
      }
    }
  >>
}

```



See also

Notation Reference: Chapter 19 [Input modes], page 587.

33.5.3 Order of precedence

The value of a property which applies at a particular time is determined as follows:

- if an `\override` or `\set` command in the input stream is in effect that value is used,
- otherwise the default value taken from a `\with` statement on the context initiation statement is used,
- otherwise the default value taken from the most recent appropriate `\context` block in the `\layout` or `\midi` blocks is used,
- otherwise LilyPond's built-in default is used.

See also

Learning Manual: Section “Modifying context properties” in *Learning Manual*.


Notation Reference: Section 33.1 [Contexts explained], page 734, Section 33.1.5 [Bottom-level contexts – voices], page 736, Section 35.2 [`\set` and `\unset`], page 758, Section 35.3 [`\override` and `\revert`], page 760, Section 27.1 [The `\layout` block], page 681.

33.6 Defining new contexts

Context definition overview

Specific contexts, like `Staff` and `Voice`, are made from simple building blocks. It is possible to create new types of contexts with different combinations of engraver plug-ins.

The next example shows how to build a different type of `Voice` context from scratch. It will be similar to `Voice`, but only prints centered slash note heads. It can be used to indicate improvisation in jazz pieces.



These settings are defined within a `\context` block inside a `\layout` block.

```
\layout {
  \context {
    ...
  }
}
```

In the following discussion, the example input shown should go in place of the ‘...’ in the previous fragment.

First it is necessary to define a name for the new context:

```
\name ImproVoice
```

Since it is similar to the Voice context, we want commands that work in (existing) Voice contexts to continue working. This is achieved by giving the new context an alias of Voice,

```
\alias Voice
```

The context will print notes and instructive texts, so we need to add the engravers that provide this functionality, plus the engraver that groups notes, stems, and rests occurring at the same musical moment into columns.

```
\consists Note_heads_engraver
\consists Text_engraver
\consists Rhythmic_column_engraver
```

The note heads should all be placed on the center line.

```
\consists Pitch_squash_engraver
squashedPosition = 0
```

The Pitch_squash_engraver modifies note heads (created by the Note_heads_engraver) and sets their vertical position to the value of squashedPosition, in this case 0, the center line.

The notes should look like a slash without a stem.

```
\override NoteHead.style = #'slash
\hide Stem
```

All these plug-ins have to communicate under the control of the context. The mechanisms with which contexts communicate are established by declaring the context `\type`. Within a `\layout` block, most contexts are of type `Engraver_group`. Some special contexts use other context types. Copying and modifying an existing context definition will also fill in the type. Since this example creates a definition from scratch, it needs to be specified explicitly.

```
\type Engraver_group
```

Put together, we get

```
\context {
  \name ImproVoice
  \type Engraver_group
  \consists Note_heads_engraver
  \consists Text_engraver
  \consists Rhythmic_column_engraver
  \consists Pitch_squash_engraver
  squashedPosition = 0
  \override NoteHead.style = #'slash
  \hide Stem
  \alias Voice
}
```

Contexts form hierarchies. We want to place the ImproVoice context within the Staff context, just like normal Voice contexts. Therefore, we modify the Staff definition with the `\accepts` command.

```
\context {
  \Staff
  \accepts ImproVoice
}
```

Often when reusing an existing context definition, the resulting context can be used anywhere where the original context would have been useful. Doing

```
\layout {
  ...
  \inherit-acceptability to from
}
```

arranges to have contexts of type *to* accepted by all contexts also accepting *from*. For example, using

```
\layout {
  ...
  \inherit-acceptability ImproVoice Voice
}
```

adds an `\accepts` for `ImproVoice` to both `Staff` and `RhythmicStaff` definitions.

The opposite of `\accepts` is `\denies`, which is sometimes needed when reusing existing context definitions.

Arranging the required pieces into a `\layout` block leaves us with

```
\layout {
  \context {
    \name ImproVoice
    ...
  }
  \inherit-acceptability ImproVoice Voice
}
```

Then the output at the start of this subsection can be entered as

```
\relative {
  a'4 d8 bes8
  \new ImproVoice {
    c4^"ad lib" c
    c4 c^"undress"
    c c_"while playing :)")
  }
  a1
}
```

See also

Internals Reference: Section “Contexts” in *Internals Reference*, Section “Engravers and Performers” in *Internals Reference*.

New contexts in MIDI

In MIDI output, the syntax for defining new context types is the same, except that the `\context` block should be placed inside a `\midi` block, and the `\type` should normally be `Performer_group` rather than `Engraver_group`. The term *engraver* refers to a context plug-in that creates visual output. A *performer*, on the other hand, is relevant in MIDI output only. When plug-ins have “translator” in their name rather than “engraver” or “performer”, they are relevant for both graphical and audio output. Thus, when adapting a context definition for the `\midi` block, you need to

- copy it in a `\midi` block,
- change `Engraver_group` to `Performer_group`,

- remove `\consists` for engravers (they are not relevant), and possibly add `\consists` for performers.

Please note that, in order to maintain consistent interpretation between graphical and MIDI output, it is recommended to copy any custom context definition in a `\midi` block. It should at the minimum include those commands that specify the context hierarchy, such as `\accepts`, `\defaultchild`, and `\inherit-acceptability`. Copying aliases is advised as well.

Thus, to complete the example above, the following can be added:

```
\midi {
  \context {
    \name ImproVoice
    \type Performer_group
    \alias Voice
    \consists Note_performer
    \consists Beam_performer
    \consists Dynamic_performer
    \consists Tie_performer
    \consists Slur_performer
  }
  \context {
    \Staff
    \accepts ImproVoice
  }
}
```

This makes the `ImproVoice` context also work in MIDI output.

Replacing the `Score` context

In order to write a context `MyScore` that acts as the topmost context, as the `Score` context usually does, use `\inherit-acceptability MyScore Score`. The following example defines a `ProportionalScore` context where proportional notation is enabled (see Section 30.6 [Proportional notation], page 720).

```
\layout {
  \context {
    \Score
    \name ProportionalScore
    \alias Score
    proportionalNotationDuration = #1/8
  }
  \inherit-acceptability ProportionalScore Score
}
```

```
music = { c'1 2 4 8 16 16 }
```

```
\new Score \music
\new ProportionalScore \music
```



Since the topmost context needs to contain a number of fundamental engravers, inheriting settings with `\Score` is easiest in most cases. If you nevertheless define a score-level context from scratch without inheriting the `Score` definition, the argument to `\type` should be `Score_engraver` (or `Score_performer` in `\midi`) rather than `Engraver_group`. Furthermore, giving the topmost context the `Score` alias is strongly recommended given that a number of engravers need to access the topmost context using its alias.

33.7 Context layout order

Contexts are normally positioned in a system from top to bottom in the order in which they are encountered in the input file. When contexts are nested, the outer context includes inner nested contexts as specified in the input file, provided the inner contexts are included in the outer context's “accepts” list. Nested contexts which are not included in the outer context's “accepts” list are repositioned below the outer context rather than nested within it.

The “accepts” list of a context can be changed with the `\accepts` or `\denies` commands. `\accepts` adds a context to the “accepts” list and `\denies` removes a context from the list.

For example, a `TabStaff` by default `\accepts` `TabVoice` contexts and `\denies` `Voice` contexts. If a `Voice` context is written within the `TabStaff`, it would be set on a separate staff.


```
\score {
  \new TabStaff <<
    \new TabVoice { c'1 }
    \new Voice { d'1 }
  >>
}
```



However, by using the `\accepts` command, `Voice` can be forced onto the `TabStaff` context.

```
\score {
  \new TabStaff <<
    \new TabVoice { c'1 }
    \new Voice { d'1 }
  >>

  \layout {
    \context {
      \TabStaff
      \accepts Voice
    }
  }
}
```



`\denies` is mainly used when a new context is being based on another, but the required nesting differs. For example, the `VaticanaStaff` context is based on the `Staff` context, but with the `VaticanaVoice` context substituted for the `Voice` context in the “accepts” list.

Note that a context is silently created implicitly if a command is encountered when there is no suitable context available to contain it.

Within a context definition, the type of subcontext to be implicitly created is specified using `\defaultchild`. A number of music events require a bottom-level context: when such an event is encountered, subcontexts are created recursively until reaching a context with no `\defaultchild` setting.

Implicit context creation can at times give rise to unexpected new staves or scores. Using `\new` to create contexts explicitly avoids those problems.

Sometimes a context is required to exist for just a brief period, a good example being the staff context for an *ossia*. This is usually achieved by introducing the context definition at the appropriate place in parallel with corresponding section of the main music. By default, the temporary context is placed below all the existing contexts. To reposition it above the context called “main”, it should be defined like this:

```
\new Staff \with { alignAboveContext = "main" }
```

A similar situation arises when positioning a temporary lyrics context within a multi-staff layout such as a `ChoirStaff`, for example, when adding a second verse to a repeated section. By default the temporary lyrics context is placed beneath the lower staves. By defining the temporary lyrics context with `alignBelowContext` it can be positioned correctly beneath the (named) lyrics context containing the first verse.

Examples showing this repositioning of temporary contexts can be found elsewhere – see Section “Nesting music expressions” in *Learning Manual*, Section 6.2 [Modifying single staves], page 249, and Section 9.2 [Techniques specific to lyrics], page 358.

See also

Learning Manual: Section “Nesting music expressions” in *Learning Manual*.

Notation Reference: Section 6.2 [Modifying single staves], page 249, Section 9.2 [Techniques specific to lyrics], page 358.

Application Usage: Section “An extra staff appears” in *Application Usage*.

Installed Files: `ly/engraver-init.ly`.

34 Explaining the Internals Reference

See also

Notation Reference: Section B.24 [Naming conventions], page 972.

34.1 Navigating the program reference

Suppose we want to move the fingering indication in the fragment below:

c' '-2



If you visit the documentation on fingering instructions (in Section 7.1.2 [Fingering instructions], page 281), you will notice:

See also

Internals Reference: Section “Fingering” in *Internals Reference*.

The programmer’s reference is available as an HTML document. It is highly recommended that you read it in HTML form, either online or by downloading the HTML documentation. This section will be much more difficult to understand if you are using the PDF manual.

Follow the link to Section “Fingering” in *Internals Reference*. At the top of the page, you will see

Fingering objects are created by the following engraver(s): Section “Fingering_engraver” in *Internals Reference* and Section “New_fingering_engraver” in *Internals Reference*.

By following related links inside the program reference, we can follow the flow of information within the program:

- Section “Fingering” in *Internals Reference*: Section “Fingering” in *Internals Reference* objects are created by the following engraver(s): Section “Fingering_engraver” in *Internals Reference*.
- Section “Fingering_engraver” in *Internals Reference*: Music types accepted: Section “fingering-event” in *Internals Reference*
- Section “fingering-event” in *Internals Reference*: Music event type fingering-event is in Music expressions named Section “FingeringEvent” in *Internals Reference*

This path goes against the flow of information in the program: it starts from the output, and ends at the input event. You could also start at an input event, and read with the flow of information, eventually ending up at the output object(s).

The program reference can also be browsed like a normal document. It contains chapters on Music definitions on Section “Translation” in *Internals Reference*, and the Section “Backend” in *Internals Reference*. Every chapter lists all the definitions used and all properties that may be tuned.

34.2 Layout interfaces

The HTML page that we found in the previous section describes the layout object called Section “Fingering” in *Internals Reference*. Such an object is a symbol within the score. It has properties that store numbers (like thicknesses and directions), but also pointers to related objects. A layout object is also called a *Grob*, which is short for Graphical Object. For more details about Grobs, see Section “grob-interface” in *Internals Reference*.

The page for Fingering lists the definitions for the Fingering object. For example, the page says

```
padding (dimension, in staff space):
0.5
```

which means that the number will be kept at a distance of at least 0.5 of the note head.

Each layout object may have several functions as a notational or typographical element. For example, the Fingering object has the following aspects

- Its size is independent of the horizontal spacing, unlike slurs or beams.
- It is a piece of text. Granted, it is usually a very short text.
- That piece of text is typeset with a font, unlike slurs or beams.
- Horizontally, the center of the symbol should be aligned to the center of the note head.
- Vertically, the symbol is placed next to the note and the staff.
- The vertical position is also coordinated with other superscript and subscript symbols.

Each of these aspects is captured in so-called *interfaces*, which are listed on the Section “Fingering” in *Internals Reference* page at the bottom

This object supports the following interfaces: Section “item-interface” in *Internals Reference*, Section “self-alignment-interface” in *Internals Reference*, Section “side-position-interface” in *Internals Reference*, Section “text-interface” in *Internals Reference*, Section “text-script-interface” in *Internals Reference*, Section “font-interface” in *Internals Reference*, Section “finger-interface” in *Internals Reference*, and Section “grob-interface” in *Internals Reference*.

Clicking any of the links will take you to the page of the respective object interface. Each interface has a number of properties. Some of them are not user-serviceable (‘Internal properties’), but others can be modified.

We have been talking of *the* Fingering object, but actually it does not amount to much. The initialization file (see Section “Other sources of information” in *Learning Manual*) `scm/define-grobs.scm` shows the soul of the ‘object’,

```
(Fingering
 . ((padding . 0.5)
    (avoid-slur . around)
    (slur-padding . 0.2)
    (staff-padding . 0.5)
    (self-alignment-X . 0)
    (self-alignment-Y . 0)
    (script-priority . 100)
    (stencil . ,ly:text-interface::print)
    (direction . ,ly:script-interface::calc-direction)
    (font-encoding . fetaText)
    (font-size . -5) ; don't overlap when next to heads.
    (meta . ((class . Item)
              (interfaces . (finger-interface
                             font-interface
                             text-script-interface
                             text-interface
                             side-position-interface
                             self-alignment-interface
                             item-interface))))))
```

As you can see, the Fingering object is nothing more than a bunch of variable settings, and the web page in the Internals Reference is directly generated from this definition.

34.3 Determining the grob property

Recall that we wanted to change the position of the **2** in

`c' '-2`



Since the **2** is vertically positioned next to its note, we have to meddle with the interface associated with this positioning. This is done using `side-position-interface`. The page for this interface says

`side-position-interface`

Position a victim object (this one) next to other objects (the support). The property `direction` signifies where to put the victim object relative to the support (left or right, up or down?)

Below this description, the variable `padding` is described as

`padding` (dimension, in staff space)

Add this much extra space between objects that are next to each other.

By increasing the value of `padding`, we can move the fingering away from the note head. The following command will insert “three staff spaces” worth of distance between the note and a fingering mark:

```
\once \override Voice.Fingering.padding = 3
```

Inserting the padding before the fingering object is created results in the following:

```
\once \override Voice.Fingering.padding = 3
```

`c' '-2`



In this case, the context for this tweak is `Voice`. See Section “Fingering-engraver” in *Internals Reference* plug-in, which says:

Fingering-engraver is part of contexts: . . . Section “Voice” in *Internals Reference*

35 Modifying properties

35.1 Overview of modifying properties

Within each context, there are two different kinds of properties: *context properties* and *grob properties*. Context properties apply to a context as a whole, whereas grob properties are used for initializing grobs engraved from within a context.

Context properties control the translation from music to notation. For example, `localAlterations` is used to determine whether to print accidentals; or `currentBarNumber` for determining which bar number to print. They can also change value over time while interpreting a piece of music; `currentBarNumber` is an obvious example of this.

The `\set` command (and its counterpart `\unset`) is used to alter values for context properties, whereas the `\override` command (and its counterpart `\revert`) is used to change values for grob properties.

35.2 `\set` and `\unset`

The `\set` command syntax is

```
\set context.property = value
```

where *value* must be preceded by the ‘#’ character if it is a Scheme object.

The counterpart command `\unset`’s syntax is

```
\unset context.property
```

This removes a previously set definition of the *property* from the *context*. Any properties that have been set in an enclosing *context* are not altered by an `\unset` in the same enclosed context.

For example, multi-measure rests are combined into a single bar (as explained in Section 6.3.4 [Compressing empty measures], page 273) if the context property `skipBars` is set to `#t`:

```
R1*2
\set Score.skipBars = ##t
R1*2
```




If the *context* argument is left out, then the property is set in the current ‘bottom’ context (typically `ChordNames`, `Voice`, `TabVoice`, or `Lyrics`).

```
<<
\set Score.autoBeaming = ##f
\relative {
  e' '8 e e e
  \set autoBeaming = ##t
  e8 e e e
} \\\
\relative {
  c' '8 c c c c8 c c c
}
>>
```



Note that the bottom context may not always contain an *engraver* that uses the *property* that you wish to change. For example, attempting to set the `skipBars` property of the default, bottom context has no effect because it is a property of the *Score*, not *Voice* context.


```
R1*2
\set skipBars = ##t
R1*2
```



Contexts are hierarchical; any change specified for an enclosing context (e.g., *Staff*) would also apply to all *Voices* in that current *Staff* context (assuming, of course, that the *Voice* context didn't have an override of its own).

All contexts inherit settings established in the top-most *Global* context (via `\grobdescriptions`), although a few of those defaults get overridden in their own context definitions.

```
<<
\set Score.autoBeaming = ##t
\relative {
  \unset autoBeaming
  e' '8 e e e
  \unset Score.autoBeaming
  e8 e e e
} \\\
\relative {
  c' '8 c c c c8 c c c
}
>>
```



Like `\set`, the *context* argument does not have to be specified for a bottom context, so the two statements

```
\set Voice.autoBeaming = ##t
\set autoBeaming = ##t
```

are equivalent if the current bottom context is *Voice*.

As described above, `\unset` restores the default value of a context property. However, it is sometimes useful to change a value for some time, then return to the previously used value. For this purpose, there are the two commands `\pushContextProperty` and `\popContextProperty`: the first one pushes the current value to a stack, while the second one pops a value from the stack and restores the property to it.

```
{
  c'
  \pushContextProperty Staff.fontSize
  \set Staff.fontSize = 3
  c'
  \pushContextProperty Staff.fontSize
  \set Staff.fontSize = 6
}
```

```

c'
\popContextProperty Staff.fontSize
c'
\popContextProperty Staff.fontSize
c'
}

```



35.3 \override and \revert

There is a special type of context property: the grob description. Grob descriptions start with a capital letter and exist as association lists only in all-grob-descriptions, but they get turned into more complex and efficient data structures supporting hierarchical manipulations when placed into contexts. See `scm/define-grobs.scm` for the settings of each grob.

The syntax for the `\override` command is

```
\override [context.]GrobName.property = value
```

For example, we can increase the thickness of a note stem by overriding the `thickness` property of the `Stem` object:

```

c''4 c''
\override Voice.Stem.thickness = 3.0
c''4 c''

```



If no context is specified in an `\override` command, the bottom context is used:

```

\override Staff.Stem.thickness = 3.0
<<
  \relative {
    e''4 e
    \override Stem.thickness = 0.5
    e4 e
  } \
  \relative {
    c''4 c c c
  }
>>

```



Some tweakable options are called ‘subproperties’ and reside inside properties. To tweak those, use commands in the form

```
\override Stem.details.beamed-lengths = #'(4 4 3)
```

or to modify the ends of spanners, use a form like these

```

\override TextSpanner.bound-details.left.text = "left text"
\override TextSpanner.bound-details.right.text = "right text"

```

The effects of `\override` can be undone by `\revert`; its syntax is

```
\revert [context.]GrobName.property
```

For example,

```
\relative {
  c' '4
  \override Voice.Stem.thickness = 3.0
  c4 c
  \revert Voice.Stem.thickness
  c4
}
```



The effects of `\override` and `\revert` apply to all grobs in the affected context from the current time forward:

```
<<
  \relative {
    e' '4
    \override Staff.Stem.thickness = 3.0
    e4 e e
  } \\\
  \relative {
    c' '4 c c
    \revert Staff.Stem.thickness
    c4
  }
>>
```



35.4 The `\once` command

`\once` is used in conjunction with the `\set` or `\override` command to affect only the current musical moment.

```
c' '4
\once \set fontSize = 4.7
c' '4
c' '4
```



See also

Internals Reference: Section “Backend” in *Internals Reference*.

35.5 `\set` versus `\override`

The `\set` and `\override` commands manipulate properties associated with contexts. The properties exist in a hierarchy of contexts where each context contains zero or more others below it. A property that is not set in a specific context shows the value from the nearest enclosing context where it is set.

The lifetime and value of a context property is dynamic and only available when music is being interpreted (i.e., ‘iterated’). At the time of the context’s creation, properties are initialized from its corresponding definitions (along with any other modifications) of that context. Any subsequent changes are achieved with any ‘property-setting’ commands that are within the music itself.

Graphical Object (or “grob”) definitions are a *special* category of context properties as their structure and use is different from that of normal context properties. Unlike normal context properties, grob definitions are subdivided into *grob properties*.

Also, in contrast to normal context properties, grob definitions have their own internal ‘book-keeping’ used to keep track of their own individual grob properties and any subproperties. This means that it is possible to define those parts within different contexts and yet still have the overall grob definition at the time of grob creation from all the pieces provided amongst the current and enclosing contexts.

A grob is usually created by an engraver at the time of interpreting a music expression, and receives its initial properties from the current grob definition of the engraver’s context. The engraver (or other ‘backend’ parts of LilyPond) can then change (or add to) the grob’s initial properties. However, this does not affect the context’s own grob definition.

What LilyPond calls *grob properties* in the context of ‘user-level’ tweaks are really the properties of a *context’s* own grob definition.

Grob definitions are accessed with a different set of commands and are manipulated using `\override` and `\revert`, and have a name starting with a capital letter (e.g., ‘NoteHead’); whereas normal context properties are manipulated using `\set` and `\unset` and are named starting with a lowercase letter.

The commands `\tweak` and `\overrideProperty` change grob properties by bypassing all context properties completely and, instead, catch grobs as they are being created, setting properties on them for a music event (`\tweak`) or, in the case of `\overrideProperty` for a specific override.

35.6 `\tweak` and `\single`

When multiple grobs occur at the same musical moment the `\override` command cannot be used to modify just one of them. In this case the `\tweak` command is used.

The `\tweak` command has the following syntax

```
\tweak [layout-object.]grob-property value
```

and applies to the music expression that immediately follows *value* in the music stream. Specifying *layout-object* is necessary for disambiguation if the music expression causes the indirect creation of grobs with different types (for example, NoteHead causes Stem).

For an introduction to the syntax and uses of the `tweak` command see Section “Tweaking methods” in *Learning Manual*.

Items that may appear more than once at the same musical moment include, but are not limited to, the following:

- note heads of notes inside a chord
- articulation signs on a single note
- ties between notes in a chord

- triplet brackets starting at the same time

In this example, the color of one note head and the type of another note head are modified within a single chord:

```
< c''
  \tweak color #red
  d''
  g''
  \tweak duration-log 1
  a''
> 4
```



`\tweak` can also be used to modify slurs:

```
\relative { c'-\tweak thickness 5 ( d e f ) }
```



Tweaking a whole chord tweaks all the contained notes:

```
{ \tweak color #red <c'' e''>4 }
```



As mentioned above, the simple `\tweak` command syntax form cannot be used to modify any object that is not directly created from the input. In particular, it will not affect stems, automatic beams, or accidentals, since these are generated later by `NoteHead` layout objects rather than by music elements in the input stream.

Such indirectly created layout objects can be tweaked using the form of the `\tweak` command in which the grob name is specified explicitly:

```
\tweak Stem.color #(universal-color 'orange)
\tweak Beam.color #(universal-color 'skyblue) c''8 e''
<c'' e'' \tweak Accidental.font-size -3 ges''>4
```



`\tweak` cannot be used to modify clefs or time signatures, since these become separated from any preceding `\tweak` command in the input stream by the automatic insertion of extra elements required to specify the context.

Multiple `\tweak` commands placed before a music expression all affect the grob(s) created at this musical moment.

```

c'
-\tweak springs-and-rods #ly:spanner::set-spacing-rods
-\tweak minimum-length 15
-\tweak style #'dashed-line
-\tweak dash-fraction 0.2
-\tweak thickness 3
-\tweak color #red
\glissando
f''

```



The music stream which is generated from a section of an input file, including any automatically inserted elements, may be examined, see Section “Displaying music expressions” in *Extending*. This may be helpful in determining what may be modified by a `\tweak` command, or in determining how to adjust the input to make a `\tweak` apply.

The `\single` command takes one or more `\override` commands (which are intended to apply at a given musical moment or beyond) and converts them effectively into a *single* ‘tweak’ that now applies to the specific grobs created.

The file `ly/property-init.ly` contains many definitions of multiple `\override` commands and so can be used in conjunction with the `\single` command. For example, the function `\easyHeadsOn` can be used with `\single` to affect just one note head in a chord;

```

\relative c' {
  <\single \easyHeadsOn c' g'>2
}

```



See also

Learning Manual: Section “Tweaking methods” in *Learning Manual*.

Extending LilyPond: Section “Displaying music expressions” in *Extending*.

Known issues and warnings

The `\tweak` command cannot be used to modify the control points of just one of several ties in a chord, other than the first one encountered in the input file.

35.7 The `\offset` command

While it is possible to set grob properties to new values with the `\override`, `\tweak`, and `\overrideProperty` commands, it is often more convenient to modify such properties relative to a default value. The `\offset` command is available for this purpose.

The syntax for `\offset` is

```
[-]\offset property offsets item
```

The command works by adding the contents of *offsets* to the default setting of the property *property* of the grob indicated by *item*.

Depending on the formulation of the command, `\offset` may act as either a `\tweak` or `\override`. The variations in usage are discussed after consideration is given to grob properties that may be used with `\offset`.

Properties which may be offset

Many, but not all, grob properties may be offset. If *property* cannot be offset, the object will remain unchanged and a warning will be issued. In such cases, `\override` or `\tweak` should be used to modify the object instead.

One can work by trial and error and let the warnings be the guide to what may or may not be offset. A more systematic approach is possible, however.

The following criteria determine whether a property can be modified with `\offset`:

- The property has a ‘default setting’ in the grob’s description. Such properties are listed for each grob in Section “All layout objects” in *Internals Reference*. (They are also found in `scm/define-grobs.scm`.)
- The property takes a numerical value. Numerical values include number, list of numbers, number-pair, and number-pair-list. The pages at Section “All layout objects” in *Internals Reference* list the type of data characteristic to each property. It is immaterial whether the default setting is a function.
- The property cannot be a ‘subproperty’ – a property residing within another property.
- Properties set to infinite values cannot be offset. There is no sensible way to offset positive and negative infinity.

The following examples consider several grob properties against the criteria outlined above.

- Properties that may be offset

`Hairpin.height`

This property is not a subproperty, and it is listed at Section “Hairpin” in *Internals Reference*. For a value, it takes ‘dimension, in staff space’ set to 0.6666 – clearly a non-infinite number.

`Arpeggio.positions`

The page Section “Arpeggio” in *Internals Reference* lists a `positions` property which accepts a ‘pair of numbers’. It defaults to `ly:arpeggio::positions` – a callback which will be evaluated during the typesetting phase to yield a pair of numbers for any given Arpeggio object.

- Properties that may not be offset

`Hairpin.color`

There is no listing for `color` at Section “Hairpin” in *Internals Reference*.

`Hairpin.circled-tip`

The listing for `Hairpin.circled-tip` at Section “Hairpin” in *Internals Reference* shows that it takes a boolean value. Booleans are non-numerical.

`Stem.details.lengths`

Though listed at Section “Stem” in *Internals Reference* and defaulting to a list of numbers, this is a ‘subproperty’. There is currently no support for ‘nested properties’.

`\offset` as an override

If *item* is a grob name like `Arpeggio` or `Staff.OttavaBracket`, the result is an `\override` of the specified grob type.

```
\offset property offsets [context.]GrobName
```


Note that the leading hyphen is *never* used with the ‘override’ form, just as it is never used with the `\override` command itself.

The following example uses the ‘override’ form to lengthen the default arpeggios shown in the first measure to cover the extent of the chords more fully. The arpeggios are stretched by a half

staff space to top and bottom. Also shown is the same operation done on the first chord with an ordinary override of the `positions` property. This method is not at all expressive of the task of ‘stretching by a half staff space’, as the endpoints must be specified with absolute rather than relative coordinates. Furthermore, individual overrides would be needed for the other chords, as they vary in size and position.

```
arpeggioMusic = {
  <c' e' g'>\arpeggio <a' c' e'>\arpeggio
  <d' f' a' c'>\arpeggio <c' e' g' b' d' f' a'>\arpeggio
}


{
  \arpeggioMusic
  \bar "||"
  \offset positions #'(-0.5 . 0.5) Arpeggio
  \arpeggioMusic
  \bar "||"
  \once \override Arpeggio.positions = #'(-3.5 . -0.5)
  <c' e' g'>1\arpeggio
  \bar "||"
}
```



In its ‘override’ usage, `\offset` may be prefaced with `\once` or `\temporary` and reverted using `\revert` with *property* (see Section “Intermediate substitution functions” in *Extending*). This follows from the fact that `\offset` actually creates an `\override` of *property*.

```
music = { c'8< d' e' f'\! }

{
  \music
  \offset height 1 Hairpin
  \music
  \music
  \revert Hairpin.height
  \music
  \bar "||"
  \once \offset height 1 Hairpin
  \music \music
  \bar "||"
  \override Hairpin.height = 0.2
  \music
  \temporary \offset height 2 Hairpin
  \music
  \music
  \revert Hairpin.height
  \music
  \bar "||"
}
```



Also like `\override`, the ‘override’ form of `\offset` may be used with `\undo` and `\single`.

```
longStem = \offset length 6 Stem
```

```
{
  \longStem c'4 c''' c' c''
  \bar "||"
  \undo \longStem c'4 c''' c' c''
  \bar "||"
  \single \longStem c'4 c''' c' c''
  \bar "||"
}
```



`\offset` as a tweak

If *item* is a music expression such as `(` or `\arpeggio`, the result is the same music expression with a tweak applied.

```
[-]\offset [GrobName.]property offsets music-expression
```

The syntax of `\offset` in its ‘tweak’ form is analogous to the `\tweak` command itself, both in ordering and in the presence or absence of the leading hyphen.

The following example uses the ‘tweak’ form to adjust the vertical position of the `BreathingSign` object. Compare this with the ordinary `\tweak` command also demonstrated. The syntax is equivalent; however, the output of `\tweak` is less intuitive, since `BreathingSign.Y-offset` is calculated from the middle staff line. It is not necessary to know how `Y-offset` is calculated when using `\offset`.

```
{
  c'4
  \breathe
  c'4
  \offset Y-offset 2 \breathe
  c'2
  \tweak Y-offset 3 \breathe
}
```



In the previous example, the tweaked objects were created directly from the user input: the `\breathe` command was an explicit instruction to return a `BreathingSign` object. Since the focus of the command was unambiguous, there was no need to specify the object's name. When an object is *indirectly* created, however, it is necessary to include the grob's name. This is the same as for the `\tweak` command.

In the following example, the `Beam` object is lowered two staff spaces by applying `\offset` to the `positions` property.

The first application of `\offset` requires that the grob's name be included, because nothing in the input explicitly creates the beam. In the second application, the beam is created manually with the music expression `[]`; therefore, the grob's name is not needed. (Also illustrated is a shorthand: a single number will be applied to both members of a number-pair.)

```
{
  c''8 g'' e'' d''
  \offset Beam.positions #'(-2 . -2)
  c''8 g'' e'' d''
  c''8 g'' e'' d''
  c''8-\offset positions -2 [ g'' e'' d'']
}
```




`\offset` with broken spanners

Independently modifying segments of a spanner extending over a line break or breaks is also possible. In this case, `offsets` takes a list of values of the property's required data type.

The `\offset` command used in this manner is similar to the `\alterBroken` command. (See Section 36.4.1 [Modifying broken spanners], page 774.) In contrast with `\alterBroken`, however, the values given to `\offset` are relative, not absolute.

The following example displaces the 'broken' `OttavaBracket` object through its `staff-padding` property. Since the property takes a number, `offsets` is provided with a list of numbers to account for the two segments created by the line break. The bracket piece on the first line is effectively untouched since 0 is added to its default value of `staff-padding`. The segment on the second line is raised three staff spaces from its default height. The default height happens to be 2, though it is not necessary to know this to achieve the desired positioning.


```
{
  \offset staff-padding #'(0 3) Staff.OttavaBracket
  \ottava 1
  c''2 c'''
  \break
  c''2 c'''
}
```





The following example mimics the effect of the `\shape` command by offsetting the control-points property of the Slur object. Here, *offsets* is a list of number-pair-lists, one for each slur segment. This example achieves a result identical to the corresponding illustration at Section 36.11 [Modifying shapes], page 799.

```
{
  c'4-\offset control-points #'(
    ((0 . 0) (0 . 0) (0 . 0) (0 . 1))
    ((0.5 . 1.5) (1 . 0) (0 . 0) (0 . -1.5))
  ) ( f'4 g' c' )
  \break
  d'4 c' f' c'
}
```



See Section “Adjusting slur positions vertically” in *Snippets* for an `\offsetPositions` Scheme function that eases the vertical shifting of slurs.

35.8 Modifying alists

Some user-configurable properties are internally represented as *alists* (association lists), which store pairs of *keys* and *values*. The structure of an alist is:

```
'((key1 . value1)
  (key2 . value2)
  (key3 . value3)
  ...)
```

If an alist is a grob property or `\paper` variable, its keys can be modified individually without affecting other keys.

For example, to reduce the space between adjacent staves in a staff group, use the `staff-staff-spacing` property of the `StaffGrouper` grob. The property is an alist with four keys: `basic-distance`, `minimum-distance`, `padding`, and `stretchability`. The standard settings for this property are listed in the “Backend” section of the Internals Reference (see Section “StaffGrouper” in *Internals Reference*):

```
'((basic-distance . 9)
  (minimum-distance . 7)
  (padding . 1)
  (stretchability . 5))
```

One way to bring the staves closer together is by reducing the value of the `basic-distance` key (9) to match the value of `minimum-distance` (7). To modify a single key individually, use a *nested declaration*:


```

% default space between staves
\new PianoStaff <<
  \new Staff { \clef treble c''1 }
  \new Staff { \clef bass   c1   }
>>

% reduced space between staves
\new PianoStaff \with {
  % this is the nested declaration
  \override StaffGrouper.staff-staff-spacing.basic-distance = 7
} <<
  \new Staff { \clef treble c''1 }
  \new Staff { \clef bass   c1   }
>>

```




Using a nested declaration will update the specified key (such as `basic-distance` in the above example) without altering any other keys already set for the same property.

Now suppose we want the staves to be as close as possible without overlapping. The simplest way to do this is to set all four alist keys to zero. However, it is not necessary to enter four nested declarations, one for each key. Instead, the property can be completely redefined with one declaration, as an alist:

```

\new PianoStaff \with {
  \override StaffGrouper.staff-staff-spacing =
    #'((basic-distance . 0)
      (minimum-distance . 0)
      (padding . 0)
      (stretchability . 0))
} <<
  \new Staff { \clef treble c''1 }
  \new Staff { \clef bass   c1   }
>>

```



Note that any keys not explicitly listed in the alist definition will be reset to their *default-when-unset* values. In the case of `staff-staff-spacing`, any unset key values would be reset

to zero (except `stretchability`, which takes the value of `basic-distance` when unset). Thus the following two declarations are equivalent:

```
\override StaffGrouper.staff-staff-spacing =  
  #'((basic-distance . 7))
```

```
\override StaffGrouper.staff-staff-spacing =  
  #'((basic-distance . 7)  
    (minimum-distance . 0)  
    (padding . 0)  
    (stretchability . 7))
```

One (possibly unintended) consequence of this is the removal of any standard settings that are set in an initialization file and loaded each time an input file is compiled. In the above example, the standard settings for padding and minimum-distance (defined in `scm/define-grobs.scm`) are reset to their default-when-unset values (zero for both keys). Defining a property or variable as an alist (of any size) will always reset all unset key values to their default-when-unset values. Unless this is the intended result, it is safer to update key values individually with a nested declaration.

Note: Nested declarations will not work for context property alists (such as `beamExceptions`, `keyAlterations`, `timeSignatureSettings`, etc.). These properties can only be modified by completely redefining them as alists.

36 Useful concepts and properties

This section discusses various common layout issues and the tweaking methods related to them.

See also

Learning Manual: Section “Tweaking output” in *Learning Manual*, Section “Other sources of information” in *Learning Manual*.

Notation Reference: Chapter 34 [Explaining the Internals Reference], page 755, Chapter 35 [Modifying properties], page 758.

Extending LilyPond: Section “Interfaces for programmers” in *Extending*.

Installed Files: scm/define-grobs.scm.

Snippets: Section “Tweaks and overrides” in *Snippets*.

Internals Reference: Section “All layout objects” in *Internals Reference*.

36.1 Direction and placement

In typesetting music the direction and placement of many items is a matter of choice. For example, the stems of notes can be directed up or down; lyrics, dynamics, and other expressive marks may be placed above or below the staff; text may be aligned left, right or center; etc. Most of these choices may be left to be determined automatically by LilyPond, but in some cases it may be desirable to force a particular direction or placement.

36.1.1 Articulation direction indicators

By default some directions are always up or always down (e.g., dynamics or fermata), while other things can alternate between up or down based on the stem direction (like slurs or accents).

The default action may be overridden by prefixing the articulation by a *direction indicator*. Three direction indicators are available: `^` (meaning “up”), `_` (meaning “down”) and `-` (meaning “use default direction”). The direction indicator can usually be omitted, in which case `-` is assumed, but a direction indicator is **always** required before

- `\tweak` commands
- `\markup` commands
- `\tag` commands
- string markups, e.g., `-"string"`
- fingering instructions, e.g., `-1`
- articulation shortcuts, e.g., `-. , -> , --`

Direction indicators affect only the next note:

```
\relative {
  c' '2( c)
  c2_( c)
  c2( c)
  c2^( c)
}
```



36.1.2 The direction property

The position or direction of many layout objects is controlled by the direction property.

The value of the direction property may be set to 1, meaning “up” or “above”, or to -1, meaning “down” or “below”. The symbols UP and DOWN may be used instead of 1 and -1 respectively. The default direction may be specified by setting direction to 0 or CENTER. Alternatively, in many cases predefined commands exist to specify the direction. These are of the form

```
\xxxUp, \xxxDown or \xxxNeutral
```

where \xxxNeutral means “use the default” direction. See Section “Within-staff objects” in *Learning Manual*.

In a few cases, arpeggio for example, the value of the direction property can specify whether the object is to be placed to the right or left of the parent. In this case -1 or LEFT means “to the left” and 1 or RIGHT means “to the right”. 0 or CENTER means “use the default” direction.

These indications affect all notes until they are canceled.

```
\relative {
  c' '2( c)
  \slurDown
  c2( c)
  c2( c)
  \slurNeutral
  c2( c)
}
```



In polyphonic music, it is generally better to specify an explicit voice than change an object’s direction. For more information, see Section 5.2 [Multiple voices], page 221.

See also

Learning Manual: Section “Within-staff objects” in *Learning Manual*.

Notation Reference: Section 5.2 [Multiple voices], page 221.

36.2 Distances and measurements

Distances in LilyPond are of two types: absolute and scaled.

Absolute distances are used for specifying margins, indents, and other page layout details, and are by default specified in millimeters. In general, distance units may be specified by appending \mm (millimeter), \cm (centimeter), \in (inches), \pt (points), or \bp (big points).

	mm	cm	in	pt	bp
mm	1	0.1	0.0394	2.8453	2.8346
cm	10	1	0.3937	28.4528	28.3465
in	25.4	2.54	1	72.27	72
pt	0.3515	0.0351	0.0138	1	0.996
bp	0.3538	0.0354	0.0139	1.0038	1

Page layout distances can also be specified in scalable units (see the following paragraph) by appending \staff-space to the quantity. See Chapter 26 [Page layout], page 669, for a detailed description of LilyPond’s page layout.

Scaled distances are always specified in units of the staff space or, rarely, the half staff space. The staff space is the distance between two adjacent staff lines. The default value can be changed globally by setting the global staff size, or it can be overridden locally by changing the staff-space property of `StaffSymbol`. Scaled distances automatically scale with any change to either the global staff size or the staff-space property of `StaffSymbol`, but fonts scale automatically only with changes to the global staff size. The global staff size thus enables the overall size of a rendered score to be easily varied. For the methods of setting the global staff size see Section 27.2 [Setting the staff size], page 683.

If just a section of a score needs to be rendered to a different scale, for example an ossia section or a footnote, the global staff size cannot simply be changed as this would affect the entire score. In such cases the change in size is made by overriding both the staff-space property of `StaffSymbol` and the size of the fonts. A Scheme function, `magstep`, is available to convert from a font size change to the equivalent change in staff-space. For an explanation and an example of its use, see Section “Length and thickness of objects” in *Learning Manual*.

See also

Learning Manual: Section “Length and thickness of objects” in *Learning Manual*.

Notation Reference: Chapter 26 [Page layout], page 669, Section 27.2 [Setting the staff size], page 683.

36.3 Dimensions

The dimensions of a graphical object specify the positions of the left and right edges and the bottom and top edges of the objects’ bounding box as distances from the objects’ reference point in units of staff spaces. These positions are usually coded as two Scheme pairs. For example, the text markup command `\with-dimensions` takes three arguments, the first two of which are a Scheme pair giving the left and right edge positions and a Scheme pair giving the bottom and top edge positions:

```
\with-dimensions #'(-5 . 10) #'(-3 . 15) arg
```

This specifies a bounding box for `arg` with its left edge at -5, its right edge at 10, its bottom edge at -3 and its top edge at 15, all measured from the objects’ reference point in units of staff spaces.

For more information on how such boxes are defined, including the formal definition of horizontal and vertical space as set up by the `\hspace` and `\vspace` markup commands, see Section “LilyPond’s box model” in *Extending*.

See also

Notation Reference: Section A.1.8 [Other markup commands], page 872, (documentation for commands similar to `\with-dimensions`, such as `\with-dimension` or `\with-dimension-from`), Section 36.2 [Distances and measurements], page 773.

36.4 Spanners

Many objects of musical notation extend over several notes or even several bars. Examples are slurs, beams, tuplet brackets, volta repeat brackets, crescendi, trills, and glissandi. Such objects are collectively called “spanners”, and have special properties to control their appearance and behavior, as well as special tweaking methods related to the fact that they can be broken across systems.

36.4.1 Modifying broken spanners

When a spanner crosses a line break or breaks, each piece inherits the attributes of the original spanner. Thus, ordinary tweaking of a broken spanner applies the same modifications to each

of its segments. In the example below, overriding thickness affects the slur on either side of the line break.

```
\relative c'' {
  r2
  \once\override Slur.thickness = 10
  c8( d e f
  \break
  g8 f e d) r2
}
```



Independently modifying the appearance of individual pieces of a broken spanner is possible with the `\alterBroken` command. This command can produce either an `\override` or a `\tweak` of a spanner property.

The syntax for `\alterBroken` is

```
[ - ] \alterBroken property values target
```

The argument *values* is a list of values, one for each broken piece. If *target* is a grob name like `Slur` or `Staff.PianoPedalBracket`, the result is an `\override` of the specified grob type. If *target* is a music expression such as `'(` or `'[` the result is the same music expression with an appropriate tweak applied.

The leading hyphen must be used with the `\tweak` form. Do not add it when `\alterBroken` is used as an `\override`.

In its `\override` usage, `\alterBroken` may be prefaced by `\once` or `\temporary` and reverted by using `\revert` with *property* (see Section “Intermediate substitution functions” in *Extending*).

The following code applies an independent `\override` to each of the slur segments in the previous example:

```
\relative c'' {
  r2
  \alterBroken thickness #'(10 1) Slur
  c8( d e f
  \break
  g8 f e d) r2
}
```



The `\alterBroken` command may be used with any spanner object, including `Tie`, `PhrasingSlur`, `Beam` and `TextSpanner`. For example, an editor preparing a scholarly edition

may wish to indicate the absence of part of a phrasing slur in a source by dashing only the segment which has been added. The following example illustrates how this can be done, in this case using the `\tweak` form of the command:

```
% The empty list is conveniently used below, because it is the
% default setting of dash-definition, resulting in a solid curve.
\relative {
  c''2-\alterBroken dash-definition #'((() ((0 1.0 0.4 0.75))) \e
  \break
  g2 e\
}
```



It is important to understand that `\alterBroken` sets each piece of a broken spanner to the corresponding value in *values*. When there are fewer values than pieces, any additional piece will be assigned the empty list. This may lead to undesired results if the layout property is not set to the empty list by default. In such cases, each segment should be assigned an appropriate value.

Known issues and warnings

Line breaks may occur in different places following changes in layout. Settings chosen for `\alterBroken` may be unsuitable for a spanner that is no longer broken or is split into more segments than before. Explicit use of `\break` can guard against this situation.

The `\alterBroken` command is ineffective for spanner properties accessed before line breaking such as *direction*.

See also

Extending LilyPond: Section “Difficult tweaks” in *Extending*.

36.4.2 Setting minimum lengths for spanners

The spanner-interface interface provides three properties that apply to several spanners.

The minimum-length property

The minimum length of the spanner is specified by the *minimum-length* property. Increasing this usually has the necessary effect of increasing the spacing of the notes between the two end points. However, this override has no effect on many spanners, as their length is determined by other considerations. A few examples where it is effective are shown below.


```
a' ~ a'
a'
% increase the length of the tie
-\tweak minimum-length 5
~ a'
```



```

\relative \compressMMRests {
  a'1
  R1*23
  % increase the length of the rest bar
  \once \override MultiMeasureRest.minimum-length = 20
  R1*23
  a1
}

```



```

\relative {
  a' \< a a a \!
  % increase the length of the hairpin
  \override Hairpin.minimum-length = 20
  a \< a a a \!
}

```



This override can also be used to increase the length of slurs and phrasing slurs:

```

\relative {
  a' ( g)
  a
  -\tweak minimum-length 5
  ( g)

  a\ ( g\ )
  a
  -\tweak minimum-length 5
  \ ( g\ )
}

```



For some layout objects, the `minimum-length` property becomes effective only if the `set-spacing-rods` procedure is called explicitly. To do this, the `springs-and-rods` property should be set to `ly:spanner::set-spacing-rods`. For example, the minimum length of a glissando has no effect unless the `springs-and-rods` property is set:

```

% default
e' \glissando c''

% not effective alone
\once \override Glissando.minimum-length = 20
e' \glissando c''

% effective only when both overrides are present

```



```
\once \override Glissando.minimum-length = 20
\once \override Glissando.springs-and-rods =
      #ly:spanner::set-spacing-rods
e' \glissando c''
```



The same is true of the Beam object:

```
% not effective alone
\once \override Beam.minimum-length = 20
e'8 e' e' e'

% effective only when both overrides are present
\once \override Beam.minimum-length = 20
\once \override Beam.springs-and-rods =
      #ly:spanner::set-spacing-rods
e'8 e' e' e'
```



The minimum-length-after-break property

The property `minimum-length-after-break` can be used to stretch broken spanners starting after a line break. As for the `minimum-length` property, it is often needed to set the `springs-and-rods` property to `ly:spanner::set-spacing-rods`.

```
{
  \once \override Tie.minimum-length-after-break = 20
  a1~
  \break
  a1

  \once \override Slur.minimum-length-after-break = 20
  a1(
  \break
  d'1)


  \once \override TextSpanner.springs-and-rods =
    #ly:spanner::set-spacing-rods
  \once \override TextSpanner.minimum-length-after-break = 20
  a1\startTextSpan
  \break
  a1\stopTextSpan

  \once \override Hairpin.after-line-breaking = ##t
  \once \override Hairpin.to-barline = ##f
  \once \override Hairpin.minimum-length-after-break = 20
  a1\<
  \break
  a1\!
```

```

\once \override Glissando.springs-and-rods =
  #ly:spanner::set-spacing-rods
% for completeness; not necessary for manual breaks
\once \override Glissando.breakable = ##t
\once \override Glissando.after-line-breaking = ##t
\once \override Glissando.minimum-length-after-break = 20
a1\glissando
\break
d'1
}

```



36.4.3 Controlling spanner end points


The `to-barline` property of the `spanner-interface`, usually defaulting to `#t`, causes hairpins and other spanners that are terminated on the first note of a measure to end instead on the immediately preceding bar line. If set to `#f`, the spanner extends beyond the bar line and end on the note itself:

```

\relative {
  a' \< a a a a \! a a a \break
  \override Hairpin.to-barline = ##f
  a \< a a a a \! a a a
}

```





This property is not effective for all spanners. For example, setting it to `#t` has no effect on slurs or phrasing slurs or on other spanners for which terminating on the bar line would not be meaningful.

36.5 Line styles

The Section “line-interface” in *Internals Reference* groups all objects printing lines. All objects supporting these interfaces can be printed using different line styles. Here is an example showing the available values.

```
\relative {
  d'2 \glissando d'2
  \once \override Glissando.style = #'dashed-line
  d,2 \glissando d'2
  \override Glissando.style = #'dotted-line
  d,2 \glissando d'2
  \override Glissando.style = #'zigzag
  d,2 \glissando d'2
  \override Glissando.style = #'trill
  d,2 \glissando d'2
}
```



Some objects may support specific additional styles.

36.6 Line spanners

Some performance indications, e.g., *rallentando* and *accelerando* and trills are written as text and are extended over many measures with lines, sometimes dotted or wavy.

The locations of the two end points of the spanner are computed on the fly, but it is possible to override their Y-coordinates. The properties that need to be specified are nested two levels down within the property hierarchy, but the syntax of the `\override` command is quite simple:

```
e'2 \glissando b'
\once \override Glissando.bound-details.left.Y = 3
\once \override Glissando.bound-details.right.Y = -2
e'2 \glissando b'
```



The units for the Y property are *staff spaces*, with the center line of the staff being the zero point. For the glissando, this is the value for Y at the X-coordinate corresponding to the center point of each note head, if the line is imagined to be extended to there.

If Y is not set, the value is computed from the vertical position of the corresponding attachment point of the spanner.

In case of a line break, the values for the end points are specified by the `left-broken` and `right-broken` sublists of `bound-details`. For example:

```
\override Glissando.bound-details.right-broken.Y = -3
c''1 \glissando \break
f''1
```



A number of further properties of the `left` and `right` sublists of the `bound-details` property may be modified in the same way as `Y`:

Y This sets the Y-coordinate of the end point, measured in staff spaces from the staff center line. By default, it is the center of the bound object, so a glissando points to the vertical center of the note head.

For horizontal spanners, such as text spanners and trill spanners, it is hard-coded to 0.

attach-dir

This determines where the line starts and ends in the X-direction, relative to the bound object. So, a value of `-1` (or `LEFT`) makes the line start/end at the left side of the note head it is attached to.

X This is the absolute X-coordinate of the end point. It is usually computed on the fly, and overriding it has little useful effect.

stencil Line spanners may have symbols at the beginning or end, which is contained in this subproperty. This is for internal use; it is recommended that `text` be used instead.

text

This is a markup that is evaluated to yield the stencil. It is used to put *cresc.*, *tr*, and other text on horizontal spanners.

```
\override TextSpanner.bound-details.left.text
= \markup { \small \bold Slower }
\relative { c''2\startTextSpan b c a\stopTextSpan }
```



stencil-align-dir-y

stencil-offset

Without setting one of these, the stencil is simply put at the end point, centered on the line, as defined by the `X` and `Y` subproperties. Setting either `stencil-align-dir-y` or `stencil-offset` will move the symbol at the edge vertically relative to the end point of the line:

```

\override TextSpanner.bound-details
  .left.stencil-align-dir-y = -2
\override TextSpanner.bound-details
  .right.stencil-align-dir-y = #UP

\override TextSpanner.bound-details.left.text = "ggg"
\override TextSpanner.bound-details.right.text = "hhh"

\relative { c'4^\startTextSpan c c c \stopTextSpan }

```



Note that negative values move the text *up*, contrary to the effect that might be expected, as a value of -1 or DOWN means align the *bottom* edge of the text with the spanner line. A value of 1 or UP aligns the top edge of the text with the spanner line.

- arrow Setting this subproperty to `#t` produces an arrowhead at the end points of the line.
- padding This subproperty controls the space between the specified end point of the line and the actual end. Without padding, a glissando would start and end in the center of each note head.

The music function `\endSpanners` prematurely terminates all spanners in its argument, obeying the `to-barline` property if set.

```

\relative c' {
  \endSpanners c1 \> c
  \endSpanners { r4 c2.\< c1\startTextSpan } c1 c
}

```



When using `\endSpanners` it is not necessary to close `\startTextSpan` with `\stopTextSpan`, nor is it necessary to close hairpins with `\!`.

See also

Internals Reference: Section “TextSpanner” in *Internals Reference*, Section “Glissando” in *Internals Reference*, Section “VoiceFollower” in *Internals Reference*, Section “TrillSpanner” in *Internals Reference*, Section “line-spanner-interface” in *Internals Reference*.

36.7 Visibility of objects

There are four main ways in which the visibility of layout objects can be controlled: their stencil can be removed, they can be made transparent, they can be colored white, or their break-visibility property can be overridden. The first three apply to all layout objects; the last to just a few – the *breakable* objects. The Learning Manual introduces these four techniques, see Section “Visibility and color of objects” in *Learning Manual*.

There are also a few other techniques which are specific to certain layout objects. These are covered under Special considerations.

36.7.1 Removing the stencil

Every layout object has a stencil property. By default this is set to the specific function which draws that object. If this property is overridden to `#f` no function will be called and the object will not be drawn. The default action can be recovered with `\revert`.

```
a1 a
\override Score.BarLine.stencil = ##f
a a
\revert Score.BarLine.stencil
a a a
```



This rather common operation has a shortcut `\omit`:

```
a1 a
\omit Score.BarLine
a a
\undo \omit Score.BarLine
a a a
```



36.7.2 Making objects transparent

Every layout object has a transparent property which by default is set to `#f`. If set to `#t` the object still occupies space but is made invisible.

```
a'4 a'
\once \override NoteHead.transparent = ##t
a' a'
```



This rather common operation has a shortcut `\hide`:

```
a'4 a'
\once \hide NoteHead
a' a'
```



36.7.3 Painting objects white

Every layout object has a color property which by default is set to black. If this is overridden to white the object will be indistinguishable from the white background. However, if the object crosses other objects the color of the crossing points will be determined by the order in which they are drawn, and this may leave a ghostly image of the white object, as shown here:

```
\override Staff.Clef.color = #white
a'1
```



This may be avoided by changing the order of printing the objects. All layout objects have a `layer` property which should be set to an integer. Objects with the lowest value of `layer` are drawn first, then objects with progressively higher values are drawn, so objects with higher values overwrite objects with lower values. By default most objects are assigned a `layer` value of 1, although a few objects, including `StaffSymbol` and `BarLine`, are assigned a value of 0. The order of printing objects with the same value of `layer` is indeterminate.

In the example above the white clef, with a default `layer` value of 1, is drawn after the staff lines (default `layer` value 0), so overwriting them. To change this, the `Clef` object must be given in a lower value of `layer`, say -1, so that it is drawn earlier:

```
\override Staff.Clef.color = #white
\override Staff.Clef.layer = -1
a'1
```



Selected snippets

Using the whiteout property

Any graphical object can be printed over a white background to mask parts of objects that lie beneath. This can be useful to improve the appearance of collisions in complex situations when repositioning objects is impractical. It is necessary to explicitly set the `layer` property to control which objects are masked by the white background.

In this example the collision of the tie with the time signature is improved by masking out the part of the tie that crosses the time signature, setting the `whiteout` property of `TimeSignature`. To do this, `TimeSignature` is moved to a layer above `Tie`, which is left in the default `layer` 1, and `StaffSymbol` is moved to a layer above `TimeSignature` so it is not masked.

```
{
  \override Score.StaffSymbol.layer = 4
  \override Staff.TimeSignature.layer = 3
  b'2 b'~
  \once \override Staff.TimeSignature.whiteout = ##t
  \time 3/4
  b' r4
}
```



36.7.4 Using break-visibility

Most layout objects are printed only once, but some like bar lines, clefs, time signatures and key signatures, may need to be printed twice when a line break occurs – once at the end of the line and again at the start of the next line. Such objects are called *breakable*, and have a property,

the break-visibility property to control their visibility at the three positions in which they may appear – at the start of a line, within a line if they are changed, and at the end of a line if a change takes place there.

For example, the time signature by default will be printed at the start of the first line, but nowhere else unless it changes, when it will be printed at the point at which the change occurs. If this change occurs at the end of a line the new time signature will be printed at the start of the next line and a cautionary time signature will be printed at the end of the previous line as well.

This behavior is controlled by the break-visibility property, which is explained in Section “Visibility and color of objects” in *Learning Manual*. This property takes a vector of three Booleans which, in order, determine whether the object is printed at the end of, within the body of, or at the beginning of a line. Or to be more precise, before a line break, where there is no line break, or after a line break.

Alternatively, these eight combinations may be specified by predefined functions, defined in `scm/output-lib.scm`, where the last three columns indicate whether the layout objects will be visible in the positions shown at the head of the columns:

Function form	Vector form	Before break	At no break	After break
<code>all-visible</code>	<code>##t ##t ##t</code>	yes	yes	yes
<code>begin-of-line-visible</code>	<code>##f ##f ##t</code>	no	no	yes
<code>center-visible</code>	<code>##f ##t ##f</code>	no	yes	no
<code>end-of-line-visible</code>	<code>##t ##f ##f</code>	yes	no	no
<code>begin-of-line-invisible</code>	<code>##t ##t ##f</code>	yes	yes	no
<code>center-invisible</code>	<code>##t ##f ##t</code>	yes	no	yes
<code>end-of-line-invisible</code>	<code>##f ##t ##t</code>	no	yes	yes
<code>all-invisible</code>	<code>##f ##f ##f</code>	no	no	no

The default settings of break-visibility depend on the layout object. The following table shows all the layout objects of interest which are affected by break-visibility and the default setting of this property:

Layout object	Usual context	Default setting
<code>BarLine</code>	Score	calculated
<code>BarNumber</code>	Score	<code>begin-of-line-visible</code>
<code>BreathingSign</code>	Voice	<code>begin-of-line-invisible</code>
<code>Clef</code>	Staff	<code>begin-of-line-visible</code>
<code>Custos</code>	Staff	<code>end-of-line-visible</code>
<code>Divisio</code>	Staff	<code>begin-of-line-invisible</code>
<code>DoublePercentRepeat</code>	Voice	<code>begin-of-line-invisible</code>
<code>KeyCancellation</code>	Staff	<code>begin-of-line-invisible</code>
<code>KeySignature</code>	Staff	<code>begin-of-line-visible</code>
<code>ClefModifier</code>	Staff	<code>begin-of-line-visible</code>
<code>RehearsalMark</code>	Score	<code>end-of-line-invisible</code>
<code>TimeSignature</code>	Staff	<code>all-visible</code>

The example below shows the use of the vector form to control the visibility of bar lines:


```

\relative {
  f'4 g a b
  f4 g a b
  % Remove bar line at the end of the current line
  \once \override Score.BarLine.break-visibility = ##(f #t #t)
  \break
  f4 g a b
  f4 g a b
}

```



Although all three components of the vector used to override `break-visibility` must be present, not all of them are effective with every layout object, and some combinations may even give errors. The following limitations apply:

- Bar lines cannot be printed at the start of line.
- A bar number cannot be printed at the start of the *first* line unless it is set to be different from 1.
- Clef – see the next section.
- Double percent repeats are either *all printed* or *all suppressed*. Use `begin-of-line-invisible` to print them and `all-invisible` to suppress them.
- Key signature – see the next section.
- ClefModifier – see the next section.

36.7.5 Special considerations

Visibility following explicit changes

The `break-visibility` property controls the visibility of key signatures and changes of clef only at the start of lines, i.e., after a break. It has no effect on the visibility of the key signature or clef following an explicit key change or an explicit clef change within or at the end of a line. In the following example the key signature following the explicit change to B-flat major is still visible, even though `all-invisible` is set.

```

\relative {
  \key g \major
  f'4 g a b
  % Try to remove all key signatures
  \override Staff.KeySignature.break-visibility = #all-invisible
  \key bes \major
  f4 g a b
  \break
  f4 g a b
  f4 g a b
}

```





The visibility of such explicit key signature and clef changes is controlled by the `explicitKeySignatureVisibility` and `explicitClefVisibility` properties. These are the equivalent of the `break-visibility` property and both take a vector of three Booleans or the predefined functions listed above, exactly like `break-visibility`. Both are properties of the `Staff` context, not the layout objects themselves, and so they are set using the `\set` command. Both are set by default to `all-visible`. These properties control only the visibility of key signatures and clefs resulting from explicit changes and do not affect key signatures and clefs at the beginning of lines; `break-visibility` must still be overridden in the appropriate object to remove these.

```
\relative {
  \key g \major
  f'4 g a b
  \set Staff.explicitKeySignatureVisibility = #all-invisible
  \override Staff.KeySignature.break-visibility = #all-invisible
  \key bes \major
  f4 g a b \break
  f4 g a b
  f4 g a b
}
```



Visibility of cancelling accidentals

To remove the cancelling accidentals printed at an explicit key change, set the `Staff` context property `printKeyCancellation` to `#f`:

```
\relative {
  \key g \major
  f'4 g a b
  \set Staff.explicitKeySignatureVisibility = #all-invisible
  \set Staff.printKeyCancellation = #f
  \override Staff.KeySignature.break-visibility = #all-invisible
  \key bes \major
  f4 g a b \break
  f4 g a b
  f4 g a b
}
```



With these overrides only the accidentals before the notes remain to indicate the change of key.

Note that when changing the key to C major or A minor the cancelling accidentals would be the *only* indication of the key change. In this case setting `printKeyCancellation` to `#f` has no effect:

```
\relative {
  \key g \major
  f'4 g a b
  \set Staff.explicitKeySignatureVisibility = #all-invisible
  \set Staff.printKeyCancellation = ##f
  \key c \major
  f4 g a b \break
  f4 g a b
  f4 g a b
}
```



To suppress the cancelling accidentals even when the key is changed to C major or A minor, override the visibility of the `KeyCancellation` grob instead:

```
\relative {
  \key g \major
  f'4 g a b
  \set Staff.explicitKeySignatureVisibility = #all-invisible
  \override Staff.KeyCancellation.break-visibility = #all-invisible
  \key c \major
  f4 g a b \break
  f4 g a b
  f4 g a b
}
```



Transposed clefs

The small transposition symbol on transposed clefs is produced by the `ClefModifier` layout object. Its visibility is automatically inherited from the `Clef` object, so it is not necessary to apply any required `break-visibility` overrides to the `ClefModifier` layout objects to suppress transposition symbols for invisible clefs.

For explicit clef changes, the `explicitClefVisibility` property controls both the clef symbol and any transposition symbol associated with it.

See also

Learning Manual: Section “Visibility and color of objects” in *Learning Manual*.

36.8 Rotating objects

Both layout objects and elements of markup text can be rotated by any angle about any point, but the method of doing so differs.

36.8.1 Rotating layout objects

All layout objects which support the grob-interface can be rotated by setting their rotation property. This takes a list of three items: the angle of rotation counter-clockwise, and the x and y coordinates of the point relative to the object’s reference point about which the rotation is to be performed. The angle of rotation is specified in degrees and the coordinates in staff spaces.

The angle of rotation and the coordinates of the rotation point must be determined by trial and error.

There are only a few situations where the rotation of layout objects is useful; the following example shows one situation where they may be:

```
g4\< e' d'' f''\!
\override Hairpin.rotation = #'(15 -1 0)
g4\< e' d'' f''\!
```



36.8.2 Rotating markup

All markup text can be rotated to lie at any angle by prefixing it with the `\rotate` command. The command takes two arguments: the angle of rotation in degrees counter-clockwise and the text to be rotated. The extents of the text are not rotated: they take their values from the extremes of the x and y coordinates of the rotated text. In the following example the outside-staff-priority property for text is set to `#f` to disable the automatic collision avoidance, which would push some of the text too high.


```
\override TextScript.outside-staff-priority = ##f
g4^\markup { \rotate #30 "a G" }
b^\markup { \rotate #30 "a B" }
des'^\markup { \rotate #30 "a D-Flat" }
fis'^\markup { \rotate #30 "an F-Sharp" }
```



36.9 Aligning objects

All graphical objects have a *reference point*; coordinate-wise, this reference point is defined to have position (0,0).

All grobs also have a *horizontal extent* and a *vertical extent*. The horizontal extent is a pair of numbers giving the displacements from the reference point of the left and right edges, displacements to the left being negative. The vertical extent is a pair of numbers giving the displacement from the reference point to the bottom and top edges, displacements down being negative. In the image below, the point with zero coordinates is the reference point; the horizontal extent is #'(-9 . 26), the vertical extent is #'(-10 . 29).



See Section “LilyPond’s box model” in *Extending* for details on extents of music glyphs.

Graphical objects also have *alignment points*, which are not necessarily the same as their reference point. An alignment point is a point relative to an object that LilyPond uses when aligning that object with other objects. Self-alignment points are relative to the object itself; parent-alignment points are relative to the object’s parent, if one exists.

Most grobs have parents that influence their positioning. For these objects, LilyPond moves the grob so that its alignment point is at the same position as the parent’s alignment point. For example, `TextScript.parent-alignment-X` is the property of a `TextScript` grob that specifies the alignment point along the X axis, relative to that `TextScript` grob’s parent (its associated `NoteColumn` grob), to which LilyPond aligns that `TextScript` grob. When placing a `TextScript` grob horizontally, LilyPond aligns the grob’s self-alignment point with a parent-alignment point relative to the `NoteColumn` grob that is the `TextScript`’s parent. If the `NoteColumn` grob has two or more children, those child grobs can have different parent-alignment points. See Section 36.9.3 [Using the self-alignment-interface], page 792, for more information.

An object’s position on a staff is given by the values of the `X-offset` and `Y-offset` properties. The value of `X-offset` gives the displacement from the X coordinate of the reference point of the parent object, and the value of `Y-offset` gives the displacement from the center line of the staff.¹ The values of `X-offset` and `Y-offset` may be set directly or may be set to be calculated by procedures in order to achieve alignment with the parent object.

Note: Many objects have special positioning considerations which cause any setting of `X-offset` or `Y-offset` to be ignored or modified, even though the object supports the self-alignment-interface. Overriding the `X-offset` or `Y-offset` properties to a fixed value causes the respective self-alignment property to be disregarded.

¹ For objects not directly associated with a staff other conventions might apply. To name an example, `Y-offset` values for `InstrumentName` grobs are measured from the top of the current system’s topmost staff.

For example, an accidental can be repositioned vertically by setting `Y-offset` but any changes to `X-offset` have no effect.

Many graphical objects can be aligned to a previously placed object using the `self-alignment-interface` and/or the `side-position-interface`. For a list of these objects, see Section “`self-alignment-interface`” in *Internals Reference* and Section “`side-position-interface`” in *Internals Reference*.

Rehearsal marks may be aligned with breakable objects such as bar lines, clef symbols, time signature symbols, and key signatures. There are special properties to be found in the `break-aligned-interface` for positioning rehearsal marks on such objects.

See also


Notation Reference: Section 36.9.4 [Using the `break-alignable-interface`], page 795.

Extending LilyPond: Section “Callback functions” in *Extending*.

36.9.1 Setting `X-offset` and `Y-offset` directly

Numerical values may be given to the `X-offset` and `Y-offset` properties of many objects. The following example shows three notes with the default fingering position and the positions with `X-offset` and `Y-offset` modified.

```
f' -3
f' -\tweak X-offset 0
    -\tweak Y-offset 0
    -3
f' -\tweak X-offset -1
    -\tweak Y-offset 0.5
    -3
```



36.9.2 Using the `side-position-interface`

An object that supports the `side-position-interface` can be placed next to its parent object so that the specified edges of the two objects touch. The object may be placed above, below, to the right, or to the left of the parent. The parent cannot be specified; it is determined by the order of elements in the input stream. Most objects have the associated note head as their parent.

The values of the `side-axis` and `direction` properties determine where the object is to be placed, as follows:

<code>side-axis</code> property	<code>direction</code> property	placement
0	-1	left
0	1	right
1	-1	below
1	1	above

When `side-axis` is 0, `X-offset` should be set to the procedure `ly:side-position-interface::x-aligned-side`. This procedure returns the correct value of `X-offset` to place the object to the left or right side of the parent according to value of `direction`.

When `side-axis` is 1, `Y-offset` should be set to the procedure `ly:side-position-interface::y-aligned-side`. This procedure returns the correct value of `Y-offset` to place the object to the top or bottom of the parent according to value of `direction`.

Instead of values 0 and 1 you might use the Scheme symbols `X` and `Y` for specifying a side axis. Similarly, you might use the symbols `DOWN` (`LEFT`) and `UP` (`RIGHT`) instead of values -1 and 1 for specifying a direction.

36.9.3 Using the self-alignment-interface


The `self-alignment-interface` defines objects' alignment points. This interface applies to many graphical objects in LilyPond (see Section “`self-alignment-interface`” in *Internals Reference* for a list).

The alignment interface is based on the dimension of the grob's bounding box. The `X` (`Y`) coordinate of a grob's alignment point is a multiple of half the width (height) of this bounding box. In other words, one unit is half the total `X` (`Y`) extent of the object.

An `X` (`Y`) coordinate of -1 represents the left (lower) edge of the bounding box. An `X` (`Y`) coordinate of 0 represents the center. An `X` (`Y`) coordinate of 1 represents the right (upper) edge of the bounding box.

A coordinate can be any real number, including values less than -1 or greater than 1.

The image below shows the general case, where both the parent and the ‘self’ grob have non-zero horizontal and vertical alignment parameters to position the alignment points A_P and A_S (these two points are chosen arbitrarily here for the sake of demonstrating the concept).



Self-aligning and parent-aligning objects horizontally

The horizontal alignment of an object that supports the `self-alignment-interface` is controlled by the value of the `self-alignment-X` property, provided the object's `X`-offset property is set to `ly:self-alignment-interface::x-aligned-on-self`. Negative values move the object to the right, positive to the left. A value of 0 centers the object (more specifically, its bounding box) on the alignment point of its parent, a value of -1 aligns the left edge of the object to the alignment point of its parent, and a value of 1 aligns the right edge of the object to the alignment point of its parent. The symbols `LEFT`, `CENTER`, and `RIGHT` may be used instead of the values -1, 0, and 1, respectively.

Value `#f` horizontally aligns the grob using its reference point. This value only works, however, if the grob has a parent; LilyPond returns an error if it has none.

If an object has a parent, its horizontal alignment is also similarly affected by the `parent-alignment-X` property.

The following image shows various `self-alignment-X` and `parent-alignment-X` value combinations for TextScript objects whose parents are their associated NoteColumn grobs. Here, the TextScript grobs are gray boxes having the horizontal extent `'(-1 . 3)` and the vertical extent `'(-1 . 2)`; the reference point of the boxes is marked with a dot. The reference point of a NoteColumn grob is always (0,0); suspended NoteHead grobs (i.e., note heads in chords on the other, non-default side of the stem) stick out but are not taken into account. The horizontal position of the parent-alignment point is represented by a vertical line, and the alignment point of TextScript is marked with a cross.

The image shows four staves, each with four gray boxes representing TextScript objects. Each box has a dot (reference point) and a cross (alignment point). The boxes are positioned relative to the staff lines and the parent NoteColumn grobs. The staves are labeled with their respective `parent-alignment-X` and `self-alignment-X` values.

- Staff 1: `parent-alignment-X = ##f`. The boxes are aligned to the right of the staff lines. The alignment points (crosses) are at the right edge of the boxes.
- Staff 2: `parent-alignment-X = #-1`. The boxes are aligned to the left of the staff lines. The alignment points (crosses) are at the left edge of the boxes.
- Staff 3: `parent-alignment-X = #0`. The boxes are aligned to the center of the staff lines. The alignment points (crosses) are at the center of the boxes.
- Staff 4: `parent-alignment-X = #1`. The boxes are aligned to the left of the staff lines. The alignment points (crosses) are at the left edge of the boxes.

Either `\override` or `\tweak` can be used to modify the value of `self-alignment-X`. To separately align several annotations on a single note, however, you must use `\tweak`.

```
a' - \tweak self-alignment-X -1 ^"left-aligned"
      - \tweak self-alignment-X 0 ^"center-aligned"
      - \tweak self-alignment-X #RIGHT ^"right-aligned"
      - \tweak self-alignment-X -2.5 ^"aligned farther to the right"
```

The image shows a musical staff with a single note. Four annotations are placed above the note, each with a different horizontal alignment: 'right-aligned' (aligned to the right), 'center-aligned' (aligned to the center), 'left-aligned' (aligned to the left), and 'aligned farther to the right' (aligned to the right, but further to the right than the other annotations).

Self-aligning objects vertically

Objects may be aligned vertically (using `self-alignment-Y`) in an analogous way to aligning them horizontally if the `Y-offset` property is set to `ly:self-alignment-interface::y-aligned-on-self`. However, other mechanisms are often involved in vertical alignment: the value of `Y-offset` is just one variable taken into account. This may make adjusting the value of some objects tricky. The units are just half the vertical extent of the object, which is usually quite small, so very large numbers may be required. A value of -1 aligns the lower edge of the object with the alignment point of the parent object, a value of 0 aligns the center of the object with the alignment point of the parent, and a value of 1 aligns the top edge of the object with the alignment point of the parent. The symbols `DOWN`, `CENTER`, and `UP` may be substituted for -1, 0, and 1, respectively.

Value `#f` vertically aligns the grob using its reference point. This value only works, however, if the grob has a parent; LilyPond returns an error if it has none.

Note that using `parent-alignment-Y` almost never works; there are too many other constraints that influence how an object is vertically positioned relative to its parent grob. Take the previous image as an example: the vertical value of the parent's reference point (the `NoteColumn` grob) depends on the attached object (the `TextScript` grob) together with various padding property values – as can be seen, LilyPond tries to move the `TextScript` grobs as near as possible to the staff. Due to this interdependency between parent and object itself, accessing or modifying `parent-alignment-Y` usually fails and often produces warnings about ‘cyclic dependencies’.

The standard way to adjust vertical distances is to modify one of the various padding properties LilyPond offers, for example, `outside-staff-padding`.

Self-aligning objects in both directions

By setting both `self-alignment-X` and `self-alignment-Y`, an object may be aligned in both directions simultaneously.

The following example shows how to adjust the position of instrument names. The `InstrumentName` grob is an example of a grob that has no parent: `self-alignment-X` gives an alignment relative to the left margin and the start of the staff (i.e., the system's indentation), and `self-alignment-Y` aligns the `InstrumentName` grob relative to the related staff's middle line.

```
sn = #(define-music-function (name x y) (string? number? number?)
  #{
    \new RhythmicStaff \with {
      instrumentName = #name
      \override InstrumentName.self-alignment-X = #x
      \override InstrumentName.self-alignment-Y = #y
    } { f'1 }
  #})

<<
  \sn "AAA" #1 #3
  \sn "AAAAA" #1 #3
  \sn "BBB" #0.5 #1.5
  \sn "BBBBB" #0.5 #1.5
  \sn "CCC" #0 #0
  \sn "CCCCC" #0 #0
  \sn "DDD" #-0.5 #-1.5
  \sn "DDDDD" #-0.5 #-1.5
  \sn "EEE" #-1 #-3
```


```

\sn "EEEEEE" #-1 #-3
>>

\layout {
  indent = 5\cm

  \context {
    \RhythmicStaff
    \override VerticalAxisGroup.staff-staff-spacing =
      #'((minimum-distance . 0)
        (basic-distance . 0)
        (padding . 2.5))
  }
}

```



36.9.4 Using the break-alignable-interface

Rehearsal marks, text marks, bar numbers, and more generally all objects that support the break-alignable-interface, collectively referred to as “break-alignable objects”, may be aligned with notation objects such as bar lines, key signatures, time signatures, and generally any object that supports the break-aligned-interface. To be more precise, break-aligned items have a break-align-symbol property, providing symbols that can be used as ‘anchor points’ for other objects via the break-align-symbols property. See Section “break-alignment-interface” in *Internals Reference*, for a complete list of available symbols.

Each type of object has its own default reference point, to which break-alignable items are aligned:

```

\override Score.TextMark.self-alignment-X = #CENTER
% Align text mark to the right edge of the clef.
\override Score.TextMark.break-align-symbols = #'(clef)
\clef treble
\key a \major
\textMark "↓"
e'1

% Align text mark to the left edge of the time signature.

```

```
\override Score.TextMark.break-align-symbols = #'(time-signature)
\key a \major
\time 3/4
\textMark "↓"
e'2.
```

```
% Center text mark above the breathing mark.
\override Score.TextMark.break-align-symbols = #'(breathing-sign)
\key a \major
\time 4/4
e'1
\breathes
\textEndMark "↓"
```




A list of possible target alignment objects may be specified. If some of the objects are invisible at that point due to the setting of break-visibility or the explicit visibility settings for keys and clefs, the rehearsal mark or bar number is aligned to the first object in the list which is visible. If no objects in the list are visible the object is aligned to the bar line. If the bar line is invisible the object is aligned to the place where the bar line would be.

```
\override Score.TextMark.self-alignment-X = #CENTER
% Align text mark to the right edge of the key signature.
\override Score.TextMark.break-align-symbols = #'(key-signature clef)
\key a \major
\clef treble
\textMark "↓"
e'1
```

```
% Align text mark to the right edge of the clef.
\set Staff.explicitKeySignatureVisibility = #all-invisible
\override Score.TextMark.break-align-symbols = #'(key-signature clef)
\key a \major
\clef bass
\textMark "↓"
gis,1
```

```
% Center text mark above the bar line.
\set Staff.explicitKeySignatureVisibility = #all-invisible
\set Staff.explicitClefVisibility = #all-invisible
\override Score.TextMark.break-align-symbols = #'(key-signature clef)
\key a \major
\clef treble
\textMark "↓"
e'1
```



The alignment of the break-alignable item relative to the notation object can be changed, as shown in the following example. In a score with multiple staves, this setting should be done for all the staves.

```
\override Score.TextMark.self-alignment-X = #CENTER
% Align text mark with the right edge of the key signature.
\override Score.TextMark.break-align-symbols = #'(key-signature)
\key a \major
\clef treble
\time 4/4
\textMark "↓"
e'1

% Center text mark above the key signature
\once \override
  Score.KeySignature.break-align-anchor-alignment = #CENTER
\textMark "↓"
\key a \major
e'1


% Align text mark with the left edge of the key signature.
\once \override
  Score.KeySignature.break-align-anchor-alignment = #LEFT
\key a \major
\textMark "↓"
e'1
```



The break-alignable item can also be offset to the right or left of the left edge by an arbitrary amount. The units are staff spaces:

```
\override Score.TextMark.self-alignment-X = #CENTER
% Align text mark with the left edge of the key signature,
% then shifted right by 3.5 staff spaces.
\override Score.TextMark.break-align-symbols = #'(key-signature)
\once \override Score.KeySignature.break-align-anchor = 3.5
\key a \major
\textMark "↓"
e'1

% Align text mark with the left edge of the key signature,
% then shifted left by 2 staff spaces.
\once \override Score.KeySignature.break-align-anchor = -2
\key a \major
\textMark "↓"
e'1
```



See also

Internals Reference: Section “break-alignable-interface” in *Internals Reference*, Section “break-alignment-interface” in *Internals Reference*.

36.10 Modifying stencils

All layout objects have a `stencil` property which is part of the `grob-interface`. By default, this property is usually set to a function specific to the object that is tailor-made to render the symbol which represents it in the output. For example, the standard setting for the `stencil` property of the `MultiMeasureRest` object is `ly:multi-measure-rest::print`.

The standard symbol for any object can be replaced by modifying the `stencil` property to reference a different, specially-written, procedure. This requires a high level of knowledge of the internal workings of LilyPond, but there is an easier way which can often produce adequate results.

This is to set the `stencil` property to the procedure which prints text – `ly:text-interface::print` – and to add a `text` property to the object which is set to contain the markup text which produces the required symbol. Due to the flexibility of markup, much can be achieved – see in particular Section 8.2.4 [Graphic notation inside markup], page 331.

The following example demonstrates this by changing the note head symbol to a cross within a circle.

```
Xin0 = {
  \once \override NoteHead.stencil = #ly:text-interface::print
  \once \override NoteHead.text = \markup {
    \combine
      \halign #-0.7 \draw-circle #0.85 #0.2 ##f
      \musicglyph "noteheads.s2cross"
  }
}
\relative {
  a' a \Xin0 a a
}
```



Any of the *Feta* glyphs used in the *Emmentaler* font can be supplied to the `\musicglyph` markup command – see Section B.8 [The *Emmentaler* font], page 905.

EPS files and Postscript commands can both be inserted inline using the `\epsfile` and `\postscript` markup commands respectively – see Section A.1.3 [Graphical markup], page 838.

See also

Notation Reference: Section 8.2.4 [Graphic notation inside markup], page 331, Section 8.2 [Formatting text], page 319, Section A.1 [Text markup commands], page 807, Section B.8 [The *Emmentaler* font], page 905, Section A.1.3 [Graphical markup], page 838.

36.11 Modifying shapes

36.11.1 Modifying ties and slurs

Ties, Slurs, PhrasingSlurs, LaissezVibrerTies and RepeatTies are all drawn as third-order Bézier curves. If the shape of the tie or slur which is calculated automatically is not optimum, the shape may be modified manually in two ways:

- by specifying the displacements to be made to the control points of the automatically calculated Bézier curve, or
- by explicitly specifying the positions of the four control points required to define the wanted curve.

Both methods are explained below. The first method is more suitable if only slight adjustments to the curve are required; the second may be better for creating curves which are related to just a single note.

Cubic Bézier curves

Third-order or cubic Bézier curves are defined by four control points. The first and fourth control points are precisely the starting and ending points of the curve. The intermediate two control points define the shape. Animations showing how the curve is drawn can be found on the web, but the following description and image may be helpful. The curve starts from the first control point heading directly towards the second, gradually bending over to head towards the third and continuing to bend over to head towards the fourth, arriving there traveling directly from the third control point. The curve is entirely contained in the quadrilateral defined by the four control points.



Translations, rotations and scaling of the control points all result in exactly the same operations on the curve.

Specifying displacements from current control points

In this example the automatic placement of the tie is not optimum, and `\tieDown` would not help.

```
<<
  { e'1~ 1 }
  \\
  \relative { r4 <g' c,> <g c,> <g c,> }
  >>
```



Adjusting the control points of the tie with `\shape` allows the collisions to be avoided.

The syntax of `\shape` is

```
[-]\shape displacements item
```

This will reposition the control points of *item* by the amounts given by *displacements*. The *displacements* argument is a list of number pairs or a list of such lists. Each element of a pair represents the displacement of one of the coordinates of a control point. If *item* is a string, the

result is `\once\override` for the specified grob type. If *item* is a music expression, the result is the same music expression with an appropriate tweak applied.

In other words, the `\shape` function can act as either a `\once\override` command or a `\tweak` command depending on whether the *item* argument is a grob name, like “Slur”, or a music expression, like “(”. The *displacements* argument specifies the displacements of the four control points as a list of four pairs of (dx . dy) values in units of staff spaces (or a list of such lists if the curve has more than one segment).

The leading hyphen is required if and only if the `\tweak` form is being used.

So, using the same example as above and the `\once\override` form of `\shape`, this will raise the tie by half a staff space:

```
<<
{
  \shape #'((0 . 0.5) (0 . 0.5) (0 . 0.5) (0 . 0.5)) Tie
  e'1~ 1
}
\\
\relative { r4 <g' c,> <g c,> <g c,> }
>>
```



This positioning of the tie is better, but maybe it should be raised more in the center. The following example does this, this time using the alternative `\tweak` form:

```
<<
{
  e'1-\shape #'((0 . 0.5) (0 . 1) (0 . 1) (0 . 0.5)) ~ e'
}
\\
\relative { r4 <g' c,> <g c,> <g c,> }
>>
```



To aid the tweaking process, the `\vshape` function is provided. Its name means *visual shape*: it acts exactly like `\shape`, except that the control points and polygon are additionally displayed.

```
\relative {
  c'8\(\ a) e4 gis a\
  \vshape #'((0 . -0.3) (0.5 . -0.2)
             (0.5 . -0.3) (0 . -0.7)) PhrasingSlur
  c8\(\ a) e4 gis a\
}
```



It is advisable to start with `\vshape` and adjust until a satisfactory curve is obtained, then simply remove the “v” letter in `\vshape`.

Two different curves starting at the same musical moment may also be shaped:

```
\relative {
  c'8(\( a) a'4 e c\)
  \shape #'((0.7 . -0.4) (0.5 . -0.4)
            (0.3 . -0.3) (0 . -0.2)) Slur
  \shape #'((0 . 0) (0 . 0.5)
            (0 . 0.5) (0 . 0)) PhrasingSlur
  c8(\( a) a'4 e c\)
}
```



The `\shape` function can also displace the control points of curves which stretch across line breaks. Each piece of the broken curve can be given its own list of offsets. If changes to a particular segment are not needed, the empty list can serve as a placeholder. In this example the line break makes the single slur look like two:

```
\relative {
  c'4( f g c
  \break
  d,4 c' f, c)
}
```



Changing the shapes of the two halves of the slur makes it clearer that the slur continues over the line break:

```
% () may be used as a shorthand for ((0 . 0) (0 . 0) (0 . 0) (0 . 0))
% if any of the segments does not need to be changed
\relative c' {
  \shape #'(
    (( 0 . 0) (0 . 0) (0 . 0) (0 . 1))
    ((0.5 . 1.5) (1 . 0) (0 . 0) (0 . -1.5))
  ) Slur
  c4( f g c
  \break
  d,4 c' f, c)
}
```





If an S-shaped curve is required the control points must always be adjusted manually – LilyPond will never select such shapes automatically.

```
\relative c'' {
  c8( e b-> f d' a e-> g)
  \shape #'((0 . -1) (5.5 . -0.5) (-5.5 . -10.5) (0 . -5.5))
  PhrasingSlur
  c8\(( e b-> f d' a e-> g\)
}
```




Specifying control points explicitly

The coordinates of the Bézier control points are specified in units of staff spaces. The X coordinate is relative to the reference point of the note to which the tie or slur is attached, and the Y coordinate is relative to the staff center line. The coordinates are specified as a list of four pairs of decimal numbers (reals). One approach is to estimate the coordinates of the two end points, and then guess the two intermediate points. The optimum values are then found by trial and error. Be aware that these values may need to be manually adjusted if any further changes are made to the music or the layout.

One situation where specifying the control points explicitly is preferable to specifying displacements is when they need to be specified relative to a single note. Here is an example of this. It shows one way of indicating a slur extending into alternative sections of a volta repeat.

```
\relative {
  c''1
  \repeat volta 3 { c4 d( e f }
  \alternative {
    \volta 1 { g2) d }
    \volta 2 {
      g2
      % create a slur and move it to a new position
      % the <> is just an empty chord to carry the slur termination
      -\tweak control-points
        #'((-2 . 3.8) (-1 . 3.9) (0 . 4) (1 . 3.4)) ( <> )
      f,
    }
  }
  \volta 3 {
    e'2
    % create a slur and move it to a new position
    -\tweak control-points
      #'((-2 . 3) (-1 . 3.1) (0 . 3.2) (1 . 2.4)) ( <> )
    f,
  }
}
```



Known issues and warnings

It is not possible to modify shapes of ties or slurs by changing the `control-points` property if there are multiple ties or slurs at the same musical moment – the `\tweak` command will also not work in this case. However, the `tie-configuration` property of `TieColumn` can be overridden to set start line and direction as required.

See also

Internals Reference: Section “`TieColumn`” in *Internals Reference*.

Appendices

Appendix A Markup commands

A.1 Text markup commands

The following commands can all be used inside `\markup { }`.

A.1.1 Font markup

`\abs-fontsize size (number) arg (markup)`

Use *size* as the absolute font size (in points) to display *arg*.

This function adjusts the baseline-skip and word-space properties accordingly.

```
\markup {
  default text font size
  \hspace #2
  \abs-fontsize #16 { text font size 16 }
  \hspace #2
  \abs-fontsize #12 { text font size 12 }
}
```

default text font size **text font size 16** text font size 12

Used properties:

- baseline-skip (3)
- word-space (0.6)

`\bold arg (markup)`

Print *arg* with a bold face.

```
\markup {
  default
  \hspace #2
  \bold bold
}
```

default **bold**

The code `\markup \bold ...` is a shorthand for `\markup \override #'(font-series . bold) ...` – using the more verbose form, it is possible to obtain nuances such as semi-bold, if the text font has such variants. Refer to the documentation for the `font-series` properties (Section “User backend properties” in *Internals Reference*).

`\box arg (markup)`

Draw a box around *arg*.

This function looks at the thickness, box-padding, and font-size properties to determine the line thickness and padding around the markup.

```
\markup {
  \override #'(box-padding . 0.5)
  \box \line { V. S. }
}
```

V. S.

Note that the box does not horizontally displace its argument. Use markup commands like `\left-align` or `\table` to make LilyPond realign it.

```

\markup {
  \override #'(box-padding . 1.5)
  \column {
    "text"
    \box "text"
    \left-align \box "text"
  }
}

```

Used properties:

- box-padding (0.2)
- font-size (0)
- thickness (1)

`\caps arg` (markup)

Print *arg* in (fake) small caps.

This function is a copy of the `\smallCaps` command.

```

\markup {
  default
  \hspace #2
  \caps {
    Text in small caps
  }
}

```

default **TEXT IN SMALL CAPS**

Use `\fontCaps` for real small caps (if the font provides it).

`\dynamic arg` (markup)

Print *arg* using the (music) font for dynamics.

This font only contains letters **f**, **m**, **n**, **p**, **r**, **s**, and **z**. When producing phrases like ‘più **f**’, the normal words (like ‘più’) should be done in a different font. The recommended font for this is bold and italic.

```

\markup {
  \dynamic {
    sfzp
  }
}

```

sfzp

`\figured-bass arg` (markup)

Set *arg* as small numbers for figured bass.

Specially slashed digits can be achieved with a trailing backslash (for numbers 6, 7, and 9) or a trailing plus (for numbers 2, 4, and 5).¹

¹ Internally, this works by activating the ‘dlig’ OpenType feature of the Emmentaler font.

The use of a backslash is in analogy to `\figuremode` (see Section 15.3.2 [Entering figured bass], page 526). Note that to get a backslash character in markup it must be escaped by doubling it. Additionally, it must be put into double quotes.

```
\markup {
  \figured-bass {
    2 3 4+ 7 "9\"
  }
}
```

2 3 4 7 9

`\finger arg` (markup)

Set *arg* as small numbers for fingering instructions.

```
\markup {
  \finger {
    1 2 3 4 5
  }
}
```

1 2 3 4 5

`\font-select defs` (pair) *arg* (markup)

Output the markup *arg* using fonts specified in *defs*.

defs is either a single pair (*family* . *font-name*) or a non-empty list of such pairs. Here, *family* is usually serif, sans or typewriter; *font-name* is a string. Font families not mentioned in the call to `\font-select` remain unchanged.

```
\markup {
  \font-select #'((sans . "Liberation Sans")
                  (typewriter . "Liberation Mono"))
  {
    \sans { Sans-serif font. }
    \typewriter { Typewriter font. }
    Serif font.
    \font-select #'(serif . "Liberation Serif") {
      Another serif font.
    }
  }
}
```

Sans-serif font. Typewriter font. Serif font. Another serif font.

`\fontCaps arg` (markup)

Print *arg* in small caps.

This command sets the font-variant property to small-caps.

Unlike `\smallCaps`, which merely uses capital letters at a smaller font size, this uses the actual variant of the font for small caps. (As a consequence, if you configure a custom text font, this command has no effect if that font does not have a small caps variant.)

```
\markup \fontCaps "Small caps"
```

SMALL CAPS

`\fontsize increment` (number) *arg* (markup)

Increase current font size by *increment* to print *arg*.

This function adjusts the baseline-skip and word-space properties accordingly.

```
\markup {
  default
  \hspace #2
  \fontsize #-1.5 smaller
}
```

default *smaller*

Used properties:

- baseline-skip (2)
- word-space (1)
- font-size (0)

`\huge arg` (markup)

Set font size to value 2 to print *arg*.

```
\markup {
  default
  \hspace #2
  \huge huge
}
```

default *huge*

`\italic arg` (markup)

Print *arg* in italics.

This command sets the font-shape property to italic.

```
\markup {
  default
  \hspace #2
  \italic italic
}
```

default *italic*

`\large arg` (markup)

Set font size to value 1 to print *arg*.

```
\markup {
  default
  \hspace #2
  \large large
}
```

default *large*

`\larger arg` (markup)

Increase current font size by 1 to print *arg*.

This function adjusts the baseline-skip and word-space properties accordingly.

```
\markup {
  default
  \hspace #2
  \larger larger
}
```

default larger

`\magnify sz (number) arg (markup)`

Magnify current font by factor *sz* to print *arg*.

```
\markup {
  default
  \hspace #2
  \magnify #1.5 {
    50% larger
  }
}
```

default 50% larger

Note that magnification only works if a font name is explicitly selected. Use `\fontsize` otherwise.

`\normal-size-sub arg (markup)`

Set *arg* in subscript with a normal font size.

```
\markup {
  default
  \normal-size-sub {
    subscript in standard size
  }
}
```

default subscript in standard size

Used properties:

- `font-size (0)`

`\normal-size-super arg (markup)`

Set *arg* in superscript with a normal font size.

```
\markup {
  default
  \normal-size-super {
    superscript in standard size
  }
}
```

default superscript in standard size

Used properties:

- `font-size (0)`

`\normal-text arg (markup)`

Print *arg* with default text font.

This resets all font-related properties (except the size), no matter what font was used earlier.

```

\markup {
  \huge \bold \sans \fontCaps {
    huge bold sans caps
  }
  \hspace #2
  \normal-text {
    huge normal
  }
  \hspace #2
  as before
}

```

HUGE BOLD SANS CAPS huge normal **AS BEFORE**

`\normal-weight arg` (markup)

Switch to normal weight (in contrast to bold) to print *arg*.

This command sets the font-series property to normal.

```

\markup {
  \bold {
    some bold text
  }
  \hspace #2
  \normal-weight {
    normal font series
  }
  \hspace #2
  bold again
}

```

some bold text normal font series **bold again**

`\normalsize arg` (markup)

Set font size to default (i.e., to value 0) to print *arg*.

```

\markup {
  \teeny {
    this is very small
  }
  \hspace #2
  \normalsize {
    normal size
  }
  \hspace #2
  teeny again
}

```

this is very small **normal size** teeny again

`\number arg` (markup)

Print *arg* using the (music) font for numbers.

This font also contains symbols for figured bass, some punctuation, spaces of various widths, some letters and text variants of accidentals, the common time, and the cut time symbol. Use `\dynamic` to access the (very small number of) letters. For

accidentals you might use `\number` in combination with Unicode characters to access the text representation forms of accidental glyphs, as the following table shows.

Unicode value Unicode character

U+266D	♭
U+266E	♮
U+266F	♯
U+1D12A	𝄖
U+1D12B	𝄗
U+1D134	𝄞
U+1D135	𝄟

Examples:

```
\number ♭ → ♭
\number { \char ##x266F } → ♯
```

To get accidentals protected against overrides of `font-name` it is preferable to use `\text-doubleflat`, `\text-flat`, `\text-natural`, `\text-sharp`, `\text-doublesharp`, or the general `\text-accidental` for the text variants of accidentals. For the time signature symbols, use `\text-common-time` and `\text-cut-time`.

The appearance of digits in the Emmentaler font can be controlled with four OpenType features: ‘`tnum`’, ‘`cv47`’, ‘`ss01`’, and ‘`kern`’, which can be arbitrarily combined.

<code>tnum</code>	If off (which is the default), glyphs ‘zero’ to ‘nine’ have no left and right side bearings. If on, the glyphs all have the same advance width by making the bearings non-zero.
<code>cv47</code>	If on, glyphs ‘four’ and ‘seven’ have shorter vertical strokes. Default is off.
<code>ss01</code>	If on, glyphs ‘zero’ to ‘nine’ have a fatter design, making them more readable at small sizes. Default is off.
<code>kern</code>	If on (which is the default), provide pairwise kerning between (most) glyphs.

```

\markuplist
\number
\fontsize #4.5
\override #'((padding . 2)
              (baseline-skip . 4)
              (box-padding . 0)
              (thickness . 0.1))
\table #'(-1 -1 -1 -1) {
  0123456789 \box 147 \concat { \box 1 \box 4 \box 7 }
\normal-text \normal-size "(time signatures)"
\override #'(font-features . ("cv47")) {
  0123456789 \box 147 \concat { \box 1 \box 4 \box 7 } }
\normal-text \normal-size "(alternatives)"
\override #'(font-features . ("tnum" "cv47" "-kern")) {
  0123456789 \box 147 \concat { \box 1 \box 4 \box 7 } }
\normal-text \normal-size "(fixed-width)"
\override #'(font-features . ("tnum" "cv47" "ss01")) {
  0123456789 \box 147 \concat { \box 1 \box 4 \box 7 } }
\normal-text \normal-size "(figured bass)"
\override #'(font-features . ("cv47" "ss01")) {
  0123456789 \box 147 \concat { \box 1 \box 4 \box 7 } }
\normal-text \normal-size "(fingering)"
}

```

0123456789 **147** **147** (time signatures)

0123456789 **147** **147** (alternatives)

0123456789 **147** **147** (fixed-width)

0123456789 **147** **147** (figured bass)

0123456789 **147** **147** (fingering)

See also the markup commands `\figured-bass` and `\finger`, which set the font features accordingly.

`\overtie arg` (markup)

Print a tie over *arg*.

```

\markup \line {
  \overtie "overtied"
  \override #'((offset . 5) (thickness . 1))
  \overtie "overtied"
  \override #'((offset . 1) (thickness . 5))
  \overtie "overtied"
}

```

overtied **overtied** **overtied**

Used properties:

- `shorten-pair ((0 . 0))`

- height-limit (0.7)
- direction (1)
- offset (2)
- thickness (1)

`\replace` *replacements* (list) *arg* (markup)

Use *replacements* to replace strings in *arg*.

Each (*key* . *value*) pair of the *replacements* alist specifies what should be replaced; *key* gets replaced by *value*. Note the quasi-quoting syntax with a backquote in the second example.

```
\markup \replace #'(("2nd" . "Second"))
"2nd time"
\markup \replace
#`(("2nd" . ,#{ \markup \concat { 2 \super nd } #}))
\center-column {
  \line { Play only }
  \line { the 2nd time }
}
```

Second time

Play only
the 2nd time

Used properties:

- replacement-alist

`\sans` *arg* (markup)

Print *arg* with a sans-serif font.

This command sets the font-family property to sans.

```
\markup {
  default
  \hspace #2
  \sans {
    sans serif
  }
}

default  sans serif
```

`\serif` *arg* (markup)

Print *arg* with a serif font.

This command sets the font-family property to serif.

```
\markup {
  \sans \bold {
    sans serif, bold
  }
  \hspace #2
  \serif {
    text in serif font
  }
  \hspace #2
  return to sans
```

```
    }
  }
```

sans serif, bold text in serif font return to sans

`\simple str` (string)

Print string *str*.

`\markup \simple "x"` is equivalent to `\markup "x"`. This command was previously used internally, but no longer is, and is being kept for backward compatibility only.

`\small arg` (markup)

Set font size to value -1 to print *arg*.

```
\markup {
  default
  \hspace #2
  \small small
}
```

default small

`\smallCaps arg` (markup)

Print *arg* in (fake) small caps.

Unlike `\fontCaps`, which uses the actual small caps variant of the current font, this fakes small caps by using capital letters at a smaller font size. It can thus be used for fonts that don't have a small caps variant.

```
\markup {
  default
  \hspace #2
  \smallCaps {
    Text in small caps
  }
}
```

default TEXT IN SMALL CAPS

`\smaller arg` (markup)

Decrease current font size by 1 to print *arg*.

This function adjusts the baseline-skip and word-space properties accordingly.

```
\markup {
  \fontsize #3.5 {
    large text
    \hspace #2
    \smaller { smaller text }
    \hspace #2
    large text
  }
}
```

large text smaller text large text

`\sub arg` (markup)

Set *arg* in subscript.

```
\markup { \concat { H \sub 2 0 } }
```

H_2O

See also `\super`.

Used properties:

- `font-size` (0)

`\super arg` (markup)

Set *arg* in superscript.

```
\markup { E = \concat { mc \super 2 } }
```

$E = mc^2$

See also `\sub`.

Used properties:

- `font-size` (0)

`\teeny arg` (markup)

Set font size to value -3 to print *arg*.

```
\markup {
  default
  \hspace #2
  \teeny teeny
}
```

default *teeny*

`\tie arg` (markup)

Add a horizontal bow at the bottom or top of *arg*.

This function uses `make-tie-stencil` to create the bow; it looks at the `thickness` and `offset` properties to determine the line thickness and vertical offset, respectively. The added bow fits the extent of *arg*; use the `shorten-pair` property to modify this. The `direction` property may be set explicitly using `override` or `direction` modifiers, or implicitly by using `voiceOne`, etc.

```
\markup {
  \override #'(direction . 1)
  \tie "above"
  \override #'(direction . -1)
  \tie "below"
}
```

above below

See also `\undertie` and `\overtie`, which are shorthands for this function.

Used properties:

- `shorten-pair` ((0 . 0))
- `height-limit` (0.7)
- `direction` (1)
- `offset` (2)
- `thickness` (1)

`\tiny arg` (markup)

Set font size to value -2 to print *arg*.


```
\markup {
  default
  \hspace #2
  \tiny tiny
}
```

```
default tiny
```

`\typewriter arg (markup)`

Print *arg* in typewriter.

This command sets the font-family property to typewriter, also switching off the ‘liga’ OpenType feature to disable ligatures like ‘ff’ or ‘fi’.

```
\markup {
  "default fi ff"
  \hspace #2
  \typewriter "typewriter fi ff"
}
```

```
default fi ff typewriter fi ff
```

`\underline arg (markup)`

Underline *arg*.

This function looks at the property thickness to determine the line thickness, at offset to determine the line’s vertical offset from *arg*, and at underline-skip to determine the distance of additional lines from the others.

The underline-shift property is used to make subsequent calls work correctly. Overriding it makes little sense since it would end up adding the provided value to the one of offset.

```
\markup \justify-line {
  \underline "underlined"
  \override #'(offset . 5)
  \override #'(thickness . 1)
  \underline "underlined"
  \override #'(offset . 1)
  \override #'(thickness . 5)
  \underline "underlined"
  \override #'(offset . 5)
  \override #'(underline-skip . 4)
  \underline \underline \underline "underlined thrice"
}
```

```
underlined    underlined    underlined    underlined thrice
```

Used properties:

- underline-skip (2)
- underline-shift (0)
- offset (2)
- thickness (1)

`\undertie arg (markup)`

Print a tie under *arg*.

```
\markup \line {
  \undertie "undertied"
  \override #'(offset . 5) (thickness . 1))
  \undertie "undertied"
  \override #'(offset . 1) (thickness . 5))
  \undertie "undertied"
}
```

undertied undertied undertied

Used properties:

- shorten-pair ((0 . 0))
- height-limit (0.7)
- direction (1)
- offset (2)
- thickness (1)

`\upright arg` (markup)

Print *arg* upright.

This command is the opposite of `\italic`; it sets the font-shape property to upright.

```
\markup {
  \italic {
    italic text
  }
  \hspace #2
  \upright {
    upright text
  }
  \hspace #2
  italic again
}
```

italic text upright text *italic again*

`\volta-number arg` (markup)

Set *arg* in a font appropriate for volta numbers.

```
\markup \volta-number "4."
```

4.

`\with-string-transformer transformer` (procedure) *arg* (markup)

Apply string transformer function *transformer* to *arg*.

Whenever a string is interpreted inside *arg*, function *transformer* is called first, and its result is then interpreted. The arguments passed to *transformer* are the output definition, the property alist chain, and the markup *arg*. See Section “New markup command definition” in *Extending* about the two first arguments.

```
\markup \with-string-transformer
  #(lambda (layout props str)
    (string-upcase str))
  \concat { "abc" \larger "def" }
```

ABCDEF

A.1.2 Markup for text alignment

`\abs-hspace` *amount* (number)

Create an invisible object taking up absolute horizontal space of *amount* points.

```
\markup {
  one
  \abs-hspace #20
  two
  \abs-hspace #40
  three
}
```

one two three

See also `\hspace`.

`\abs-vspace` *amount* (number)

Create an invisible object taking up absolute vertical space of *amount* points.

```
\markup {
  \center-column {
    one
    \abs-vspace #20
    two
    \abs-vspace #40
    three
  }
}
```

one

two

three

See also `\vspace`.

`\align-on-other` *axis* (non-negative, exact integer) *other-dir* (boolean-or-number) *other* (markup) *self-dir* (boolean-or-number) *self* (markup)

Align markup *self* on markup *other* along *axis*.

This function uses *self-dir* and *other-dir* for mutual alignment of *self* and *other*, respectively, translating *self* as requested relative to its surroundings. *other* is not printed.

If *self-dir* or *other-dir* is #f, use the reference point of *self* or *other*, respectively.

```
\markup \column {
  12
  \align-on-other #X #RIGHT 12
                                #LEFT 12345
  \align-on-other #X #RIGHT 123
                                #LEFT \fermata
  123
  \align-on-other #X #RIGHT 123
```

```

                                ##f \fermata
    }

```

```

    12
    12345
    ♯
    123
    ♯

```

`\center-align arg` (markup)
Align *arg* to its X center.

```

\markup {
  \column {
    one
    \center-align two
    three
  }
}

```

```

    one
    two
    three

```

`\center-column args` (markup list)
Put *args* into a centered column.
See also `\column`.

```

\markup {
  \center-column {
    one
    two
    three
  }
}

```

```

    one
    two
    three

```

Used properties:

- `baseline-skip`

`\column args` (markup list)
Stack the markups in *args* vertically.

The property `baseline-skip` determines the space between markups in *args* (to be more precise, the space between the baselines of the markups).

```

\markup {
  \column {
    one
    two
    three
  }
}

```

one
two
three

The baseline of the output of `\column` is the baseline of its first line.

Used properties:

- `baseline-skip`

`\combine arg1 (markup) arg2 (markup)`

Print *arg1*, then print *arg2* on top of it.

Note: `\combine` cannot take a list of markups enclosed in curly braces as an argument; for this purpose use `\overlay` instead.

```
\markup {
  \fontsize #5
  \override #'(thickness . 2)
  \combine
    \draw-line #'(0 . 4)
    \arrow-head #Y #DOWN ##f
}
```



`\concat args (markup list)`

Concatenate *args* in a horizontal line, without spaces in between.

Strings are concatenated on the input level, allowing ligatures. For example, `\concat { "f" "i" }` is equivalent to "fi".

```
\markup {
  \concat {
    one two three
  }
}
```

onetwothree

`\dir-column args (markup list)`

Make a column of *args*.

Depending on the setting of the `direction` layout property, the arguments are stacked upwards or downwards.

```
\markup {
  \override #`(direction . ,UP)
  \dir-column {
    going up
  }
  \hspace #1
  \dir-column {
    going down
  }
  \hspace #1
  \override #'(direction . 1)
  \dir-column {
    going up
  }
}
```

```

    }

    up          up
    going going going
    down

```

The baseline of the output of `\dir-column` is the baseline of its first line.

Used properties:

- `baseline-skip`
- `direction`

`\fill-line` *args* (markup list)

Put markups *args* into a horizontal line at fixed positions.

If there is a single argument, it gets centered. If there are two arguments, they get aligned to the left and right, respectively. Otherwise, if there are n arguments, the markups are aligned to n equally spaced positions, with the first markup left-aligned, the last markup right-aligned, and the remaining markups centered at the respective positions. If there are no arguments, return an empty stencil.

The width of the horizontal line can be modified by overriding the `line-width` property. The space between arguments is at least as large as the value of the `word-space` property, at the cost of lengthening the line if necessary.

```

\markup {
  \column {
    \fill-line { Words positioned evenly across a line }
    \fill-line { | | | | | }
    \null
    \fill-line {
      \line { Text markups }
      \line { \i{talic} { positioned evenly } }
      \line { across a line }
    }
    \null
    \override #'(line-width . 50)
    \fill-line { Width explicitly specified }
  }
}

```

Words positioned	evenly	across	a	line
Text markups	<i>positioned evenly</i>		across a line	
Width	explicitly	specified		

See also `\justify-line`.

Used properties:

- `line-width` (`#f`)
- `word-space` (`0.6`)
- `text-direction` (`1`)

`\fill-with-pattern` *space* (number) *dir* (direction) *pattern* (markup) *left* (markup) *right* (markup)

Put *left* and *right* at the start and end of a line, respectively, and fill the space in between with repeated *pattern* markups.

Patterns are spaced apart by *space* and aligned to direction *dir*. The width of the line is given by the `line-width` property.

```
\markup \column {
  "right-aligned:"
  \fill-with-pattern #1 #RIGHT . first right
  \fill-with-pattern #1 #RIGHT . second right
  \null
  "center-aligned:"
  \fill-with-pattern #1.5 #CENTER - left right
  \null
  "left-aligned:"
  \override #'(line-width . 50) {
    \fill-with-pattern #2 #LEFT : left first
    \fill-with-pattern #2 #LEFT : left second
  }
}
```

right-aligned:

```
first .....right
second .....right
```

center-aligned:

```
left - - - - - right
```

left-aligned:

```
left: : : : : : : : : : : : : : first
left: : : : : : : : : : : : : : second
```

Used properties:

- `line-width`
- `word-space`

`\general-align` *axis* (integer) *dir* (number) *arg* (markup)

Align *arg* in *axis* direction to the *dir* side.

```
\markup {
  \column {
    one
    \general-align #X #LEFT two
    three
    \null
    one
    \general-align #X #CENTER two
    three
    \null
    \line {
      one
      \general-align #Y #UP two
    }
  }
}
```

```

        three
    }
    \null
    \line {
        one
        \general-align #Y #3.2 two
        three
    }
}

```

```

one
two
three

```

```

one
two
three

```

```

one two three

```

```

one three
two

```

`\halign` *dir* (number) *arg* (markup)

Print *arg* with horizontal alignment set to *dir*.

If *dir* is -1, *arg* is left-aligned, while +1 makes it right-aligned. Values in between interpolate the alignment accordingly.

```

\markup {
  \column {
    one
    \halign #LEFT two
    three
    \null
    one
    \halign #CENTER two
    three
    \null
    one
    \halign #RIGHT two
    three
    \null
    one
    \halign #-5 two
    three
  }
}

```


one
two
three

one
two
three


one
two
three

one
two
three

`\hcenter-in` *length* (number) *arg* (markup)

Center *arg* horizontally within a box of extending *length*/2 to the left and right.

```
\new StaffGroup <<
  \new Staff {
    \set Staff.instrumentName = \markup {
      \hcenter-in #12 Oboe
    }
    c''1
  }
  \new Staff {
    \set Staff.instrumentName = \markup {
      \hcenter-in #12 Bassoon
    }
    \clef tenor
    c'1
  }
>>
```



`\hspace` *amount* (number)

Create an invisible object taking up *amount* horizontal space.

```
\markup {
  one
  \hspace #2
  two
  \hspace #8
  three
}
```

one two three

amount can be also a negative value, which can be best visualized as if the current drawing point gets moved to the left.

```
\markup \concat {
  \hspace #4
  \column {
    \box \concat { AAAA \hspace #4 }
    \box \concat { AAAA \hspace #-4 }
    \box \concat { \hspace #4 AAAA }
    \box \concat { \hspace #-4 AAAA }
  }
}
```



See also `\abs-hspace`.

`\justify` *args* (markup list)

Print *args* as lines aligned both at the left and the right.

Like `\wordwrap`, but with lines stretched to justify the margins. Use `\override #'(line-width . X)` to set the line width; *X* is the number of staff spaces.

```
\markup {
  \justify {
    Lorem ipsum dolor sit amet, consectetur adipisicing elit,
    sed do eiusmod tempor incididunt ut labore et dolore
    magna aliqua. Ut enim ad minim veniam, quis nostrud
    exercitation ullamco laboris nisi ut aliquip ex ea
    commodo consequat.
  }
}
```

Lorem ipsum dolor sit amet, consectetur adipisicing elit, sed do eiusmod tempor incididunt ut labore et dolore magna aliqua. Ut enim ad minim veniam, quis nostrud exercitation ullamco laboris nisi ut aliquip ex ea commodo consequat.

The baseline of the output of `\justify` is the baseline of its first line.

Used properties:

- `text-direction` (1)
- `word-space`
- `line-width` (#f)
- `baseline-skip`

`\justify-field` *symbol* (symbol)

Justify the data that has been assigned to *symbol*.

```

\header {
  title = "My title"
  myText = "Lorem ipsum dolor sit amet, consectetur
    adipisicing elit, sed do eiusmod tempor incididunt
    ut labore et dolore magna aliqua. Ut enim ad minim
    veniam, quis nostrud exercitation ullamco laboris
    nisi ut aliquip ex ea commodo consequat."
}

\paper {
  bookTitleMarkup = \markup {
    \column {
      \fill-line { \fromproperty #'header:title }
      \null
      \justify-field #'header:myText
    }
  }
}

\markup {
  \null
}

```

My title

Lorem ipsum dolor sit amet, consectetur adipisicing elit, sed do eiusmod tempor incididunt ut labore et dolore magna aliqua. Ut enim ad minim veniam, quis nostrud exercitation ullamco laboris nisi ut aliquip ex ea commodo consequat.

`\justify-line` *args* (markup list)

Put markups *args* into a horizontal line, equally spaced.

If there is a single argument, it gets centered. If there are two arguments, they get aligned to the left and right, respectively. Otherwise, the markups are spread to fill the entire line, separated by equally large spaces. If there are no arguments, return an empty stencil.

The width of the horizontal line can be modified by overriding the `line-width` property. The space between arguments is at least as large as the value of the `word-space` property, at the cost of lengthening the line if necessary.

```

\markup {
  \justify-line {
    Constant space between neighboring words
  }
}

```

Constant space between neighboring words

See also `\fill-line`.

Used properties:

- `line-width` (`#f`)

- word-space (0.6)
- text-direction (1)

`\justify-string` (*arg* (string))

Print string *arg* as lines aligned both at the left and the right.

Paragraphs are indicated by double newlines. Use `\override #'(line-width . X)` to set the line width; *X* is the number of staff spaces.

```
\markup {
  \override #'(line-width . 40)
  \justify-string "Lorem ipsum dolor sit amet, consectetur
    adipisicing elit, sed do eiusmod tempor incididunt ut
    labore et dolore magna aliqua.
```

```

    Ut enim ad minim veniam, quis nostrud exercitation
    ullamco laboris nisi ut aliquip ex ea commodo
    consequat.
```

```

    Excepteur sint occaecat cupidatat non proident, sunt
    in culpa qui officia deserunt mollit anim id est
    laborum"
```

```
}
```

Lorem ipsum dolor sit amet, consectetur
 adipisicing elit, sed do eiusmod tempor
 incididunt ut labore et dolore magna
 aliqua.

Ut enim ad minim veniam, quis nostrud
 exercitation ullamco laboris nisi ut
 aliquip ex ea commodo consequat.

Excepteur sint occaecat cupidatat non
 proident, sunt in culpa qui officia
 deserunt mollit anim id est laborum

The baseline of the output of `\justify-string` is the baseline of its first line.

Used properties:

- text-direction (1)
- word-space
- line-width
- baseline-skip

`\left-align` (*arg* (markup))

Align *arg* on its left edge.

```
\markup {
  \column {
    one
    \left-align two
    three
  }
}
```

one
two
three

`\left-column` *args* (markup list)

Put *args* into a left-aligned column.

```
\markup {
  \left-column {
    one
    two
    three
  }
}
```

one
two
three

Used properties:

- `baseline-skip`

`\line` *args* (markup list)

Put *args* into a horizontal line.

The property `word-space` determines the space between markups in *args*. For right-to-left scripts like Hebrew, `text-direction` should be set to -1.

```
\markup
  \override #'(word-space . 3)
  \column {
    \line { "A B" "C D" "E F" }
    \override #'(text-direction . -1)
    \line { "A B" "C D" "E F" }
  }
```

A B C D E F
E F C D A B

Used properties:

- `text-direction` (1)
- `word-space`

`\lower` *amount* (number) *arg* (markup)

Lower *arg* by the distance *amount*.

A negative *amount* indicates raising; see also `\raise`.

The argument to `\lower` is the vertical displacement amount, measured in (global) staff spaces, which is independent of the markup's current font size. If you need vertical movement that takes the font size into account, use `\translate-scaled` instead.

This function is normally used to move one element inside of a markup relative to the other elements. When using it on the whole markup, bear in mind that spacing mechanisms that place the markup itself on the page could cancel this shift. Consider using grob properties such as `padding`, `Y-offset`, or `extra-offset`, or spacing variables such as `markup-system-spacing`.

```

\markup {
  one
  \lower #3 two
  three
}

one    three
      two

```

`\overlay` *args* (markup list)

Take a list of markups *args* and combine them.

```

\markup {
  \fontsize #5
  \override #'(thickness . 2)
  \overlay {
    \draw-line #'(0 . 4)
    \arrow-head #Y #DOWN ##f
    \translate #'(0 . 4) \arrow-head #Y #UP ##f
  }
}

```



`\pad-around` *amount* (number) *arg* (markup)

Add padding *amount* all around *arg*.

Identical to function `\pad-markup`.

```

\markup {
  \box {
    default
  }
  \hspace #2
  \box {
    \pad-around #0.5 {
      padded
    }
  }
}

```

default

padded

`\pad-markup` *amount* (number) *arg* (markup)

Add padding *amount* all around *arg*.

Identical to function `\pad-around`.

```

\markup {
  \box {
    default
  }
  \hspace #2
  \box {
    \pad-markup #1 {
      padded
    }
  }
}

```

```

    }
  }
}

```

default

padded

`\pad-to-box` *x-ext* (pair of numbers) *y-ext* (pair of numbers) *arg* (markup)

Make *arg* take at least *x-ext*, *y-ext* space.

```

\markup {
  \box {
    default
  }
  \hspace #4
  \box {
    \pad-to-box #'(0 . 10) #'(0 . 3) {
      padded
    }
  }
}

```

default

padded

`\pad-x` *amount* (number) *arg* (markup)

Add padding *amount* around *arg* in the X direction.

```

\markup {
  \box {
    default
  }
  \hspace #4
  \box {
    \pad-x #2 {
      padded
    }
  }
}

```

default

padded

`\pad-x-left` *amount* (number) *arg* (markup)

Add padding *amount* to the left of *arg* in the X direction.

```

\markup {
  \box {
    default
  }
  \hspace #4
  \box {
    \pad-x-left #2 {
      padded
    }
  }
}

```

default	padded

`\pad-x-right` *amount* (number) *arg* (markup)

Add padding *amount* to the right of *arg* in the X direction.

```
\markup {
  \box {
    default
  }
  \hspace #4
  \box {
    \pad-x-right #2 {
      padded
    }
  }
}
```

default	padded

`\put-adjacent` *axis* (integer) *dir* (direction) *arg1* (markup) *arg2* (markup)

Put *arg2* next to *arg1* along *axis* to the *dir* side, without moving *arg1*.

```
\markup \column {
  text
  \put-adjacent #X #LEFT text *
  text
}

text
*text
text
```

`\raise` *amount* (number) *arg* (markup)

Raise *arg* by the distance *amount*.

A negative *amount* indicates lowering, see also `\lower`.

The argument to `\raise` is the vertical displacement amount, measured in (global) staff spaces, which is independent of the markup's current font size. If you need vertical movement that takes the font size into account, use `\translate-scaled` instead.

This function is normally used to move one element inside of a markup relative to the other elements. When using it on the whole markup, bear in mind that spacing mechanisms that place the markup itself on the page could cancel this shift. Consider using grob properties such as padding, Y-offset, or extra-offset, or spacing variables such as markup-system-spacing.

```
\markup { C \small \bold \raise #1.0 9/7+ }
```

C 9/7+

`\right-align` *arg* (markup)

Align *arg* on its right edge.


```

\markup {
  \column {
    one
    \right-align two
    three
  }
}

one
two
three

```

`\right-column` *args* (markup list)

Put *args* into a right-aligned column.

```

\markup {
  \right-column {
    one
    two
    three
  }
}

one
two
three

```

Used properties:

- `baseline-skip`

`\rotate` *ang* (number) *arg* (markup)

Rotate *arg* by *ang* degrees around its center.

```

\markup {
  default
  \hspace #2
  \rotate #45
  \line {
    rotated 45°
  }
}

```

default

rotated 45°

`\translate` *offset* (pair of numbers) *arg* (markup)

Translate *arg* relative to its surroundings.

offset is a pair of numbers representing the displacement in the X and Y axes. See also `\translate-scaled`.

This function is normally used to move one element inside of a markup relative to the other elements. When using it on the whole markup, bear in mind that spacing mechanisms that place the markup itself on the page could cancel this shift. Consider using grob properties such as `padding`, `X-offset`, `Y-offset` or `extra-offset`, or spacing variables such as `markup-system-spacing`.

```

\markup {
  *
  \translate #'(2 . 3)
  \line { translated two spaces right, three up }
}

      translated two spaces right, three up
      *

```

`\translate-scaled` *offset* (pair of numbers) *arg* (markup)

Translate *arg* by *offset*, scaling the offset by the font size.

This function is normally used to move one element inside of a markup relative to the other elements. When using it on the whole markup, bear in mind that spacing mechanisms that place the markup itself on the page could cancel this shift. Consider using grob properties such as padding, X-offset, Y-offset or extra-offset, or spacing variables such as markup-system-spacing.

See also `\translate`.

```

\markup {
  \fontsize #5 {
    * \translate #'(2 . 3) translate
    \hspace #2
    * \translate-scaled #'(2 . 3) translate-scaled
  }
}

```

*
translate
*
translate-scaled

Used properties:

- font-size (0)

`\vcenter` *arg* (markup)

Align *arg* to its Y center.

```

\markup {
  one
  \vcenter two
  three
}

      one two three

```

`\vspace` *amount* (number)

Create an invisible object taking up vertical space of *amount* multiplied by 3.

```

\markup {
  \center-column {
    one
    \vspace #1
    two
    \vspace #3
    three
  }
}

```


one

two

three

amount can be also a negative value, which can be best visualized as if the current drawing point gets moved up.

```
\markup {
  \vspace #1
  \box \column { AAAA \vspace #0.4 }
  \box \column { AAAA \vspace #-0.4 }
  \box \column { \vspace #0.4 AAAA }
  \box \column { \vspace #-0.4 AAAA }
}
```



See also `\abs-vspace`.

`\wordwrap` *args* (markup list)

Print *args* as left-aligned lines.

This function provides simple word-wrap. Use `\override #'(line-width . X)` to set the line width; *X* is the number of staff spaces.

```
\markup {
  \wordwrap {
    Lorem ipsum dolor sit amet, consectetur adipisicing elit,
    sed do eiusmod tempor incididunt ut labore et dolore
    magna aliqua. Ut enim ad minim veniam, quis nostrud
    exercitation ullamco laboris nisi ut aliquip ex ea
    commodo consequat.
  }
}
```

Lorem ipsum dolor sit amet, consectetur adipisicing elit, sed do
 eiusmod tempor incididunt ut labore et dolore magna aliqua. Ut
 enim ad minim veniam, quis nostrud exercitation ullamco
 laboris nisi ut aliquip ex ea commodo consequat.

The baseline of the output of `\wordwrap` is the baseline of its first line.

Used properties:

- `text-direction` (1)
- `word-space`
- `line-width` (#f)
- `baseline-skip`

`\wordwrap-field` *symbol* (symbol)

Word-wrap the data that has been assigned to *symbol*.

```

\header {
  title = "My title"
  myText = "Lorem ipsum dolor sit amet, consectetur
    adipisicing elit, sed do eiusmod tempor incididunt ut
    labore et dolore magna aliqua. Ut enim ad minim
    veniam, quis nostrud exercitation ullamco laboris nisi
    ut aliquip ex ea commodo consequat."
}

\paper {
  bookTitleMarkup = \markup {
    \column {
      \fill-line { \fromproperty #'header:title }
      \null
      \wordwrap-field #'header:myText
    }
  }
}

\markup {
  \null
}

```

My title

Lorem ipsum dolor sit amet, consectetur adipisicing elit, sed do eiusmod tempor incididunt ut labore et dolore magna aliqua. Ut enim ad minim veniam, quis nostrud exercitation ullamco laboris nisi ut aliquip ex ea commodo consequat.

`\wordwrap-string arg (string)`

Print string *arg* as left-aligned lines.

Paragraphs are indicated by double newlines. Use `\override #'(line-width . X)` to set the line width; *X* is the number of staff spaces.

```

\markup {
  \override #'(line-width . 40)
  \wordwrap-string "Lorem ipsum dolor sit amet,
    consectetur adipisicing elit, sed do eiusmod tempor
    incididunt ut labore et dolore magna aliqua.

    Ut enim ad minim veniam, quis nostrud exercitation
    ullamco laboris nisi ut aliquip ex ea commodo
    consequat.

    Excepteur sint occaecat cupidatat non proident,
    sunt in culpa qui officia deserunt mollit anim id
    est laborum"
}

```

Lorem ipsum dolor sit amet,
 consectetur adipisicing elit, sed do
 eiusmod tempor incididunt ut labore et
 dolore magna aliqua.
 Ut enim ad minim veniam, quis
 nostrud exercitation ullamco laboris
 nisi ut aliquip ex ea commodo
 consequat.
 Excepteur sint occaecat cupidatat non
 proident, sunt in culpa qui officia
 deserunt mollit anim id est laborum

The baseline of the output of `\wordwrap-string` is the baseline of its first line.

Used properties:

- `text-direction` (1)
- `word-space`
- `line-width`
- `baseline-skip`

A.1.3 Graphical markup

`\arrow-head axis (integer) dir (direction) filled (boolean)`

Print an arrow head along *axis* in direction *dir*.

Fill the head if *filled* is set to `#t`.

```

\markup {
  \fontsize #5 {
    \general-align #Y #DOWN {
      \arrow-head #Y #UP ##t
      \arrow-head #Y #DOWN ##f
      \hspace #2
      \arrow-head #X #RIGHT ##f
      \arrow-head #X #LEFT ##f
    }
  }
}

```

▲Υ ><

`\beam width (number) slope (number) thickness (number)`

Draw a beam with given *width*, *slope*, and *thickness*.

```

\markup {
  \beam #5 #1 #2
}

```



`\bracket arg (markup)`

Draw vertical brackets around *arg*.

```
\markup {
  \bracket {
    \note {2.} #UP
  }
}
```




`\circle arg` (markup)

Draw a circle around *arg*.

Use properties *thickness*, *circle-padding*, and *font-size* to set the line thickness and padding around the markup. If *bbox* is set to *#t*, make the circle enclose the bounding box of *arg*, otherwise use either the width or the height of *arg* (whatever is larger) as the diameter.

```
\markup {
  \circle {
    Hi
  }
  \circle {
    \center-column { "short" "short" "very very long" }
  }
  \override #'(bbox . #t) \circle {
    \center-column { "short" "short" "very very long" }
  }
}
```



Note that the circle does not horizontally displace its argument. Use markup commands like `\left-align` or `\table` to make LilyPond realign it.

Used properties:

- *bbox* (*#f*)
- *circle-padding* (*0.2*)
- *font-size* (*0*)
- *thickness* (*1*)

`\draw-circle radius` (number) *thickness* (number) *filled* (boolean)

Draw a circle with given *radius* and *thickness*.

Fill the circle if *filled* is set to *#t*.

```
\markup {
  \draw-circle #2 #0.5 ##f
  \hspace #2
  \draw-circle #2 #0 ##t
}
```



`\draw-dashed-line` *dest* (pair of numbers)

Draw a dashed line along vector *dest*.

Properties `on` and `off` give the length of a dash and the space between two dashes, respectively; `phase` shortens the first dash by the given amount.

If the `full-length` property is set to `#t` (which is the default), the value of property `off` (and `on` under some boundary conditions) gets adjusted so that there is neither whitespace at the end of the line nor the last dash truncated.


```
\markup {
  \override #'((on . 0.3) (off . 0.5))
  \draw-dashed-line #'(6 . 2)

  \draw-dashed-line #'(6 . 2)

  \override #'(full-length . #f)
  \draw-dashed-line #'(6 . 2)

  \override #'(phase . 0.5)
  \draw-dashed-line #'(6 . 2)

  \override #'((full-length . #f) (phase . 0.5))
  \draw-dashed-line #'(6 . 2)
}
```



Used properties:


- `full-length` (`#t`)
- `phase` (0)
- `off` (1)
- `on` (1)
- `thickness` (1)

`\draw-dotted-line` *dest* (pair of numbers)

Draw a dotted line along vector *dest*.

Property `off` gives the space between two dots; its value gets adjusted so that the first and last dot exactly start and end the line, respectively. `phase` shifts all dots along the vector by the given amount.

```
\markup {
  \draw-dotted-line #'(5.1 . 2.3)
  \override #'((thickness . 2) (off . 0.2))
  \draw-dotted-line #'(5.1 . 2.3)
}
```



Used properties:

- `phase` (0)
- `off` (1)
- `thickness` (1)

`\draw-hline`

Draw a horizontal line.

The property `span-factor` sets the length of the line as a multiple of the `line-width` property.

```
\markup {
  \column {
    \draw-hline
    \override #'(span-factor . 1/3)
    \draw-hline
  }
}
```

Used properties:

- `span-factor` (1)
- `line-width`
- `thickness` (1)

`\draw-line` *dest* (pair of numbers)

Draw a line along vector *dest*.

```
\markup {
  \draw-line #'(4 . 4)
  \override #'(thickness . 5)
  \draw-line #'(-3 . 0)
}
```



Used properties:

- `thickness` (1)


`\draw-squiggle-line` *sq-length* (number) *dest* (pair of numbers) *eq-end?* (boolean)

Draw a squiggled line along vector *dest*.

sq-length is the length of the first bow; this value gets always adjusted so that an integer number of squiggles is printed. If *eq-end?* is set to `#t`, the squiggled line ends with a bow in the same direction as the starting one.

The appearance of the squiggled line may be customized by overriding the `thickness`, `angularity`, `height`, and `orientation` properties.

```
\markup
\column {
  \draw-squiggle-line #0.5 #'(6 . 0) ##t
  \override #'(orientation . -1)
  \draw-squiggle-line #0.5 #'(6 . 0) ##t
  \draw-squiggle-line #0.5 #'(6 . 0) ##f
  \override #'(height . 1)
  \draw-squiggle-line #0.5 #'(6 . 0) ##t
  \override #'(thickness . 5)
  \draw-squiggle-line #0.5 #'(6 . -2) ##t
  \override #'(angularity . 2)
  \draw-squiggle-line #0.5 #'(6 . 2) ##t
}
```

Used properties:

- orientation (1)
- height (0.5)
- angularity (0)
- thickness (0.5)

`\ellipse arg (markup)`

Draw an ellipse around *arg*.

Use properties *thickness*, *x-padding*, *y-padding*, and *font-size* to set the line thickness and padding around the markup.

This is the same as function `\oval` but with different padding defaults.

```
\markup {
  \ellipse {
    Hi
  }
}
```



Note that the ellipse does not horizontally displace its argument. Use markup commands like `\left-align` or `\table` to make LilyPond realign it.

Used properties:

- *y-padding* (0.2)
- *x-padding* (0.2)
- *font-size* (0)
- *thickness* (1)

`\epsfile axis (number) size (number) file-name (string)`

Inline an image *file-name*, scaled along *axis* to *size*.

See `\image` for details on this command; calling

```
\markup \epsfile axis size file-name
```

is the same as

```
\markup
  \override #'(background-color . #f)
  \image axis size file-name
```

`\filled-box xext (pair of numbers) yext (pair of numbers) blot (number)`

Draw a box of dimensions *xext* and *yext*, with rounded corners given by *blot*.

For example,

```
\filled-box #'(-.3 . 1.8) #'(-.3 . 1.8) #0
```

creates a box extending horizontally from -0.3 to 1.8 and vertically from -0.3 up to 1.8, with corners formed from a circle of diameter 0 (i.e., sharp corners).

```

\markup {
  \filled-box #'(0 . 4) #'(0 . 4) #0
  \filled-box #'(0 . 2) #'(-4 . 2) #0.4
  \combine
    \filled-box #'(1 . 8) #'(0 . 7) #0.2
    \with-color #white
    \filled-box #'(3.6 . 5.6) #'(3.5 . 5.5) #0.7
}

```



`\hbracket arg (markup)`

Draw horizontal brackets around *arg*.

```

\markup {
  \hbracket {
    \line {
      one two three
    }
  }
}

```

one two three

`\image axis (number) size (number) file-name (string)`

Inline an image *file-name*, scaled along *axis* to *size*.

The image format is determined based on the extension of *file-name*, which should be .png for a PNG image, or .eps for an EPS image (.PNG and .EPS are allowed as well).

EPS files are only supported in the PostScript backend – for all output formats –, and in the Cairo backend – when creating PostScript or EPS output.

If the image has transparency, it will appear over a colored background with the color specified by the `background-color` property, which defaults to "white".

To disable the colored background, set `background-color` to #f. For EPS images, this always works (where EPS images work in the first place). On the other hand, for PNG images, it works in the Cairo backend (which can output all supported formats), as well as in the SVG backend, but *not* in the PostScript backend, which is the default. See Section “Advanced command-line options for LilyPond” in *Application Usage* for how to activate the Cairo backend.

Use `\withRelativeDir` as a prefix to *file-name* if the file should be found relative to the input file.

Used properties:

- `background-color` ("white")

`\oval arg (markup)`

Draw an oval around *arg*.

Use properties `thickness`, `x-padding`, `y-padding`, and `font-size` to set the line thickness and padding around the markup.

This is the same as function `\ellipse` but with different padding defaults.

```
\markup {
  \oval {
    Hi
  }
}
```



Note that the oval does not horizontally displace its argument. Use markup commands like `\left-align` or `\table` to make LilyPond realign it.

Used properties:


- `y-padding` (0.75)
- `x-padding` (0.75)
- `font-size` (0)
- `thickness` (1)

`\parenthesize` *arg* (markup)

Draw parentheses around *arg*.

This is useful for parenthesizing a column containing several lines of text.

```
\markup {
  \parenthesize
  \column {
    foo
    bar
  }
  \override #'(angularity . 2)
  \parenthesize
  \column {
    bah
    baz
  }
}
```



Used properties:

- `width` (0.25)
- `line-thickness` (0.1)
- `thickness` (1)
- `size` (1)
- `padding`
- `angularity` (0)

`\path` *thickness* (number) *commands* (list)

Draw a path with line *thickness* according to the directions given in *commands*.

commands is a list of lists where the car of each sublist is a drawing command and the cdr comprises the associated arguments for each command.

There are seven commands available to use in *commands*: `moveto`, `rmoveto`, `lineto`, `rlineto`, `curveto`, `rcurveto`, and `closepath`. Note that the commands that begin

with ‘r’ are the relative variants of the other three commands. You may also use the standard SVG single-letter equivalents: `moveto` = M, `lineto` = L, `curveto` = C, `closepath` = Z. The relative commands are written lowercase: `rmoveto` = r, `rlineto` = l, `rcurveto` = c.

The commands `moveto`, `rmoveto`, `lineto`, and `rlineto` take 2 arguments, namely the X and Y coordinates of the destination point.

The commands `curveto` and `rcurveto` create cubic Bézier curves, and take 6 arguments; the first two are the X and Y coordinates for the first control point, the second two are the X and Y coordinates for the second control point, and the last two are the X and Y coordinates for the destination point.

The `closepath` command takes zero arguments and closes the current subpath in the active path.

Line-cap styles and line-join styles may be customized by overriding the `line-cap-style` and `line-join-style` properties, respectively. Available line-cap styles are `butt`, `round`, and `square`. Available line-join styles are `miter`, `round`, and `bevel`.

The property `filled` specifies whether or not the path is filled with color.

```
samplePath =
  #'((lineto -1 1)
    (lineto 1 1)
    (lineto 1 -1)
    (curveto -5 -5 -5 5 -1 0)
    (closepath))

\markup \scale #'(2 . 2) {
  \path #0.25 #samplePath

  \override #'(line-join-style . miter)
  \path #0.25 #samplePath

  \override #'(filled . #t)
  \path #0.25 #samplePath
}
```



Used properties:

- `filled (#f)`
- `line-join-style (round)`
- `line-cap-style (round)`

`\polygon` *points* (list of number pairs)

A polygon delimited by the list of *points*.

Property `extroversion` defines how the shape of the polygon is adapted to its thickness: if it is 0, the polygon is traced as-is. If it is -1, the outer side of the line is just on the given points. If set to 1, the line has its inner side on the points. The thickness property controls the thickness of the line; for filled polygons, this means the diameter of the blot.

```

regularPentagon =
  #'((1 . 0) (0.31 . 0.95) (-0.81 . 0.59)
    (-0.81 . -0.59) (0.31 . -0.95))

\markup \scale #'(2 . 2) {
  \polygon #'((-1 . -1) (0 . -3) (2 . 2) (1 . 2))
  \override #'(filled . #f)
  \override #'(thickness . 2)
  \combine
    \with-color #(universal-color 'blue)
    \polygon #regularPentagon
    \with-color #(universal-color 'vermillion)
    \override #'(extroversion . 1)
    \polygon #regularPentagon
}

```



Used properties:

- `thickness` (1)
- `filled` (#f)
- `extroversion` (0)

`\postscript` *str* (string)

Insert *str* directly into the output as a PostScript command string.

This command is meant as a *last resort*. Almost all needs are better fulfilled by other markup commands (see, for example, `\path` and `\draw-line`). If you do use this command, keep the following points in mind:

- `\postscript` does not work in SVG output.
- Only a subset of the PostScript language is supported during the conversion from PostScript to PDF.
- There are no stability guarantees on the details of how LilyPond produces its own output (i.e., the context into which the PostScript code is inserted). They may change substantially across versions.
- LilyPond cannot understand the shape of the drawing, leading to suboptimal spacing. Usually, it is necessary to explicitly set up dimensions with a command like `\with-dimensions`.
- Depending on how you install LilyPond, the version of the PostScript interpreter (Ghostscript) can vary, and some of its features may be disabled.

str is processed with the following constraints.

- The string is embedded into the (intermediate) output file with the PostScript commands

```

gsave currentpoint translate 0.1 setlinewidth
before and
grestore
after it.

```

- After these preceding commands (i.e., `currentpoint translate`) the origin of the current transformation is the reference point of `\postscript`. Scale and rotation of the current transformation reflect the global staff line distance and (if applied) other transformation markup commands (e.g., `\scale` and `\rotate`) encapsulating the `\postscript` command.
- The current point is set to the coordinate (0, 0).
- If an unwanted line appears at the beginning of your PostScript code, you are probably missing a call to `newpath`.

```

ringsps = "
  0.15 setlinewidth
  0.9 0.6 moveto
  0.4 0.6 0.5 0 361 arc
  stroke
  1.0 0.6 0.5 0 361 arc
  stroke
"

rings = \markup {
  \with-dimensions #'(-0.2 . 1.6) #'(0 . 1.2)
  \postscript #ringsps
}

\relative c'' {
  c2^\bings
  a2_\bings
}

```



`\rounded-box arg (markup)`

Draw a box with rounded corners around *arg*.

This function looks at properties `thickness`, `box-padding`, and `font-size` to determine the line thickness and padding around the *arg*. The `corner-radius` property defines the radius of the round corners (default value is 1).

```

c4^\markup {
  \rounded-box {
    Overtura
  }
}
c,8. c16 c4 r

```




Note that the box does not horizontally displace its argument. Use markup commands like `\left-align` or `\table` to make LilyPond realign it.

```

\markup {
  \override #'(box-padding . 1.5)
  \column {
    "text"
    \rounded-box "text"
    \left-align \rounded-box "text"
  }
}

```



Used properties:

- box-padding (0.5)
- font-size (0)
- corner-radius (1)
- thickness (1)

`\scale` *factor-pair* (pair of numbers) *arg* (markup)

Scale *arg*.

factor-pair is a pair of numbers representing the scaling factor of the X and Y axes. Negative values may be used to produce mirror images.

```

\markup {
  \line {
    \scale #'(2 . 1)
    stretched
    \scale #'(1 . -1)
    mirrored
  }
}

```

stretched mirrored

`\triangle` *filled* (boolean)

Draw a triangle.

Fill the triangle if *filled* is set to #t.

The appearance can be controlled with properties *extroversion*, *font-size*, and *thickness*.

```

\markup {
  \triangle ##t
  \triangle ##f
  \override #'(font-size . 5)
  \override #'(thickness . 5) {
    \override #'(extroversion . 1)
    \triangle ##f
    \override #'(extroversion . -1)
    \triangle ##f
  }
}

```



Used properties:

- thickness (1)
- font-size (0)
- extroversion (0)

`\with-url url (string) arg (markup)`

Add a link to URL *url* around *arg*.

This only works in the PDF backend.²

```
\markup {
  \with-url "https://lilypond.org/" {
    LilyPond ... \italic {
      music notation for everyone
    }
  }
}
```

LilyPond ... music notation for everyone

A.1.4 Markup for music and musical symbols

`\accidental alteration` (an exact rational number)

Select an accidental glyph for *alteration*, given as a rational number.

Use `\text-accidental` instead if you need glyph representation forms that fit and align well with text.

```
\markup {
  text
  \tiny { \accidental #1/2 \accidental #-1/2 }
  text
  \tiny { \text-accidental #1/2 \text-accidental #-1/2 }
  text
}

text #b text #b text
```

Used properties:

- alteration-glyph-name-alist

`\bar-line strg (string)`

Print a bar line in markup.

The allowed characters for input string *strg* are ‘;|.:!S[]{}’, having the same meaning as with the `\bar` command. The additional characters ‘{’ and ‘}’ denote left and right braces, respectively.

The output is vertically centered.

Changes of font-size are respected.

The default of height is 4 staff-space units. Apart from the bracket tips of a bracket bar line and the segno bar line all other bar lines are scaled with height. We don’t scale bracket tips and segno to meet the behavior of `SystemStartBracket` and the segno bar line.

² Due to technical limitations the link doesn’t work here in the Notation Reference.

`\bar-line` is further customizable by overriding `dot-count` and `dash-count` for dotted and dashed bar lines. The values for `hair-thickness`, `kern` and `thick-thickness` are customizable as well; defaults are the same as the values of the corresponding `BarLine` grob properties.

```
\markup {
  \override #'(word-space . 2)
  \column {
    \line {
      Examples
      \fontsize #-5 \translate-scaled #'(0 . 2) {
        \bar-line ":|.|:"
        \bar-line ";!S!;"
        \bar-line "]{|}["
      }
    }
    \line {
      Examples
      \fontsize #0 \translate-scaled #'(0 . 2) {
        \bar-line ":|.|:"
        \bar-line ";!S!;"
        \bar-line "]{|}["
      }
    }
    \line {
      Examples
      \fontsize #5 \translate-scaled #'(0 . 2) {
        \bar-line ":|.|:"
        \bar-line ";!S!;"
        \bar-line "]{|}["
      }
    }
  }
}
```

Examples 

Examples 

Examples 

Used properties:

- `thick-thickness` (6.0)
- `kern` (3.0)
- `hair-thickness` (1.9)
- `dash-count` (5)
- `dot-count` (4)

- `height` (4)
- `font-size` (0)

`\coda` Draw a coda sign.

```
\markup {
  \coda
}
```

$\oplus$

`\compound-meter` *time-sig* (number or pair)

Draw a numeric time signature based on *time-sig*.

time-sig can be a single number, a pair of numbers, a simple list, or a list of lists, as the following example demonstrates.

```
\markuplist {
  \override #'(baseline-skip . 4.5)
  \override #'(padding . 4.5)
  \table #'(-1 -1) {
    "Single number" \compound-meter #3
    "Conventional" \line {
      \compound-meter #'(4 . 4) or
      \compound-meter #'(4 4)
    }
    "Subdivided" \compound-meter #'(2 3 5 8)
    "Alternating" \line {
      \compound-meter #'((2) (3)) or
      \compound-meter #'((2 3 8) (3 4))
    }
  }
}
```

Single number **3**

Conventional $\frac{4}{4}$ or $\frac{4}{4}$

Subdivided $2 + \frac{3}{8} + 5$

Alternating $2 + 3$ or $2 + \frac{3}{8} + \frac{3}{4}$

Setting the `denominator-style` property to `note` prints denominators as a note and dots when exact representation is possible. Example:

```
\markup {
  \override #'(denominator-style . note)
  \line {
    \compound-meter #'(2 2) or
    \compound-meter #'(4 1/2) or
    \compound-meter #'((2 8/3) (3 4)) but not
    \compound-meter #'(8 20)
  }
}
```

$$\frac{2}{\text{f}} \text{ or } \frac{4}{\text{f}} \text{ or } \frac{2}{\text{f}} + \frac{3}{\text{f}} \text{ but not } \frac{8}{20}$$

The `nested-fraction-mixed` property controls whether fractional parts are printed as mixed numbers or as common fractions. Example:

```
\markup {
  \override #'(nested-fraction-mixed . #f)
  \compound-meter #'(5/2 4) or
  \override #'(nested-fraction-mixed . #t)
  \compound-meter #'(5/2 4)
}
```

$$\frac{5/2}{4} \text{ or } \frac{2\frac{1}{2}}{4}$$

The `nested-fraction-orientation` property controls how nested fractions are arranged. Supported values are `horizontal` and `vertical`. Example:

```
\markup {
  \override #'(nested-fraction-orientation . horizontal)
  \compound-meter #'(5/2 4) or
  \override #'(nested-fraction-orientation . vertical)
  \compound-meter #'(5/2 4)
}
```

$$\frac{2^{1/2}}{4} \text{ or } \frac{2\frac{1}{2}}{4}$$

The `nested-fraction-relative-font-size` property controls the size of the numerals in nested fractions. Recommended values are `-5.5` and `0`. Using large numerals may take precedence over related properties. Example:

```
\markup {
  \override #'(nested-fraction-relative-font-size . -5.5)
  \compound-meter #'(5/2 4) or
  \override #'(nested-fraction-relative-font-size . 0)
  \compound-meter #'(5/2 4)
}
```

$$\frac{2\frac{1}{2}}{4} \text{ or } 2\frac{1}{2}$$

Used properties:

- `note-staff-position` (-2)
- `note-head-style` (())
- `note-flag-style` (())
- `note-dots-direction` (0)
- `nested-fraction-relative-font-size` (())
- `nested-fraction-orientation` (default)
- `nested-fraction-mixed` (#t)
- `font-size` (0)
- `denominator-style` (default)

`\customTabClef` *num-strings* (integer) *staff-space* (number)

Draw a clef in sans-serif style for a tablature with *num-strings* lines spaced by *staff-space*.

This markup command is used to implement `\clef moderntab` within a `TabStaff` context.

```
\markup {
  \customTabClef #4 #1
}
```



`\doubleflat`

Draw a double flat symbol.

```
\markup {
  \doubleflat
}
```



`\doublesharp`

Draw a double sharp symbol.

```
\markup {
  \doublesharp
}
```




`\fermata` Create a fermata glyph.

If property `direction` is `DOWN`, use an inverted glyph.

Note that within music, one would normally use the `\fermata` articulation instead of a markup.

```
{ c''1^\markup \fermata d''1_\markup \fermata }
```

```
\markup { \fermata \override #`(direction . ,DOWN) \fermata }
```



Used properties:

- `direction` (1)

`\flat`

Draw a flat symbol.

```
\markup {
  \flat
}
```




`\multi-measure-rest-by-number` *length* (non-negative, exact integer)

Return a multi-measure rest symbol for *length* measures.

If the number of measures is greater than the number given by `expand-limit` a thick horizontal line is printed. For every multi-measure rest lasting more than one measure a number is printed on top. However, if property `multi-measure-rest-number` is set to `#t`, this number gets suppressed.

```
\markup {
  Multi-measure rests may look like
  \multi-measure-rest-by-number #12
  or
  \override #'(multi-measure-rest-number . #f)
  \multi-measure-rest-by-number #7
  (church rests)
}
```

Multi-measure rests may look like  or  (church rests)

Used properties:

- `multi-measure-rest-number` (`#t`)
- `width` (8)
- `expand-limit` (10)
- `hair-thickness` (2.0)
- `thick-thickness` (6.6)
- `word-space`
- `style` (`()`)
- `font-size` (0)

`\musicglyph` *glyph-name* (string)

Print music symbol *glyph-name*.

See Section “The Emmentaler font” in *Notation Reference* for a complete listing of the possible glyph names.

```
\markup {
  \musicglyph "f"
  \musicglyph "rests.2"
  \musicglyph "clefs.G_change"
}
```



`\natural` Draw a natural symbol.

```
\markup {
  \natural
}
```



`\note duration (duration) dir (number)`

Draw a note with a given duration and a stem.

The note duration is specified with *duration* (setting both the note head type and the number of augmentation dots). The stem direction and length is given by *dir*.

This function is wrapper around `\note-by-number`; its documentation gives more details on the available properties.

```
\markup {
  \note {4..} #UP
  \hspace #2
  \override #'(style . cross)
  \note {4..} #0.75
  \hspace #2
  \note {\breve} #0
}
```



Used properties:

- `style` (default)
- `dots-direction` (0)
- `flag-style` (())
- `font-size` (0)

`\note-by-number log (number) dot-count (number) dir (number)`

Draw a note with a given length, a number of dots, and a stem.

The note length is specified with *log*, the number of dots with *dot-count*, and the stem direction and length with *dir*. Fractional values for *dir* can be used to control the length of the stem. Value 0 suppresses the stem completely; this is useful for note head styles that don't take stems or come with built-in stems (like Kievan).

Ancient note head styles (via the *style* property, see Section B.9 [Note head styles], page 920) get mensural-style flags by default; use the *flag-style* property to override this. Supported flag styles are *default*, *old-straight-flag*, *modern-straight-flag*, *flat-flag*, *stacked*, *mensural*, and *neomensural*. The last flag style is the same as *mensural* and provided for convenience.

```
\markup {
  \note-by-number #3 #0 #DOWN
  \hspace #2
  \note-by-number #1 #2 #0.8
  \hspace #2
  \override #'(style . petrucci)
  \note-by-number #3 #0 #UP
  \hspace #2
  \override #'(flag-style . modern-straight-flag)
  \note-by-number #4 #0 #DOWN
  \override #'(style . kievan)
```

```
\note-by-number #2 #0 #0
}
```



See also function `\note`.

Used properties:

- `style` (default)
- `dots-direction` (0)
- `flag-style` (())
- `font-size` (0)


`\rest duration` (duration)

Return a rest symbol with length *duration*.

If the `multi-measure-rest` property is set to `#t`, a multi-measure rest symbol may be returned. In this case the duration needs to be entered as `{ 1*N }` to get a multi-measure rest for *N* bars. Actually, only the scaling factor (i.e., the number after ‘*’) determines the length; the basic duration is disregarded.

See also functions `\rest-by-number` and `\multi-measure-rest-by-number` for more information on the used properties.

```
\markup {
  Rests:
  \hspace #2
  \rest { 4.. }
  \hspace #2
  \rest { \breve }
  \hspace #2
  Multi-measure rests:
  \override #'(multi-measure-rest . #t)
  {
    \hspace #2
    \rest { 1*7 }
    \hspace #2
    \rest { 1*12 }
  }
}
```

Rests:  Multi-measure rests: 

Used properties:

- `multi-measure-rest-number` (#t)
- `width` (8)
- `expand-limit` (10)
- `hair-thickness` (2.0)
- `thick-thickness` (6.6)
- `word-space`
- `style` (())
- `font-size` (0)

- `style (())`
- `ledgers ((-1 0 1))`
- `font-size (0)`

`\rest-by-number` *log* (integer) *dot-count* (integer)

Draw a rest of length *log*, with *dot-count* dots.

For duration logs that appear in the `ledgers` property, rest symbols with ledger lines are selected.

```
\markup {
  \rest-by-number #3 #2
  \hspace #2
  \rest-by-number #0 #1
  \hspace #2
  \rest-by-number #-1 #0
  \hspace #2
  \override #'(ledgers . ())
  \rest-by-number #-1 #0
}
```

• • • •

Used properties:

- `style (())`
- `ledgers ((-1 0 1))`
- `font-size (0)`

`\rhythm` *music* (music)

Draw embedded rhythmic pattern as specified by *music*.

```
\relative {
  \tempo \markup {
    Swing
  }
  \hspace #0.4
  \rhythm { 8[ 8] } = \rhythm { \tuplet 3/2 { 4 8 } }
}
b8 g' c, d ees d16 ees d c r8
}
```



`\stemDown` can be used to flip the stems.

```
\markup \rhythm { \stemDown 8 16 8 }
```



`\rhythm` works by creating a `StandaloneRhythmVoice` context, which is enclosed in a `StandaloneRhythmStaff` context, which is enclosed in a `StandaloneRhythmScore` context. It is possible to apply global tweaks to the output by using a `\layout` block.

```
\layout {
  \context {
    \StandaloneRhythmVoice
    \xNotesOn
  }
}
```

```
\markup \rhythm { 8 16 8 }
```



Used properties:

- `font-size` (-2)

`\score score (score)`

Inline an image of music as specified by *score*.

The reference point (usually the middle staff line) of the lowest staff in the top system is placed on the baseline.

No page breaks and no MIDI output, i.e., both `\pageBreak` commands and `\midi{}` blocks get ignored.

```
\markup {
  Text before the score.
  \score {
    \new PianoStaff <<
      \new Staff \relative c' {
        \key f \major
        \time 3/4
        \mark \markup { Allegro }
        f2\p( a4)
      }
      \new Staff \relative c {
        \clef bass
        \key f \major
        \time 3/4
        f8( a c a c a
      }
    >>

    \layout {
      \indent = 0.0\cm
    }
  }
  Text after the score.
}
```



Used properties:

- `baseline-skip`

`\segno` Draw a segno symbol.

```
\markup {
  \segno
}
```

‰

`\semiflat`

Draw a semiflat symbol.

```
\markup {
  \semiflat
}
```

♭

`\semisharp`

Draw a semisharp symbol.

```
\markup {
  \semisharp
}
```

♯

`\sesquiflat`

Draw a 3/2 flat symbol.

```
\markup {
  \sesquiflat
}
```

♭

`\sesquisharp`

Draw a 3/2 sharp symbol.

```
\markup {
  \sesquisharp
}
```

♯

`\sharp` Draw a sharp symbol.

```
\markup {
  \sharp
}
```

#

`\text-accidental` *alteration* (an exact rational number)

Get an accidental for *alteration* that aligns well with text.

alteration must be a rational number; the function uses the `alteration-glyph-name-alist` property to map this number to an accidental glyph.

If no text variant glyph for the accidental is found, markup is constructed to fittingly scale and position the (non-text) accidental glyph.

```
\markup {
  text
  \tiny { \text-accidental #3/4 \text-accidental #1/2
          \text-accidental #-1/4 \text-accidental #-1/2 }
  text
}
```

text ## d b text

Used properties:

- `alteration-glyph-name-alist`

`\text-common-time`

Draw a common time symbol for text.

```
\markup {
  \text-common-time
}
```

C

`\text-cut-time`

Draw a cut time symbol for text.

```
\markup {
  \text-cut-time
}
```

C

`\text-doubleflat`

Draw a double flat symbol for text.

```
\markup {
  \text-doubleflat
}
```

b

`\text-doublesharp`

Draw a double sharp symbol for text.

```
\markup {
  \text-doublesharp
}
```

⌘

\text-flat

Draw a flat symbol for text.

```
\markup {
  \text-flat
}
```

b

\text-natural

Draw a natural symbol for text.

```
\markup {
  \text-natural
}
```

q

\text-sharp

Draw a sharp symbol for text.

```
\markup {
  \text-sharp
}
```

#

\tied-lyric *str* (string)

Replace '~' tilde symbols with tie characters in *str*.

```
\markup \column {
  \tied-lyric
    "Siam navi~all'onde~algenti Lasciate~in abbandono"
  \tied-lyric
    "Impetuosi venti I nostri~affetti sono"
  \tied-lyric
    "Ogni diletto~e scoglio Tutta la vita~e~un mar."
}
```

Siam navi~all'onde~algenti Lasciate~in abbandono
 Impetuosi venti I nostri~affetti sono
 Ogni diletto~e scoglio Tutta la vita~e~un mar.

Used properties:

- word-space

\varcoda Draw a varcoda sign.

```
\markup {
  \varcoda
}
```

⌘

A.1.5 Conditional markup

`\if condition?` (procedure) *argument* (markup)

Test *condition?*, and only insert *argument* if it is true.

The condition is provided as a procedure taking an output definition and a property alist chain. The procedure is applied, and its result determines whether to print the markup. This command is most useful inside `oddHeaderMarkup` or similar. Here is an example printing page numbers in bold:

```
\paper {
  oddHeaderMarkup =
    \markup \fill-line {
      ""
      \if #print-page-number
        \bold \fromproperty #'page:page-number-string
      }
  evenHeaderMarkup =
    \markup \fill-line {
      \if #print-page-number
        \bold \fromproperty #'page:page-number-string
      ""
    }
}
```

`\unless condition?` (procedure) *argument* (markup)

Test *condition?*, and only insert *argument* if it is false.

This function is similar to `\if`; the following example shows how to print the copyright notice on all pages but the last instead of just the first page.

```
\paper {
  oddFooterMarkup = \markup {
    \unless #on-last-page-of-part \fill-line {
      \fromproperty #'header:copyright
    }
  }
}

\header {
  copyright = "© LilyPond Authors. License: GFDL."
  tagline = "© LilyPond Authors. Documentation placed
under the GNU Free Documentation License
version 1.3."
}
```


A.1.6 Instrument-specific markup

`\fret-diagram definition-string` (string)

Make a (guitar) fret diagram based on *definition-string*.

For example, say

```
\markup \fret-diagram "s:1.25;6-x;5-x;4-o;3-2;2-3;1-2;"
```



for fret spacing $5/4$ of staff space, D chord diagram.

Syntax rules for *definition-string*:

- Diagram items are separated by semicolons.
- Possible items:
 - *s: number* – Set the fret spacing of the diagram (in staff spaces). Default: 1.
 - *t: number* – Set the line thickness (relative to normal line thickness). Default: 0.5.
 - *h: number* – Set the height of the diagram in frets. Default: 4.
 - *w: number* – Set the width of the diagram in strings. Default: 6.
 - *f: number* – Set fingering label type (0 = none, 1 = in circle on string, 2 = below string). Default: 0.
 - *d: number* – Set radius of dot, in terms of fret spacing. Default: 0.25.
 - *p: number* – Set the position of the dot in the fret space. 0.5 is centered; 1 is on lower fret bar, 0 is on upper fret bar. Default: 0.6.
 - *c: string1-string2-fret* – Include a barre mark from *string1* to *string2* on *fret*.
 - *string-fret* – Place a dot on *string* at *fret*. If *fret* is ‘o’, *string* is identified as open. If *fret* is ‘x’, *string* is identified as muted.
 - *string-fret-fingering* – Place a dot on *string* at *fret*, and label with *fingering* as defined by the *f:* code.
- Note: There is no limit to the number of fret indications per string.

Used properties:

- thickness (0.5)
- fret-diagram-details
- size (1.0)
- align-dir (-0.4)

`\fret-diagram-terse` *definition-string* (string)

Make a fret diagram markup using terse string-based syntax.

For example,

```
\markup \fret-diagram-terse "x;x;o;2;3;2;"
```



displays a D chord diagram.

Syntax rules for *definition-string*:

- Strings are terminated by semicolons; the number of semicolons is the number of strings in the diagram.
- Mute strings are indicated by ‘x’.
- Open strings are indicated by ‘o’.
- A number indicates a fret indication at that fret.
- If there are multiple fret indicators desired on a string, they should be separated by spaces.
- Fingerings are given by following the fret number with a ‘-’ followed by the finger indicator, e.g., ‘3-2’ for playing the third fret with the second finger.

- Where a barre indicator is desired, follow the fret (or fingering) symbol with `-(` to start a barre and `-)` to end the barre.

Used properties:


- `thickness` (0.5)
- `fret-diagram-details`
- `size` (1.0)
- `align-dir` (-0.4)

`\fret-diagram-verbose` *marking-list* (pair)

Make a fret diagram containing the symbols indicated in *marking-list*.

The following example produces a standard D chord diagram without fingering indications.

```
\markup \scale #'(1.5 . 1.5)
  \fret-diagram-verbose
    #'((mute 6) (mute 5) (open 4)
      (place-fret 3 2) (place-fret 2 3) (place-fret 1 2))
```



Possible elements in *marking-list*:

`(mute string-number)`

Place a small 'x' at the top of string *string-number*.

`(open string-number)`

Place a small 'o' at the top of string *string-number*.

`(barre start-string end-string fret-number)`

Place a barre indicator (much like a tie) from string *start-string* to string *end-string* at fret *fret-number*.

`(capo fret-number)`

Place a capo indicator (a large solid bar) across the entire fretboard at fret location *fret-number*. Also, set fret *fret-number* to be the lowest fret on the fret diagram.

`(place-fret string-number fret-number [finger-value] [color-modifier] [color] ['parenthesized ['default-paren-color]])`

Place a fret playing indication on string *string-number* at fret *fret-number* with an optional fingering label *finger-value*, an optional color modifier *color-modifier*, an optional color *color*, an optional parenthesis 'parenthesized and an optional parenthesis color 'default-paren-color.

By default, the fret playing indicator is a solid dot. This can be globally changed by setting the value of the property `dot-color` or for a single dot by setting the value of *color*. The dot can be parenthesized by adding 'parenthesized. By default the color for the parenthesis is taken from the dot. Adding 'default-paren-color will take the parenthesis color from the global `dot-color` property; as a fallback black will be used. Setting *color-modifier* to `inverted` inverts the dot color for a specific fingering.


```

box-width
    box width

box-height
    box height


space-before-divider
    spacing between two boxes before the divider

space-after-divider
    spacing between two boxes after the divider

\markup {
  \override #'((size . 1.5)
                (harp-pedal-details . ((box-width . 1)
                                         (box-offset . 2))))

  \harp-pedal "^-v|--ov^"
}

```



For global modification of harp-pedal-details, i.e., outside of the current `\markup` block, you can also use code similar to

```
\override Voice.TextScript.harp-pedal-details.box-width = 1
```

Used properties:

- thickness (0.5)
- harp-pedal-details (())
- size (1.2)

`\woodwind-diagram` *instrument* (symbol) *user-draw-commands* (list)


Make a woodwind-instrument diagram for *instrument* using *user-draw-commands*.

user-draw-commands is a list of alists, specifying the left-hand keys, the elements on the central column, and the right-hand keys. For example, this diagram

```

\markup \woodwind-diagram
  #'oboe #'((lh . (d ees))
            (cc . (five3qT1q))
            (rh . (gis)))

```



shows an oboe with the left-hand d key, left-hand ees key, and right-hand gis key depressed, while the five-hole of the central column effectuating a trill between 1/4 and 3/4 is closed.

The following instruments are supported:

- piccolo
- flute

- oboe
- clarinet
- bass-clarinet
- saxophone
- bassoon
- contrabassoon

To see all of the callable keys for a given instrument, include the function call `(print-keys 'instrument)` in your `.ly` file, where *instrument* is the instrument whose keys you want to print.


Certain keys allow for special configurations. The entire gamut of configurations possible is as follows:

1q	1/4 covered
1h	1/2 covered
3q	3/4 covered
R	ring depressed
F	fully covered; the default if no state put

Additionally, these configurations can be used in trills. So, for example, `three3qTR` effectuates a trill between 3/4 full and ring depressed on the three hole. As another example, `threeRT` effectuates a trill between R and open, whereas `threeTR` effectuates a trill between open and shut. To see all of the possibilities for all of the keys of a given instrument, invoke `(print-keys-verbose 'instrument)`.

Lastly, substituting an empty list for the pressed-key alist results in a diagram with all of the keys drawn but none filled, for example

```
\markup \woodwind-diagram #'flute #'()
```



Used properties:

- `woodwind-diagram-details (())`
- `font-size (0)`
- `graphical (#t)`
- `thickness (0.1)`
- `size (1)`

A.1.7 Accordion registers

`\discant name (string)`

Generate a discant accordion register symbol for *name*.

To make it available,

```
#(use-modules (lily accreg))
```

is required near the top of your input file.

The register names in the default `\discant` register set have been modeled after the numeric Swiss notation (as depicted in http://de.wikipedia.org/wiki/Register_%28Akkordeon%29), omitting the slashes and dropping leading zeros.

The string *name* is basically a three-digit number with the lowest digit specifying the number of 16' reeds, the tens the number of 8' reeds, and the hundreds specifying the number of 4' reeds. Without modification, the specified number of reeds in 8' is centered in the symbol. Newer instruments may have registrations where 8' can be used either within or without a tone chamber, 'cassotto'. Notationally, the central dot then indicates use of cassotto. One can suffix the tens' digits '1' and '2' with '+' or '-' to indicate clustering the dots at the right or left, respectively, rather than centered.

Some examples are

	
<code>\discant "1"</code>	<code>\discant "1+0"</code>
	
<code>\discant "120"</code>	<code>\discant "131"</code>

Used properties:

- `font-size (0)`

`\freeBass` *name* (string)

Generate a free bass/converter accordion register symbol for the usual two-reed layout as given by *name*.

To make it available,

```
#(use-modules (lily accreg))
```

is required near the top of your input file.

Available registrations are

	
<code>\freeBass "1"</code>	<code>\freeBass "11"</code>
	
<code>\freeBass "10"</code>	

Used properties:

- `font-size (0)`

`\stdBass` *name* (string)

Generate a standard bass accordion register symbol for *name*.

To make it available,

```
#(use-modules (lily accreg))
```

is required near the top of your input file.

The default bass register definitions have been modeled after the article <http://www.accordions.com/index/art/stradella.shtml> originally appearing in *Accord Magazine*.

The underlying register model is



This kind of overlapping arrangement is common for Italian instruments though the exact location of the octave breaks differ.

When not composing for a particular target instrument, using the five-reed definitions makes more sense than using a four-reed layout: in that manner, the ‘Master’ register is unambiguous. This is rather the rule in literature bothering about bass registrations at all.

Available registrations are

	
<code>\stdBass "Soprano"</code>	<code>\stdBass "Soft Bass"</code>
	
<code>\stdBass "Alto"</code>	<code>\stdBass "Soft Tenor"</code>
	
<code>\stdBass "Tenor"</code>	<code>\stdBass "Bass/Alto"</code>
	
<code>\stdBass "Master"</code>	

Used properties:

- `font-size (0)`

`\stdBassIV` *name* (string)

Generate a standard bass accordion register symbol for *name*.

To make it available,

```
 #(use-modules (lily accreg))
```

is required near the top of your input file.

The main use is for four-reed standard bass instruments with reedbank layout



Notable instruments are Morino models with MIII (the others are five-reed instead) and the Atlantic IV. Most of those models have three register switches. Some newer Morinos with MIII might have five or even seven.

The prevalent three-register layout uses the middle three switches ‘Tenor’, ‘Master’, ‘Soft Bass’. Note that the sound is quite darker than the same registrations of ‘c,’-based instruments.

Available registrations are

	
<code>\stdBassIV "Soprano"</code>	<code>\stdBassIV "Soft Bass"</code>
	
<code>\stdBassIV "Alto"</code>	<code>\stdBassIV "Bass/Alto"</code>
	
<code>\stdBassIV "Tenor"</code>	<code>\stdBassIV "Soft Bass/Alto"</code>
	
<code>\stdBassIV "Master"</code>	<code>\stdBassIV "Soft Tenor"</code>

Used properties:

- font-size (0)

`\stdBassV` *name* (string)

Generate a standard bass accordion register symbol for *name*.

To make it available,

```
#(use-modules (lily accreg))
```

is required near the top of your input file.

The main use is for five-reed standard bass instruments with reedbank layout



This tends to be the bass layout for Hohner’s Morino series without converter or MIII manual.

With the exception of the rather new 7-register layout, the highest two chord reeds are usually sounded together. Older instruments offer 5 or 3 bass registers. The Tango VM offers an additional ‘Solo Bass’ setting that mutes the chord reeds. The symbol on the register buttons of the Tango VM would actually match the physical five-octave layout reflected here, but it is not used in literature.

Composers should likely prefer the five-reed versions of these symbols. The mismatch of a four-reed instrument with five-reed symbols is easier to resolve for the player than the other way round.

Available registrations are

	
<code>\stdBassV "Bass/Alto"</code>	<code>\stdBassV "Soft Bass"</code>
	
<code>\stdBassV "Soft Bass/Alto"</code>	<code>\stdBassV "Soft Tenor"</code>
	
<code>\stdBassV "Alto"</code>	<code>\stdBassV "Soprano"</code>
	
<code>\stdBassV "Tenor"</code>	<code>\stdBassV "Sopranos"</code>
	
<code>\stdBassV "Master"</code>	<code>\stdBassV "Solo Bass"</code>

Used properties:

- `font-size (0)`

`\stdBassVI` *name* (string)


Generate a standard bass accordion register symbol for six-reed basses as given by *name*.

To make it available,

```
#(use-modules (lily accreg))
```

is required near the top of your input file.

This is primarily the register layout for the Hohner “Gola” model. The layout is



The registers are effectively quite similar to that of `\stdBass`. An additional bass reed at alto pitch is omitted for aesthetical reasons from the ‘Master’ setting, so the symbols are almost the same except for the ‘Alto/Soprano’ register with bass notes at Alto pitch and chords at Soprano pitch.

Available registrations are

	
<code>\stdBassVI "Soprano"</code>	<code>\stdBassVI "Alto/Soprano"</code>
	
<code>\stdBassVI "Alto"</code>	<code>\stdBassVI "Bass/Alto"</code>
	
<code>\stdBassVI "Soft Tenor"</code>	<code>\stdBassVI "Soft Bass"</code>
	
<code>\stdBassVI "Master"</code>	

Used properties:

- `font-size (0)`

A.1.8 Other markup commands

`\annotate-moving` *arg* (markup)

Indicate `\vspace` and `\hspace` movement with an arrow.

The arrow changes its size and thickness depending on the printed length; the maximum size of the arrow head can be controlled with the `size` property. If `size` exceeds a third of the length of the final arrow, it falls back to that third.

Note that the arrows do not reflect the actual extents of the objects created by `\vspace` and `\hspace`; you might use `\box` for that.

```

\markup
\column {
  \line { left \annotate-moving \hspace #4 right }
  \line { left \annotate-moving \hspace #-4 right }
  \line {
    \column {
      top
      \override #'(size . 0.6)
      \annotate-moving \vspace #4/3 bottom
    }
    \column {
      top
      \override #'(size . 2.0)
      \annotate-moving \vspace #-4/3 bottom
    }
  }
}

```

left → right
 right ← left
 top → bottom
 bottom → top

Used properties:

- `size (1)`
- `color ("red")`

`\append-to-tag` *tag* (symbol) *more* (markup) *arg* (markup)

Append *more* to all markup in var *arg* tagged with *tag*.

It works similar to `\appendToTag` for music, but only with markups.

```
tagged = \markup {
  \tag #'foo A
  \tag #'bar B
}
```

```
\markup { \append-to-tag #'foo postfoo \tagged }
```

A postfoo B

Used properties:

- `tags-with-appends-alist (())`

`\auto-footnote` *mkup* (markup) *note* (markup)

Have footnote *note* act as an annotation to the markup *mkup*.

```
\markup {
  \auto-footnote a b
  \override #'(padding . 0.2)
  \auto-footnote c d
}
```

a¹ c²

¹**b** _____
²**d**

The footnote will be annotated automatically.

Used properties:

- `padding (0.0)`
- `raise (0.5)`

`\backslashed-digit` *num* (integer)

Print number *num* with the Emmmentaler font, crossed through with a backslash.

This is for use in the context of figured bass notation.


```
\markup {
  \backslashed-digit #5
  \hspace #2
  \override #'(thickness . 3)
  \backslashed-digit #7
}
```

5 7

Used properties:

- `thickness` (1.6)
- `font-size` (0)

`\char num` (integer)

Produce a single Unicode character with code *num*.

Characters encoded in hexadecimal format require the prefix `#x`.

```
\markup {
  \char #65 \char ##x00a9
}
```

A ©

`\eyeglasses`

Prints out eyeglasses, indicating strongly to look at the conductor.

```
\markup { \eyeglasses }
```

66

`\first-visible args` (markup list)

Use the first markup in *args* that yields a non-empty stencil and ignore the rest.

```
\markup {
  \first-visible {
    \fromproperty #'header:composer
    \italic Unknown
  }
}
```

Unknown

`\footnote mkup` (markup) *note* (markup)

Have footnote *note* act as an annotation to the markup *mkup*.

```
\markup {
  \footnote a b
  \override #'(padding . 0.2)
  \footnote c d
}
```

a c

$$\frac{b}{d}$$

The footnote will not be annotated automatically.

`\fraction` *arg1* (markup) *arg2* (markup)

Make a fraction of markups *arg1* and *arg2*.

```
\markup {
  π ≈ \fraction 355 113
}
```

$$\pi \approx \frac{355}{113}$$

Used properties:

- `font-size (0)`

`\fromproperty` *symbol* (symbol)

Read *symbol* from the property settings and produce a stencil from the markup contained within.

If *symbol* is not defined or is not a markup, return an empty markup.

Currently, the following properties can be accessed.

- Within a `\paper` block defining titles, headers, or footers, or within a `\header` block: all fields from the `\header` block (that produce markup) are available, with `header:` as a name prefix.
- Within a `\paper` block defining headers or footers: the current page number (`symbol page:page-number-string`).
- Within the `tocItemMarkup` paper variable (or in custom-made Scheme code that uses function `add-toc-item!`) defining a table of contents entry: the entry's text and page number are available as `toc:text` and `toc:page`, respectively. An entry's indentation markup is available as `toc:indent`.

```
\header {
  myTitle = "myTitle"
  title = \markup {
    from
    \italic
    \fromproperty #'header:myTitle
  }
}
\markup {
```

```
\null
}
```

from *myTitle*

`\keep-with-tag` *tags* (symbol list or symbol) *arg* (markup)

Keep markup from *arg* that is untagged or tagged with *tags*.

All other parts of *arg* that are using a different tag are replaced with empty stencils.

It works similar to `\keepWithTag` for music, but only with markups.

```
tagged = \markup {
  untagged
  \tag #'foo A
  \tag #'bar B
}
```

```
\markup { \keep-with-tag #'bar \tagged }
\markup { \keep-with-tag #'foo \tagged }
```

untagged B

untagged A

Used properties:

- `tags-to-keep` (())

`\left-brace` *size* (number)

Print a brace from the music font, of height *size* (in points).

```
\markup {
  \left-brace #35
  \hspace #2
  \left-brace #45
}
```

{ }

`\lookup` *glyph-name* (string)

Print a brace glyph with name *glyph-name*.

This is a historical command; `\left-brace` (which looks up the glyph by absolute size and is independent of the font size) is recommended instead.

```
\markup \lookup "brace200"
```

{ }

`\markalphabet` *num* (integer)

Make a markup letter for *num*.

The letters start with A to Z and continue with double letters.

```
\markup {
  \markalphabet #8
  \hspace #2
  \markalphabet #26
}
```

H Z

`\markletter` *num* (integer)

Make a markup letter for *num*.

The letters start with A to Z (skipping letter I), and continue with double letters.

```
\markup {
  \markletter #8
  \hspace #2
  \markletter #26
}
```

H AA

`\null`

An empty markup with extents of a single point.

```
\markup {
  \null
}
```

`\on-the-fly` *procedure* (procedure) *arg* (markup)

Apply the *procedure* markup command to *arg*.

procedure takes the same arguments as `interpret-markup` and returns a stencil.

`\override` *new-prop* (pair) *arg* (markup)

Add the argument *new-prop* to the property list for printing *arg*.

In general, any property may be overridden that is part of `font-interface` (Section “font-interface” in *Internals Reference*), `text-interface` (Section “text-interface” in *Internals Reference*), or `instrument-specific-markup-interface` (Section “instrument-specific-markup-interface” in *Internals Reference*). Additionally, various markup commands listen to other properties, too, as described in a markup function’s documentation.

new-prop is either a single alist pair or a non-empty list of alist pairs.

```
\markup {
  \undertie "undertied"
  \override #'(offset . 15)
  \undertie "offset undertied"
  \override #'((offset . 15) (thickness . 3))
  \undertie "offset thick undertied"
}
```

undertied offset undertied offset thick undertied

`\page-link` *page-number* (number) *arg* (markup)

Add a link to a score’s page *page-number* around *arg*.

This only works in the PDF backend.

```
\markup {
  \page-link #2 { \italic { This links to page 2... } }
}
```

This links to page 2...

`\page-ref` *label* (symbol) *gauge* (markup) *default* (markup)

Print a page number reference.

label is the label set on the referenced page (using `\label` or `\tocItem`), *gauge* a markup used to estimate the maximum width of the page number, and *default* the value to display when *label* is not found.

If the current book or book part is set to use roman numerals for page numbers, the reference will be formatted accordingly – in which case the *gauge*'s width may require additional tweaking.

Used properties:

- `x-align` (1)

`\pattern` *count* (non-negative, exact integer) *axis* (non-negative, exact integer) *space* (number) *pattern* (markup)

Print a *pattern* markup *count* times.

Patterns are spaced apart by *space* (defined as for `\hspace` or `\vspace`, respectively) and distributed on *axis*.

```
\markup \column {
  "Horizontally repeated:"
  \pattern #7 #X #2 \flat
  \null
  "Vertically repeated:"
  \pattern #3 #Y #0.5 \flat
}
```

Horizontally repeated:

b b b b b b b

Vertically repeated:

b
b
b

`\property-recursive` *symbol* (symbol)

Print out a warning when header field markup in *symbol* contains some recursive markup definition.

`\push-to-tag` *tag* (symbol) *more* (markup) *arg* (markup)

Prepend *more* to all markup in *arg* tagged with *tag*.

It works similar to `\pushToTag` for music, but only with markups.

```
tagged = \markup {
  \tag #'foo A
  \tag #'bar B
}
```

```
\markup { \push-to-tag #'foo prefoo \tagged }

prefoo A B
```

Used properties:

- tags-with-pushes-alist (())

`\qr-code` *width* (non-negative number) *str* (string)

Insert a QR code for string *str*, usually a URL, with a given *width*.

```
\markup \vcenter {
  \center-column { Engraved with LilyPond }
  \hspace #1.5
  \qr-code #10.0 "https://lilypond.org"
}
```

Engraved
with
LilyPond



The `error-correction-level` property can be set to one of the symbols `low`, `medium`, `quarter`, or `high`. The higher the level of error correction is, the more the QR code contains redundancy, potentially helping detectors, e.g., in poor lighting conditions; however, a higher correction level also makes the code denser.

```
\markup \vcenter {
  \center-column { Engraved with LilyPond }
  \hspace #1.5
  \override #'(error-correction-level . high)
  \qr-code #10.0 "https://lilypond.org"
}
```

Engraved
with
LilyPond



The `quiet-zone-size` property specifies the width of the “quiet zone”, namely the white area around the QR code. It is expressed as a multiple of the width of one little square inside the QR code. Use at least 4 for best results.

Used properties:

- quiet-zone-size (4)
- error-correction-level (low)

`\remove-with-tag` *tags* (symbol list or symbol) *arg* (markup)

Remove markup from *arg* that is tagged with *tags*.

The removed markup is replaced with empty stencils. It works similar to `\removeWithTag` for music, but only with markups.

```
tagged = \markup {
  \tag #'foo A
  \tag #'bar B
}

\markup { \remove-with-tag #'foo \tagged }
\markup { \remove-with-tag #'bar \tagged }
```

B

A

Used properties:

- `tags-to-remove (())`

`\replace-with-tag` *tag* (symbol) *replacement* (markup) *arg* (markup)

Replace tagged markups in *arg*.

Everything tagged with *tag* (including the tagging itself) gets replaced with *replacement*.

It works similar to `\replaceWithTag` for music, but only with markups.

```
tagged = \markup {
  \tag #'foo A
  \tag #'bar B
}

\markup { \replace-with-tag #'foo C \tagged }
```

C B

Used properties:

- `tags-with-replacement-alist (())`

`\right-brace` *size* (number)

A music brace in point size *size*, rotated 180 degrees.

```
\markup {
  \right-brace #45
  \hspace #2
  \right-brace #35
}
```

} }

`\slashed-digit` *num* (integer)

Print number *num* with the Emmentaler font, crossed through with a slash.

This is for use in the context of figured bass notation.

```
\markup {
  \slashed-digit #5
  \hspace #2
  \override #'(thickness . 3)
  \slashed-digit #7
}
```

5 7

Used properties:

- thickness (1.6)
- font-size (0)

`\stencil stil (stencil)`

Use stencil *stil* as markup.

```
\markup {
  \stencil #(make-circle-stencil 2 0 #t)
}
```



`\strut`

Create a box of the same height as the space in the current font.

`\tag tags (symbol list or symbol) arg (markup)`

Tag markup *arg* with *tag*.

tag can be one or multiple tags. This allows later on to reference *arg*; for example, to remove it or to add markup before or after the tagged markup. It works similar to `\tag` for music, but only with markups.

```
tagged = \markup {
  \tag #'foo A
  \tag #'bar B
}

\markup { \keep-with-tag #'bar \tagged }
\markup { \keep-with-tag #'foo \tagged }
```

B

A

Used properties:

- tags-with-replacement-alist (())
- tags-with-appends-alist (())
- tags-with-pushes-alist (())
- tags-to-remove (())
- tags-to-keep (())

`\transparent arg (markup)`

Make *arg* transparent.


```
\markup {
  \transparent {
    invisible text
  }
}
```

`\verbatim-file` *name* (string)

Read the contents of file *name* and include it verbatim.

```
\markup {
  \verbatim-file "en/included/simple.ly"
}

% A simple piece in LilyPond, a scale.
\version "2.19.21"
\relative {
  c' d e f g a b c
}
```

Use `\withRelativeDir` as a prefix to *name* if the file should be found relative to the input file.

`\whiteout` *arg* (markup)

Provide a white background for *arg*.

The shape of the white background is determined by the `style` property. The default is `box` which produces a rectangle. `rounded-box` produces a rounded rectangle, and `outline` approximates the outline of the markup.

The color of the background can be controlled with the `color` property, defaulting to "white".

```
\markup {
  \combine
  \filled-box #'(-1 . 62) #'(-3 . 4) #1
  \override #'(line-width . 60)
  \fill-line {
    \override #'(thickness . 1.5)
    \whiteout box
    \override #'((style . rounded-box) (thickness . 3))
    \whiteout rounded-box
    \override #'((style . outline) (thickness . 3))
    \whiteout outline
    \override #'((color . "red") (style . outline))
    \whiteout red-outline
  }
}
```

`box`

`rounded-box`

`outline`

`red-outline`

Used properties:

- `color ("white")`
- `thickness (())`

- style (box)

`\with-color col (color) arg (markup)`

Use color *col* to draw *arg*.

See Section 7.1.5 [Coloring objects], page 288, for valid color specifications.

```
\markup {
  \with-color #red red
  \hspace #2
  \with-color #green green
  \hspace #2
  \with-color "#0000ff" blue
}
```

red green blue

`\with-dimension axis (integer) val (pair of numbers) arg (markup)`

Set the dimension of *arg* along *axis* to *val*.

If *axis* is equal to X, set the horizontal dimension. If *axis* is equal to Y, set the vertical dimension.

`\with-dimension-from axis (integer) arg1 (markup) arg2 (markup)`

Print *arg2* but replace the dimension along *axis* with the one from *arg1*.

If *axis* is set to X, replace the horizontal dimension. If *axis* is set to Y, replace the vertical dimension.

`\with-dimensions x (pair of numbers) y (pair of numbers) arg (markup)`

Set the horizontal and vertical dimensions of *arg* to *x* and *y*.

`\with-dimensions-from arg1 (markup) arg2 (markup)`

Print *arg2* with the horizontal and vertical dimensions of *arg1*.

`\with-link label (symbol) arg (markup)`

Add a link to the page holding label *label* around *arg*.

This only works in the PDF backend.

```
\markup {
  \with-link #'label {
    \italic { This links to the page
              containing the label... }
  }
}
```

`\with-outline outline (markup) arg (markup)`

Print *arg* with the outline and dimensions of *outline*.

The outline is used by skylines to resolve collisions (not for whiteout).

`\with-true-dimension axis (integer) arg (markup)`

Give *arg* its actual dimension (extent) on *axis*.

Sometimes, the extents of a markup's printed ink differs from the default extents. The main case is if glyphs are involved. By default, the extents of a glyph are based on the glyph's *metrics* (i.e., a default vertical and horizontal size for the glyph), which, for various reasons, are often not identical to its *bounding box* (i.e., the smallest rectangle that completely encompasses the glyph's outline) – in most cases, the outline protrudes the box spanned up by the metrics.

```
\markup {
  text
  \fontsize #10
  \override #'((box-padding . 0) (thickness . 0.2))
  \box
    \musicglyph "scripts.trill"
  text
}
```



For purposes other than setting text, this behavior may not be wanted. You can use `\with-true-dimension` in order to give the markup its actual printed extent.

```
\markup {
  text
  \fontsize #10
  \override #'((box-padding . 0) (thickness . 0.2))
  \box
    \with-true-dimension #X
    \musicglyph "scripts.trill"
  text
}
```



`\with-true-dimensions arg (markup)`

Give *arg* its actual dimensions (extents).

Calling

```
\markup \with-true-dimensions arg
```

is short for

```
\markup
  \with-true-dimension #X
  \with-true-dimension #Y
  arg
```

i.e., `\with-true-dimensions` has the effect of `\with-true-dimension` on both axes.

A.2 Text markup list commands

The following commands can all be used with `\markuplist`.

`\column-lines args (markup list)`

Stack the markups in *args* vertically.

Like `\column`, but return a list of lines instead of a single markup. The property `baseline-skip` determines the space between each markup in *args*.

Used properties:

- `baseline-skip`

`\justified-lines args (markup list)`

Print *args* as lines aligned both at the left and the right.

Like `\justify`, but return a list of lines instead of a single markup. Use `\override-lines #'(line-width . X)` to set the line width; X is the number of staff spaces.

Used properties:

- `text-direction` (1)
- `word-space`
- `line-width` (#f)
- `baseline-skip`

`\override-lines` *new-prop* (pair) *args* (markup list)

Add the argument *new-prop* to the property list for printing *args*.

Like `\override` but for markup lists.

`\score-lines` *score* (score)

Inline an image of music as specified by *score*.

Like `\score` but return a list of lines instead of a single markup.

Used properties:

- `tags-with-replacement-alist` (())
- `tags-with-appends-alist` (())
- `tags-with-pushes-alist` (())
- `tags-to-remove` (())
- `tags-to-keep` (())

`\string-lines` *str* (string)

Split string *str* into lines.

The character to split at is specified by the property `split-char`, defaulting to `#\newline`. Surrounding whitespace is removed from every resulting string. The returned list of markups is ready to be formatted by other markup or markup list commands like `\column`, `\line`, etc.

```
\markup {
  \column
  \string-lines
  "foo, foo,
  bar, bar,
  buzz, buzz!"
}
```

```
foo, foo,
bar, bar,
buzz, buzz!
```

Used properties:

- `split-char` (#\newline)

`\table` *column-align* (number list) *lst* (markup list)

Print a table.

column-align specifies how each column is aligned; possible values are -1, 0, and 1. The number of elements in *column-align* determines how many columns will be printed.

The entries to print are given by *lst*, a markup list. If needed, the last row is filled up with `point-stencils`.

Override the padding property to increase the horizontal distance between columns.
 Override baseline-skip to increase the vertical distance between rows.

```
% A markup command to print a fixed-width number.
\markup fwnum =
  \markup \override #'(font-features . ("ss01" "-kern"))
  \number \etc
```

```
\markuplist {
  \override #'(padding . 2)
  \table #'(0 1 0 -1) {
    \underline { center-aligned right-aligned
                  center-aligned left-aligned }
    one      \fwnum    1 thousandth \fwnum 0.001
    eleven   \fwnum    11 hundredth  \fwnum 0.01
    twenty   \fwnum    20 tenth      \fwnum 0.1
    thousand \fwnum 1000 one          \fwnum 1.0
  }
}
```

center-aligned right-aligned center-aligned left-aligned

one	1	thousandth	0.001
eleven	11	hundredth	0.01
twenty	20	tenth	0.1
thousand	1000	one	1.0

Used properties:

- baseline-skip
- padding (0)

`\table-of-contents`

Print a table of contents.

This function uses the paper variable `tocTitleMarkup` for the title; it then prints `\tocItem` entries line by line.

See Section 21.7 [Table of contents], page 622, for a complete discussion.

Used properties:

- baseline-skip

`\tag-list` *tags* (symbol list or symbol) *arg* (markup list)

Tag markup list *arg* with *tag*.

tag can be one or multiple tags. This allows later on to reference *arg*; for example, to remove it or to add markup before or after the tagged markup list.

It works like the `\tag` command for markups but with markup lists. You will need it if you have to reference a whole list; for example, to use `\push-to-tag` and `\append-to-tag` without pushing or appending before or after every single item of the list, but before or after the whole list instead.

```

tagged = \markuplist {
  \tag-list #'foo { foo bar }
}

\markup { \push-to-tag #'foo test \tagged }

test foo bar

```

Used properties:

- tags-with-replacement-alist (())
- tags-with-appends-alist (())
- tags-with-pushes-alist (())
- tags-to-remove (())
- tags-to-keep (())

`\wordwrap-lines` *args* (markup list)

Print *args* as left-aligned lines.

Like `\wordwrap`, but return a list of lines instead of a single markup. Use `\override-lines #'(line-width . X)` to set the line width, where *X* is the number of staff spaces.

Used properties:

- text-direction (1)
- word-space
- line-width (#f)
- baseline-skip

Appendix B Notation manual tables



B.1 Chord name chart






The following chart shows LilyPond’s standard system for printing chord names, along with the pitches they represent. Additional (unsupported) naming systems are also demonstrated in the “Chord names alternative” snippet in Section “Chord notation” in *Snippets*, including the notation inspired by Harald Banter (1982) that was used by default in early LilyPond releases (up to version 1.7).

B.2 Common chord modifiers

The following table shows chord modifiers that can be used to generate standard chord structures.

Type	Interval	Modifier	Example	Output
Major	Major third, perfect fifth	(nothing)	c1	
Minor	Minor third, perfect fifth	m or m5	c1:m	
Augmented	Major third, augmented fifth	aug	c1:aug	

Diminished	Minor third, diminished fifth	dim	c1:dim	
Dominant seventh	Major triad, minor seventh	7	c1:7	
Major seventh	Major triad, major seventh	maj7 or maj	c1:maj7	
Minor seventh	Minor triad, minor seventh	m7	c1:m7	
Diminished seventh	Diminished triad, diminished seventh	dim7	c1:dim7	
Augmented seventh	Augmented triad, minor seventh	aug7	c1:aug7	
Half-diminished seventh	Diminished triad, minor seventh	m7.5-	c1:m7.5-	
Minor-major seventh	Minor triad, major seventh	m7+	c1:m7+	
Major sixth	Major triad, sixth	6	c1:6	
Minor sixth	Minor triad, sixth	m6	c1:m6	
Dominant ninth	Dominant seventh, major ninth	9	c1:9	

Major ninth	Major seventh, major ninth	maj9	c1:maj9	
Minor ninth	Minor seventh, major ninth	m9	c1:m9	
Dominant eleventh	Dominant ninth, perfect eleventh	11	c1:11	
Major eleventh	Major ninth, perfect eleventh	maj11	c1:maj11	
Minor eleventh	Minor ninth, perfect eleventh	m11	c1:m11	
Dominant thirteenth	Dominant ninth, major thirteenth	13	c1:13	
Dominant thirteenth	Dominant eleventh, major thirteenth	13.11	c1:13.11	
Major thirteenth	Major eleventh, major thirteenth	maj13.11	c1:maj13.11	
Minor thirteenth	Minor eleventh, major thirteenth	m13.11	c1:m13.11	
Suspended second	Major second, perfect fifth	sus2	c1:sus2	
Suspended fourth	Perfect fourth, perfect fifth	sus4	c1:sus4	

Power chord
(two-voiced)

Perfect fifth

1.5

c1:5

Power chord
(three-voiced)Perfect fifth,
octave

1.5.8


c1:5.8




B.3 Predefined string tunings

The chart below shows the predefined string tunings.

Guitar tunings




Bass tunings




Mandolin tunings



Banjo tunings




banjo-double-d-tuning




Ukulele tunings

ukulele-tuning ukulele-d-tuning tenor-ukulele-tuning



baritone-ukulele-tuning

























































Orchestral string tunings

violin-tuning viola-tuning cello-tuning double-bass-tuning

































































B.4 Predefined fretboard diagrams

B.4.1 Diagrams for Guitar

C  3 2 1	Cm  1 3 4 2 1	C+  2 1 1 4	C°  1 2 4 3	C^o7  1 3 2 4	C⁷  3 2 4 1	C^Δ  3 2	Cm⁷  1 3 1 2 1	C⁹  2 1 3 3 3
C#  3 1 2 1	C#m  2 1 3	C#+  4 3 1 2	C#°  3 4	C#^o7  1 3 2 4	C#⁷  2 3 1 4	C#^Δ  4 3 1 1 1	C#m⁷  4 2 1	C#⁹  2 1 3 3 3
D^b  3 1 2 1	D^bm  2 1 3	D^b+  4 3 1 2	D^b°  3 4	D^b°7  1 3 2 4	D^b7  2 3 1 4	D^bΔ  4 3 1 1 1	D^bm⁷  4 2 1	D^b9  2 1 3 3 3
D  1 3 2	Dm  2 3 1	D+  2 3 1	D°  1 3 1	D^o7  1 2	D⁷  2 1 3	D^Δ  1 2 3	Dm⁷  2 1 1	D⁹  2 1 3 3 3
D#  3 1 2 1	D#m  3 2 4 1	D#+  3 2 1 4	D#°  3 1 4 1	D#^o7  1 3 2 4	D#⁷  1 3 2 4	D#^Δ  1 2 3 4	D#m⁷  1 2 3 4	D#⁹  2 1 3 3 3
E^b  3 1 2 1	E^bm  3 2 4 1	E^b+  3 2 1 4	E^b°  3 1 4 1	E^b°7  1 3 2 4	E^b7  1 3 2 4	E^bΔ  1 2 3 4	E^bm⁷  1 2 3 4	E^b9  2 1 3 3 3

 E	 Em	 E+	 E°	 E°7	 E7	 EΔ	 Em7	 E9
 F	 Fm	 F+	 F°	 F°7	 F7	 FΔ	 Fm7	 F9
 F#	 F#m	 F#+	 F#°	 F#°7	 F#7	 F#Δ	 F#m7	 F#9
 Gb	 Gbm	 Gb+	 Gb°	 Gb°7	 Gb7	 GbΔ	 Gbm7	 Gb9
 G	 Gm	 G+	 G°	 G°7	 G7	 GΔ	 Gm7	 G9
 G#	 G#m	 G#+	 G#°	 G#°7	 G#7	 G#Δ	 G#m7	 G#9
 Ab	 Abm	 Ab+	 Ab°	 Ab°7	 Ab7	 AbΔ	 Abm7	 Ab9
 A	 Am	 A+	 A°	 A°7	 A7	 AΔ	 Am7	 A9
 A#	 A#m	 A#+	 A#°	 A#°7	 A#7	 A#Δ	 A#m7	 A#9
 Bb	 Bbm	 Bb+	 Bb°	 Bb°7	 Bb7	 BbΔ	 Bbm7	 Bb9
 B	 Bm	 B+	 B°	 B°7	 B7	 BΔ	 Bm7	 B9

B.4.2 Diagrams for Ukulele


										
										
										
										
										
										
										
										
										
										
										

$G^\sharp$ 	$G^\sharp m$ 	$G^\sharp +$ 	$G^\sharp^\circ$ 	$G^\sharp 7$ 	$G^\sharp^\Delta$ 	$G^\sharp m 7$ 	$G^\sharp 6$ 	$G^\sharp \text{sus} 2$ 	$G^\sharp \text{sus} 4$ 	$G^\sharp 9$
$A^\flat$ 	$A^\flat m$ 	$A^\flat +$ 	$A^\flat^\circ$ 	$A^\flat 7$ 	$A^\flat^\Delta$ 	$A^\flat m 7$ 	$A^\flat 6$ 	$A^\flat \text{sus} 2$ 	$A^\flat \text{sus} 4$ 	$A^\flat 9$
A 	$A m$ 	$A +$ 	A° 	$A 7$ 	A^Δ 	$A m 7$ 	$A 6$ 	$A \text{sus} 2$ 	$A \text{sus} 4$ 	$A 9$
$A^\sharp$ 	$A^\sharp m$ 	$A^\sharp +$ 	$A^\sharp^\circ$ 	$A^\sharp 7$ 	$A^\sharp^\Delta$ 	$A^\sharp m 7$ 	$A^\sharp 6$ 	$A^\sharp \text{sus} 2$ 	$A^\sharp \text{sus} 4$ 	$A^\sharp 9$
$B^\flat$ 	$B^\flat m$ 	$B^\flat +$ 	$B^\flat^\circ$ 	$B^\flat 7$ 	$B^\flat^\Delta$ 	$B^\flat m 7$ 	$B^\flat 6$ 	$B^\flat \text{sus} 2$ 	$B^\flat \text{sus} 4$ 	$B^\flat 9$
B 	$B m$ 	$B +$ 	B° 	$B 7$ 	B^Δ 	$B m 7$ 	$B 6$ 	$B \text{sus} 2$ 	$B \text{sus} 4$ 	$B 9$

B.4.3 Diagrams for Mandolin

C 	$C m$ 	$C +$ 	$C^{\circ 7}$ 	$C 7$ 	C^Δ 	$C m 7$ 	$C^\emptyset$ 	$C 6$ 	$C \text{sus} 2$ 	$C \text{sus} 4$ 	$C 9$
$C^\sharp$ 	$C^\sharp m$ 	$C^\sharp +$ 	$C^\sharp^{\circ 7}$ 	$C^\sharp 7$ 	$C^\sharp^\Delta$ 	$C^\sharp m 7$ 	$C^\sharp^\emptyset$ 	$C^\sharp 6$ 	$C^\sharp \text{sus} 2$ 	$C^\sharp \text{sus} 4$ 	$C^\sharp 9$
$D^\flat$ 	$D^\flat m$ 	$D^\flat +$ 	$D^\flat^{\circ 7}$ 	$D^\flat 7$ 	$D^\flat^\Delta$ 	$D^\flat m 7$ 	$D^\flat^\emptyset$ 	$D^\flat 6$ 	$D^\flat \text{sus} 2$ 	$D^\flat \text{sus} 4$ 	$D^\flat 9$
D 	$D m$ 	$D +$ 	$D^{\circ 7}$ 	$D 7$ 	D^Δ 	$D m 7$ 	$D^\emptyset$ 	$D 6$ 	$D \text{sus} 2$ 	$D \text{sus} 4$ 	$D 9$

D [#]	D [#] m	D [#] +	D [#] °7	D [#] 7	D [#] Δ	D [#] m7	D [#] ∅	D [#] 6	D [#] sus2	D [#] sus4	D [#] 9
3 1 1 4	3 1 1 2	1 2 3	2 1 4 3	2 1 4 3	2 1 4 3	3 1 4 2	2 1 4 3	2 1 3 4	3 1 1 1	3 1 1 4	2 1 3 4
E ^b	E ^b m	E ^b +	E ^b °7	E ^b 7	E ^b Δ	E ^b m7	E ^b ∅	E ^b 6	E ^b sus2	E ^b sus4	E ^b 9
3 1 1 4	3 1 1 2	1 2 3	2 1 4 3	2 1 4 3	2 1 4 3	3 1 4 2	2 1 4 3	2 1 3 4	3 1 1 1	3 1 1 4	2 1 3 4
E	E ^m	E ⁺	E°7	E7	EΔ	E ^m 7	E∅	E6	E ^{sus2}	E ^{sus4}	E9
1 2 3	2 3	1 2 3 4	2 1 4 3	1 2	1 1 2	2	1	1 3 2	3 1 1 1	3 1	2 1 3 4
F	F ^m	F ⁺	F°7	F7	FΔ	F ^m 7	F∅	F6	F ^{sus2}	F ^{sus4}	F9
2 3 1	1 3 4 1	1 2 3 4	1 3 2	2 1 3 1	2 3 4 1	1 1 3 1	1 1 2 1	2 3 1	3 4 1	4 2 1 1	2 1 3 4
F [#]	F [#] m	F [#] +	F [#] °7	F [#] 7	F [#] Δ	F [#] m7	F [#] ∅	F [#] 6	F [#] sus2	F [#] sus4	F [#] 9
2 3 4 1	1 3 4 1	1 2 3 4	2 1 4 3	2 1 3 1	2 3 4 1	1 1 3 1	1 1 2 1	3 1 4 2	3 1 1 1	4 2 1 1	2 1 3
G ^b	G ^b m	G ^b +	G ^b °7	G ^b 7	G ^b Δ	G ^b m7	G ^b ∅	G ^b 6	G ^b sus2	G ^b sus4	G ^b 9
2 3 4 1	1 3 4 1	1 2 3 4	2 1 4 3	2 1 3 1	2 3 4 1	1 1 3 1	1 1 2 1	3 1 4 2	3 1 1 1	4 2 1 1	2 1 3
G	G ^m	G ⁺	G°7	G7	GΔ	G ^m 7	G∅	G6	G ^{sus2}	G ^{sus4}	G9
1 2	1 3	1 2 3	2 1 4 3	2 1	1 1	1 1	1 1 2 1	2	3	1 1	1 4
G [#]	G [#] m	G [#] +	G [#] °7	G [#] 7	G [#] Δ	G [#] m7	G [#] ∅	G [#] 6	G [#] sus2	G [#] sus4	G [#] 9
1 1 3 4	1 1 2 4	1 2 3 4	1 3 2	1 1 3 2	1 1 3 3	1 1 2 2	1 2 2	1 1 3 1	1 1 1 4	1 1 3 4	1 3 2 4
A ^b	A ^b m	A ^b +	A ^b °7	A ^b 7	A ^b Δ	A ^b m7	A ^b ∅	A ^b 6	A ^b sus2	A ^b sus4	A ^b 9
1 1 3 4	1 1 2 4	1 2 3 4	1 3 2	1 1 3 2	1 1 3 3	1 1 2 2	1 2 2	1 1 3 1	1 1 1 4	1 1 3 4	1 3 2 4
A	A ^m	A ⁺	A°7	A7	AΔ	A ^m 7	A∅	A6	A ^{sus2}	A ^{sus4}	A9
1 1 3	1 1 2	2 3 4 1	2 1 4 3	1 1 3 2	1 1 3 3	1 1 2 2	2 1 3 4	1 1 3 1	1 1 1	1	1 3 2 4



B.5 Predefined paper sizes

Paper sizes are defined in file `scm/paper.scm`.

ISO 216, A series

"a10"	26 mm x 37 mm (1.02 in x 1.46 in)
"a9"	37 mm x 52 mm (1.46 in x 2.05 in)
"a8"	52 mm x 74 mm (2.05 in x 2.91 in)
"a7"	74 mm x 105 mm (2.91 in x 4.13 in)
"a6"	105 mm x 148 mm (4.13 in x 5.83 in)
"a5"	148 mm x 210 mm (5.83 in x 8.27 in)
"a4"	210 mm x 297 mm (8.27 in x 11.69 in)
"a3"	297 mm x 420 mm (11.69 in x 16.54 in)
"a2"	420 mm x 594 mm (16.54 in x 23.39 in)
"a1"	594 mm x 841 mm (23.39 in x 33.11 in)
"a0"	841 mm x 1189 mm (33.11 in x 46.81 in)

Two extended sizes as defined in DIN 476

"2a0"	1189 mm x 1682 mm (46.81 in x 66.22 in)
"4a0"	1682 mm x 2378 mm (66.22 in x 93.62 in)

ISO 216, B series

"b10"	31 mm x 44 mm (1.22 in x 1.73 in)
"b9"	44 mm x 62 mm (1.73 in x 2.44 in)
"b8"	62 mm x 88 mm (2.44 in x 3.46 in)
"b7"	88 mm x 125 mm (3.46 in x 4.92 in)
"b6"	125 mm x 176 mm (4.92 in x 6.93 in)
"b5"	176 mm x 250 mm (6.93 in x 9.84 in)
"b4"	250 mm x 353 mm (9.84 in x 13.90 in)
"b3"	353 mm x 500 mm (13.90 in x 19.69 in)
"b2"	500 mm x 707 mm (19.69 in x 27.83 in)
"b1"	707 mm x 1000 mm (27.83 in x 39.37 in)
"b0"	1000 mm x 1414 mm (39.37 in x 55.67 in)

ISO 269, C series

"c10"	28 mm x 40 mm (1.10 in x 1.57 in)
"c9"	40 mm x 57 mm (1.57 in x 2.24 in)
"c8"	57 mm x 81 mm (2.24 in x 3.19 in)
"c7"	81 mm x 114 mm (3.19 in x 4.49 in)
"c6"	114 mm x 162 mm (4.49 in x 6.38 in)

"c5"	162 mm x 229 mm (6.38 in x 9.02 in)
"c4"	229 mm x 324 mm (9.02 in x 12.76 in)
"c3"	324 mm x 458 mm (12.76 in x 18.03 in)
"c2"	458 mm x 648 mm (18.03 in x 25.51 in)
"c1"	648 mm x 917 mm (25.51 in x 36.10 in)
"c0"	917 mm x 1297 mm (36.10 in x 51.06 in)

North American paper sizes

"junior-legal"	5.0 in x 8.0 in (127 mm x 203 mm)
"legal"	8.5 in x 14.0 in (216 mm x 356 mm)
"ledger"	17.0 in x 11.0 in (432 mm x 279 mm)
"17x11"	17.0 in x 11.0 in (432 mm x 279 mm)
"letter"	8.5 in x 11.0 in (216 mm x 279 mm)
"tabloid"	11.0 in x 17.0 in (279 mm x 432 mm)
"11x17"	11.0 in x 17.0 in (279 mm x 432 mm)

Sizes by IEEE Printer Working Group, for children's writing

"government-letter"	8.0 in x 10.5 in (203 mm x 267 mm)
"government-legal"	8.5 in x 13.0 in (216 mm x 330 mm)
"philippine-legal"	8.5 in x 13.0 in (216 mm x 330 mm)

ANSI sizes

"ansi a"	8.5 in x 11.0 in (216 mm x 279 mm)
"ansi b"	11.0 in x 17.0 in (279 mm x 432 mm)
"ansi c"	17.0 in x 22.0 in (432 mm x 559 mm)
"ansi d"	22.0 in x 34.0 in (559 mm x 864 mm)
"ansi e"	34.0 in x 44.0 in (864 mm x 1118 mm)
"engineering f"	28.0 in x 40.0 in (711 mm x 1016 mm)

North American architectural sizes

"arch a"	9.0 in x 12.0 in (229 mm x 305 mm)
"arch b"	12.0 in x 18.0 in (305 mm x 457 mm)
"arch c"	18.0 in x 24.0 in (457 mm x 610 mm)
"arch d"	24.0 in x 36.0 in (610 mm x 914 mm)
"arch e"	36.0 in x 48.0 in (914 mm x 1219 mm)
"arch e1"	30.0 in x 42.0 in (762 mm x 1067 mm)

Other sizes, including antique sizes still used in the United Kingdom

"statement"	5.5 in x 8.5 in (140 mm x 216 mm)
"half letter"	5.5 in x 8.5 in (140 mm x 216 mm)
"quarto"	8.0 in x 10.0 in (203 mm x 254 mm)
"octavo"	6.75 in x 10.5 in (171 mm x 267 mm)
"executive"	7.25 in x 10.5 in (184 mm x 267 mm)
"monarch"	7.25 in x 10.5 in (184 mm x 267 mm)
"foolscap"	8.27 in x 13.0 in (210 mm x 330 mm)
"folio"	8.27 in x 13.0 in (210 mm x 330 mm)
"super-b"	13.0 in x 19.0 in (330 mm x 483 mm)
"post"	15.5 in x 19.5 in (394 mm x 495 mm)
"crown"	15.0 in x 20.0 in (381 mm x 508 mm)
"large post"	16.5 in x 21.0 in (419 mm x 533 mm)
"demy"	17.5 in x 22.5 in (445 mm x 572 mm)
"medium"	18.0 in x 23.0 in (457 mm x 584 mm)
"broadsheet"	18.0 in x 24.0 in (457 mm x 610 mm)
"royal"	20.0 in x 25.0 in (508 mm x 635 mm)
"elephant"	23.0 in x 28.0 in (584 mm x 711 mm)

"double demy"	22.5 in x 35.0 in (572 mm x 889 mm)
"quad demy"	35.0 in x 45.0 in (889 mm x 1143 mm)
"atlas"	26.0 in x 34.0 in (660 mm x 864 mm)
"imperial"	22.0 in x 30.0 in (559 mm x 762 mm)
"antiquarian"	31.0 in x 53.0 in (787 mm x 1346 mm)

PA4-based sizes

"pa10"	26 mm x 35 mm (1.02 in x 1.38 in)
"pa9"	35 mm x 52 mm (1.38 in x 2.05 in)
"pa8"	52 mm x 70 mm (2.05 in x 2.76 in)
"pa7"	70 mm x 105 mm (2.76 in x 4.13 in)
"pa6"	105 mm x 140 mm (4.13 in x 5.51 in)
"pa5"	140 mm x 210 mm (5.51 in x 8.27 in)
"pa4"	210 mm x 280 mm (8.27 in x 11.02 in)
"pa3"	280 mm x 420 mm (11.02 in x 16.54 in)
"pa2"	420 mm x 560 mm (16.54 in x 22.05 in)
"pa1"	560 mm x 840 mm (22.05 in x 33.07 in)
"pa0"	840 mm x 1120 mm (33.07 in x 44.09 in)

Additional format for use in Southeast Asia and Australia

"f4"	210 mm x 330 mm (8.27 in x 12.99 in)

B.6 MIDI instruments

The following is a list of names that can be used for the `midiInstrument` property. Each is presented with its number among the General MIDI Standard's 128 Program Numbers.

1 acoustic grand	2 bright acoustic	3 electric grand
4 honky-tonk	5 electric piano 1	6 electric piano 2
7 harpsichord	8 clav	9 celesta
10 glockenspiel	11 music box	12 vibraphone
13 marimba	14 xylophone	15 tubular bells
16 dulcimer	17 drawbar organ	18 percussive organ
19 rock organ	20 church organ	21 reed organ
22 accordion	23 harmonica	24 concertina
25 acoustic guitar (nylon)	26 acoustic guitar (steel)	27 electric guitar (jazz)
28 electric guitar (clean)	29 electric guitar (muted)	30 overdriven guitar
31 distorted guitar	32 guitar harmonics	33 acoustic bass
34 electric bass (finger)	35 electric bass (pick)	36 fretless bass
37 slap bass 1	38 slap bass 2	39 synth bass 1
40 synth bass 2	41 violin	42 viola
43 cello	44 contrabass	45 tremolo strings
46 pizzicato strings	47 orchestral harp	48 timpani
49 string ensemble 1	50 string ensemble 2	51 synthstrings 1
52 synthstrings 2	53 choir aahs	54 voice oohs
55 synth voice	56 orchestra hit	57 trumpet
58 trombone	59 tuba	60 muted trumpet
61 french horn	62 brass section	63 synthbrass 1
64 synthbrass 2	65 soprano sax	66 alto sax
67 tenor sax	68 baritone sax	69 oboe
70 english horn	71 bassoon	72 clarinet
73 piccolo	74 flute	75 recorder
76 pan flute	77 blown bottle	78 shakuhachi
79 whistle	80 ocarina	81 lead 1 (square)
82 lead 2 (sawtooth)	83 lead 3 (calliope)	84 lead 4 (chiff)
85 lead 5 (charang)	86 lead 6 (voice)	87 lead 7 (fifths)
88 lead 8 (bass+lead)	89 pad 1 (new age)	90 pad 2 (warm)
91 pad 3 (polysynth)	92 pad 4 (choir)	93 pad 5 (bowed)
94 pad 6 (metallic)	95 pad 7 (halo)	96 pad 8 (sweep)
97 fx 1 (rain)	98 fx 2 (soundtrack)	99 fx 3 (crystal)
100 fx 4 (atmosphere)	101 fx 5 (brightness)	102 fx 6 (goblins)

103	fx 7 (echoes)	104	fx 8 (sci-fi)	105	sitar
106	banjo	107	shamisen	108	koto
109	kalimba	110	bagpipe	111	fiddle
112	shanai	113	tinkle bell	114	agogo
115	steel drums	116	woodblock	117	taiko drum
118	melodic tom	119	synth drum	120	reverse cymbal
121	guitar fret noise	122	breath noise	123	seashore
124	bird tweet	125	telephone ring	126	helicopter
127	applause	128	gunshot		

The drum kits listed below are also possible.

1	standard kit	9	room kit	17	power kit
25	electronic kit	26	tr-808 kit	33	jazz kit
41	brush kit	49	orchestra kit	57	sfx kit
128	mt-32 kit/cm-64 kit				

B.7 List of colors

Normal colors

See Section 7.1.5 [Coloring objects], page 288, for detailed usage syntax.

 black	 white	 red	 green
 blue	 cyan	 magenta	 yellow
 grey	 darkred	 darkgreen	 darkblue
 darkcyan	 darkmagenta	 darkyellow	

CSS color names

CSS color names may be used as-is in string arguments.

 aliceblue	 antiquewhite	 aqua
 aquamarine	 azure	 beige
 bisque	 black	 blanchedalmond
 blue	 blueviolet	 brown
 burlywood	 cadetblue	 chartreuse
 chocolate	 coral	 cornflowerblue
 cornsilk	 crimson	 cyan
 darkblue	 darkcyan	 darkgoldenrod
 darkgray	 darkgreen	 darkgrey
 darkkhaki	 darkmagenta	 darkolivegreen
 darkorange	 darkorchid	 darkred
 darksalmon	 darkseagreen	 darkslateblue
 darkslategray	 darkslategrey	 darkturquoise
 darkviolet	 deeppink	 deepskyblue
 dimgray	 dimgrey	 dodgerblue
 firebrick	 floralwhite	 forestgreen
 fuchsia	 gainsboro	 ghostwhite
 gold	 goldenrod	 gray
 green	 greenyellow	 grey
 honeydew	 hotpink	 indianred
 indigo	 ivory	 khaki
 lavender	 lavenderblush	 lawngreen
 lemonchiffon	 lightblue	 lightcoral
 lightcyan	 lightgoldenrodyellow	 lightgray
 lightgreen	 lightgrey	 lightpink
 lightsalmon	 lightseagreen	 lightskyblue

 lightslategray	 lightslategray	 lightsteelblue
 lightyellow	 lime	 limegreen
 linen	 magenta	 maroon
 mediumaquamarine	 mediumblue	 mediumorchid
 mediumpurple	 mediumseagreen	 mediumslateblue
 mediumspringgreen	 mediumturquoise	 mediumvioletred
 midnightblue	 mintcream	 mistyrose
 moccasin	 navajowhite	 navy
 oldlace	 olive	 olivedrab
 orange	 orangered	 orchid
 palegoldenrod	 palegreen	 paleturquoise
 palevioletred	 papayawhip	 peachpuff
 peru	 pink	 plum
 powderblue	 purple	 rebeccapurple
 red	 rosybrown	 royalblue
 saddlebrown	 salmon	 sandybrown
 seagreen	 seashell	 sienna
 silver	 skyblue	 slateblue
 slategray	 slategrey	 snow
 springgreen	 steelblue	 tan
 teal	 thistle	 tomato
 turquoise	 violet	 wheat
 white	 whitesmoke	 yellow
 yellowgreen		

CSS color definitions differ from X color names for the following colors: green, grey, maroon, purple.

X color names

X11 color names (https://en.wikipedia.org/wiki/X11_color_names) offer a wider choice than CSS names. They come in several variants:

- Any name that is spelled as a single word with capitalization (e.g., ‘LightSlateBlue’) can also be spelled as space-separated words with or without capitalization (e.g., ‘light slate blue’).
- The word ‘grey’ can always be spelled ‘gray’ (e.g., ‘DarkSlateGray’), without any difference in the output.
- Some names can take a numerical suffix (e.g., ‘LightSalmon4’).

Use the Scheme function `x11-color` to access them.

Color Names without a numerical suffix

The following table presents all color names that may be used without a numerical suffix.

 aliceblue	 antiquewhite	 aquamarine
 azure	 beige	 bisque
 black	 blanchedalmond	 blue
 blueviolet	 brown	 burlywood
 cadetblue	 chartreuse	 chocolate
 coral	 cornflowerblue	 cornsilk
 cyan	 darkblue	 darkcyan
 darkgoldenrod	 darkgray	 darkgreen
 darkgrey	 darkkhaki	 darkmagenta

	darkolivegreen		darkorange		darkorchid
	darkred		darksalmon		darkseagreen
	darkslateblue		darkslategray		darkslategrey
	darkturquoise		darkviolet		deeppink
	deepskyblue		dimgray		dimgrey
	dodgerblue		firebrick		floralwhite
	forestgreen		gainsboro		ghostwhite
	gold		goldenrod		gray
	green		greenyellow		grey
	honeydew		hotpink		indianred
	ivory		khaki		lavender
	lavenderblush		lawngreen		lemonchiffon
	lightblue		lightcoral		lightcyan
	lightgoldenrod		lightgoldenrodyellow		lightgray
	lightgreen		lightgrey		lightpink
	lightsalmon		lightseagreen		lightskyblue
	lightslateblue		lightslategray		lightslategrey
	lightsteelblue		lightyellow		limegreen
	linen		magenta		maroon
	mediumaquamarine		mediumblue		mediumorchid
	mediumpurple		mediumseagreen		mediumslateblue
	mediumspringgreen		mediumturquoise		mediumvioletred
	midnightblue		mintcream		mistyrose
	moccasin		navajowhite		navy
	navyblue		oldlace		olivedrab
	orange		orangered		orchid
	palegoldenrod		palegreen		paleturquoise
	palevioletred		papayawhip		peachpuff
	peru		pink		plum
	powderblue		purple		red
	rosybrown		royalblue		saddlebrown
	salmon		sandybrown		seagreen
	seashell		sienna		skyblue
	slateblue		slategray		slategrey
	snow		springgreen		steelblue
	tan		thistle		tomato
	turquoise		violet		violetred
	wheat		white		whitesmoke
	yellow		yellowgreen		

Color names with a numerical suffix

A subset of the X11 color names may be used with a numerical suffix in the range 1 to 4 to get darker shades. Note that for such colors, color foo is identical to color foo1.

	antiquewhite1		antiquewhite2		antiquewhite3		antiquewhite4
	aquamarine1		aquamarine2		aquamarine3		aquamarine4
	azure1		azure2		azure3		azure4
	bisque1		bisque2		bisque3		bisque4
	blue1		blue2		blue3		blue4
	brown1		brown2		brown3		brown4
	burlywood1		burlywood2		burlywood3		burlywood4

	cadetblue1		cadetblue2		cadetblue3		cadetblue4
	chartreuse1		chartreuse2		chartreuse3		chartreuse4
	chocolate1		chocolate2		chocolate3		chocolate4
	coral1		coral2		coral3		coral4
	cornsilk1		cornsilk2		cornsilk3		cornsilk4
	cyan1		cyan2		cyan3		cyan4
	darkgoldenrod1		darkgoldenrod2		darkgoldenrod3		darkgoldenrod4
	darkolivegreen1		darkolivegreen2		darkolivegreen3		darkolivegreen4
	darkorange1		darkorange2		darkorange3		darkorange4
	darkorchid1		darkorchid2		darkorchid3		darkorchid4
	darkseagreen1		darkseagreen2		darkseagreen3		darkseagreen4
	darkslategray1		darkslategray2		darkslategray3		darkslategray4
	deeppink1		deeppink2		deeppink3		deeppink4
	deepskyblue1		deepskyblue2		deepskyblue3		deepskyblue4
	dodgerblue1		dodgerblue2		dodgerblue3		dodgerblue4
	firebrick1		firebrick2		firebrick3		firebrick4
	gold1		gold2		gold3		gold4
	goldenrod1		goldenrod2		goldenrod3		goldenrod4
	green1		green2		green3		green4
	honeydew1		honeydew2		honeydew3		honeydew4
	hotpink1		hotpink2		hotpink3		hotpink4
	indianred1		indianred2		indianred3		indianred4
	ivory1		ivory2		ivory3		ivory4
	khaki1		khaki2		khaki3		khaki4
	lavenderblush1		lavenderblush2		lavenderblush3		lavenderblush4
	lemonchiffon1		lemonchiffon2		lemonchiffon3		lemonchiffon4
	lightblue1		lightblue2		lightblue3		lightblue4
	lightcyan1		lightcyan2		lightcyan3		lightcyan4
	lightgoldenrod1		lightgoldenrod2		lightgoldenrod3		lightgoldenrod4
	lightpink1		lightpink2		lightpink3		lightpink4
	lightsalmon1		lightsalmon2		lightsalmon3		lightsalmon4
	lightskyblue1		lightskyblue2		lightskyblue3		lightskyblue4
	lightsteelblue1		lightsteelblue2		lightsteelblue3		lightsteelblue4
	lightyellow1		lightyellow2		lightyellow3		lightyellow4
	magenta1		magenta2		magenta3		magenta4
	maroon1		maroon2		maroon3		maroon4
	mediumorchid1		mediumorchid2		mediumorchid3		mediumorchid4
	mediumpurple1		mediumpurple2		mediumpurple3		mediumpurple4
	mistyrose1		mistyrose2		mistyrose3		mistyrose4
	navajowhite1		navajowhite2		navajowhite3		navajowhite4
	olivedrab1		olivedrab2		olivedrab3		olivedrab4
	orange1		orange2		orange3		orange4
	orangered1		orangered2		orangered3		orangered4
	orchid1		orchid2		orchid3		orchid4
	palegreen1		palegreen2		palegreen3		palegreen4
	paleturquoise1		paleturquoise2		paleturquoise3		paleturquoise4
	palevioletred1		palevioletred2		palevioletred3		palevioletred4
	peachpuff1		peachpuff2		peachpuff3		peachpuff4
	pink1		pink2		pink3		pink4
	plum1		plum2		plum3		plum4

	purple1		purple2		purple3		purple4
	red1		red2		red3		red4
	rosybrown1		rosybrown2		rosybrown3		rosybrown4
	royalblue1		royalblue2		royalblue3		royalblue4
	salmon1		salmon2		salmon3		salmon4
	seagreen1		seagreen2		seagreen3		seagreen4
	seashell1		seashell2		seashell3		seashell4
	sienna1		sienna2		sienna3		sienna4
	skyblue1		skyblue2		skyblue3		skyblue4
	slateblue1		slateblue2		slateblue3		slateblue4
	slategray1		slategray2		slategray3		slategray4
	snow1		snow2		snow3		snow4
	springgreen1		springgreen2		springgreen3		springgreen4
	steelblue1		steelblue2		steelblue3		steelblue4
	tan1		tan2		tan3		tan4
	thistle1		thistle2		thistle3		thistle4
	tomato1		tomato2		tomato3		tomato4
	turquoise1		turquoise2		turquoise3		turquoise4
	violetred1		violetred2		violetred3		violetred4
	wheat1		wheat2		wheat3		wheat4
	yellow1		yellow2		yellow3		yellow4

Grey Scale

The set of X11 colors also contains a palette of 101 gray shades.

	gray0		gray1		gray2		gray3		gray4
	gray5		gray6		gray7		gray8		gray9
	gray10		gray11		gray12		gray13		gray14
	gray15		gray16		gray17		gray18		gray19
	gray20		gray21		gray22		gray23		gray24
	gray25		gray26		gray27		gray28		gray29
	gray30		gray31		gray32		gray33		gray34
	gray35		gray36		gray37		gray38		gray39
	gray40		gray41		gray42		gray43		gray44
	gray45		gray46		gray47		gray48		gray49
	gray50		gray51		gray52		gray53		gray54
	gray55		gray56		gray57		gray58		gray59
	gray60		gray61		gray62		gray63		gray64
	gray65		gray66		gray67		gray68		gray69
	gray70		gray71		gray72		gray73		gray74
	gray75		gray76		gray77		gray78		gray79
	gray80		gray81		gray82		gray83		gray84
	gray85		gray86		gray87		gray88		gray89
	gray90		gray91		gray92		gray93		gray94
	gray95		gray96		gray97		gray98		gray99
	gray100								

The table for color names grayN looks the same.

Color-blind-safe colors

The Scheme function `universal-color` provides a set of eight colors (<https://jfly.uni-koeln.de/color>) designed to be unambiguous to people with dichromatism.



B.8 The Emmentaler font

The Emmentaler font consists of two *subsets* of glyphs: “Feta”, used for classical notation, and “Parmesan”, used for ancient notation.

Any glyph within the Emmentaler font can be accessed directly by using text markup along with the name of the glyph (as shown in the tables below). For example;

```
g^{\markup {\musicglyph "scripts.segno" }}
or
\markup {\musicglyph "five"}
```

See Section 8.2 [Formatting text], page 319, for more information.

B.8.1 Modern glyph charts

All glyphs of the “Feta” subset.

Clef glyphs

<code>clefs.C</code>		<code>clefs.C_change</code>	
<code>clefs.varC</code>		<code>clefs.varC_change</code>	
<code>clefs.F</code>		<code>clefs.F_change</code>	
<code>clefs.G</code>		<code>clefs.G_change</code>	
<code>clefs.GG</code>		<code>clefs.GG_change</code>	
<code>clefs.tenorG</code>		<code>clefs.tenorG_change</code>	
<code>clefs.percussion</code>		<code>clefs.percussion_change</code>	
<code>clefs.varpercussion</code>		<code>clefs .varpercussion_change</code>	
<code>clefs.tab</code>		<code>clefs.tab_change</code>	

Time Signature glyphs

<code>timesig.C44</code>		<code>timesig.C44.text</code>	
<code>timesig.C22</code>		<code>timesig.C22.text</code>	
<code>timesig.X</code>			

Number glyphs

plus	+	comma	,
hyphen	-	equal	=
period	.	figuredash	-
endash	-	parenleft	(
parenright	)	slash	/
zero	0	one	1
two	2	three	3
four	4	four.alt	4
five	5	six	6
seven	7	seven.alt	7
eight	8	nine	9
fixedwidth.zero	0	fixedwidth.one	1
fixedwidth.two	2	fixedwidth.three	3
fixedwidth.four	4	fixedwidth.four.alt	4
fixedwidth.five	5	fixedwidth.six	6
fixedwidth.seven	7	fixedwidth.seven.alt	7
fixedwidth.eight	8	fixedwidth.nine	9
fattened.zero	0	fattened.one	1
fattened.two	2	fattened.three	3
fattened.four	4	fattened.four.alt	4
fattened.five	5	fattened.six	6
fattened.seven	7	fattened.seven.alt	7
fattened.eight	8	fattened.nine	9
fattened.fixedwidth.zero	0	fattened.fixedwidth.one	1
fattened.fixedwidth.two	2	fattened .fixedwidth.three	3
fattened.fixedwidth.four	4	fattened.fixedwidth .four.alt	4

fattened.fixedwidth.five	5	fattened.fixedwidth.six	6
fattened	7	fattened.fixedwidth	7
.fixedwidth.seven	8	.seven.alt	9
fattened		fattened.fixedwidth.nine	
.fixedwidth.eight			
u2007		u2009	
u200A			

Figured bass symbol glyphs

figbass.twoplus	2₊	figbass.fourplus	4₊
figbass.fiveplus	5⁺	figbass.sixstroked	6[~]
figbass.sevenstroked	7[~]	figbass.ninestroked	9[~]

Accidental glyphs

accidentals.sharp	#	accidentals	#
accidentals	#	.sharp.figbass	#
.sharp.arrowup	#	accidentals	#
accidentals	#	.sharp.arrowdown	#
.sharp.arrowboth	#	accidentals.sharp	#
accidentals.sharp	#	.slashslash.stem	#
.slashslashslash.stemstem	#	accidentals.sharp	#
accidentals	#	.slashslashslash.stem	#
.sharp.slash.stem	#	accidentals.sharp	#
accidentals.doublesharp	#	.slashslash.stemstemstem	#
accidentals.natural	b	accidentals	#
accidentals	b	.doublesharp.figbass	#
.natural.arrowup	b	accidentals	b
accidentals	b	.natural.figbass	b
.natural.arrowboth	b	accidentals	b
accidentals.flat.figbass	b	.natural.arrowdown	b
accidentals	b	accidentals.flat	b
.flat.arrowdown	b	accidentals.flat.arrowup	b
accidentals.flat.slash	b	accidentals	b
accidentals	b	.flat.arrowboth	b
.mirroredflat.flat	b	accidentals.flat	b
accidentals	b	.slashslash	b
.mirroredflat.backslash	b	accidentals.mirroredflat	b
accidentals	b	accidentals.flatflat	b
.flatflat.figbass	b	accidentals	b
accidentals.sharp.sori	#	.flatflat.slash	b
accidentals.rightparen	)	accidentals.flat.koron	p
		accidentals.leftparen	(

Default note head glyphs

<code>noteheads.uM2</code>		<code>noteheads.dM2</code>	
<code>noteheads.sM1</code>		<code>noteheads.s0</code>	
<code>noteheads.s1</code>		<code>noteheads.s2</code>	

Special note head glyphs

<code>noteheads.sM1double</code>		<code>noteheads.s0diamond</code>	
<code>noteheads.s1diamond</code>		<code>noteheads.s2diamond</code>	
<code>noteheads.s0triangle</code>		<code>noteheads.s1triangle</code>	
<code>noteheads.s2triangle</code>		<code>noteheads.s0slash</code>	
<code>noteheads.s1slash</code>		<code>noteheads.s2slash</code>	
<code>noteheads.s0cross</code>		<code>noteheads.s1cross</code>	
<code>noteheads.s2cross</code>		<code>noteheads.s2xcircle</code>	
<code>noteheads.d0arrow</code>		<code>noteheads.u0arrow</code>	
<code>noteheads.d2arrow</code>		<code>noteheads.u2arrow</code>	
<code>noteheads.s0harmonic</code>		<code>noteheads.s2harmonic</code>	

Note head glyphs for shape notes

<code>noteheads.s0do</code>		<code>noteheads.s1do</code>	
<code>noteheads.s2do</code>		<code>noteheads.s0doThin</code>	
<code>noteheads.s1doThin</code>		<code>noteheads.s2doThin</code>	
<code>noteheads.s0re</code>		<code>noteheads.s1re</code>	
<code>noteheads.s2re</code>		<code>noteheads.s0reThin</code>	
<code>noteheads.s1reThin</code>		<code>noteheads.s2reThin</code>	
<code>noteheads.s0mi</code>		<code>noteheads.s1mi</code>	
<code>noteheads.s2mi</code>		<code>noteheads.s0miMirror</code>	
<code>noteheads.s1miMirror</code>		<code>noteheads.s2miMirror</code>	
<code>noteheads.s0miThin</code>		<code>noteheads.s1miThin</code>	

noteheads.s2miThin	◆	noteheads.u0fa	▷
noteheads.d0fa	▷	noteheads.ulfa	▷
noteheads.d1fa	▷	noteheads.u2fa	◀
noteheads.d2fa	◀	noteheads.u0faThin	▷
noteheads.d0faThin	▷	noteheads.ulfaThin	▷
noteheads.d1faThin	▷	noteheads.u2faThin	◀
noteheads.d2faThin	◀	noteheads.s0sol	○
noteheads.s1sol	○	noteheads.s2sol	●
noteheads.s0la	□	noteheads.s1la	□
noteheads.s2la	■	noteheads.s0laThin	□
noteheads.s1laThin	□	noteheads.s2laThin	■
noteheads.s0ti	◇	noteheads.s1ti	◇
noteheads.s2ti	◆	noteheads.s0tiThin	◇
noteheads.s1tiThin	◇	noteheads.s2tiThin	◆
noteheads.u0doFunk	▷	noteheads.d0doFunk	▷
noteheads.u1doFunk	▷	noteheads.d1doFunk	▷
noteheads.u2doFunk	◀	noteheads.d2doFunk	◀
noteheads.u0reFunk	▷	noteheads.d0reFunk	▷
noteheads.u1reFunk	▷	noteheads.d1reFunk	▷
noteheads.u2reFunk	◀	noteheads.d2reFunk	◀
noteheads.u0miFunk	◇	noteheads.d0miFunk	◇
noteheads.u1miFunk	◇	noteheads.d1miFunk	◇
noteheads.s2miFunk	◆	noteheads.u0faFunk	▷
noteheads.d0faFunk	▷	noteheads.ulfaFunk	▷
noteheads.d1faFunk	▷	noteheads.u2faFunk	◀
noteheads.d2faFunk	◀	noteheads.s0solFunk	○
noteheads.s1solFunk	○	noteheads.s2solFunk	●

noteheads.s0laFunk	◻	noteheads.s1laFunk	◻
noteheads.s2laFunk	■	noteheads.u0tiFunk	▷
noteheads.d0tiFunk	◁	noteheads.ultiFunk	▷
noteheads.d1tiFunk	◁	noteheads.u2tiFunk	►
noteheads.d2tiFunk	◄	noteheads.s0doWalker	▢
noteheads.u1doWalker	▽	noteheads.d1doWalker	▢
noteheads.u2doWalker	▼	noteheads.d2doWalker	▲
noteheads.s0reWalker	◁	noteheads.ulreWalker	▷
noteheads.d1reWalker	◁	noteheads.u2reWalker	►
noteheads.d2reWalker	◄	noteheads.s0miWalker	◊
noteheads.s1miWalker	◊	noteheads.s2miWalker	◆
noteheads.s0faWalker	▴	noteheads.u1faWalker	▾
noteheads.d1faWalker	▴	noteheads.u2faWalker	▾
noteheads.d2faWalker	▴	noteheads.s0laWalker	◻
noteheads.s1laWalker	◻	noteheads.s2laWalker	■
noteheads.s0tiWalker	◁	noteheads.ultiWalker	▷
noteheads.d1tiWalker	◁	noteheads.u2tiWalker	►
noteheads.d2tiWalker	◄		

Rest glyphs

rests.0	—	rests.1	—
rests.0o	—	rests.1o	—
rests.M3		rests.M2	
rests.M1	■	rests.M1o	■
rests.2	♪	rests.2classical	♪
rests.2z	♪	rests.3	♪
rests.4	♪	rests.5	♪

rests.6



rests.7



rests.8



rests.9



rests.10



Flag glyphs

flags.u3



flags.u4



flags.u5



flags.u6



flags.u7



flags.u8



flags.u9



flags.u10



flags.d3



flags.d4



flags.d5



flags.d6



flags.d7



flags.d8



flags.d9



flags.d10



flags.stackedu3



flags.stackedu4



flags.stackedu5



flags.stackedu6



flags.stackedu7



flags.stackedu8



flags.stackedu9



flags.stackedu10



flags.stackedd3



flags.stackedd4



flags.stackedd5		flags.stackedd6	
flags.stackedd7		flags.stackedd8	
flags.stackedd9		flags.stackedd10	
flags.ugrace		flags.dgrace	

Dot glyphs

dots.dot	

Dynamic glyphs

space		f	
m		n	
p		r	
s		z	

Script glyphs

scripts.ufermata		scripts.dfermata	
scripts		scripts	
.uhenzeshortfermata		.dhenzeshortfermata	
scripts		scripts	
.uhenzelongfermata		.dhenzelongfermata	
scripts.ushortfermata		scripts.dshortfermata	
scripts		scripts	
.uveryshortfermata		.dveryshortfermata	
scripts.ulongfermata		scripts.dlongfermata	
scripts.uverylongfermata		scripts.dverylongfermata	
scripts.thumb		scripts.sforzato	
scripts.espr		scripts.staccato	
scripts.ustaccatissimo		scripts.dstaccatissimo	
scripts.tenuto		scripts.uportato	
scripts.dportato		scripts.umarcato	

<code>scripts.dmarcato</code>		<code>scripts.open</code>	
<code>scripts.halfopen</code>		<code>scripts.halfopenvertical</code>	
<code>scripts.stopped</code>		<code>scripts.uupbow</code>	
<code>scripts.dupbow</code>		<code>scripts.udownbow</code>	
<code>scripts.ddownbow</code>		<code>scripts.reverseturn</code>	
<code>scripts.turn</code>		<code>scripts.slashturn</code>	
<code>scripts.haydnturn</code>		<code>scripts.trill</code>	
<code>scripts.upedalheel</code>		<code>scripts.dpedalheel</code>	
<code>scripts.upedaltoe</code>		<code>scripts.dpedaltoe</code>	
<code>scripts.pedalheelcircle</code>		<code>scripts.flageolet</code>	
<code>scripts.segno</code>		<code>scripts.varsegno</code>	
<code>scripts.coda</code>		<code>scripts.varcoda</code>	
<code>scripts.rcomma</code>		<code>scripts.lcomma</code>	
<code>scripts.rvarcomma</code>		<code>scripts.lvarcomma</code>	
<code>scripts.raltcomma</code>		<code>scripts.laltcomma</code>	
<code>scripts.arpeggio</code>		<code>scripts.trill_element</code>	
<code>scripts.arpeggio</code> <code>.arrow.M1</code>		<code>scripts.arpeggio.arrow.1</code>	
<code>scripts.prall</code>		<code>scripts.mordent</code>	
<code>scripts.prallprall</code>		<code>scripts.prallmordent</code>	
<code>scripts.upprall</code>		<code>scripts.upmordent</code>	
<code>scripts.prallup</code>		<code>scripts.downprall</code>	
<code>scripts.downmordent</code>		<code>scripts.pralldown</code>	
<code>scripts.lineprall</code>		<code>scripts.bachschleifer</code>	
<code>scripts.caesura.curved</code>		<code>scripts.caesura.straight</code>	
<code>scripts.tickmark</code>		<code>scripts.snappizzicato</code>	
<code>scripts.ictus</code>		<code>scripts.uaccentus</code>	

<code>scripts.daccentus</code>		<code>scripts.usemicirculus</code>	
<code>scripts.dsemicirculus</code>		<code>scripts.circulus</code>	
<code>scripts</code> <code>.usignumcongruentiae</code>		<code>scripts</code> <code>.dsignumcongruentiae</code>	

Arrowhead glyphs

<code>arrowheads.open.01</code>		<code>arrowheads.open.0M1</code>	
<code>arrowheads.open.11</code>		<code>arrowheads.open.1M1</code>	
<code>arrowheads.close.01</code>		<code>arrowheads.close.0M1</code>	
<code>arrowheads.close.11</code>		<code>arrowheads.close.1M1</code>	

Bracket-tip glyphs

<code>brackettips.up</code>		<code>brackettips.down</code>	

Pedal glyphs

<code>pedal.*</code>		<code>pedal.M</code>	
<code>pedal..</code>		<code>pedal.P</code>	
<code>pedal.d</code>		<code>pedal.e</code>	
<code>pedal.Ped</code>			

Accordion glyphs

<code>accordion.discant</code>		<code>accordion.dot</code>	
<code>accordion.freebass</code>		<code>accordion.stdbass</code>	
<code>accordion.bayanbass</code>		<code>accordion.oldEE</code>	
<code>accordion.push</code>		<code>accordion.pull</code>	

Tie glyphs

<code>ties.lyric.short</code>		<code>ties.lyric.default</code>	

B.8.2 Ancient glyph charts

All glyphs of the “Parmesan” subset.

Vaticana glyphs

<code>clefs.vaticana.do</code>		<code>clefs.vaticana.do_change</code>	
<code>clefs.vaticana.fa</code>		<code>clefs.vaticana.fa_change</code>	
<code>custodes.vaticana.u0</code>		<code>custodes.vaticana.u1</code>	
<code>custodes.vaticana.u2</code>		<code>custodes.vaticana.d0</code>	
<code>custodes.vaticana.d1</code>		<code>custodes.vaticana.d2</code>	
<code>accidentals.vaticanaM1</code>		<code>accidentals.vaticana0</code>	
<code>dots.dotvaticana</code>		<code>noteheads</code>	
<code>noteheads.svaticana</code>		<code>noteheads.svaticana</code>	
<code>noteheads.svaticana.punctum</code>		<code>noteheads.svaticana</code>	
<code>noteheads.svaticana</code>		<code>noteheads.svaticana</code>	
<code>noteheads.svaticana.linea.punctum.cavum</code>		<code>noteheads.svaticana</code>	
<code>noteheads.svaticana.lpes</code>		<code>noteheads</code>	
<code>noteheads.svaticana.upes</code>		<code>noteheads</code>	
<code>noteheads</code>		<code>noteheads</code>	
<code>noteheads.svaticana.plica</code>		<code>noteheads.svaticana</code>	
<code>noteheads</code>		<code>noteheads.svaticana</code>	
<code>noteheads.svaticana.epiphonus</code>		<code>noteheads.svaticana</code>	
<code>noteheads.svaticana</code>		<code>noteheads.svaticana</code>	
<code>noteheads.svaticana.reverse.plica</code>		<code>noteheads.svaticana</code>	
<code>noteheads.svaticana</code>		<code>noteheads.svaticana</code>	
<code>noteheads.svaticana.inner.cephalicus</code>		<code>noteheads.svaticana</code>	
<code>noteheads</code>		<code>noteheads.svaticana</code>	
<code>noteheads.svaticana.quilisma</code>			

Medicaea glyphs

<code>clefs.medicaea.do</code>		<code>clefs.medicaea.do_change</code>	
<code>clefs.medicaea.fa</code>		<code>clefs.medicaea.fa_change</code>	
<code>custodes.medicaea.u0</code>		<code>custodes.medicaea.u1</code>	
<code>custodes.medicaea.u2</code>		<code>custodes.medicaea.d0</code>	
<code>custodes.medicaea.d1</code>		<code>custodes.medicaea.d2</code>	
<code>accidentals.medicaeaM1</code>		<code>noteheads.smedicaea</code>	
<code>noteheads</code>		<code>noteheads</code>	
<code>noteheads.smedicaea.punctum</code>		<code>noteheads.smedicaea.rvirga</code>	
<code>noteheads</code>			
<code>noteheads.smedicaea.virga</code>			

Hufnagel glyphs

clefs.hufnagel.do		clefs.hufnagel.do_change	
clefs.hufnagel.fa		clefs.hufnagel.fa_change	
clefs.hufnagel.do.fa		clefs.hufnagel .do.fa_change	
custodes.hufnagel.u0		custodes.hufnagel.u1	
custodes.hufnagel.u2		custodes.hufnagel.d0	
custodes.hufnagel.d1		custodes.hufnagel.d2	
accidentals.hufnagelM1		noteheads .shufnagel.punctum	
noteheads .shufnagel.virga		noteheads.shufnagel.lpes	

Mensural glyphs

rests.M3mensural		rests.M2mensural	
rests.M1mensural		rests.0mensural	
rests.1mensural		rests.2mensural	
rests.3mensural		rests.4mensural	
clefs.mensural.c		clefs.mensural.c_change	
clefs.blackmensural.c		clefs.blackmensural .c_change	
clefs.mensural.f		clefs.mensural.f_change	
clefs.mensural.g		clefs.mensural.g_change	
custodes.mensural.u0		custodes.mensural.u1	
custodes.mensural.u2		custodes.mensural.d0	
custodes.mensural.d1		custodes.mensural.d2	
accidentals.mensural1		accidentals.mensuralM1	
flags.mensuralu03		flags.mensuralu13	
flags.mensuralu23		flags.mensurald03	
flags.mensurald13		flags.mensurald23	
flags.mensuralu04		flags.mensuralu14	

flags.mensuralu24		flags.mensurald04	
flags.mensurald14		flags.mensurald24	
flags.mensuralu05		flags.mensuralu15	
flags.mensuralu25		flags.mensurald05	
flags.mensurald15		flags.mensurald25	
flags.mensuralu06		flags.mensuralu16	
flags.mensuralu26		flags.mensurald06	
flags.mensurald16		flags.mensurald26	
timesig.mensural44		timesig.mensural22	
timesig.mensural32		timesig.mensural64	
timesig.mensural94		timesig.mensural34	
timesig.mensural68		timesig.mensural98	
timesig.mensural48		timesig.mensural68alt	
timesig.mensural24		noteheads.uM3mensural	
noteheads.dM3mensural		noteheads.sM3ligmensural	
noteheads.uM2mensural		noteheads.dM2mensural	
noteheads.sM2ligmensural		noteheads.sM1mensural	
noteheads.urM3mensural		noteheads.drM3mensural	
noteheads		noteheads.urM2mensural	
.srM3ligmensural		noteheads	
noteheads.drM2mensural		.srM2ligmensural	
noteheads.srM1mensural		noteheads	
noteheads		.uM3semimensural	
.dM3semimensural		noteheads	
noteheads		.sM3semiligmensural	
.uM2semimensural		noteheads	
noteheads		.dM2semimensural	
.sM2semiligmensural		noteheads	
		.sM1semimensural	

noteheads		noteheads	
.urM3semimensural		.drM3semimensural	
noteheads		noteheads	
.srM3semiligmensural		.urM2semimensural	
noteheads		noteheads	
.drM2semimensural		.srM2semiligmensural	
noteheads		noteheads	
.srM1semimensural		.uM3blackmensural	
noteheads		noteheads	
.dM3blackmensural		.sM3blackligmensural	
noteheads		noteheads	
.uM2blackmensural		.dM2blackmensural	
noteheads		noteheads	
.sM2blackligmensural		.sM1blackmensural	
noteheads.s0mensural		noteheads.s1mensural	
noteheads.s2mensural		noteheads	
		.s0blackmensural	

Neomensural glyphs

rests.M3neomensural		rests.M2neomensural	
rests.M1neomensural		rests.0neomensural	
rests.1neomensural		rests.2neomensural	
rests.3neomensural		rests.4neomensural	
clefs.neomensural.c		clefs.neomensural	
timesig.neomensural44		.c_change	
timesig.neomensural32		timesig.neomensural22	
timesig.neomensural194		timesig.neomensural64	
timesig.neomensural194		timesig.neomensural34	
timesig.neomensural68		timesig.neomensural98	
timesig.neomensural48		timesig.neomensural68alt	
timesig.neomensural24		noteheads.uM3neomensural	
noteheads.dM3neomensural		noteheads.uM2neomensural	
noteheads.dM2neomensural		noteheads.sM1neomensural	
noteheads		noteheads	
.urM3neomensural		.drM3neomensural	
noteheads		noteheads	
.urM2neomensural		.drM2neomensural	
noteheads		noteheads.s0neomensural	
.srM1neomensural		noteheads.s2neomensural	
noteheads.s1neomensural			

Petrucchi glyphs

<code>clefs.petrucchi.c1</code>		<code>clefs.petrucchi.c1_change</code>	
<code>clefs.petrucchi.c2</code>		<code>clefs.petrucchi.c2_change</code>	
<code>clefs.petrucchi.c3</code>		<code>clefs.petrucchi.c3_change</code>	
<code>clefs.petrucchi.c4</code>		<code>clefs.petrucchi.c4_change</code>	
<code>clefs.petrucchi.c5</code>		<code>clefs.petrucchi.c5_change</code>	
<code>clefs.petrucchi.f</code>		<code>clefs.petrucchi.f_change</code>	
<code>clefs.petrucchi.g</code>		<code>clefs.petrucchi.g_change</code>	
<code>noteheads.s0petrucci</code>		<code>noteheads.s1petrucci</code>	
<code>noteheads.s2petrucci</code>		<code>noteheads.s0blackpetrucci</code>	
<code>noteheads.s1blackpetrucci</code>		<code>noteheads.s2blackpetrucci</code>	

Solesmes glyphs

<code>noteheads.ssolesmes.incl.parvum</code>		<code>noteheads.ssolesmes.auct.asc</code>	
<code>noteheads.ssolesmes.auct.desc</code>		<code>noteheads.ssolesmes.incl.auctum</code>	
<code>noteheads.ssolesmes.stropha</code>		<code>noteheads.ssolesmes.stropha.aucta</code>	
<code>noteheads.ssolesmes.oriscus</code>			

Kievan Notation glyphs

<code>clefs.kievan.do</code>		<code>clefs.kievan.do_change</code>	
<code>accidentals.kievan1</code>		<code>accidentals.kievanM1</code>	
<code>scripts.barline.kievan</code>		<code>dots.dotkievan</code>	
<code>noteheads.sM2kievan</code>		<code>noteheads.sM1kievan</code>	
<code>noteheads.s0kievan</code>		<code>noteheads.d2kievan</code>	
<code>noteheads.u2kievan</code>		<code>noteheads.s1kievan</code>	
<code>noteheads.sr1kievan</code>		<code>noteheads.d3kievan</code>	
<code>noteheads.u3kievan</code>			

B.9 Note head styles

The following styles may be used for note heads. Shown are the note heads for a quarter, a dotted half, a whole, a breve, a longa, and a maxima. Not all note head styles support all possible note lengths (in a meaningful way).

default	mensural
altdefault	neomensural
baroque	petrucci
slash	diamond
arrow	harmonic
triangle	harmonic-black
cross	harmonic-mixed
xcircle	

B.10 Accidental glyph sets

The following sets of accidental glyphs are available.

standard-alteration-glyph-name-alist



alteration-hufnagel-glyph-name-alist



alteration-medicaea-glyph-name-alist



alteration-vaticana-glyph-name-alist



alteration-mensural-glyph-name-alist



alteration-kievan-glyph-name-alist










B.11 Clef styles

The following table shows all the clef styles possible (including the cases where *middle C* sits relative to the clef). For more modification possibilities like ottavation digits, see Section 1.3.1 [Clef], page 19.

B.11.1 Standard clefs



Example	Output	Example	Output
<code>\clef G</code>		<code>\clef "G2"</code>	
<code>\clef treble</code>		<code>\clef violin</code>	
<code>\clef french</code>		<code>\clef GG</code>	
<code>\clef tenorG</code>			

<code>\clef soprano</code>		<code>\clef mezzosoprano</code>	
<code>\clef C</code>		<code>\clef alto</code>	
<code>\clef tenor</code>		<code>\clef baritone</code>	
<code>\clef varC</code>		<code>\clef altovarC</code>	
<code>\clef tenorvarC</code>		<code>\clef baritonevarC</code>	
<code>\clef varbaritone</code>		<code>\clef baritonevarF</code>	
<code>\clef F</code>		<code>\clef bass</code>	
<code>\clef subbass</code>			

B.11.2 Percussion staff clef

Example	Output	Example	Output
<code>\clef percussion</code>		<code>\clef varpercussion</code>	

B.11.3 Tab staff clefs

Example	Output	Example	Output
<pre>\new TabStaff { \clef tab }</pre>		<pre>\new TabStaff { \clef moderntab }</pre>	

B.11.4 Ancient music clefs

Gregorian

Example

Output


`\clef "vaticana-do1"`



`\clef "vaticana-do3"`




`\clef "vaticana-fa2"`




`\clef "medicaea-do1"`



`\clef "medicaea-do3"`




`\clef "medicaea-fa2"`



`\clef "hufnagel-do1"`



`\clef "hufnagel-do3"`



`\clef "hufnagel-fa2"`




Example

Output


`\clef "vaticana-do2"`




`\clef "vaticana-fa1"`



`\clef "medicaea-do2"`



`\clef "medicaea-fa1"`




`\clef "hufnagel-do2"`



`\clef "hufnagel-fa1"`



`\clef "hufnagel-do-fa"`



Mensural


Example

Output

`\clef "mensural-c1"`



`\clef "mensural-c3"`



`\clef "mensural-c5"`



Example










Output



`\clef "mensural-c2"`



`\clef "mensural-c4"`



<code>\clef "mensural-f"</code>		<code>\clef "mensural-f2"</code>	
<code>\clef "mensural-f3"</code>		<code>\clef "mensural-f4"</code>	
<code>\clef "mensural-f5"</code>			
<code>\clef "mensural-g1"</code>		<code>\clef "mensural-g2"</code>	
<code>\clef "mensural-g"</code>			
<code>\clef "blackmensural-c1"</code>		<code>\clef "blackmensural-c2"</code>	
<code>\clef "blackmensural-c3"</code>		<code>\clef "blackmensural-c4"</code>	
<code>\clef "blackmensural-c5"</code>			
<code>\clef "neomensural-c1"</code>		<code>\clef "neomensural-c2"</code>	
<code>\clef "neomensural-c3"</code>		<code>\clef "neomensural-c4"</code>	
<code>\clef "neomensural-c5"</code>			
<code>\clef "petrucci-c1"</code>		<code>\clef "petrucci-c2"</code>	
<code>\clef "petrucci-c3"</code>		<code>\clef "petrucci-c4"</code>	

<code>\clef "petrucci-c5"</code>			
<code>\clef "petrucci-f"</code>		<code>\clef "petrucci-f2"</code>	
<code>\clef "petrucci-f3"</code>		<code>\clef "petrucci-f4"</code>	
<code>\clef "petrucci-f5"</code>			
<code>\clef "petrucci-g1"</code>		<code>\clef "petrucci-g2"</code>	
<code>\clef "petrucci-g"</code>			

Kievan

Example

`\clef "kievan-do"`

Output



B.12 List of special characters

The following special characters references can be used; for more details, see Section 22.4.3 [ASCII aliases], page 645.

The HTML syntax is used and most of these references are the same as HTML. The rest of them are inspired by $\text{\LaTeX}$.

The characters are boxed so that you can see their size. A small padding has been added between the character and the box for more readability.

<code>&iexcl;</code>	<code>&iquest;</code>	<code>&solidus;</code>	<code>&flq;</code>	<code>&frq;</code>
<code>&frq;</code>	<code>&flqq;</code>	<code>&frqq;</code>	<code>&glq;</code>	<code>&glqq;</code>
<code>&grq;</code>	<code>&glqq;</code>	<code>&grqq;</code>	<code>&elq;</code>	<code>&elqq;</code>
<code>&erq;</code>	<code>&elqq;</code>	<code>&erqq;</code>	<code>&ensp;</code>	<code>&thinsp;</code>
<code>&emsp;</code>	<code>&thinsp;</code>	<code>&nbsp;</code>	<code>&nnbsp;</code>	<code>&nbsp;</code>

‍	◌ ‍	◌ ·	◻ •	◼
&copyright;	© &registered;	® &trademark;	™ †	†
‡	‡ №	№ ª	ª º	º
¶	¶ §	§ °	§ №	№
‰	‰ ¦	¡ ´	¿ &acutedbl;	″
`	◌ ˘	◌ ˇ	◌ &cedilla;	◌
&circumflex;	◌ &diaeresis;	◌ &macron;	◌ &aa;	å
&AA;	Å &ae;	æ &AE;	Æ ä	ä
Ä	Ä &dh;	ð &DH;	Ð &dj;	đ
&DJ;	Đ &l;	ł &L;	Ł &ng;	ŋ
&NG;	Ń &o;	ø &O;	Ø &oe;	œ
&OE;	Œ ö	ö Ö	Ö &s;	ſ
&ss;	ß &th;	þ &TH;	Þ ü	ü
Ü	Ü +	⊕ −	⊖ ×	⊗
÷	÷ ¹	¹ ²	² ³	³
&sqrt;	√ &increment;	Δ &infty;	∞ ∑	Σ
±	± &bulletop;	◻ &partial;	◻ &neg;	◻
&currency;	¤ $	\$ €	£ &pounds;	£
¥	¥ ¢	¢		

B.13 List of articulations

In LilyPond’s internal logic, an ‘articulation’ is any object (other than dynamics) that may be attached directly after a rhythmic event: notes, chords; even silences and skips, or the empty chord construct `<>` (see Section “Structure of a note entry” in *Learning Manual*). Even slurs, fingerings and text scripts are technically articulations, although these are not shown here.

Therefore, the following lists include not only articulation marks, but also all other scripts in the Emmentaler font that may be attached to notes (the way an accent is entered as ‘`c'\accent`’ or ‘`c'->`’). Each example shows the script in its two possible vertical positions: respectively *up* and *down*, as well as its default (*neutral*) position. See also [Script glyphs], page 912, for a more extensive list of glyphs, for use with the `\musicglyph` markup command as explained in Section 8.2.5 [Music notation inside markup], page 334.

B.13.1 Articulation scripts

`\accent` or `->`



`\espressivo`



`\marcato` or `-^`



`\portato` or `-_`



`\staccatissimo` or `-!`



`\staccato` or `-.`



`\tenuto` or `--`



B.13.2 Ornament scripts

`\prall`



`\prallup`



`\pralldown`



`\upprall`



`\downprall`



`\prallprall`



`\lineprall`



`\prallmordent`



`\mordent`



`\upmordent`



`\downmordent`




`\trill`




`\turn``\reverseturn``\slashturn``\haydnturn`

B.13.3 Fermata scripts

`\veryshortfermata``\shortfermata``\fermata``\longfermata``\verylongfermata``\henzeshortfermata``\henzelongfermata`

B.13.4 Instrument-specific scripts

`\upbow``\downbow``\flageolet``\open``\halfopen``\heel``\varheel``\heelcircle``\toe``\vartoe``\snappizzicato``\stopped or -+``\thumb`

B.13.5 Repeat sign scripts


`\segno`



`\coda`




`\varcoda`



B.13.6 Ancient scripts

`\accentus`



`\circculus`




`\ictus`



`\semicirculus`



`\signumcongruentiae`



B.14 List of breath marks

`'chantquarterbar`



`'chanthalfbar`



`'chantfullbar`



`'chantdoubar`



`'comma`



`'varcomma`



`'tickmark`



`'upbow`



`'outsidecomma`



`'caesura`



`'curvedcaesura`



`'spacer`



B.15 Percussion notes

bassdrum
bd



acousticbassdrum
bda




snare
sn



acousticsnare
sna



electricsnare
sne



lowfloortom
tomfl



highfloortom
tomfh




lowtom
toml




hightom
tomh



lowmidtom
tomml




himidtom
tommh




hihat
hh



closedhihat
hhc



openhihat
hho



halfopenhihat
hhho



pedalhihat
hhp




crashcymbal
cymc



crashcymbala
cymca




crashcymbalb
cymcb




ridecymbal
cymr



ridecymbala
cymra



ridecymbalb
cymrb



chinesecymbal
cymch



splashcymbal
cyms



ridebell
rb



cowbell
cb



hibongo
boh



openhibongo
boho



mutehibongo
boh



lobongo
bol



openlobongo
bolo



mutelobongo
bolm



hiconga
cgh



openhiconga
cgho



mutehiconga
cghm



locongga
cgl



openlocongga
cglo



mutelocongga
cglm



hitimbale
timh



lotimbale
timl



hiagogo
agh



loagogo
agl



sidestick
ss



hisidestick
ssh



losidestick
ssl



guiro
gui



shortguiro
guis



longguiro
guil



cabasa
cab



maracas
mar



shortwhistle
whs



longwhistle
whl



handclap
hc



tambourine
tamb



vibraslap
vibs



tamtam
tt



claves
cl



hiwoodblock
wbh



lowoodblock
wbl



opencuica
cuio



mutecuica
cuim



triangle
tri



opentriangle
trio



mutetriangle
trim




B.16 List of bar lines

Each system following shows the appearance of a particular bar type at the beginning, middle, and end of a line.


For more information, see Section 2.5.1 [Bar lines], page 120, and Section 2.5.2 [Automatic bar lines], page 130.

Simple bar lines


" ; "




" ! "




" "



" | -s "




" | "




End-of-line bar lines


" x- . "



" x- | "



" x- | "




Chant bar lines


"k"




"-span |"




" | |"




" | "



", "




" : "




Section bar lines


" | | "




" . - | | "




" . . "




" . "




" . - | "




" | . "



" | . | "




" . | "




Segno bar lines


" | .s-s "




"s-s "




"s- | "




" | .s "















"s- | | "



"s "




The first system of the musical score is for the piece "S. | :-S". It consists of two staves, both in bass clef. The first staff has a key signature of one flat (B-flat) and a common time signature (C). The second staff has a key signature of one flat (B-flat) and a common time signature (C). The music is written in a simple, minimalist style, with a single note on the first staff and a single note on the second staff, both followed by a double bar line and a repeat sign. The notation is presented in a clean, black-and-white format.




Double-repeat bar lines


": |] [| :"




": | .S. | : -S"




": | . | :"




": | . :"




": | .S. | :"



": . | . :"




": . . :"




End-repeat bar lines


": | .S-S"




": |] "



": | .S"



": | ."



B.17 Default values for outside-staff-priority

The following table shows the default outside-staff-priority of all outside-staff grobs. Objects with smaller values are placed closer to the staff.

Grob	Priority
AccidentalSuggestion	0
BassFigureAlignmentPositioning	25
MultiMeasureRestScript	40
TrillSpanner	50
BarNumber	100
LigatureBracket	200
DynamicLineSpanner	250
TextSpanner	350
OttavaBracket	400
MultiMeasureRestText	450
TextScript	450
CombineTextScript	475
InstrumentSwitch	500
VoltaBracketSpanner	600
MeasureCounter	750
MeasureSpanner	750
HorizontalBracket	800
SostenutoPedalLineSpanner	1000
SustainPedalLineSpanner	1000
UnaCordaPedalLineSpanner	1000
CenteredBarNumberLineSpanner	1200
TextMark	1250
MetronomeMark	1300
JumpScript	1350
CodaMark	1400
SegnoMark	1400
SectionLabel	1450
RehearsalMark	1500

B.18 Default values for script-priority

The following table shows the default script-priority of all script-related grobs (starting with an uppercase letter) and script names (starting with a lowercase letter). Objects with smaller values are placed closer to the staff.

The Fingering, StringNumber, and StrokeFinger grobs, if part of a chord, add the vertical position of the associated note head to get the final priority value. The script-priority values of other scripts part of a chord stay unmodified.

For scripts not part of a chord, the current event position is added instead. This means that for scripts with the same script-priority value, the first one attached to a note head gets the lowest priority value.

Grobs not listed here (and which are related to scripts) get 200 as the default script-priority value.

Grob or Script	Priority
AccidentalPlacement	-100
accentus	-100
circulus	-100
ictus	-100
semicirculus	-100
staccato	-100
tenuto	-50

AccidentalSuggestion	0
Arpeggio	0
ChordBracket	0
ChordSlur	0
flageolet	50
Fingering	100
StrokeFinger	125
StringNumber	150
trill	150
fermata	175
henzelongfermata	175
henzeshortfermata	175
longfermata	175
shortfermata	175
verylongfermata	175
veryshortfermata	175
downbow	180
upbow	180
CombineTextScript	200
TextScript	200

B.19 Grobs and their break-align symbols

The ordering and spacing of notational elements like clefs, time signatures, bar lines, etc., is determined using certain Scheme symbols, the so-called *break-align symbols*. More precisely, their ordering is determined by lists of break-align symbols in the `BreakAlignment.break-align-orders` vector (see Section “break-alignment-interface” in *Internals Reference*); their spacing is controlled by the `space-alist` properties of the respective grobs, whose elements are in turn indexed by break-align symbols: For instance, the spacing of a `Clef` grob to a bar line following it is determined by the value of `Clef.space-alist.staff-bar`.

This table lists the default correspondence between break-align symbols and grobs:

break-align symbol	used by grob(s)
ambitus	Ambitus
breathing-sign	BreathingSign
clef	Clef
cue-clef	CueClef
cue-end-clef	CueEndClef
custos	Custos
key-cancellation	KeyCancellation
key-signature	KeySignature
left-edge	LeftEdge
optional-material-end-bracket	OptionalMaterialBracket
optional-material-start-bracket	OptionalMaterialBracket
signum-repetitionis	SignumRepetitionis
staff-bar	SpanBar, DoublePercentRepeat, Divisio, and BarLine
staff-ellipsis	StaffEllipsis
time-signature	TimeSignature

Furthermore, there are three abstract break-align symbols that may be used in `space-alist` definitions, namely `first-note`, `next-note` and `right-edge`. For details, see the documentation of the `space-alist` grob property in Section “break-aligned-interface” in *Internals Reference*.

The next table lists the break-align symbol used by each grob:

Grob	break-align symbol(s)
Ambitus	ambitus
BarLine	staff-bar
BreathingSign	breathing-sign
Clef	clef
CueClef	cue-clef
CueEndClef	cue-end-clef
Custos	custos
Divisio	staff-bar
DoublePercentRepeat	staff-bar
KeyCancellation	key-cancellation
KeySignature	key-signature
LeftEdge	left-edge
OptionalMaterialBracket	optional-material-start-bracket and optional-material-end-bracket
SignumRepetitionis	signum-repetitionis
SpanBar	staff-bar
StaffEllipsis	staff-ellipsis
TimeSignature	time-signature

B.20 Technical glossary

This glossary lists some the technical terms and concepts used internally in LilyPond. These terms may appear in the manuals, on mailing lists or in the source code.

alist	An association list or <i>alist</i> for short is a Scheme pair that associates a value with a key: (key . value). For example, in scm/lily.scm, the alist type-p-name-alist associates certain type predicates (e.g., ly:music?) with names (e.g., “music”) so that type check failures can be reported with a console message that includes the name of the expected type predicate.
callback	A <i>callback</i> is a routine, function or method whose reference is passed as an argument in a call to another routine, thus allowing the called routine to invoke it. The technique enables a lower-level software layer to call a function defined in a higher layer. Callbacks are used extensively in LilyPond to make user-level Scheme code control many low-level actions.
closure	In Scheme, a <i>closure</i> is created when a function, usually a lambda expression (i.e., an ad-hoc, anonymous function), is passed as a variable. The closure contains the function’s code plus references to the lexical bindings of the function’s free variables (i.e., those variables used in the expression but defined outside it). When this function is applied to different arguments later, the free variable bindings that were captured in the closure are used to obtain the values of the free variables, which in turn are used in the calculation. One useful property of closures is the preservation of internal variable values between invocations, thus permitting state to be maintained.
glyph	A <i>glyph</i> is a particular graphical representation of a typographic character, or a combination of two (or more) characters forming a ligature. A set of glyphs with a single style and shape comprise a font, and a set of fonts covering several styles and sizes comprise a typeface. See also: Section 8.3 [Fonts], page 336, Section 22.4 [Special characters], page 644.
grob	LilyPond objects that represent items of notation in the printed output such as note heads, stems, slurs, ties, fingering, clefs, etc., are called ‘Layout objects’, often

known as ‘GGraphical Objects’, or *grob*s for short. They are represented by instances of the *Grob* class.

See also: Section “Objects and interfaces” in *Learning Manual*, Section “Properties of layout objects” in *Learning Manual*.

Section B.24 [Naming conventions], page 972.

Section “grob-interface” in *Internals Reference*, Section “All layout objects” in *Internals Reference*.

immutable

An *immutable* object is one whose state cannot be modified after creation, in contrast to a mutable object, which can be modified after creation.

In LilyPond, immutable or shared properties define the default style and behavior of grobs. They are shared between many objects. In apparent contradiction to the name, they can be changed using `\override` and `\revert`.

See also below for mutable objects.

interface

Actions and properties that are common to a number of grobs are grouped together in an object called a grob-interface, or just *interface* for short.

See also: Section B.24 [Naming conventions], page 972, Section 34.2 [Layout interfaces], page 755.

Section “Objects and interfaces” in *Learning Manual*, Section “Properties found in interfaces” in *Learning Manual*.

Section “Graphical Object Interfaces” in *Internals Reference*.

lexer

A *lexer* is a program that converts a sequence of characters into a sequence of tokens, a process called *lexical analysis*. The LilyPond lexer converts the stream obtained from an input `.ly` file into a tokenized stream more suited to the next stage of processing – parsing (see below). The LilyPond lexer is built using the `flex` program from the lexer file `lily/lexer.ll`, which contains the lexical rules. This file is part of the source code and not included in the LilyPond binary installation.

mutable

A *mutable* object is one whose state can be modified after creation, in contrast to an immutable object, whose state is fixed at the time of creation.

In LilyPond, mutable properties contain values that are specific to one grob. Typically, lists of other objects or results from computations are stored in mutable properties.

See also above for immutable objects.

output-def

An instance of the *Output-def* class contains the methods and data structures associated with an output block. Instances are created for MIDI, layout, and paper blocks.

parser

A *parser* analyzes the sequence of tokens produced by a lexer to determine its grammatical structure, grouping the tokens progressively into larger groupings according to the rules of the grammar. If the sequence of tokens is valid the end product is a tree of tokens whose root is the grammar’s start symbol. If this cannot be achieved the file is invalid and an appropriate error message is produced. The syntactic groupings and the rules for constructing the groupings from their parts for the LilyPond syntax are defined in file `lily/parser.yy`. During compilation, this file gets processed by a parser generator, `bison`, to build the parser. It is part of the source code and not included in the LilyPond binary installation.

parser variable

These are variables defined directly in Scheme. Their direct use by users is strongly discouraged because their scoping semantics can be confusing.

When the value of such a variable is changed in a .ly file, the change is global, and unless explicitly reverted, the new value persists to the end of the file, affecting subsequent `\score` blocks as well as external files added with the `\include` command. This can lead to unintended consequences, and in complex typesetting projects the consequent errors can be difficult to track down.

Among others, the following parser variables are used by LilyPond:

```
afterGraceFraction
input-language
musicQuotes
output-count
output-suffix
partCombineListener
pitchnames
toplevel-bookparts
toplevel-scores
showLastLength
showFirstLength
```

prob *PR*roperty *O*bjects, or *probs* for short, are instances of the `Prob` class, a simple base class for objects that have mutable and immutable property alists and the methods to manipulate them. The `Music` and `Stream_event` classes derive from `Prob`. Instances of the `Prob` class are also created to hold the formatted content of system grobs and titling blocks during page layout.

smob *Sm*obs, or *ScheM*e *O*bjects, are part of the mechanism used by Guile to export C and C++ objects to Scheme code. In LilyPond, smobs are created from C++ objects through macros. There are two types of smob objects: simple smobs, intended for simple immutable objects like numbers, and complex smobs, used for objects with identities. If you have access to the LilyPond sources, more information can be found in file `lily/includes/smob.hh`.

spanner *Spanners* are a class of grobs that are not horizontally fixed on one point of the score but extend from one point to another. Examples include beams, ties, and slurs, as well as hairpins and staff lines. Whereas non-spanners can only be broken into at most two visible pieces (for example, a clef duplicated at the end of the line and the beginning of the next line), spanners are broken into as many pieces as required by their start and end points (such as a long crescendo extending on three systems, or staff lines, which always span the whole score).

Technically, spanners are defined as grobs having the `spanner-interface`; on the C++ side of LilyPond, they are instances of the `Spanner` subclass of `Grob`. The left and right bounds of a spanner can be retrieved and set using `ly:spanner-bound` and `ly:spanner-set-bound!`, respectively. The bounds are always items. The `X` parent of a spanner has little musical sense, but is usually set to the left bound.

See also: Section 36.4 [Spanners], page 774.

Section “All layout objects” in *Internals Reference*, Section “spanner-interface” in *Internals Reference*.

stencil An instance of the `Stencil` class holds the information required to print a typographical object, a *stencil*. It is a simple smob containing a confining box, which defines the vertical and horizontal extents of the object, and a Scheme expression, which prints the object when evaluated. Stencils may be combined to form more

complex stencils defined by a tree of Scheme expressions, which in turn are formed from the Scheme expressions of the component stencils.

The `stencil` property, which connects a grob to its stencil, is defined in the `grob-interface` interface.

See also Section “`grob-interface`” in *Internals Reference*.

B.21 Available music functions

In the following, the first argument of a function is printed with a slanted typeface, followed by the first argument’s type in parentheses. Then comes the second argument, followed by the second argument’s type, again in parentheses, and so on. After the arrow the type of the return value is printed.

If an argument and its type is enclosed in brackets, the argument is optional and can be omitted, indicating that LilyPond should use a default value instead. However, if a function’s last argument is tagged as optional, it *cannot* be omitted: you have to pass `\default` if you do not want to explicitly specify a value. See Section “Scheme function usage” in *Extending* for more details on how optional arguments are handled.

`\absolute` *music* (music) $\Rightarrow$ music

Make *music* absolute.

This does not actually change the music itself but rather hides it from surrounding `\relative` (page 956) and `\fixed` (page 947) commands.

`\acciaccatura` *music* (music) $\Rightarrow$ music

Create an acciaccatura from *music*.

`\accidentalStyle` *style* (symbol list) $\Rightarrow$ music

Set accidental style to *style*.

style is a (predefined) symbol list like `piano-cautionary`; see Section 1.3.5 [Automatic accidentals], page 31, for the available styles. If it is preceded by a context name, the settings are applied to that context (example: `Staff.piano-cautionary`). Otherwise, the context defaults to `Staff`, except for piano styles, which use `GrandStaff` as a context.

`\addChordShape` *key-symbol* (symbol) *tuning* (pair) *shape-definition* (string or pair) $\Rightarrow$ void

Add *shape-definition* as a chord shape.

It gets added to the `chord-shape-table` hash with the key `(cons key-symbol tuning)`.

`\addInstrumentDefinition` *name* (string) *lst* (list) $\Rightarrow$ void

Create instrument *name* with properties *lst*.

This function is deprecated.

`\addQuote` *name* (string) *music* (music) $\Rightarrow$ void

Define *music* as a quotable music expression named *name*.

`\addToTagGroup` *tag-group* (symbol list) *more-tags* (symbol list) $\Rightarrow$ void

Add *more-tags* to the tag group identified by *tag-group*.

`\after` *delta* (duration) *ev* (music) *mus* (music) $\Rightarrow$ music

Add music *ev* with a delay of *delta* after the onset of *mus*.

ev is usually a post-event.

`\afterGrace` [*fraction* (non-negative rational, fraction, or moment)] *main* (music) *grace* (music) $\Rightarrow$ music

Create *grace* as grace notes after a *main* music expression.

The musical position of the grace expression is after a given fraction of the main note's duration has passed. If optional argument *fraction* is omitted, the fraction value is taken from `afterGraceFraction`, defaulting to 3/4.

`\allowPageTurn` $\Rightarrow$ music

Allow a page turn.

May be used at top level (i.e., between scores or markups), or inside a score.

`\allowVoltaHook` *bar* (string) $\Rightarrow$ void

Allow the volta bracket hook being drawn over bar line *bar*.

`\alterBroken` *property* (key list or symbol) *arg* (list) *target* (key list or music) $\Rightarrow$ music

Override *property* for pieces of broken spanner *target* with *arg*.

target may either be music in the form of a starting spanner event, or a symbol list of the form *Context.Grob* or just *Grob*. If *target* is in the form of a spanner event, *property* may also have the form *Grob.property* for specifying a directed tweak.

arg is a list of values, one for each broken piece.

`\ambitusAfter` *target* (symbol) $\Rightarrow$ music

Move the ambitus after the break-align symbol *target*.

`\appendToTag` *tag* (symbol) *more* (music) *music* (music) $\Rightarrow$ music

Append *more* to *music* tagged with *tag*.

A post-event can be added to the articulations of rhythmic events or chords; other expressions may be added to chords, sequential or simultaneous music.

`\appendToTagMarkup` *tag* (symbol) *more* (markup) *music* (music) $\Rightarrow$ music

Append *more* to every markup in *music* tagged with *tag*.

`\applyContext` *proc* (procedure) $\Rightarrow$ music

Modify context properties with Scheme procedure *proc*.

`\applyMusic` *func* (procedure) *music* (music) $\Rightarrow$ music

Apply procedure *func* to *music*.

`\applyOutput` *target* (symbol list or symbol) *proc* (procedure) $\Rightarrow$ music

Apply function *proc* to every layout object matched by *target*.

target takes the form *Context* or *Context.Grob*.

`\appoggiatura` *music* (music) $\Rightarrow$ music

Create an appoggiatura from *music*.

`\approximatePitch` *note* (music) $\Rightarrow$ music

Indicate that the pitch of *note* approximates a pitch that cannot be known exactly, such as the highest note a singer can sing.

`\arpeggioArrowDown` $\Rightarrow$ music

Let `\arpeggio` produce a wavy line with a down arrow.

`\arpeggioArrowUp` $\Rightarrow$ music

Let `\arpeggio` produce a wavy line with an up arrow.

`\arpeggioBracket` $\Rightarrow$ music

Let `\arpeggio` produce a square bracket.

Note: For a bracket designating a non-arpeggiated chord, it is better to use `\nonArpeggiato` than to use `\arpeggio` and alter the appearance.

`\arpeggioNormal` $\Rightarrow$ music

Let `\arpeggio` produce a wavy line without an arrow.

`\arpeggioParenthesis` $\Rightarrow$ music

Let `\arpeggio` produce a vertical slur.

Note: For a vertical slur designating a quasi-non-arpeggiated chord, it is better to use `\chordSlur` than to use `\arpeggio` and alter the appearance.

`\arpeggioParenthesisDashed` $\Rightarrow$ music

Let `\arpeggio` produce a dashed vertical slur.

Note: For a vertical slur designating a quasi-non-arpeggiated chord, it is better to use `\chordSlur` than to use `\arpeggio` and alter the appearance.

`\assertBeamQuant` *l* (pair) *r* (pair) $\Rightarrow$ music

Testing function: check whether the beam quantums *l* and *r* are correct.

`\assertBeamSlope` *comp* (procedure) $\Rightarrow$ music

Testing function: check whether the slope of the beam is the same as *comp*.

`\atLeft` *m* (music) $\Rightarrow$ post-event

Set side-axis to X and direction to LEFT for *mus*.

`\atRight` *m* (music) $\Rightarrow$ post-event

Set side-axis to X and direction to RIGHT for *mus*.

`\augmentum` *expr* (music) $\Rightarrow$ music

Add augmentum dots (*morae*) to Gregorian chant *expr*.

`\autoChange` [*pitch* (pitch)] [*clef-1* (context modification)] [*clef-2* (context modification)]
music (music) $\Rightarrow$ music

Make voices for *music* that switch between staves automatically.

The optional argument *pitch* specifies where to switch staves; the default is *c'*. Optional arguments *clef-1* and *clef-2* specify which clefs to use; this only works for implicitly instantiated staves.

Example:

```
\autoChange d' \with { \clef alto } { g4 d' g' }
```

`\balloonGrobText` *grob-name* (symbol) *offset* (pair of numbers) *text* (markup) $\Rightarrow$ music

Attach *text* to *grob-name* at offset *offset*.

Use like `\once` (page 951).

`\balloonText` *offset* (pair of numbers) *text* (markup) $\Rightarrow$ post-event

Attach *text* at *offset*.

Use like `\tweak` (page 960).

`\bar` *type* (string) $\Rightarrow$ music

Insert a bar line of type *type*, overriding any automatic bar lines.

`\barNumberCheck` *n* (integer) $\Rightarrow$ music

Print a warning if the current bar number is not *n*.

`\beamExceptions` *music* (music) $\Rightarrow$ any type

Set beam exceptions.

This function extracts a value suitable for setting `Timing.beamExceptions` from the given pattern with explicit beams in *music*. A bar check ‘|’ has to be used between bars of patterns in order to reset the timing.

`\bendAfter` *delta* (real number) $\Rightarrow$ post-event

Create a fall or doit of pitch interval *delta*.

`\bendHold` *mus* (music) $\Rightarrow$ post-event

Set `BendSpanner.style` to ‘hold’ for *mus*.

`\bendStartLevel` *idx* (non-negative, exact integer) *mus* (music) $\Rightarrow$ post-event
Set `Bendspanner.details.successive-level` to *idx* for *mus*.

`\bookOutputName` *newfilename* (string) $\Rightarrow$ void
Direct output for the current book block to *newfilename*.
This is equivalent to setting `output-filename` in the current book's `\paper` block.

`\bookOutputSuffix` *newsuffix* (string) $\Rightarrow$ void
Set the output file name suffix for the current book block to *newsuffix*.
This is equivalent to setting `output-suffix` in the current book's `\paper` block.

`\breakAlignInsert` [*positions* (vector)] *symbol-to-move* (symbol) *sorting-symbol* (symbol)
anchor-symbol (symbol) $\Rightarrow$ music
Re-order break-align symbols.
This function is for tasks like putting a clef change after the bar line, which would be accomplished by `\breakAlignInsert` `clef` after `staff-bar`.
sorting-symbol can be before or after. Depending on its value, the break-align symbol *symbol-to-move* gets moved directly before/after the symbol *anchor-symbol* in the `break-align-orders` vector of `Score.BreakAlignment`.
The available break-align symbols and their corresponding grobs are listed in Section “Grobs and their break-align symbols” in *Notation Reference*.
The optional argument *positions* determines whether the specified change should become visible at the beginning/the end/the middle of a line. Possible values are: `#all-visible` (default), `#begin-of-line-invisible`, `#center-invisible`, `#end-of-line-invisible`, `#begin-of-line-visible`, `#center-visible`, `#end-of-line-visible`, `#all-invisible`.

`\breathe` $\Rightarrow$ music
Insert a breath mark.

`\cadenzaOff` $\Rightarrow$ music
Resume advancing `Timing.measurePosition`.
This sets `Timing.timing` to `#t`.

`\cadenzaOn` $\Rightarrow$ music
Stop advancing `Timing.measurePosition`.
This sets `Timing.timing` to `#f`.
Compare to `\senzaMisura` (page 957).

`\caesura` $\Rightarrow$ music
Insert a caesura.

`\chordRepeats` [*event-types* (list)] *music* (music) $\Rightarrow$ music
Extend ‘q’ to also repeat articulation.
This function walks through *music*, putting the notes of the previous chord into repeat chords, as well as an optional list of *event-types* such as `#'(string-number-event)`.

`\clef` *type* (string) $\Rightarrow$ music
Set the current clef to *type*.

`\codaMark` [*num* (non-negative, exact integer)] $\Rightarrow$ music
Create a coda mark.
num may be 1 for the first mark, 2 for the second, etc., or it may be `\default` to use the next number in sequence automatically.

`\compressMMRests music (music) ⇒ music`

Convert empty bars to multi-measure rests in *music*.

`\contextPropertyCheck property-path (symbol list or symbol) [expected-value (any type)] ⇒ music`

Check that the context property identified by *property-path* is set to *expected-value* in that very context: being set in an enclosing context is insufficient. If *expected-value* is `\default`, check that the property is unset in that context.

If *property-path* does not name a context, the check occurs in the current context.

Print a warning if the requested context is not visible looking upward from the current context or if the state of the property in the requested context is unexpected.

Caveat: Like some other context-specific commands, a context given in *property-path* is ignored in certain cases, such as inside `\with`.

`\crossStaff notes (music) ⇒ music`

Create cross-staff stems for *notes*.

`\cueClef type (string) ⇒ music`

Set the current cue clef to *type*.

`\cueClefUnset ⇒ music`

Unset the current cue clef.

`\cueDuring what (string) dir (direction) main-music (music) ⇒ music`

Create a cue.

This function inserts the contents of quote *what* corresponding to *main-music*, in a CueVoice context called cue oriented by *dir*.

`\cueDuringWithClef what (string) dir (direction) clef (string) main-music (music) ⇒ music`

Create a cue with clef.

This function inserts the contents of quote *what* corresponding to *main-music*, in a CueVoice context called cue oriented by *dir* and using clef *clef*.

`\deadNote note (music) ⇒ music`

Print *note* with a cross-shaped note head.

`\defineBarLine bar (string) glyph-list (list) ⇒ void`

Define bar line settings for bar line *bar*.

The list *glyph-list* must have three entries, defining substitute glyphs for the end of a line, the beginning of a line, and a span bar, respectively. The substitute glyphs may be either strings or Booleans: `#t` calls for the same value as *bar* and `#f` calls for no glyph.

`\displayLilyMusic [port (output port)] music (music) ⇒ music`

Write LilyPond's input representation of *music*.

If *port* is omitted, the output defaults to the console (stdout).

`\displayMusic [port (output port)] music (music) ⇒ music`

Write the internal representation of *music*.

If *port* is omitted, the output defaults to the console (stdout).

`\displayScheme [port (output port)] expr (any type) ⇒ any type`

Write the internal Scheme representation of *expr*.

If *port* is omitted, the output defaults to the console (stdout).

`\dropNote num (integer) music (music) ⇒ music`

'Drop' the *num*-th note in each chord of *music*.

This function moves the affected notes down (usually by an octave) to be lower than the other notes of the chord. The position in a chord is counted downwards from the top.

The opposite function is `\raiseNote` (page 955).

`\enablePerStaffTiming` $\Rightarrow$ void

Enable polymeter with unaligned measures.

This function moves the timing management from `Score` to `Staff`-like contexts. This is done by removing the `Timing_translator` from `Score`, and adding it to all contexts having the `Staff` alias.

Use this within an output definition.

`\endSpanners music` (*music*) $\Rightarrow$ *music*

Terminate spanners.

This function prematurely ends all spanners in *music* by inserting an end-spanner event at the end of the argument, without the need of specific end-spanner commands.

`\eventChords music` (*music*) $\Rightarrow$ *music*

Compatibility function: Handle isolated rhythmic events in *music*.

Use this to wrap `EventChord` around isolated rhythmic events occurring since version 2.15.28, after expanding repeat chords ‘q’.

Not needed for new code.

`\featherDurations scale` (non-negative rational, fraction, or moment) *music* (*music*) $\Rightarrow$ *music*

Adjust feathered beam durations in *music* by *scale*.

`\finger finger` (index or markup) $\Rightarrow$ post-event

Apply *finger* as a fingering indication.

`\fixed pitch` (*pitch*) *music* (*music*) $\Rightarrow$ *music*

Use the octave of *pitch* as the default octave for *music*.

`\footnote [mark (markup)] offset` (pair of numbers) *footnote* (markup) *item* (symbol list or *music*) $\Rightarrow$ *music*

Make the markup *footnote* a footnote on *item*.

The footnote is marked with a markup *mark* moved by *offset* with respect to the marked *music*.

If *mark* is not given or specified as `\default`, it is replaced by an automatically generated sequence number. If *item* is a symbol list of form *Grob* or *Context.Grob*, then grobs of that type are marked at the current time step in the given context (default `Bottom`).

If *item* is *music*, the *music* gets a footnote attached to a grob immediately attached to the event, like `\tweak` does. For attaching a footnote to an *indirectly* caused grob, write `\single\footnote`, use *item* to specify the grob, and follow it with the *music* to annotate.

Like with `\tweak`, if you use a footnote on a following post-event, the `\footnote` command itself needs to be attached to the preceding note or rest as a post-event with ‘-’.

`\grace music` (*music*) $\Rightarrow$ *music*

Insert *music* as grace notes.

`\grobdescriptions descriptions` (list) $\Rightarrow$ any type

Create a context modification from *descriptions*.

The argument is a list in the format of all-grob-descriptions.

`\harmonicByFret` *fret* (number) *music* (music) $\Rightarrow$ music

Convert *music* into mixed harmonics.

The resulting notes resemble harmonics played on a fretted instrument by touching the strings at *fret*.

`\harmonicByRatio` *ratio* (number) *music* (music) $\Rightarrow$ music

Convert *music* into mixed harmonics.

The resulting notes resemble harmonics played on a fretted instrument by touching the strings at the point given through *ratio*.

`\harmonicNote` *note* (music) $\Rightarrow$ music

Print *note* with a diamond-shaped note head.

`\harmonicsOn` $\Rightarrow$ music

Set the default note head style to a diamond-shaped style.

`\hide` *item* (symbol list or music) $\Rightarrow$ music

Make *item* invisible while still retaining its dimensions.

If *item* is a symbol list of form *GrobName* or *Context.GrobName*, the result is an override for the grob name specified by it. If *item* is a music expression, the result is the same music expression with an appropriate tweak applied to it.

This function sets *item*'s transparent property to #t.

`\incipit` [*offset* (number)] *incipit-music* (music) $\Rightarrow$ music

Output *incipit-music* as an incipit.

incipit-music is typeset within a *MensuralStaff* context; the result is positioned before the main staff (as part of an *InstrumentName* grob) to indicate the music's original notation. The optional argument *offset* specifies how much the incipit should be moved to the left (default value is 0).

In the special case that *incipit-music* has the form `\new xxx ...`, where *xxx* is a context type not accepted by *MensuralStaff*, it is taken directly.

`\inherit-acceptability` *to* (symbol) *from* (symbol) $\Rightarrow$ void

Make two contexts 'compatible'.

When used in an output definition, modify all context definitions such that context *to* is accepted as a child by all contexts that also accept *from*.

`\initialContextFrom` *music* (music) $\Rightarrow$ music

Enter the initial context of *music* and ignore the rest of it.

This is useful for prepending music while preserving the influence of the original music on the context.

Example:

```
{
  \initialContextFrom \originalMusic
  \prependedMusic
  \originalMusic
  \appendedMusic
}
```

`\inStaffSegno` $\Rightarrow$ music

Put the segno variant *varsegno* at this position into the staff.

This is compatible with the *repeat* command.

`\instrumentSwitch` *name* (string) $\Rightarrow$ music

Switch instrument to *name*.

name must have been predefined with function `\addInstrumentDefinition` (page 942).

This function is deprecated.

`\inversion around (pitch) to (pitch) music (music) ⇒ music`

Invert *music* about *around* and transpose from *around* to *to*.

`\invertChords num (integer) music (music) ⇒ music`

Invert any chords in *music* into their *num*-th position.

Chord inversions may be directed downwards using negative integers.

`\jump text (markup) ⇒ music`

Use *text* to mark a point of departure, e.g., ‘Gavotte I D.C.’.

`\keepWithTag tags (symbol list or symbol) music (music) ⇒ music`

Keep tagged music.

This function only includes elements of *music* that are tagged with one of the tags in *tags*. *tags* may be either a single symbol or a list of symbols.

Each tag may be declared as a member of at most one tag group (defined with `\tagGroup`). If none of a *music* element’s tags share a tag group with one of the specified *tags*, the element is retained.

`\key [tonic (pitch)] [pitch-alist (list of number pairs)] ⇒ music`

Set key to *tonic* and scale *pitch-alist*.

If both arguments are omitted (i.e., replaced by `\default`), just generate a `KeyChangeEvent`, which prints the current key signature again.

`\killCues music (music) ⇒ music`

Remove cue notes from *music*.

`\label label (symbol) ⇒ music`

Create *label* as a referable label.

The value stored in *label* is the page number, which can be extracted with the `\page-ref` markup command later on.

`\language language (string) ⇒ void`

Set note names for language *language*.

This function updates the Scheme variables `pitchnames` and `input-language`. The former is an alist that holds the pitches of all note names for the selected language; the latter holds the language name itself (as a symbol).

`\languageRestore ⇒ void`

Restore the previously-saved `pitchnames` alist.

`\languageSaveAndChange language (string) ⇒ void`

Save current `pitchnames` alist and change note names to *language*.

`\ligature music (music) ⇒ music`

Make a ligature from Gregorian Chant *music*.

This is equivalent to enclosing *music* with `\[` and `\]`.

`\magnifyMusic mag (positive number) music (music) ⇒ music`

Magnify the size of *music* by factor *mag*.

This doesn’t change the staff size. Stems, beams, slurs, ties, and horizontal spacing are adjusted automatically.

`\magnifyStaff mag` (positive number) $\Rightarrow$ music

Change the staff size by factor *mag*.

This adjusts notation size and horizontal spacing automatically.

`\makeClusters arg` (music) $\Rightarrow$ music

Display chords in *arg* as clusters.

`\makeDefaultStringTuning symbol` (symbol) *pitches* (list) $\Rightarrow$ void

Define string tuning *symbol* by a list of *pitches*.

symbol also gets registered in `defaultStringTunings` for documentation purposes.

`\mark [label` (index or markup)] $\Rightarrow$ music

Create a rehearsal mark.

If *label* is an integer, create the rehearsal mark for the given sequence number. If *label* is `\default`, create the next sequential rehearsal mark. If *label* is markup, use it for the mark.

`\markupMap path` (symbol list or symbol) *markupfun* (markup-function) *music* (music) $\Rightarrow$ music

Apply *markupfun* to property *path* in *music*.

Argument *path* is either of the form *property* or *MusicExpression.property*. If *MusicExpression* is not given, *markupfun* gets applied to all properties called *property*, otherwise it is restricted to *MusicExpression* events. If *property* is not a markup, it is ignored.

In the following example, both the tempo indication and the bowing instruction are printed in red. If you replace text with `TempoChangeEvent.text`, only the tempo indication changes the color.

```
\markupMap
  text
  \markup \with-color #red \etc
  { \tempo "Largo" g'2_"arco" c'' }
```

`\measure music` (music) $\Rightarrow$ music

Create a complete measure from *music*.

This is equivalent to `\measureRemainder music`, but with a bar check at the beginning as well as the end.

`\measureRemainder music` (duration-or-music) $\Rightarrow$ music

End the current measure after *music*.

The effect is equivalent to this:

```
{
  \initialContextFrom %{ copy of music %}
  \setMeasureLengthFromHere %{ duration of music %}
  music |
  \setDefaultMeasureLength
}
```

Passing a duration as *music* (e.g., `\measureRemainder 2`) is reserved for future use.

See `\setMeasureLengthFromHere` (page 957) for more information.

Compare to `\premeasure` (page 954).

`\modalInversion around` (pitch) *to* (pitch) *scale* (music) *music* (music) $\Rightarrow$ music

Invert *music* about *around* using *scale* and transpose from *around* to *to*.

`\modalTranspose` *from* (pitch) *to* (pitch) *scale* (music) *music* (music) $\Rightarrow$ music
Transpose *music* from *pitch from* to *pitch to* using *scale*.

`\musicLength` *music* (music) $\Rightarrow$ any type
Return the duration of *music* as a `ly:moment`.

Examples:

`\musicLength 8` $\Rightarrow$ `#{ly:make-moment 1/8}`

`\musicLength {8. 8 8}` $\Rightarrow$ `#{ly:make-moment 7/16}`

`\musicMap` *proc* (procedure) *mus* (music) $\Rightarrow$ music
Apply *proc* to *mus* and all of the music it contains.

`\noPageBreak` $\Rightarrow$ music
Forbid a page break.
May be used at top level (i.e., between scores or markups), or inside a score.

`\noPageTurn` $\Rightarrow$ music
Forbid a page turn.
May be used at top level (i.e., between scores or markups), or inside a score.

`\noStanza` $\Rightarrow$ music
Forget the current stanza setting, thereby stopping any stanza reminders derived from it.

`\octaveCheck` *pitch* (pitch) $\Rightarrow$ music
Do an octave check.
This prints a warning if the interval between the previous note and *pitch* is not within a fourth.

`\offset` *property* (symbol list or symbol) *offsets* (any type) *item* (key list or music) $\Rightarrow$ music
Offset the default value of *property* of *item* by *offsets*.
If *item* is a string, the result is an override for the specified grob type. If *item* is a music expression, the result is the same music expression with an appropriate tweak applied to it.

`\omit` *item* (symbol list or music) $\Rightarrow$ music
Omit *item* without taking up space.
If *item* is a symbol list of form *GrobName* or *Context.GrobName*, the result is an override for the grob name specified by it. If *item* is a music expression, the result is the same music expression with an appropriate tweak applied to it.
This function sets *item*'s stencil property to `#f`.

`\once` *music* (music) $\Rightarrow$ music
Set property once to `#t` on all layout instruction events in *music*.

`\ottava` *octave* (integer) $\Rightarrow$ music
Set the octavation to *octave*.
A positive value *n* indicates *n* octaves higher; a negative value *n* octaves lower, and value 0 means no octavation.

`\overrideProperty` *grob-property-path* (list of indices or symbols) *value* (any type) $\Rightarrow$ music
Set the grob property specified by *grob-property-path* to *value*.
grob-property-path is a symbol list of the form *Context.GrobName.property* or *GrobName.property*, possibly with subproperties given as well.
As opposed to `\override`, which overrides the context-dependent defaults with which a grob is created, this command uses `Apply_output_engraver` at the grob

acknowledge stage. This may be necessary for overriding values set after the initial grob creation.

`\overrideTimeSignatureSettings` *time-signature* (boolean-or-fraction) *beat-base* (positive exact rational, fraction (as pair), moment, or +inf.0) *structure* (a number list or a list of them) *beam-exceptions* (list) $\Rightarrow$ music

Override time signature settings.

This function sets the `timeSignatureSettings` entry for *time-signature* to use *beat-base*, *structure*, and *beam-exceptions*.

beat-base and *beam-exceptions* are used as-is for `beatBase` and `beamExceptions`.

structure is used to derive values for `beatStructure` and `submeasureStructure`, as described for `\time` (page 959).

`\pageBreak` $\Rightarrow$ music

Force a page break.

May be used at top-level (i.e., between scores or markups), or inside a score.

`\pageTurn` $\Rightarrow$ music

Force a page turn.

May be used at top-level (i.e., between scores or markups), or inside a score.

`\palmMute` *note* (music) $\Rightarrow$ music

Print *note* with a triangle-shaped note head.

`\palmMuteOn` $\Rightarrow$ music

Set the default note head style to a triangle-shaped style.

`\parallelMusic` *voice-ids* (list) *music* (music) $\Rightarrow$ void

Define parallel music sequences.

Within *music*, parallel music sequences are separated by ‘|’ characters. The sequences are assigned to the LilyPond music identifiers provided in *voice-ids*.

For example, this code

```
\parallelMusic A,B,C {
  c c | d d | e e |
  d d | e e | f f |
}
```

is equivalent to

```
A = { c c | d d }
B = { d d | e e }
C = { e e | f f }
```

The last bar checks in a sequence are not copied to the result in order to facilitate ending the last entry at non-bar boundaries.

`\parenthesize` *arg* (symbol list or music) $\Rightarrow$ music

Tag *arg* to be parenthesized.

arg may be either a music event or a grob path.

`\partCombine` [*chord-range* (pair of numbers)] *part1* (music) *part2* (music) $\Rightarrow$ music

Combine two parts into a single staff.

This takes the music in *part1* and *part2* and returns a music expression containing simultaneous Voice contexts (called one for the upper and two for the lower voice). Where appropriate, *part1* and *part2* are combined into a single voice (called shared or solo, depending on context).

Optional argument *chord-range* is a pair (*start* . *stop*) that defines the range in which the two voices are printed as chords (or unison); the default value is (0 . 8), which means that intervals up to and including a ninth are unified.

`\partCombineDown [chord-range (pair of numbers)] part1 (music) part2 (music) ⇒ music`

Combine two parts into a single staff with all stems downwards.

For details, see `\partCombine` (page 952).

`\partCombineForce [type (symbol)] ⇒ music`

Override the part-combiner mode with *type*.

The following table gives the possible values for *type*, together with the corresponding shorthand functions.

<code>apart</code>	<code>\partCombineApart</code>
<code>chords</code>	<code>\partCombineChords</code>
<code>unisono</code>	<code>\partCombineUnisono</code>
<code>solo1</code>	<code>\partCombineSoloI</code>
<code>solo2</code>	<code>\partCombineSoloII</code>
<code>\default</code>	<code>\partCombineAutomatic</code>

`\partCombineUp [chord-range (pair of numbers)] part1 (music) part2 (music) ⇒ music`

Combine two parts into a single staff with all stems upwards.

For details, see `\partCombine` (page 952).

`\partial dur (duration) ⇒ music`

End the current measure after *dur*.

Adjust `Timing.measurePosition` to end the current measure at *dur* past the point of use. As a special case, when used at the start, create an anacrusis before the first measure.

Notational elements that communicate metric structure (e.g., beam breaks) will be engraved appropriately for the final *dur* part of a measure. Compare to `\setMeasureLengthFromHere` (page 957).

The calculation requires `Timing.measureLength` to be finite, so `\partial` cannot be used in a *senza-misura* passage.

See also `\premeasure` (page 954).

`\phrasingSlurDashPattern dash-fraction (number) dash-period (number) ⇒ music`

Set up a custom dash pattern style for phrasing slurs.

dash-fraction gives the size of one dash relative to *dash-period*; *dash-period* is the length of one dash plus one space. LilyPond adjusts *dash-period* to produce symmetrical output.

More complex patterns can be achieved by directly manipulating the `PhrasingSlur.dash-definition` property.

`\pitchedTrill main-note (music) secondary-note (music) ⇒ music`

Print a pitched trill.

main-note is the main note of the trill; *secondary-note* gets printed as a stemless note head in parentheses.

`\pointAndClickOff ⇒ void`

Suppress links to LilyPond source code in music output.

`\pointAndClickOn ⇒ void`

Generate links to LilyPond source code in music output.

This enables the creation of code in a PDF or SVG output file to reference the originating LilyPond source code (i.e., file name, line number, and column). This is helpful when developing a score; however, the output file becomes much larger.

`\pointAndClickTypes types` (symbol list or symbol) $\Rightarrow$ void

Generate point-and-click info for music of type *types* only.

types is a single music expression (such as `#'note-event`) or a list of music expressions.

`\polymetric [time-signature-command (music)]` $\Rightarrow$ music

Apply *time-signature-command* to the local context rather than to Timing.

Example:

```
\context Staff \polymetric \time 6/8
```

The local measure must align with the reference measure defined in Timing. So that explicit changes to `Timing.measureLength` (e.g., for ad-hoc irregular measures) remain visible, this command does not set the `measureLength` property in the local context.

A nominally incompatible local measure can be fitted to the controlling Timing measure by applying `\scaleDurations` (page 956) to this command. That adjusts the value of the internal property `meterScalingFactor` in the local context.

To unset the local properties and resume using the values from the Timing context, use `\polymetric \default`.

`\popContextProperty path` (list of indices or symbols) $\Rightarrow$ music

Pop value of context property *path* from stack and set it.

This is the opposite to function `\pushContextProperty` (page 955).

`\preBend mus` (music) $\Rightarrow$ post-event

Set `BendSpanner.style` to 'pre-bend for *mus*.

`\preBendHold mus` (music) $\Rightarrow$ post-event

Set `BendSpanner.style` to 'pre-bend-hold for *mus*.

`\premeasure music` (duration-or-music) $\Rightarrow$ music

Create a lead-in partial measure from *music*.

The effect is equivalent to this:

```
{
  \initialContextFrom %{ copy of music %}
  \partial %{ duration of music %}
  music |
}
```

Passing a duration as *music* (e.g., `\premeasure 2`) is reserved for future use.

Compare to `\measureRemainder` (page 950).

`\propertyOverride grob-property-path` (list of indices or symbols) *value* (any type) $\Rightarrow$ music

Set the grob property specified by *grob-property-path* to *value*.

grob-property-path is a symbol list of the form `Context.GrobName.property` or `GrobName.property`, possibly with subproperties given as well. This music function is mostly intended for use from Scheme as a substitute for the built-in `\override` command.

`\propertyRevert grob-property-path` (list of indices or symbols) $\Rightarrow$ music

Revert the grob property specified by *grob-property-path* to its previous value.

grob-property-path is a symbol list of the form *Context.GrobName.property* or *GrobName.property*, possibly with subproperties given as well. This music function is mostly intended for use from Scheme as a substitute for the built-in `\revert` command.

`\propertySet` *property-path* (symbol list or symbol) *value* (any type) $\Rightarrow$ music

Set the context property specified by *property-path* to *value*.

This music function is mostly intended for use from Scheme as a substitute for the built-in `\set` command.

`\propertyTweak` *prop* (key list or symbol) *value* (any type) *item* (key list or music) $\Rightarrow$ music

Add a tweak to *item*, usually music.

This function sets the value of property *prop* to *value*; it generally behaves like `\tweak` but will turn into an `\override` when *item* is a symbol list. In that case, *item* specifies the grob path to override. This is mainly useful when using `\propertyTweak` as a component for building other functions like `\omit`. It is not the default behavior for `\tweak` since many input strings in `\lyricmode` can serve equally as music or as symbols, which causes surprising behavior when tweaking lyrics using the less specific semantics of `\propertyTweak`.

prop can contain additional elements in which case a nested property (inside of an alist) is tweaked.

`\propertyUnset` *property-path* (symbol list or symbol) $\Rightarrow$ music

Unset the context property specified by *property-path*.

This music function is mostly intended for use from Scheme as a substitute for the built-in `\unset` command.

`\pushContextProperty` *path* (list of indices or symbols) $\Rightarrow$ music

Push the current value of context property *path* to a stack.

The property can later be restored to the saved value with function `\popContextProperty` (page 954).

`\pushToTag` *tag* (symbol) *more* (music) *music* (music) $\Rightarrow$ music

Add *more* to the front of *music* tagged with *tag*.

A post-event can be added to the articulations of rhythmic events or chords; other expressions may be added to chords, sequential or simultaneous music.

`\pushToTagMarkup` *tag* (symbol) *more* (markup) *music* (music) $\Rightarrow$ music

Prepend *more* to every markup in *music* tagged with *tag*.

`\quoteDuring` *what* (string) *main-music* (music) $\Rightarrow$ music

Indicate a section of music to be quoted.

what indicates the name of the quoted voice specified with `\addQuote` (page 942). *main-music* is used to indicate the length of music to be quoted; it usually contains spacers or multi-measure rests.

`\raiseNote` *num* (integer) *music* (music) $\Rightarrow$ music

‘Raise’ the *num*-th note in each chord of *music*.

This function moves the affected notes up (usually by an octave) to be higher than the other notes of the chord. The position in a chord is counted upwards from the bottom.

The opposite function is `\dropNote` (page 946).

`\reduceChords` *music* (music) $\Rightarrow$ music

Reduce chords contained in *music* to single notes.

This is intended mainly for reusing music in a `RhythmicStaff` context. It does not reduce simultaneous music.

`\relative [pitch (pitch)] music (music) ⇒ music`

Make *music* relative to *pitch*.

If *pitch* is omitted, the first note in *music* is given in absolute pitch.

`\removeFromTagGroup tag-group (symbol list) tags (symbol list) ⇒ void`

Remove *tags* from the tag group identified by *tag-group*.

`\removeWithTag tags (symbol list or symbol) music (music) ⇒ music`

Remove elements of *music* that are tagged with one of the tags in *tags*.

tags may be either a single symbol or a list of symbols.

`\replaceWithTag tag (symbol) replacement (music) music (music) ⇒ music`

Replace tagged elements in *music*.

Everything tagged with *tag* (including the tagging itself) gets replaced with *replacement*.

`\replaceWithTagMarkup tag (symbol) replacement (markup) music (music) ⇒ music`

Replace tagged markup in *music*.

All markup tagged with *tag* (including the tagging itself) gets replaced with *replacement*.

`\resetRelativeOctave pitch (pitch) ⇒ music`

Set the octave inside a `\relative` section to *pitch*.

`\resetTagGroup tag-group (symbol list) ⇒ void`

Reset the tag group equal to *tag-group*.

`\resetTagGroups ⇒ void`

Reset all tag groups previously created with `\tagGroup`.

`\responsum music (music) ⇒ music`

Prepend character U+211F (RESPONSE) to the lyrics represented by *music*.

`\retrograde music (music) ⇒ music`

Return *music* in reverse order.

`\revertTimeSignatureSettings time-signature (pair) ⇒ music`

Revert `timeSignatureSettings` for time signatures equal to *time-signature*.

`\rightHandFinger finger (index or markup) ⇒ post-event`

Apply *finger* as a right-hand fingering indication.

`\scaleDurations fraction (non-negative rational, fraction, or moment) music (music) ⇒ music`

Multiply the duration of events in *music* by *fraction*.

`\sectionLabel text (markup) ⇒ music`

Mark the beginning of a named passage with *text*, e.g., “Coda”.

This is well suited for use at a section division created with `\section`, but it does not imply `\section` and may be used alone.

`\segnoMark [num (non-negative, exact integer)] ⇒ music`

Create a segno mark (or bar line).

num may be 1 for the first segno, 2 for the second, etc., or it may be `\default` to use the next number in sequence automatically.

If the `segnoStyle` context property is 'bar-line, a segno bar line is created instead of a segno mark.

`\senzaMisura` $\Rightarrow$ music

Cancel the time signature; begin free time.

This sets `Timing.timeSignature` to `#f`.

This sets `Timing.measureLength` to `+inf.0`, allowing `Timing.measurePosition` to advance indefinitely without starting a new measure.

Beyond this point, ending the current measure requires setting `Timing.measureLength` back to a finite value *before* (not *at*) the transition to the next measure. See `\measure` (page 950) and related functions for assistance.

Compare to `\cadenzaOn` (page 945).

`\setDefaultMeasureLength` $\Rightarrow$ music

Set `Timing.measureLength` from `Timing.timeSignature`.

`\setMeasureLengthFromHere` *dur* (duration) $\Rightarrow$ music

End the current measure after *dur*.

Adjust `Timing.measureLength` to end at *dur* past the point of use. The resulting measure length remains in effect until it is changed by another command.

Notational elements that communicate metric structure (e.g., beam breaks) will be engraved appropriately to continue the measure. Compare to `\partial` (page 953).

See also `\measure` (page 950) and `\measureRemainder` (page 950).

`\shape` *offsets* (list) *item* (key list or music) $\Rightarrow$ music

Offset control points of *item* by *offsets*.

offsets is a list of number pairs (*x* . *y*) or a list of such lists. Each pair represents an offset to a control point. The ‘y’ value of each pair is scaled by staff space.

If *item* is a string, the result is `\once\override` for the specified grob type. If *item* is a music expression, the result is the same music expression with an appropriate tweak applied.

`\shiftDurations` *dur* (integer) *dots* (integer) *arg* (music) $\Rightarrow$ music

Change duration of *arg*.

This function walks over all durations and dot counts in *arg*, adding *dur* to the durations and *dots* to the dot counts.

`\single overrides` (music) *music* (music) $\Rightarrow$ music

Convert *overrides* to tweaks and apply them to *music*.

This does not convert `\revert`, `\set` or `\unset`.

`\skip` *arg* (duration-or-music) $\Rightarrow$ music

Skip over *arg*, which may be music or a duration.

`\slashedGrace` *music* (music) $\Rightarrow$ music

Create slashed graces from *music*.

This produces slashes through stems, but no slur.

`\slurDashPattern` *dash-fraction* (number) *dash-period* (number) $\Rightarrow$ music

Set up a custom dash pattern style for slurs.

dash-fraction gives the size of one dash relative to *dash-period*; *dash-period* is the length of one dash plus one space. LilyPond adjusts *dash-period* to produce symmetrical output.

More complex patterns can be achieved by directly manipulating the `Slur.dash-definition` property.

`\staffHighlight` *color* (color) $\Rightarrow$ music

Start a highlight with color *color*.

`\stanza text (markup)` $\Rightarrow$ music

Set and display the stanza number *text* in lyrics.

`\startGradualTempoChange [text (markup)]` $\Rightarrow$ music

Start an accelerando or ritardando.

Begin a gradual departure from the tempo most recently set with `\tempo`. The gradual change extends to the next `\stopGradualTempoChange` or `\tempo` command. When `\stopGradualTempoChange` is used, it defines the target tempo; otherwise, `\tempo` defines it.

The *text* argument is a placeholder. Only `\default` is accepted. It is intended eventually to serve the same purpose as the *text* argument to `\tempo`.

`\stopGradualTempoChange [text (markup)] tempo-unit (duration) metronome-count (number)`
 $\Rightarrow$ music

End an accelerando or ritardando.

End a gradual tempo change at the tempo defined by *tempo-unit* and *metronome-count*. Unless there is a simultaneous `\tempo` command setting a new tempo, resume the tempo most recently set with `\tempo`.

The *text* argument is a placeholder. Only `\default` is accepted. It is intended eventually to serve the same purpose as the *text* argument to `\tempo`.

`\storePredefinedDiagram fretboard-table (hash table) chord (music) tuning (pair)`
`diagram-definition (string or pair)` $\Rightarrow$ void

Add a predefined fret diagram to *fretboard-table*.

It is defined by *diagram-definition* for the chord pitches *chord* and the string tuning *tuning*.

`\stringTuning chord (music)` $\Rightarrow$ any type

Convert *chord* to a string tuning.

chord must be in absolute pitches and should have the highest string number (generally the lowest pitch) first.

`\styledNoteHeads style (symbol) heads (symbol list or symbol) music (music)` $\Rightarrow$ music

Set *heads* in *music* to *style*.

`\tabChordRepeats [event-types (list)] music (music)` $\Rightarrow$ music

Extend ‘q’ to also repeat string and fingering information.

This function walks through *music* putting the notes, fingerings and string numbers of the previous chord into repeat chords, as well as an optional list of *event-types* such as `#'` (articulation-event).

`\tabChordRepetition` $\Rightarrow$ void

Include the string and fingering information in a chord repetition.

This function is deprecated; use `\tabChordRepeats` instead.

`\tag tags (symbol list or symbol) music (music)` $\Rightarrow$ music

Tag *music* with *tags*.

This function adds the single symbol or symbol list *tags* to the *tags* property of *music* and returns the result.

`\tagGroup tags (symbol list)` $\Rightarrow$ void

Define a tag group comprising the symbols in the symbol list *tags*.

Tag groups must not overlap.

`\tagGroupRef tags` (symbol list) $\Rightarrow$ any type

Define a tag group comprising the symbols in the symbol list *tags*.

It returns the created tag group for further reference.

`\temporary music` (music) $\Rightarrow$ music

Make `\override` reversible with `\revert`.

This function makes any `\override` in *music* replace an existing grob property value only temporarily, restoring the old value when a corresponding `\revert` is executed. This is achieved by clearing the pop-first property normally set on `\overrides`.

An `\override/\revert` sequence created by using `\temporary` and `\undo` on the same music containing overrides will cancel out perfectly or cause a warning.

Non-property-related music is ignored, warnings are generated for any property-changing music that isn't an `\override`.

`\textEndMark text` (markup) $\Rightarrow$ music

Create a right-aligned text mark using *text*.

`\textMark text` (markup) $\Rightarrow$ music

Create a (left-aligned) text mark using *text*.

`\tieDashPattern dash-fraction` (number) *dash-period* (number) $\Rightarrow$ music

Set up a custom dash pattern style for ties.

dash-fraction gives the size of one dash relative to *dash-period*; *dash-period* is the length of one dash plus one space. LilyPond adjusts *dash-period* to produce symmetrical output.

More complex patterns can be achieved by directly manipulating the Tie .dash-definition property.

`\time [structure` (a number list or a list of them)] *time-sig* (time signature) $\Rightarrow$ music

Set the time signature to *time-sig*.

When *structure* is a plain list of numbers, it is used as-is for `beatStructure`, and `submeasureStructure` is left at the default.

When *structure* is a list of lists, `beatStructure` is derived by discarding the grouping, and `submeasureStructure` is derived by summing each group. For example, a *structure* of '((1 2) (4 8)) yields a `beatStructure` of '(1 2 4 8) and a `submeasureStructure` of '(3 12).

time-sig may be a fraction, e.g., 3/4.

time-sig may also describe a complex time signature as a Scheme expression. Fractions are represented as pairs, (*numerator* . *denominator*), where the denominator is always a number. The numerator is one number or a list of two or more numbers. A list represents concatenation.

For example, a time signature of $(3+1)/8 + 2/4$ can be created with `\time #'(((3 1) . 8) (2 . 4))`

`\timeAbbrev time-sig` (pair) $\Rightarrow$ music

Set the time signature to *time-sig*.

This is like `\time time-sig`, except that it allows abbreviating fractions as lists. For example, a time signature of $(3+1)/8 + 2/4$ can be created with `\timeAbbrev #'((3 1 8) (2 4))`, and a time signature of $(3+2)/8$ with either `\timeAbbrev #'((3 2 8))` or the shorter version `\timeAbbrev 3,2,8`.

This is for backward compatibility. Using `\time` (page 959) instead is recommended.

`\times fraction` (fraction, as pair) *music* (music) $\Rightarrow$ music

Scale *music* in time by *fraction*.

`\tocItem [label (symbol list or symbol)] text (markup)  $\Rightarrow$  music`

Add *text* as an entry to the table of contents.

This uses the `\tocItemMarkup` paper variable markup for formatting and assigns it to *label* if one is provided. If a hierarchy of labels is given, make the current item a child of the corresponding objects.

`\transpose from (pitch) to (pitch) music (music)  $\Rightarrow$  music`

Transpose *music* from pitch *from* to pitch *to*.

`\transposedCueDuring what (string) dir (direction) pitch (pitch) main-music (music)  $\Rightarrow$  music`

Create a transposed cue.

This function inserts notes from the part *what* into a `CueVoice` context called *cue*, using the transposition defined by *pitch*. This happens simultaneously with *main-music*, which is usually a rest. The argument *dir* determines whether the cue notes should be notated as a first or second voice.

`\transposition pitch (pitch)  $\Rightarrow$  music`

Set instrument transposition to *pitch*.

`\tuplet ratio (fraction, as pair) [tuplet-span (duration)] music (music)  $\Rightarrow$  music`

Scale the given *music* to tuplets.

ratio is a fraction that specifies how many notes are played in place of the nominal value: it will be $3/2$ for triplets, namely three notes being played in place of two.

If the optional duration *tuplet-span* is specified, it is used instead of `tupletSpannerDuration` for grouping the tuplets. For example,

```
\tuplet 3/2 4 { c8 c c c c c }
```

results in two groups of three tuplets, each group lasting for a quarter note.

`\tupletSpan [tuplet-span (duration)]  $\Rightarrow$  music`

Set `tupletSpannerDuration` to the duration *tuplet-span*.

This context property is the length into which `\tuplet` without an explicit tuplet span argument of its own will group its tuplets. To revert to the default of not subdividing the contents of a `\tuplet` command without an explicit tuplet span argument, use

```
\tupletSpan \default
```

`\tweak prop (key list or symbol) value (any type) music (music)  $\Rightarrow$  music`

Add a tweak to *music*.

Layout objects created by *music* get their property *prop* set to *value*. If *prop* has the form *Grob.property*, like with

```
\tweak Accidental.color #red cis'
```

an indirectly created grob (`Accidental` is caused by `NoteHead`) can be tweaked; otherwise only directly created grobs are affected.

prop can contain additional elements in which case a nested property (inside of an alist) is tweaked.

If *music* is an event-chord, every contained rhythmic-event is tweaked instead.

`\undo music (music)  $\Rightarrow$  music`

Convert `\override` and `\set` in *music* to `\revert` and `\unset`, respectively.

Any reverts and unsets already in *music* cause a warning. Non-property-related music is ignored.

`\unfolded music (music) ⇒ music`

Mask *music* until the innermost enclosing repeat is unfolded.

`\unfoldRepeats [types (symbol list or symbol)] music (music) ⇒ music`

Unfold `\repeat`.

This forces `\repeat volta`, `\repeat tremolo` or `\repeat percent` commands in *music* to be interpreted as `\repeat unfold`, if specified in the optional symbol-list *types*. The default for *types* is an empty list, which forces any of those commands in *music* to be interpreted as `\repeat unfold`. Possible entries are `volta`, `tremolo` or `percent`. Multiple entries are possible.

`\verboseBarNumbers ⇒ music`

Print bar numbers at every bar line and line break.

This function is a concise way to add detail to documentation examples. The output is subject to change without notice.

See Section “`Bar_number_engraver`” in *Internals Reference*.

`\versus music (music) ⇒ music`

Prepend character U+2123 (VERSICLE) to the lyrics represented by *music*.

`\voices ids (list of indices or symbols) music (music) ⇒ music`

Specify voice order in simultaneous music.

This takes the key list *ids* of numbers (indicating the use of ‘`\voiceOne`’...) or symbols (indicating voice names, typically converted from strings by argument list processing) and assign the following `\`-separated music in *music* to contexts according to that list. Named rather than numbered contexts can be used for continuing one voice (for the sake of spanners and lyrics), usually requiring a `\voiceOne`-style override at the beginning of the passage and a `\oneVoice` override at its end.

The default

```
<< ... \ \ ... \ \ ... >>
```

construct would correspond to

```
\voices 1,2,3 << ... \ \ ... \ \ ... >>
```

`\void arg (any type) ⇒ void`

Accept a Scheme argument *arg* and return a void expression.

Use this if you want to have a Scheme expression evaluated because of its side effects but its return value being ignored.

`\volta volta-numbers (number list) music (music) ⇒ music`

Mark *music* as being limited to the volte given in *volta-numbers*.

This gets used when the innermost enclosing repeat is unfolded. Volta number begins at 1 and increases by 1 with each repetition.

`\vshape offsets (list) item (key list or music) ⇒ music`

Like `\shape`, but additionally show control points for ease of tweaking.

`\withMusicProperty sym (symbol) val (any type) music (music) ⇒ music`

Set music property *sym* to *val* in *music*.

`\withRelativeDir file-name (string) ⇒ any type`

Prepend directory of current input file to string *file-name*.

Use this for markup commands that include files, and where such files should be found relative to the input file. Example:

```
\markup { \image #X #3 \withRelativeDir "test.png" }
```


`\xNote note (music) ⇒ music`

Print *note* with a cross-shaped note head.

`\= id (index or symbol) event (post-event) ⇒ post-event`

Assign an ID to a spanner or an item.

This sets the `spanner-id` or `id` property of *event* to the given *id*, which is a non-negative integer or a symbol.

For spanners this can be used to tell LilyPond how to connect overlapping or parallel slurs or phrasing slurs within a single Voice context.

```
\fixed c' { c\=1( d\=2( e\=1) f\=2) }
```



For items this can be used, for example, to tell LilyPond how to connect a `FingerGlideSpanner` with non-matching fingers.

```
\fixed c' { c\glide \= #'foo -1 d\= #'foo -2 }
```



`\% count (number) music (music) ⇒ music`

This is the same as `\repeat percent count music`.

See `\repeat`.

`\* count (number) music (music) ⇒ music`

This is the same as `\repeat unfold count music`.

See `\repeat`.

`\~ music (music) ⇒ music`

Insert *pes* or *flexa* between previous and next note.

B.22 Context modification identifiers

The following commands are defined for use as context modifications within a `\layout` or `\with` block.

`\EnableGregorianDivisiones`

Configure division commands such as `\section` to create `Divisio` grobs rather than `BarLine` grobs. This does not affect measure bar lines or the properties of the grobs themselves.

- Sets translator property `caesuraTypeTransform` to `caesura-to-divisio`.
- Sets translator property `doubleRepeatBarType` to `'()`.
- Sets translator property `endRepeatBarType` to `'()`.
- Sets translator property `fineBarType` to `""`.
- Sets translator property `sectionBarType` to `""`.
- Sets translator property `startRepeatBarType` to `'()`.
- Sets translator property `underlyingRepeatBarType` to `""`.
- Sets translator property `doubleRepeatSegnoBarType` to `"S-||"`.
- Sets translator property `endRepeatSegnoBarType` to `"S-||"`.

- Sets translator property `fineSegnoBarType` to "S-||".
- Sets translator property `fineStartRepeatSegnoBarType` to "S-||".
- Sets translator property `segnoBarType` to "S-||".
- Sets translator property `startRepeatSegnoBarType` to "S-||".

`\RemoveAllEmptyStaves`

Remove staves which are considered to be empty according to the list of interfaces set by `keepAliveInterfaces`, including those in the first system.

- Sets grob property `remove-empty` in Section “VerticalAxisGroup” in *Internals Reference* to `#t`.
- Sets grob property `remove-first` in Section “VerticalAxisGroup” in *Internals Reference* to `#t`.

`\RemoveEmptyStaves`

Remove staves which are considered to be empty according to the list of interfaces set by `keepAliveInterfaces`.

- Sets grob property `remove-empty` in Section “VerticalAxisGroup” in *Internals Reference* to `#t`.

B.23 Paper variables

The following paper variables are predefined by LilyPond. Default values that are scaled to paper size are given for the default paper size, A4. The mentioned `xxx-default` variables are paper variables, too.

Some values like `mm` or `pt` are constants and thus essentially read-only; changing them would confuse LilyPond thoroughly.

Most paper variables can be either set in `\paper` or in `\layout`, see Section 27.1 [The `\layout` block], page 681.

`annotate-spacing` (boolean)

If this value is set to `#t`, dimensions of vertical layout variables that may be altered for page formatting are graphically displayed. Default: `#f`.

`auto-first-page-number` (boolean)

The page-breaking algorithm is affected by the first page number being odd or even. If set to `#t`, the algorithm decides whether to start with an odd or even number. This results in the first page number remaining as is or being increased by one. Default: `#f`.

`binding-offset` (number)

This amount gets added to inner-margin so that nothing is hidden by the binding. Has only an effect if `two-sided` is set to `#t`. Default: `binding-offset-default` (5 mm, scaled to paper size).

`blank-after-score-page-penalty` (number)

The penalty for having a blank page after the end of one score and before the next. By default, this is smaller than `blank-page-penalty` so that LilyPond prefers blank pages after scores to blank pages within a score. Default: 2.

`blank-last-page-penalty` (number)

The penalty for ending the score on an odd-numbered page. Default: 0.

`blank-page-penalty` (number)

The penalty for having a blank page in the middle of a score. Note that this is not used by `ly:optimal-breaking`, which never considers blank pages in the middle of a score. Default: 5.

blot-diameter (non-negative number)

This value globally defines the smallest ‘round’ feature LilyPond uses while constructing almost all non-glyph elements like beams or stems. Essentially, it sets up how round the corners and line ends are. It only makes sense to change the value if you use a different music glyph font with crisper corners, say. Default: 0.4 pt.

book-title (procedure)

Internal. This is what LilyPond actually uses for handling bookTitleMarkup.

book-title-properties (association list (list of pairs))

Internal.

bookpart-level-page-numbering (boolean)

If set to #t, restart page numbering for each \bookpart block. Otherwise all pages in the document are enumerated continuously. Default: #f.

bookTitleMarkup (markup)

The titling markup within a \book, using standard fields from the \header block. The default value is defined in file titling-init.ly.

bottom-margin (non-negative number)

The margin between the bottom of the printable area and the bottom of the page. Default: bottom-margin-default (10 mm, scaled to paper size).

bp (positive number)

The big point unit, also called *desktop publishing point* (DTP point). It is 1/72 of an inch, approx. 0.353 mm (0.0138 in).

check-consistency (boolean)

If set to #t, print a warning if the left margin, line width, and right margin do not exactly add up to paper-width, and replace each of these (except paper-width) with its default value (scaled to the paper size if necessary). If set to #f, ignore any inconsistencies and allow systems to run off the edge of the page. Default: #t.

clip-regions (association list (list of pairs))

A list of rhythm location pairs to output fragments of a score.

```
clip-regions
= #(list (cons (make-rhythmic-location 2 0 1)
              (make-rhythmic-location 4 0 1))
        (cons (make-rhythmic-location 5 1 2)
              (make-rhythmic-location 7 3 4)))
```

The above example defines two regions: the first is from the beginning of bar 2 to the beginning of bar 4, the second starts after a half note duration in bar 5 and ends after the third quarter in bar 7.

Has only an effect if LilyPond’s command-line option -dclip-systems is active. Default: unset.

cm (positive number)

The centimeter unit, approx. 0.39 in.

debug-beam-scoring (boolean)

If set to #t, print demerits together with their cause, followed by the number of configurations that have been scored before concluding. Default: #f.

Example:

```
L 18.95 C 655.12 c19/625 → demerits for stem lengths ('L') and collisions
('C'), scored 19 out of 625 initially considered configurations.
```

Possible demerit causes: collision ('C'), inappropriate stem length ('L'), beam direction different from damping direction ('Sd'), difference between beam slope and musical slope ('Sm'), deviation from ideal slope ('Si'), horizontal inter-quants ('H'), forbidden quants ('Fl'/'Fs').

Demerits are configurable, see Section "beam-interface" in *Internals Reference* for a list of tunable parameters.

debug-slur-scoring (boolean)

If set to #t, print demerits together with their cause, followed by the sum of all demerits and the index of the slur configuration finally chosen. Default: #f.

Example:

slope=2.00, R edge=10.51, variance=0.03 TOTAL=12.54 idx=4 → demerits for slope, distance of the right edge to the attachment point, variance of distance between note heads and slur. Total demerits: 12.54, index of the chosen configuration: 4.

Possible demerit causes: distance of the left/right slur edge to the attachment points ('L edge'/'R edge'), inappropriate slope ('slope'), distance variations between note heads and slur ('variance'), distances for heads that are between the slur and an imaginary line between the attachment points ('encompass'), too small distance between slur and tie extrema ('extra').

Demerits are configurable, see Section "slur-interface" in *Internals Reference* for a list of tunable parameters.

debug-tie-scoring (boolean)

If set to #t, print the basic configuration of ties, followed by demerits and their corresponding causes and the total sum of demerits. Default: unset.

Example:

0 (0.23) u: vdist=1.08 lhdist=1.79 tie/stem dir=8.00 TOTAL=10.87 → offset from the center of the staff according tie specification: 0 staff-spaces, vertical distance of the tie's center in y-direction to the bottom (or top) of the tie: 0.23, direction: up. Demerits for vertical and horizontal distance to note head, same direction of stem and tie. Total demerits: 10.87.

Possible demerit causes: wrong tie direction ('wrong dir'), vertical distance to note heads ('vdist'), horizontal distance to left or right note head ('lhdist'/'rhdist'), same direction of stem and tie ('tie/stem dir'), position and direction of tie not matching, e.g., tie is in the upper half of the staff but has direction DOWN ('tie/pos dir'), tie is too short ('minlength'), tip of tie collides with staff line ('tipline'), collision with dot ('dot collision'), center of tie is too close to a staff line ('line center'), y-position (edge or center) of currently considered tie is less than the y-position of the previous tie ('monotone edge'/'monotone cent'), edge or center of tie is too close to the one considered previously ('tietie center'/'tietie edge'), unsymmetrical horizontal positioning with respect to the note heads ('length symm'), unsymmetrical vertical positioning with respect to the note heads ('pos symmetry').

Demerits are configurable, see Section "tie-interface" in *Internals Reference* for a list of tunable parameters.

dimension-variables (list)

Internal.

evenFooterMarkup (markup)

The footer markup used for even-numbered pages. If not set, oddFooterMarkup is used instead. The default value is defined in file titling-init.ly.

`evenHeaderMarkup` (markup)

The header markup used for even-numbered pages. If not set, `oddHeaderMarkup` is used instead. The default value is defined in file `titling-init.ly`.

`first-page-number` (integer)

The value of the page number on the first page. Default: 1.

`footnote-footer-padding` (number)

The padding between the footer and the bottom-most footnote. Default: 0.5 mm.

`footnote-number-raise` (number)

This controls how high the annotation numbers of both footnotes and in-notes are raised relative to the footnote or in-note text. Default: 0.5 mm.

`footnote-numbering-function` (procedure)

This variable holds the name of the function that formats both footnote and in-note numbers (without positioning it). LilyPond provides two predefined functions (in file `output-lib.scm`): `numbered-footnotes` ('1', '2', etc.) and `symbol-footnotes` ('*', '†', etc.). Default: `numbered-footnotes`.

The function takes an integer as an argument (starting with value 0) and returns the appropriate markup. You can create your own function, for example,

```
footnote-numbering-function =
  #(lambda (x)
    #{ \markup \concat { "[" #(number->string (1+ x)) "]" } #})
```

`footnote-padding` (number)

The padding between two footnotes. Default: 0.5 mm.

`footnote-separator-markup` (markup)

Markup to separate the music from the footnotes, usually a horizontal line. The default value is defined in file `paper-defaults-init.ly`.

`horizontal-shift` (number)

If set, the main content block of all pages (but not headers and footers) is shifted horizontally. Positive values shift to the right (on both even and odd pages). Default: 0 mm.

`in` (positive number)

The inch unit, equal to 2.54 cm.

`in-note-padding` (number)

The padding between two in-notes. Default: 0.5 mm.

`in-note-system-padding` (number)

The padding between an in-note and the associated music system. Default: 0.5 mm.

`incipit-width` (positive number)

The width of an incipit as created by the `\incipit` command. Must be smaller than or equal to `indent`. Default: $(\text{indent} / 2)$.

`indent` (non-negative number)

The indentation of the first system in a score. The space within the line-width available for the first system is reduced by this amount. Default: `indent-default` (15 mm, scaled to paper size).

`inner-margin` (non-negative number)

The margin all pages have at the inner side if they are part of a book. Has only an effect if `two-sided` is set to `#t`. If unset, `inner-margin-default` (15 mm, scaled to paper size) is used in computations. Default: `unset`.

`is-last-bookpart` (boolean)

To be documented.

`label-alist-table` (list)

Internal. LilyPond uses this to construct a table of contents.

`label-page-table` (association list (list of pairs))

Internal. LilyPond uses this to implement the `\with-link` functionality and to construct a table of contents.

`landscape` (boolean)

Internal. Use `set-default-paper-size` or `set-paper-size` to set the paper orientation.

`last-bottom-spacing` (association list (list of pairs))

The distance from the last system or top-level markup on a page to the bottom of the printable area (i.e., the top of the bottom margin). The default value is defined in file `paper-defaults-init.ly`.

`left-margin` (non-negative number)

The margin between the left edge of the page and the start of the staff lines in unindented systems. If `left-margin` is not set, and both `line-width` and `right-margin` are set, then `left-margin` is set to $(\text{paper-width} - \text{line-width} - \text{right-margin})$. If only `line-width` is set, then both margins are set to $((\text{paper-width} - \text{line-width}) / 2)$, and the systems are consequently centered on the page. If unset, `left-margin-default` (15 mm, scaled to paper size) is used in computations. Default: unset.

If `two-sided` is set to `#t`, this value is ignored. Also see `check-consistency`.

`line-thickness` (positive number)

This value globally defines the default line thickness LilyPond uses while constructing many non-glyph elements like lines or boxes. The actual line thickness is usually specified as a factor of this base value, either as a default value, or overridden by the user. The default depends on the staff space and is computed as $(0.328571 + 0.0342857 * \text{staff-space})$ (see function `calc-line-thickness` in file `paper.scm`), which is synchronized with the Emmentaler font.

`line-width` (positive number)

The horizontal extent of the staff lines in unindented, non-ragged systems, equal to $(\text{paper-width} - \text{left-margin} - \text{right-margin})$ if not set. If `line-width` is set, and both `left-margin` and `right-margin` are not set, then the margins are updated to center the systems on the page automatically. Also see `check-consistency`. Default: unset.

As a feature of LilyPond, if the command-line option `-dcrop` is set, the dimensions of the cropped output file are always rounded up to integer (PostScript) big points; this might cause a little bit of whitespace at the right margin. To avoid that, set `line-width` to an integer big point value like `450\bp`.

`make-footer` (procedure)

Internal. This is what LilyPond actually uses for for handling `evenFooterMarkup` and `oddFooterMarkup`.

`make-header` (procedure)

Internal. This is what LilyPond actually uses for for handling `evenHeaderMarkup` and `oddHeaderMarkup`.

- `markup-markup-spacing` (association list (list of pairs))
 The distance between two (title or top-level) markups. The default value is defined in file `paper-defaults-init.ly`.
- `markup-system-spacing` (association list (list of pairs))
 The distance between a (title or top-level) markup and the system that follows it. The default value is defined in file `paper-defaults-init.ly`.
- `max-systems-per-page` (non-negative, exact integer)
 The maximum number of systems that are placed on a page. This is currently supported only by the `ly:optimal-breaking` algorithm. Default: unset.
- `min-systems-per-page` (non-negative, exact integer)
 The minimum number of systems that are placed on a page. This may cause pages to be overfilled if it is made too large. This is currently supported only by the `ly:optimal-breaking` algorithm. Default: unset.
- `mm` (positive number)
 The millimeter unit, approx. 0.039 in.
- `number-footnote-table` (list)
 Internal. LilyPond uses this to manage footnotes and footnote numbers.
- `oddFooterMarkup` (markup)
 The footer markup used for odd-numbered pages. The default value is defined in file `titling-init.ly`.
- `oddHeaderMarkup` (markup)
 The header markup used for odd-numbered pages. The default value is defined in file `titling-init.ly`.
- `orphan-penalty` (number)
 To be documented. See `lily/page-breaking.cc`. Default is 100000.
- `outer-margin` (non-negative number)
 The margin all pages have at the outer side if they are part of a book. Has only an effect if `two-sided` is set to `#t`. If unset, `outer-margin-default` (15 mm, scaled to paper size) is used in computations. Default: unset.
- `output-filename` (string)
 If set, use this value as the output file name for LilyPond output. See also `output-suffix`. The default is the input file name (without the file extension).
- `output-scale` (positive number)
 Internal. This value globally defines the output scale LilyPond uses while creating output. Use `set-global-staff-size` or `layout-set-staff-size` to change the scaling. Default: 1.7573, which corresponds to a 20 pt staff size.
- `output-suffix` (string)
 If set, use this value as the output file name suffix for LilyPond output, appended to the output name with a dash in between. See also `output-filename`. The default is no output suffix if there is only a single book block (either implicit or explicit), and a running integer starting with value 1 otherwise.
- `page-breaking` (procedure)
 The page-breaking algorithm to use. Choices are `ly:minimal-breaking`, `ly:page-turn-breaking`, `ly:one-page-breaking`, `ly:one-line-breaking`, `ly:one-line-auto-height-breaking`, and `ly:optimal-breaking`. Default: `ly:optimal-breaking`.

`page-breaking-system-system-spacing` (association list (list of pairs))

This tricks the page breaker into thinking that `system-system-spacing` is set to something different than it really is. For example, if `page-breaking-system-system-spacing.padding` is set to something substantially larger than `system-system-spacing.padding`, then the page breaker puts fewer systems on each page. Default: unset.

`page-count` (non-negative, exact integer)

The number of pages to be used for a score. Default: unset.

`page-number-type` (symbol)

The type of numerals used for page numbers. Choices include `arabic`, `roman-ij-lower`, `roman-ij-upper`, `roman-lower`, and `roman-upper`. Default: `arabic`.

`page-post-process` (procedure)

If this function is defined (within the `\paper` block), LilyPond uses it to post-process pages, for example, to extract the table of contents and writing the information to an auxiliary file. The call happens after page breaking has been performed.

The syntax is

```
#(define (page-post-process layout pages) ... )
```

`page-spacing-weight` (number)

When using the `ly:optimal-breaking` algorithm for page breaking, LilyPond has to make trade-offs between horizontal and vertical stretching so that the overall spacing is more acceptable. This parameter controls the relative importance of (vertical) page spacing and (horizontal) line spacing. High values makes page spacing more important. Default: 10.

`paper-height` (positive number)

The height of the page. Note that the automatic scaling of some vertical dimensions is not affected if you set this value directly. Default: 297 mm (A4 paper height).

`paper-width` (positive number)

The width of the page. While setting `paper-width` directly has no effect on the automatic scaling of some horizontal dimensions, it does influence the `line-width` variable. If both `paper-width` and `line-width` are set, then `left-margin` and `right-margin` also get updated. Also see `check-consistency`. Default: 210 mm (A4 paper width).

`papersize` (string)

Internal. Use `set-default-paper-size` or `set-paper-size` to set the paper size.

`print-all-headers` (boolean)

If set to `#t`, print all headers for each `\score` in the output. If set to `#f`, only the piece and opus header variables are printed. Default: `#f`.

`print-first-page-number` (boolean)

If set to `#t`, a page number is printed on the first page. Default: `#f`.

`print-page-number` (boolean)

If set to `#f`, page numbers are not printed. Default: `#t`.

`property-defaults` (association list (list of pairs))

This variable holds some settings that are used for top-level markups and as fallback values if nothing else is specified, for example, the standard fonts or the baseline skip. The default value is defined in file `paper-defaults-init.ly`.

pt (positive number)

The point unit, equal to approx. 0.351 mm (0.0139 in).

ragged-bottom (boolean)

If set to #t, systems are set at at their natural spacing, neither compressed nor stretched vertically to fit the page. Default: #f.

ragged-last (boolean)

If set to #t, the last system in the score does not fill the line width. Instead, the last system ends at its natural horizontal length. Default: #f.

ragged-last-bottom (boolean)

If set to #f, then the last page, and the last page in each section created with a \bookpart block, is vertically justified in the same way as the earlier pages. Default: #t.

ragged-right (boolean)

If set to #t, systems don't fill the line width. Instead, systems end at their natural horizontal length. Default: #t for scores with only one system, and #f for scores with two or more systems.

reset-footnotes-on-new-page (boolean)

If set to #t, footnote and in-note numbers are reset on each page break. For footnotes and in-notes numbered consecutively across page breaks, set to #f. Default: #t.

right-margin (non-negative number)

The margin between the right edge of the page and the end of the staff lines in non-ragged systems. If right-margin is not set, and both line-width and left-margin are set, then right-margin is set to (paper-width - line-width - left-margin). If only line-width is set, then both margins are set to ((paper-width - line-width) / 2), and the systems are consequently centered on the page. If unset, right-margin-default (15 mm, scaled to paper size) is used in computations. Default: unset.

If two-sided is set to #t, this value is ignored. Also see check-consistency.

score-markup-spacing (association list (list of pairs))

The distance between the last system of a score and the (title or top-level) markup that follows it. The default value is defined in file paper-defaults-init.ly.

score-system-spacing (association list (list of pairs))

The distance between the last system of a score and the first system of the score that follows it, if no (title or top-level) markup exists between them. The default value is defined in file paper-defaults-init.ly.

score-title (procedure)

Internal. This is what LilyPond actually uses for handling scoreTitleMarkup.

score-title-properties (association list (list of pairs))

Internal.

scoreTitleMarkup (markup)

The titling markup of a score within a \book, using standard fields from the \header block. The default value is defined in file titling-init.ly.

short-indent (non-negative number)

The level of indentation for all systems in a score besides the first system. The space within the line-width available for systems other than the first one is reduced by this amount. Default: short-indent-default (0 mm).

`staff-height` (positive number)

Internal. Use `set-global-staff-size` or `layout-set-staff-size` to set the staff height. Default: 20 pt.

`staff-space` (positive number)

Internal. One staff height contains four staff spaces. Use `set-global-staff-size` or `layout-set-staff-size` to set this value. Default: 5 pt.

`system-count` (non-negative, exact integer)

The number of systems to be used for a score. Default: unset.

`system-separator-markup` (markup)

A markup object that is inserted between systems, often used for orchestral scores. The `\slashSeparator` markup, defined in file `titling-init.ly`, is provided as a sensible standard value. Default: unset.

`system-system-spacing` (association list (list of pairs))

The distance between two systems in the same score. The default value is defined in file `paper-defaults-init.ly`.

`systems-per-page` (non-negative, exact integer)

The number of systems that should be placed on a page. This is currently supported only by the `ly:optimal-breaking` algorithm. Default: unset.

`tagline` (markup)

This markup gets placed at the bottom of the last page (via `oddFooterMarkup`). The default value is defined in file `titling-init.ly`.

`text-font-size` (positive number)

This value globally defines the standard text size for markups. The default depends on the staff height and is computed as $(\text{staff-height} / 20 * 11)$.

`tocFormatMarkup` (procedure)

How the top-level entries of the table of contents are formatted (if there are several hierarchical levels). This variable holds a function like `make-bold-markup`. The default value is defined in file `toc-init.ly`.

`tocIndentMarkup` (markup)

How the outline's hierarchy in the table of contents is made apparent. This markup is printed zero, one, or several times depending on the level of each entry. The default value is defined in file `toc-init.ly`.

`tocItemMarkup` (markup)

How an item in the table of contents is formatted. The default value of this markup is defined in file `toc-init.ly`.

`tocTitleMarkup` (markup)

How the title of the table of contents is formatted. The default value of this markup is defined in file `toc-init.ly`.

`top-margin` (non-negative number)

The margin between the top of the page and the top of the printable area. Default: `top-margin-default` (10 mm, scaled to paper size).

`top-markup-spacing` (association list (list of pairs))

The distance from the top of the printable area (i.e., the bottom of the top margin) to the first (title or top-level) markup on a page, when there is no system between the two. The default value is defined in file `paper-defaults-init.ly`.

top-system-spacing (association list (list of pairs))

The distance from the top of the printable area (i.e., the bottom of the top margin) to the first system on a page, when there is no (title or top-level) markup between the two. The default value is defined in file paper-defaults-init.ly.

two-sided (boolean)

If set to #t, use inner-margin, outer-margin and binding-offset to determine margins depending on whether the page number is odd or even. left-margin and right-margin are then ignored. Default: #f.

B.24 Naming conventions

Naming conventions are used so that it is easier to keep the nature of an object in mind.

Object/property type	Naming convention	Examples
Keywords	aaaa	\score, \addlyrics
Music functions and shortcuts	aaaa or aaaaAaaaAaaa	\time, \stemUp
Markup functions	aaaa or aaaa-aaaa-aaaa	\bold, \with-dimensions
Paper variables	aaaa or aaaa-aaaa-aaaa	indent, page-breaking
Music expressions	Aaaa or AaaaAaaaAaaa	NoteEvent, SequentialMusic
Music classes	aaaa or aaaa-aaaa-aaaa	note-event, rhythmic-event
Music properties	aaaa or aaaa-aaaa-aaaa	force-accidental, iterator-ctor
Contexts	Aaaa or AaaaAaaaAaaa	Staff, GrandStaff
Context properties	aaaa or aaaaAaaaAaaa	stanza, instrumentName
Engravers	Aaaa_engraver or Aaaa_aaaa_aaaa_engraver	Clef_engraver, Note_heads_engraver
Layout Objects	Aaaa or AaaaAaaaAaaa	Slur, NoteHead
Layout Object Properties	aaa or aaa-aaa-aaa	direction, beam-thickness
Interfaces	aaa-aaa-interface	grob-interface, break-aligned-interface
Scheme functions defined in Guile	aaaa or aaaa-aaaa-aaaa	map, for-each
Scheme functions defined in LilyPond	ly:aaaa or ly:aaaa-aaaa-aaaa or aaaa or aaaa-aaaa-aaaa ¹	ly:round-filled-box, music-map

B.25 Predefined type predicates

Predicates return #t (true) if their argument is of the named type and #f (false) if it isn't.

B.25.1 R5RS primary predicates

Primary predicates can be applied to any expression. They can be used on their own as predicates for LilyPond functions. The predicates here are part of the Scheme standard R5RS.

Type predicate	Description
boolean?	boolean
char?	character
complex?	complex number

¹ For historical reasons, some but not all of the functions defined by LilyPond start with the ly: prefix.

eof-object?	end-of-file object
input-port?	input port
integer?	integer
list?	list (use cheap-list? for faster processing)
null?	null
number?	number
output-port?	output port
pair?	pair
port?	port
procedure?	procedure
rational?	rational number
real?	real number
string?	string
symbol?	symbol
vector?	vector

B.25.2 R5RS secondary predicates

Secondary predicates are only applicable to specific expressions (for example, to numbers). They will throw a type error when applied to expressions they are not intended for. The predicates here are part of the Scheme standard R5RS.

Type predicate	Description
char-alphabetic?	alphabetic character
char-lower-case?	lower-case character
char-numeric?	numeric character
char-upper-case?	upper-case character
char-whitespace?	whitespace character
even?	even number
exact?	exact number
inexact?	inexact number
negative?	negative number
odd?	odd number
positive?	positive number
zero?	zero

B.25.3 Guile predicates

These predicates are defined by Guile but are not part of a Scheme standard.

Type predicate	Description
hash-table?	hash table

B.25.4 LilyPond scheme predicates

These predicates are only available within LilyPond and defined in Scheme.

Type predicate	Description
alist?	association list (list of pairs)
boolean-or-symbol?	boolean or symbol
cheap-list?	list (use this instead of list? for faster processing)
color?	color
exact-rational?	an exact rational number
fraction?	fraction, as pair
grob-list?	list of grobs
grouped-number-list?	list of non-empty lists of numbers

index?	non-negative, exact integer
index-or-markup?	index or markup
key?	index or symbol
key-list?	list of indices or symbols
key-list-or-music?	key list or music
key-list-or-symbol?	key list or symbol
ly:skyline-pair?	pair of skylines
markup?	markup
markup-command-list?	markup command list
markup-list?	markup list
moment-pair?	pair of moment objects
musical-length?	non-negative exact rational, fraction (as pair), moment, or +inf.0
musical-length-as-moment?	non-negative moment with no grace part
musical-length-as-number?	non-negative exact rational or +inf.0
non-negative-number?	non-negative number
number-list?	number list
number-or-grob?	number or grob
number-or-number-pair?	number or pair of numbers
number-or-pair?	number or pair
number-or-string?	number or string
number-pair?	pair of numbers
number-pair-list?	list of number pairs
optionally-grouped-beat-structure?	a number list or a list of them
positive-exact-rational?	a positive, exact rational number
positive-fraction?	positive, finite fraction, as pair
positive-musical-length?	positive exact rational, fraction (as pair), moment, or +inf.0
positive-musical-length-as-moment?	positive moment with no grace part
positive-musical-length-as-number?	positive exact rational or +inf.0
positive-number?	positive number
rational-or-procedure?	an exact rational or procedure
rhythmic-location?	rhythmic location
sane-simple-time-signature?	simple time signature
sane-time-signature?	time signature
scale?	non-negative rational, fraction, or moment
scheme?	any type
string-or-music?	string or music
string-or-pair?	string or pair
string-or-symbol?	string or symbol
symbol-key-alist?	alist, with symbols as keys
symbol-list?	symbol list
symbol-list-or-music?	symbol list or music
symbol-list-or-symbol?	symbol list or symbol
time-signature?	time signature
void?	void

B.25.5 LilyPond exported predicates

These predicates are only available within LilyPond and usually defined in C++.

Type predicate	Description
ly:book?	book

ly:book-or-bookpart?	book or bookpart
ly:bookpart?	bookpart
ly:context?	context
ly:context-def?	context definition
ly:context-mod?	context modification
ly:dimension?	dimension, in staff space
ly:dir?	direction
ly:dispatcher?	dispatcher
ly:duration?	duration
ly:event?	post-event
ly:font-metric?	font metric
ly:grob?	graphical (layout) object
ly:grob-array?	array of grobs
ly:grob-properties?	grob properties
ly:input-location?	input location
ly:item?	item
ly:iterator?	iterator
ly:lily-lexer?	lily-lexer
ly:lily-parser?	lily-parser
ly:listener?	listener
ly:moment?	moment
ly:music?	music
ly:music-function?	music function
ly:music-list?	list of music objects
ly:music-output?	music output
ly:note-scale?	note scale
ly:otf-font?	OpenType font
ly:output-def?	output definition
ly:page-marker?	page marker
ly:pango-font?	Pango font
ly:paper-book?	paper book
ly:paper-system?	paper-system Prob
ly:pitch?	pitch
ly:prob?	property object
ly:score?	score
ly:skyline?	skyline
ly:source-file?	source file
ly:spanner?	spanner
ly:spring?	spring
ly:stencil?	stencil
ly:stream-event?	stream event
ly:transform?	coordinate transform
ly:translator?	translator
ly:translator-group?	translator group
ly:unpure-pure-container?	unpure/pure container

Appendix C Cheat sheet

Syntax	Description	Example
<code>1 2 8 16</code>	durations	
<code>c4. c4..</code>	augmentation dots	
<code>c d e f g a b</code>	scale	
<code>f# b</code>	alteration	
<code>\clef treble \clef bass</code>	clefs	
<code>\time 3/4 \time 4/4</code>	time signature	
<code>r4 r8</code>	rest	
<code>d ~ d</code>	tie	
<code>\key es \major</code>	key signature	
<code>note'</code>	raise octave	
<code>note,</code>	lower octave	

`c( d e)`

slur

`c\ ( c( d) e\ )`

phrasing slur

`a8[ b]`

beam

`<< \new Staff ... >>`

more staves

`c-> c-.`

articulations

`c2\mf c\s fz`

dynamics

`a\< a a\!`

crescendo

`a\> a a\!`

decrescendo

`< >`

chord

`\partial 8`

pickup / upbeat

`\tuplet 3/2 {f g a}`

triplets

`\grace`

grace notes



`\lyricmode { twinkle }`

entering lyrics

twinkle


`\new Lyrics`

printing lyrics

twinkle

`twin -- kle`

lyric hyphen

`\chordmode { c:dim f:maj7 }`

chords

`\new ChordNames`

printing chord names

C[°] F^Δ`<<{e f} \ \ {c d}>>`

polyphony

`s4 s8 s16`

spacer rests

Appendix D GNU Free Documentation License

Version 1.3, 3 November 2008

Copyright © 2000, 2001, 2002, 2007, 2008 Free Software Foundation, Inc.
<https://fsf.org/>

Everyone is permitted to copy and distribute verbatim copies of this license document, but changing it is not allowed.

0. PREAMBLE

The purpose of this License is to make a manual, textbook, or other functional and useful document *free* in the sense of freedom: to assure everyone the effective freedom to copy and redistribute it, with or without modifying it, either commercially or noncommercially. Secondly, this License preserves for the author and publisher a way to get credit for their work, while not being considered responsible for modifications made by others.

This License is a kind of “copyleft”, which means that derivative works of the document must themselves be free in the same sense. It complements the GNU General Public License, which is a copyleft license designed for free software.

We have designed this License in order to use it for manuals for free software, because free software needs free documentation: a free program should come with manuals providing the same freedoms that the software does. But this License is not limited to software manuals; it can be used for any textual work, regardless of subject matter or whether it is published as a printed book. We recommend this License principally for works whose purpose is instruction or reference.

1. APPLICABILITY AND DEFINITIONS

This License applies to any manual or other work, in any medium, that contains a notice placed by the copyright holder saying it can be distributed under the terms of this License. Such a notice grants a world-wide, royalty-free license, unlimited in duration, to use that work under the conditions stated herein. The “Document”, below, refers to any such manual or work. Any member of the public is a licensee, and is addressed as “you”. You accept the license if you copy, modify or distribute the work in a way requiring permission under copyright law.

A “Modified Version” of the Document means any work containing the Document or a portion of it, either copied verbatim, or with modifications and/or translated into another language.

A “Secondary Section” is a named appendix or a front-matter section of the Document that deals exclusively with the relationship of the publishers or authors of the Document to the Document’s overall subject (or to related matters) and contains nothing that could fall directly within that overall subject. (Thus, if the Document is in part a textbook of mathematics, a Secondary Section may not explain any mathematics.) The relationship could be a matter of historical connection with the subject or with related matters, or of legal, commercial, philosophical, ethical or political position regarding them.

The “Invariant Sections” are certain Secondary Sections whose titles are designated, as being those of Invariant Sections, in the notice that says that the Document is released under this License. If a section does not fit the above definition of Secondary then it is not allowed to be designated as Invariant. The Document may contain zero Invariant Sections. If the Document does not identify any Invariant Sections then there are none.

The “Cover Texts” are certain short passages of text that are listed, as Front-Cover Texts or Back-Cover Texts, in the notice that says that the Document is released under this License. A Front-Cover Text may be at most 5 words, and a Back-Cover Text may be at most 25 words.

A “Transparent” copy of the Document means a machine-readable copy, represented in a format whose specification is available to the general public, that is suitable for revising the document straightforwardly with generic text editors or (for images composed of pixels) generic paint programs or (for drawings) some widely available drawing editor, and that is suitable for input to text formatters or for automatic translation to a variety of formats suitable for input to text formatters. A copy made in an otherwise Transparent file format whose markup, or absence of markup, has been arranged to thwart or discourage subsequent modification by readers is not Transparent. An image format is not Transparent if used for any substantial amount of text. A copy that is not “Transparent” is called “Opaque”.

Examples of suitable formats for Transparent copies include plain ASCII without markup, Texinfo input format, LaTeX input format, SGML or XML using a publicly available DTD, and standard-conforming simple HTML, PostScript or PDF designed for human modification. Examples of transparent image formats include PNG, XCF and JPG. Opaque formats include proprietary formats that can be read and edited only by proprietary word processors, SGML or XML for which the DTD and/or processing tools are not generally available, and the machine-generated HTML, PostScript or PDF produced by some word processors for output purposes only.

The “Title Page” means, for a printed book, the title page itself, plus such following pages as are needed to hold, legibly, the material this License requires to appear in the title page. For works in formats which do not have any title page as such, “Title Page” means the text near the most prominent appearance of the work’s title, preceding the beginning of the body of the text.

The “publisher” means any person or entity that distributes copies of the Document to the public.

A section “Entitled XYZ” means a named subunit of the Document whose title either is precisely XYZ or contains XYZ in parentheses following text that translates XYZ in another language. (Here XYZ stands for a specific section name mentioned below, such as “Acknowledgements”, “Dedications”, “Endorsements”, or “History”.) To “Preserve the Title” of such a section when you modify the Document means that it remains a section “Entitled XYZ” according to this definition.

The Document may include Warranty Disclaimers next to the notice which states that this License applies to the Document. These Warranty Disclaimers are considered to be included by reference in this License, but only as regards disclaiming warranties: any other implication that these Warranty Disclaimers may have is void and has no effect on the meaning of this License.

2. VERBATIM COPYING

You may copy and distribute the Document in any medium, either commercially or noncommercially, provided that this License, the copyright notices, and the license notice saying this License applies to the Document are reproduced in all copies, and that you add no other conditions whatsoever to those of this License. You may not use technical measures to obstruct or control the reading or further copying of the copies you make or distribute. However, you may accept compensation in exchange for copies. If you distribute a large enough number of copies you must also follow the conditions in section 3.

You may also lend copies, under the same conditions stated above, and you may publicly display copies.

3. COPYING IN QUANTITY

If you publish printed copies (or copies in media that commonly have printed covers) of the Document, numbering more than 100, and the Document’s license notice requires Cover Texts, you must enclose the copies in covers that carry, clearly and legibly, all these Cover Texts: Front-Cover Texts on the front cover, and Back-Cover Texts on the back cover. Both

covers must also clearly and legibly identify you as the publisher of these copies. The front cover must present the full title with all words of the title equally prominent and visible. You may add other material on the covers in addition. Copying with changes limited to the covers, as long as they preserve the title of the Document and satisfy these conditions, can be treated as verbatim copying in other respects.

If the required texts for either cover are too voluminous to fit legibly, you should put the first ones listed (as many as fit reasonably) on the actual cover, and continue the rest onto adjacent pages.

If you publish or distribute Opaque copies of the Document numbering more than 100, you must either include a machine-readable Transparent copy along with each Opaque copy, or state in or with each Opaque copy a computer-network location from which the general network-using public has access to download using public-standard network protocols a complete Transparent copy of the Document, free of added material. If you use the latter option, you must take reasonably prudent steps, when you begin distribution of Opaque copies in quantity, to ensure that this Transparent copy will remain thus accessible at the stated location until at least one year after the last time you distribute an Opaque copy (directly or through your agents or retailers) of that edition to the public.

It is requested, but not required, that you contact the authors of the Document well before redistributing any large number of copies, to give them a chance to provide you with an updated version of the Document.

4. MODIFICATIONS

You may copy and distribute a Modified Version of the Document under the conditions of sections 2 and 3 above, provided that you release the Modified Version under precisely this License, with the Modified Version filling the role of the Document, thus licensing distribution and modification of the Modified Version to whoever possesses a copy of it. In addition, you must do these things in the Modified Version:

- A. Use in the Title Page (and on the covers, if any) a title distinct from that of the Document, and from those of previous versions (which should, if there were any, be listed in the History section of the Document). You may use the same title as a previous version if the original publisher of that version gives permission.
- B. List on the Title Page, as authors, one or more persons or entities responsible for authorship of the modifications in the Modified Version, together with at least five of the principal authors of the Document (all of its principal authors, if it has fewer than five), unless they release you from this requirement.
- C. State on the Title page the name of the publisher of the Modified Version, as the publisher.
- D. Preserve all the copyright notices of the Document.
- E. Add an appropriate copyright notice for your modifications adjacent to the other copyright notices.
- F. Include, immediately after the copyright notices, a license notice giving the public permission to use the Modified Version under the terms of this License, in the form shown in the Addendum below.
- G. Preserve in that license notice the full lists of Invariant Sections and required Cover Texts given in the Document's license notice.
- H. Include an unaltered copy of this License.
- I. Preserve the section Entitled "History", Preserve its Title, and add to it an item stating at least the title, year, new authors, and publisher of the Modified Version as given on the Title Page. If there is no section Entitled "History" in the Document, create one stating the title, year, authors, and publisher of the Document as given on its

Title Page, then add an item describing the Modified Version as stated in the previous sentence.

- J. Preserve the network location, if any, given in the Document for public access to a Transparent copy of the Document, and likewise the network locations given in the Document for previous versions it was based on. These may be placed in the “History” section. You may omit a network location for a work that was published at least four years before the Document itself, or if the original publisher of the version it refers to gives permission.
- K. For any section Entitled “Acknowledgements” or “Dedications”, Preserve the Title of the section, and preserve in the section all the substance and tone of each of the contributor acknowledgements and/or dedications given therein.
- L. Preserve all the Invariant Sections of the Document, unaltered in their text and in their titles. Section numbers or the equivalent are not considered part of the section titles.
- M. Delete any section Entitled “Endorsements”. Such a section may not be included in the Modified Version.
- N. Do not retitle any existing section to be Entitled “Endorsements” or to conflict in title with any Invariant Section.
- O. Preserve any Warranty Disclaimers.

If the Modified Version includes new front-matter sections or appendices that qualify as Secondary Sections and contain no material copied from the Document, you may at your option designate some or all of these sections as invariant. To do this, add their titles to the list of Invariant Sections in the Modified Version’s license notice. These titles must be distinct from any other section titles.

You may add a section Entitled “Endorsements”, provided it contains nothing but endorsements of your Modified Version by various parties—for example, statements of peer review or that the text has been approved by an organization as the authoritative definition of a standard.

You may add a passage of up to five words as a Front-Cover Text, and a passage of up to 25 words as a Back-Cover Text, to the end of the list of Cover Texts in the Modified Version. Only one passage of Front-Cover Text and one of Back-Cover Text may be added by (or through arrangements made by) any one entity. If the Document already includes a cover text for the same cover, previously added by you or by arrangement made by the same entity you are acting on behalf of, you may not add another; but you may replace the old one, on explicit permission from the previous publisher that added the old one.

The author(s) and publisher(s) of the Document do not by this License give permission to use their names for publicity for or to assert or imply endorsement of any Modified Version.

5. COMBINING DOCUMENTS

You may combine the Document with other documents released under this License, under the terms defined in section 4 above for modified versions, provided that you include in the combination all of the Invariant Sections of all of the original documents, unmodified, and list them all as Invariant Sections of your combined work in its license notice, and that you preserve all their Warranty Disclaimers.

The combined work need only contain one copy of this License, and multiple identical Invariant Sections may be replaced with a single copy. If there are multiple Invariant Sections with the same name but different contents, make the title of each such section unique by adding at the end of it, in parentheses, the name of the original author or publisher of that section if known, or else a unique number. Make the same adjustment to the section titles in the list of Invariant Sections in the license notice of the combined work.

In the combination, you must combine any sections Entitled “History” in the various original documents, forming one section Entitled “History”; likewise combine any sections Entitled “Acknowledgements”, and any sections Entitled “Dedications”. You must delete all sections Entitled “Endorsements.”

6. COLLECTIONS OF DOCUMENTS

You may make a collection consisting of the Document and other documents released under this License, and replace the individual copies of this License in the various documents with a single copy that is included in the collection, provided that you follow the rules of this License for verbatim copying of each of the documents in all other respects.

You may extract a single document from such a collection, and distribute it individually under this License, provided you insert a copy of this License into the extracted document, and follow this License in all other respects regarding verbatim copying of that document.

7. AGGREGATION WITH INDEPENDENT WORKS

A compilation of the Document or its derivatives with other separate and independent documents or works, in or on a volume of a storage or distribution medium, is called an “aggregate” if the copyright resulting from the compilation is not used to limit the legal rights of the compilation’s users beyond what the individual works permit. When the Document is included in an aggregate, this License does not apply to the other works in the aggregate which are not themselves derivative works of the Document.

If the Cover Text requirement of section 3 is applicable to these copies of the Document, then if the Document is less than one half of the entire aggregate, the Document’s Cover Texts may be placed on covers that bracket the Document within the aggregate, or the electronic equivalent of covers if the Document is in electronic form. Otherwise they must appear on printed covers that bracket the whole aggregate.

8. TRANSLATION

Translation is considered a kind of modification, so you may distribute translations of the Document under the terms of section 4. Replacing Invariant Sections with translations requires special permission from their copyright holders, but you may include translations of some or all Invariant Sections in addition to the original versions of these Invariant Sections. You may include a translation of this License, and all the license notices in the Document, and any Warranty Disclaimers, provided that you also include the original English version of this License and the original versions of those notices and disclaimers. In case of a disagreement between the translation and the original version of this License or a notice or disclaimer, the original version will prevail.

If a section in the Document is Entitled “Acknowledgements”, “Dedications”, or “History”, the requirement (section 4) to Preserve its Title (section 1) will typically require changing the actual title.

9. TERMINATION

You may not copy, modify, sublicense, or distribute the Document except as expressly provided under this License. Any attempt otherwise to copy, modify, sublicense, or distribute it is void, and will automatically terminate your rights under this License.

However, if you cease all violation of this License, then your license from a particular copyright holder is reinstated (a) provisionally, unless and until the copyright holder explicitly and finally terminates your license, and (b) permanently, if the copyright holder fails to notify you of the violation by some reasonable means prior to 60 days after the cessation.

Moreover, your license from a particular copyright holder is reinstated permanently if the copyright holder notifies you of the violation by some reasonable means, this is the first time you have received notice of violation of this License (for any work) from that copyright holder, and you cure the violation prior to 30 days after your receipt of the notice.

Termination of your rights under this section does not terminate the licenses of parties who have received copies or rights from you under this License. If your rights have been terminated and not permanently reinstated, receipt of a copy of some or all of the same material does not give you any rights to use it.

10. FUTURE REVISIONS OF THIS LICENSE

The Free Software Foundation may publish new, revised versions of the GNU Free Documentation License from time to time. Such new versions will be similar in spirit to the present version, but may differ in detail to address new problems or concerns. See <https://www.gnu.org/licenses/>.

Each version of the License is given a distinguishing version number. If the Document specifies that a particular numbered version of this License “or any later version” applies to it, you have the option of following the terms and conditions either of that specified version or of any later version that has been published (not as a draft) by the Free Software Foundation. If the Document does not specify a version number of this License, you may choose any version ever published (not as a draft) by the Free Software Foundation. If the Document specifies that a proxy can decide which future versions of this License can be used, that proxy’s public statement of acceptance of a version permanently authorizes you to choose that version for the Document.

11. RELICENSING

“Massive Multiauthor Collaboration Site” (or “MMC Site”) means any World Wide Web server that publishes copyrightable works and also provides prominent facilities for anybody to edit those works. A public wiki that anybody can edit is an example of such a server. A “Massive Multiauthor Collaboration” (or “MMC”) contained in the site means any set of copyrightable works thus published on the MMC site.

“CC-BY-SA” means the Creative Commons Attribution-Share Alike 3.0 license published by Creative Commons Corporation, a not-for-profit corporation with a principal place of business in San Francisco, California, as well as future copyleft versions of that license published by that same organization.

“Incorporate” means to publish or republish a Document, in whole or in part, as part of another Document.

An MMC is “eligible for relicensing” if it is licensed under this License, and if all works that were first published under this License somewhere other than this MMC, and subsequently incorporated in whole or in part into the MMC, (1) had no cover texts or invariant sections, and (2) were thus incorporated prior to November 1, 2008.

The operator of an MMC Site may republish an MMC contained in the site under CC-BY-SA on the same site at any time before August 1, 2009, provided the MMC is eligible for relicensing.

ADDENDUM: How to use this License for your documents

To use this License in a document you have written, include a copy of the License in the document and put the following copyright and license notices just after the title page:

```
Copyright (C)  year  your name.
Permission is granted to copy, distribute and/or modify this document
under the terms of the GNU Free Documentation License, Version 1.3
or any later version published by the Free Software Foundation;
with no Invariant Sections, no Front-Cover Texts, and no Back-Cover
Texts.  A copy of the license is included in the section entitled ``GNU
Free Documentation License''.
```

If you have Invariant Sections, Front-Cover Texts and Back-Cover Texts, replace the “with...Texts.” line with this:

```
with the Invariant Sections being list their titles, with
the Front-Cover Texts being list, and with the Back-Cover Texts
being list.
```

If you have Invariant Sections without Cover Texts, or some other combination of the three, merge those two alternatives to suit the situation.

If your document contains nontrivial examples of program code, we recommend releasing these examples in parallel under your choice of free software license, such as the GNU General Public License, to permit their use in free software.

Appendix E Index

In addition to all the LilyPond commands and keywords, this index lists musical terms and words that relate to each of them, with links to those sections of the manual that describe or discuss that topic.

!		—	
!	8, 528	-	155, 528, 772
\!	159, 529	\-	534
"		-!	927
" "	140	-+	928
#		--	357, 927
#f (false)	972	-	927
#t (true)	972	->	927
%		-^	927
%	590, 596	-_	927
\%	208, 962	.	
%{ ... %}	590, 596		53
,		/	
'	3	/	61, 511, 528
(		/+	511
(.....	170	:	
\(.....	173	:	212, 508
)		<	
)	170	<	215
\)	173	\<	159
*		<...>	215
*	61	<<	219
*	188, 962	<< ... \ \ ... >>	223
+		<< ... >>	219
+	528	<>	161, 216, 414
\+	528	=	
,		=	12
, ...	3	\=	170, 962
—		>	
-	155, 528, 772	>	215
\-	534	\>	159
-!	927	>>	219
-+	928	?	
--	357, 927	?	8
-	927	[	
->	927	[.....	114
-^	927	\[.....	539
-_	927		

- \ 223, 528
 \\ 223, 528
] 114
 \] 539
 ^ 510, 772
 ^ 440
 - 353, 772
 -- 357
 | 140
 ~ 63, 353, 962
 \~ 557, 562
1
 15ma 26
 15mb 26
8
 8va 26
 8vb 26
A
 a due part 232
 \abs-fontsize 323, 807
 \abs-hspace 820
 \abs-vspace 820
 absolute 3
 \absolute 942
 absolute dynamics 159
 absolute octave entry 3
 absolute octave specification 3
 \accent 155, 927
 ‘accent’ articulation 155, 927
 \accentus 556, 929
 ‘accentus’ Gregorian articulation 556, 929
 \accepts 749, 750, 753
 acciaccatura 147
 \acciaccatura 147, 942
 acciaccatura, multi-note 151
 accidental 8, 31
 \accidental 849
 accidental glyph set 920
 accidental style 31
 accidental style, choral 35
 accidental style, choral-cautionary 35
 accidental style, default 31, 33
 accidental style, dodecaphonic 36
 accidental style, dodecaphonic-first 37
 accidental style, dodecaphonic-no-repeat 37
 accidental style, forget 37
 accidental style, modern 33, 34
 accidental style, modern-cautionary 33, 34
 accidental style, modern-voice-cautionary 34
 accidental style, neo-modern 35
 accidental style, neo-modern-cautionary 36
 accidental style, neo-modern-voice 36
 accidental style, neo-modern-voice-cautionary 36
 accidental style, no-reset 37
 accidental style, piano 35
 accidental style, piano-cautionary 35
 accidental style, teaching 37
 accidental style, voice 33
 accidental, alternate glyphs 39
 accidental, and simultaneous notes 38
 accidental, automatic 31
 accidental, cautionary 8
 accidental, Gregorian 555
 accidental, hiding, on tied notes at start of system 9
 accidental, in cadenzas 91
 accidental, in chords 38
 accidental, in unmetered music 91
 accidental, Kievan 564
 accidental, mensural 545
 accidental, multi-voice 34
 accidental, musica ficta 546
 accidental, on tied note 8
 accidental, parenthesized 8
 accidental, quarter tone 10
 accidental, reminder 8
 \accidentalStyle 31, 942
 AccidentalSuggestion 158
 accordion 424
 accordion discant symbol 424
 accordion register symbol 424
 accordion shift symbol 424
 acoustic bass 930
 acoustic snare 930
 add-grace-property 149
 add-stem-support 283
 add-toc-item! 623
 \addChordShape 470, 942
 adding custom fret diagram 469
 adding white background, to text 882
 \addInstrumentDefinition 942
 addition, in chords 510
 additional voices in polyphonic music 229
 additionalPitchPrefix 516
 additive time signature 80
 \addlyrics 347, 349, 350
 \addQuote 265, 942
 \addToTagGroup 633, 942
 adjusting start and end, slur 171
 Aeolian 24
 \aeolian 24
 \after 160, 209, 942
 \afterGrace 148, 942
 afterGraceFraction 940
 agogo 930
 Aiken shape note head 46
 Aiken shape note head, thin variant 48
 \aikenHeads 46

- \aikenHeadsMinor..... 47
- \aikenThinHeads..... 46
- \aikenThinHeadsMinor..... 47
- al coda..... 196
- al fine..... 195
- al niente, hairpin..... 164
- \alias..... 749, 750
- align to object..... 795
- \align-on-other..... 820
- alignAboveContext..... 255, 360, 754
- alignBelowContext..... 255, 360, 369, 754
- aligning markup..... 326
- aligning markup text..... 326
- aligning objects..... 789
- aligning text..... 326
- aligning to cadenza..... 152
- alignment point..... 790
- alignment, bar numbers..... 138
- alignment, breaking vertical, dynamics..... 166
- alignment, breaking vertical, text scripts..... 166
- alignment, horizontal, lyrics..... 364
- alignment, horizontal, melisma..... 365
- alignment, text, commands..... 331
- alignment, vertical, dynamics..... 165
- alignment, vertical, text..... 327
- alignment, vertical, text scripts..... 165
- alist..... 939
- alla breve..... 80, 81
- alla coda..... 196
- \allowBreak..... 120, 687
- \allowPageTurn..... 694, 943
- \allowVoltaHook..... 943
- alpha transparency..... 289
- alteration, figured bass, glyphs..... 529
- alteration, figured bass, position..... 529
- \alterBroken..... 775, 943
- altered chord..... 509
- alternate accidental glyph..... 39
- alternate fretboard table..... 475
- alternating time signature..... 80
- \alternative..... 190, 192
- alternative chord name..... 515
- alternative ending..... 190
- alternative ending, and lyrics..... 370
- alternative ending, with ties..... 64
- alternative melody, switching to..... 384
- alternative style, of breve notes..... 54
- alto clef..... 19, 921
- alto varC clef..... 921
- ‘Amazing Grace’, bagpipe example..... 498
- ambitus..... 40
- ambitus, line gap..... 42
- ambitus, multiple voices..... 41
- ambitus, per voice..... 41
- ambitus, placement..... 43
- ambitusAfter..... 43, 943
- AmbitusLine..... 42
- anacrusis..... 90
- anacrusis, in a repeat..... 190
- analysis bracket, musicological..... 303
- analysis bracket, with label..... 304
- ancient clef..... 19
- ancient music clef..... 542, 923
- angled hairpin..... 789
- annotate moving by spacing, in text..... 872
- \annotate-moving..... 872
- annotate-spacing..... 727, 963
- anthem..... 389
- \append-to-tag..... 636, 873
- \appendToTag..... 634, 943
- \appendToTagMarkup..... 636, 943
- \applyContext..... 740, 943
- \applyMusic..... 943
- \applyOutput..... 943
- \applySwing..... 663
- \applySwingWithOffset..... 663
- appoggiatura..... 147
- \appoggiatura..... 147, 943
- approximate pitch..... 10
- \approximatePitch..... 10, 943
- Arabic improvisation..... 579
- Arabic key signatures..... 576
- Arabic maqam..... 574
- Arabic music..... 574
- Arabic music example..... 579
- Arabic music template..... 579
- Arabic note name..... 575
- Arabic semi-flat symbol..... 576
- Arabic time signatures..... 578
- \arabicStringNumbers..... 432
- arpeggio..... 181
- \arpeggio..... 181
- arpeggio symbol, special..... 182
- arpeggio, and ties..... 65
- arpeggio, cross-staff parenthesis-style..... 185
- arpeggio, cross-voice..... 184
- arpeggio-direction..... 181
- \arpeggioArrowDown..... 181, 943
- \arpeggioArrowUp..... 181, 943
- \arpeggioBracket..... 182, 943
- \arpeggioNormal..... 181, 943
- \arpeggioParenthesis..... 182, 944
- \arpeggioParenthesisDashed..... 182, 944
- arranger..... 600
- Arrastre..... 286
- \arrow-head..... 332, 838
- \articulate..... 662
- articulate.ly script..... 662
- articulation..... 927
- articulation, accent..... 155, 927
- articulation, bachschleifer..... 155
- articulation, default values, modifying..... 157
- articulation, espressivo..... 155, 927
- articulation, Gregorian..... 556
- articulation, Gregorian, accentus..... 556, 929
- articulation, Gregorian, circulus..... 556, 929
- articulation, Gregorian, episem finis..... 556
- articulation, Gregorian, episem initium..... 556
- articulation, Gregorian, ictus..... 556, 929
- articulation, Gregorian, semicirculus..... 556, 929
- articulation, half-open..... 155, 928
- articulation, marcato..... 155, 927
- articulation, open..... 155, 496, 928
- articulation, portato..... 155, 927
- articulation, staccatissimo..... 155, 927
- articulation, staccato..... 155, 927
- articulation, stopped..... 155, 496, 928
- articulation, tenuto..... 155, 927
- articulation-event..... 267
- artificial harmonics..... 429

`\ascendens` 557, 562
`\assertBeamQuant` 944
`\assertBeamSlope` 944
`associatedVoice` 347, 349, 384
`association list` 939
`\atLeft` 156, 944
`\atRight` 156, 944
`\auctum` 557, 562
`aug` 508
`augmentation dot, changing number` 54
`\augmentum` 562, 944
`auto-beaming, properties for time signatures` 81
`auto-first-page-number` 678, 963
`\auto-footnote` 873
`autoBeaming` 104, 734
`\autoBeamOff` 101, 420
`\autoBeamOn` 101
`\autoBreaksOff` 689
`\autoBreaksOn` 689
`\autoChange` 416, 944
`\autoChange, and relative music` 417
`\autoLineBreaksOff` 689
`\autoLineBreaksOn` 689
`automatic accidental` 31
`automatic bar line` 130
`automatic chord diagram` 477
`automatic fret diagram` 477
`automatic part combining` 232
`automatic replacement, of strings` 646
`automatic staff change` 416
`\autoPageBreaksOff` 691
`\autoPageBreaksOn` 691

B

`Bézier curve, control points` 799
`bachschleifer` 156
`\bachschleifer` 155
`'bachschleifer' articulation` 155
`backslashed digit` 873
`\backslashed-digit` 873
`bagpipe` 498
`bagpipe, example` 498
`balance, in MIDI` 661
`balloon` 299
`balloon help` 299
`Balloon_engraver` 299
`\balloonGrobText` 299, 944
`\balloonLengthOff` 299
`\balloonLengthOn` 299
`\balloonText` 299, 944
`banjo tablature` 431, 484
`banjo tuning` 485
`banjo-c-tuning` 485
`banjo-double-c-tuning` 485
`banjo-double-d-tuning` 485
`banjo-modal-tuning` 485
`banjo-open-d-tuning` 485
`banjo-open-dm-tuning` 485
`banjo-open-g-tuning` 485
`\bar` 120, 129, 944
`bar check, with repeats` 190
`bar line` 120
`bar line, automatic` 130

`bar line, avoided by lyrics` 366
`bar line, between staves` 125, 246
`bar line, cadenzas` 91
`bar line, caesura` 130, 131
`bar line, default` 131
`bar line, default, changing` 129
`bar line, defining` 125
`bar line, dotted` 130
`bar line, double` 120, 130, 131, 146
`bar line, final` 120, 131, 146
`bar line, for repeat at start of piece` 189
`bar line, hairpin, stopping at` 163
`bar line, in ChordNames` 519
`bar line, in Gregorian chant` 555
`bar line, in hymns` 409
`bar line, in Kievan chant` 565
`bar line, in markup` 849
`bar line, invisible` 120
`bar line, list` 932
`bar line, manual` 120
`bar line, measure` 131
`bar line, phrase` 130, 131
`bar line, repeat` 131
`bar line, section` 131, 146
`bar line, segno` 122, 131, 198
`bar line, short` 121
`bar line, single` 131
`bar line, submeasure` 130
`bar line, symbols on` 313
`bar line, text over` 313
`bar line, tick` 121
`bar line, underlying repeat` 130
`bar line, unmetered music` 91
`bar number` 78, 132
`bar number, alignment` 138
`bar number, alternative, in repeat` 202
`bar number, broken measure` 134
`bar number, cadenzas` 91
`bar number, centered` 139
`bar number, check` 140
`bar number, collision` 140
`bar number, modulo bar number` 135
`bar number, printed at regular intervals` 133
`bar number, printed in first measure` 133
`bar number, regular spacing` 132
`bar number, removal` 138
`bar number, style` 135
`bar number, unmetered music` 91
`bar number, with letter, in repeat` 202
`bar, check` 140
`\bar-line` 849
`baritone clef` 19, 921
`baritone varC clef` 921
`baritone varF clef` 921
`BarNumber` 132
`\barNumberCheck` 141, 944
`barNumberVisibility` 132
`barré indication` 456
`barré line` 481
`Bartók pizzicato` 429
`bartype` 129
`base-shortest-duration` 711
`bass` 930
`bass clef` 19, 921
`bass note, for chords` 511

- bass, figured..... 525
- bass, thorough..... 525
- \bassFigureExtendersOff..... 528
- \bassFigureExtendersOn..... 528
- \bassFigureStaffAlignmentDown..... 531
- \bassFigureStaffAlignmentNeutral..... 531
- \bassFigureStaffAlignmentUp..... 531
- basso continuo..... 525
- \beam..... 838
- beam, cadenzas..... 91
- beam, cross-staff..... 414
- beam, customizing rules..... 101
- beam, endings, in a score..... 111
- beam, endings, with multiple voices..... 111
- beam, feathered..... 118
- beam, horizontal..... 444
- beam, in tablature..... 444
- beam, line breaks..... 102
- beam, manual..... 101, 114
- beam, nibs..... 116
- beam, \partCombine with \autoBeamOff..... 103
- beam, slashed..... 119
- beam, subdividing..... 109
- beam, unmetered music..... 91
- beam, with knee gap, changing..... 103
- beam, with lyrics..... 104
- beam, with melisma..... 102
- beam, with polymetric meters..... 94
- beam-like flags..... 117
- \beamBreak..... 114
- beamed tuplet, line break within..... 60
- beamExceptions..... 81, 104, 944
- beaming, strict-beat..... 110
- beaming, time signature default properties..... 81
- beamlet, orientation..... 110
- beat repeat..... 208
- beat, grouping..... 110
- beatBase..... 81, 104, 109
- beats per minute..... 86
- beatStructure..... 81, 104, 109
- beginners' music..... 45
- \bendAfter..... 176, 944
- \bendHold..... 440, 944
- bending, string, in tablature..... 440
- \bendStartLevel..... 440, 945
- big point (bp)..... 773
- binding gutter..... 676
- binding-offset..... 676, 963
- bisbigliando..... 425
- bison program..... 940
- bitmap fonts..... 337
- black mensural clef..... 542, 923
- \blackTriangleMarkup..... 516
- blank-after-score-page-penalty..... 678, 963
- blank-last-page-penalty..... 678, 963
- blank-page-penalty..... 678, 963
- block chord..... 183
- block comment..... 590, 596
- blot-diameter..... 964
- BNF..... 940
- \bold..... 323, 807
- bongo..... 930
- \book..... 591, 594
- \book, and \layout..... 593
- \book, and variables..... 592
- book-title..... 964
- book-title-properties..... 964
- bookmarks..... 620, 622
- \bookOutputName..... 945
- \bookOutputSuffix..... 945
- \bookpart..... 592, 594, 691
- \bookpart, and \layout..... 593
- \bookpart, and variables..... 592
- bookpart-level-page-numbering..... 679, 964
- bookTitleMarkup..... 605, 964
- Bottom..... 737
- bottom-margin..... 672, 964
- bounding box..... 774
- bounding box, of glyph..... 883
- bowing indication..... 428
- bowing, down..... 155, 928
- bowing, up..... 155, 928
- \box..... 331, 807
- \bp..... 773, 964
- brace, at start of single staff..... 245
- brace, in markup..... 876
- brace, nested..... 247
- brace, vertical..... 243
- bracket..... 295, 303
- \bracket..... 168, 331, 838
- bracket, angle..... 215
- bracket, at start of single staff..... 245
- bracket, cross-staff..... 420
- bracket, horizontal..... 303
- bracket, nested..... 247
- bracket, non-arpeggiato..... 183
- bracket, phrasing..... 303
- bracket, phrasing, with label..... 304
- bracket, square, at start of staff group..... 245
- bracket, vertical..... 243
- bracket, vertical, marking divided voices..... 391
- bracket, volta..... 204
- \break..... 687
- break, in unmetered music..... 93
- break-align symbol..... 716
- break-align-orders..... 717
- break-align-symbol..... 795, 938
- break-align-symbols..... 795
- break-alignable-interface..... 795
- break-aligned-interface..... 795
- break-visibility..... 784
- breakable..... 102
- breakable glissando..... 179
- \breakAlignInsert..... 945
- breakbefore..... 602
- \breakDynamicSpan..... 166
- breaking lines..... 687
- breaking pages..... 720
- breaking vertical alignment of dynamics..... 166
- breath mark..... 175
- breath mark symbol, changing..... 175
- breath mark symbol, list..... 929
- \breathe..... 175, 945
- \breve..... 52, 67
- breve note, alternative style..... 54
- breve rest..... 67
- broken chord..... 181
- broken spanner, modifying..... 774

C

- C clef 19, 921
- cabasa 930
- cadenza 91, 152
- cadenza, accidentals 91
- cadenza, aligning to 152
- cadenza, bar lines 91
- cadenza, bar numbers 91
- cadenza, beams 91
- cadenza, line breaks 93
- cadenza, page breaks 93
- \cadenzaOff 91, 945
- \cadenzaOn 91, 945
- caesura 76
- \caesura 76, 77, 130, 131, 409, 556, 565, 945
- caesura bar line 130, 131
- caesura bar line, in hymns 409
- caesura bar line, in Kievan chant 565
- callback 939
- canticle 400, 405
- capo 461
- \caps 808
- cautionary accidental 8
- \cavum 557, 562
- \center-align 326, 821
- \center-column 329, 821
- CENTER 792, 794
- centered dynamics in piano music 414
- centering column of text 821
- centering text on page 330
- centimeter (cm) 773
- CFF2, font format 336
- \change 414
- changing breath mark symbol 175
- changing chord separator 520
- changing direction of text column 822
- changing font 323
- changing instrument name 263
- changing number of augmentation dots 54
- changing properties 758, 764
- changing staff automatically 416
- changing staff manually 414
- changing tempo without metronome mark 89
- changing tuplet number 57
- chant 400, 405
- \char 874
- character name 393
- chart, fingering 496
- check mark 175
- check-consistency 675, 964
- Chinese cymbal 930
- choir staff 243
- ChoirStaff 735
- choral 35
- 'choral' accidental style 35
- choral tenor clef 20
- choral-cautionary 35
- 'choral-cautionary' accidental style 35
- chord 215, 507, 512
- chord bracket 183
- chord bracket, cross-staff 420
- chord diagram 455, 466
- chord diagram, automatic 477
- chord grid 521
- chord mode 507
- chord name 507, 512
- chord name, exceptions 518
- chord name, with fret diagrams 467
- chord separator, changing 520
- chord shape, for fretted instrument 470
- chord slur 183
- chord step, altering 510
- chord, accidentals in 38
- chord, alternative name 515
- chord, and relative octave entry 7
- chord, and tie 63
- chord, block 183
- chord, broken 181
- chord, cross-staff 420
- chord, empty 150, 161, 216, 414
- chord, fingering 282
- chord, glissando, in tablatures 449
- chord, inversion 512
- chord, jazz 515
- chord, major 7, layout 519
- chord, modifying a single note 763
- chord, power 483
- chord, quality 508
- chord, relative pitch 216
- chord, repetition 217, 435
- chord, rolled 183
- chord, rotating 512
- chord, splitting across staves with \autoChange .. 418
- chord, suppressing repeated 474, 514
- chord, voicing 512
- chord, volta repeat, below 519
- chordChanges 474, 514
- ChordGrid 521, 736
- ChordGridScore 735
- \chordmode 6, 16, 467, 587
- chordNameExceptions 517, 518
- chordNameLowercaseMinor 516
- ChordNames 467, 737
- ChordNames, with bar lines 519
- chordNameSeparator 517, 520
- chordNoteNamer 517
- chordPrefixSpacer 518
- \chordRepeats 435, 945
- chordRootNamer 516
- \chords 514, 587
- \chordSlur 183
- chorus level, in MIDI 661
- Christian Harmony note head 46
- church mode 24
- church rest 275
- \circle 331, 839
- circling text 839
- \circulus 556, 929
- 'circulus' Gregorian articulation 556, 929
- claves 930
- clef 8, 19, 554, 564
- \clef 19, 945
- clef, alto 19, 921
- clef, alto varC 921
- clef, ancient 19
- clef, ancient music 542, 923
- clef, baritone 19
- clef, baritone varC 921
- clef, baritone varF 921

- clef, bass 19, 921
- clef, black mensural 542, 923
- clef, C 19, 921
- clef, F 19, 921
- clef, french 19, 921
- clef, G 19, 921
- clef, G2 921
- clef, GG 921
- clef, Kievan 542, 923
- clef, mensural 542, 923
- clef, mezzo-soprano 19, 921
- clef, moderntab 454
- clef, percussion 487, 922
- clef, Petrucci 542, 923
- clef, soprano 19, 921
- clef, style 542, 921
- clef, subbass 19, 921
- clef, tab 454, 922
- clef, tenor 19, 921
- clef, tenor G 921
- clef, tenor varC 921
- clef, transposing 20
- clef, treble 19, 921
- clef, tweaking properties 22
- clef, varbaritone 19, 921
- clef, varC 921
- clef, violin 19, 921
- clef, visibility following explicit change 786
- clef, visibility of transposition 788
- clef, with cue notes 20
- clip-regions 647, 964
- closure 939
- cluster 220
- \cm 773, 964
- coda 196
- \coda 155, 851, 929
- 'coda' sign 155, 929
- 'coda' sign, manual 206
- 'coda' sign, variant 155, 200, 929
- 'coda' sign, with repeats 195
- \codaMark 130, 198, 206, 945
- collision 226
- collision, bar number 140
- collision, cross-staff voices 415
- collision, ignoring 219, 231
- color 288
- color 288
- color blind 290
- color fonts 337
- color, CSS-like codes 289
- color, in chord 290
- color, list 900
- color, RGB 290
- color, suitable for dichromatism 904
- coloring note 288
- coloring note, in chord 290
- coloring object 288, 783
- coloring text 883
- coloring voice 226
- column 715
- \column 329, 821
- column, text 318, 329
- \column-lines 884
- \combine 332, 822
- combining parts 232
- combining parts, changing text 236
- comma interval 580
- comment 590, 596
- common time 80
- common-shortest-duration 711
- Completion_heads_engraver 97, 571
- Completion_rest_engraver 97, 571
- complex time signature 80
- composer 600
- \compound-meter 851
- \compressEmptyMeasures 273
- compressing music 62
- \compressMMRests 71, 73, 274, 946
- \concat 822
- concatenating text 822
- condensing rests 75
- conducting signs 110
- conga 930
- \consists 743, 749, 750
- constante hairpin 165
- contemporary glissando 178
- \context 737, 744
- context definitions, with MIDI 656
- context property, changing default 744
- context, adding alias 750
- context, creating and referencing 737
- context, defining in MIDI 751
- context, defining new 749
- context, implicit 754
- \context, in \layout block 744
- context, keeping alive 740
- context, layout order 753
- context, lifetime 740
- context, overlaying multiple 244
- context, properties 758
- context, Score-level 752
- context-spec-music 229
- \contextPropertyCheck 946
- continuation, of notes 534
- control pitch 12
- control point, Bézier curve 799
- control point, tweaking 764
- controlling general text alignment 824
- controlpitch 12
- copyright 600
- copyright sign 645
- count visibility, of percent repeats 209
- counter, percent repeat 209
- countPercentRepeats 209
- cowbell 930
- \cr 159
- crash cymbal 930
- creating a table 885
- creating empty text object 877
- creating horizontal space, in text 820, 826
- creating text fraction 875
- creating vertical space, in text 820, 835, 881
- \cresc 161
- crescendo 159
- crescendo-event 267
- crescendoSpanner 167
- crescendoText 167
- \crescHairpin 161
- \crescTextCresc 161
- cross 43

cross note head 43
 cross-staff beam 414
 cross-staff chord 420
 cross-staff chord bracket 420
 cross-staff collision 415
 cross-staff line 418
 cross-staff note 414, 420
 cross-staff parenthesis-style arpeggio 185
 cross-staff stem 420
 cross-staff tremolo 212
 cross-voice arpeggio 184
 \crossStaff 420, 946
 CSS color codes 289
 cue clef 20
 cue note 265, 268
 cue note, formatting 268
 cue note, removing 272
 cue, in vocal score 397
 cue, musical 395
 \cueClef 268, 946
 \cueClefUnset 268, 946
 \cueDuring 269, 946
 \cueDuring, and tags 629
 \cueDuringWithClef 269, 946
 CueVoice 268, 737
 cuica 930
 currentBarNumber 78, 132
 custodes 540
 custom fret diagram 455, 464
 custom fret diagram, adding 469
 custom fretboard fret diagram 471
 custom metronome mark markup 90
 custom rehearsal mark 142
 custom string tuning 452
 customized fret diagram 463
 customizing chord name 515
 \customTabClef 853
 custos 540
 cut time 80
 cymbal, various 930

D

D.C. 196
 D.C., manual 207
 D.S. 197
 D.S., forced at start 198
 D.S., manual 207
 da capo 196
 da capo, manual 207
 dal segno 197
 dal segno, forced at start 198
 dal segno, manual 207
 dampened note, on fretted instrument 482
 dash patterns, slur 171, 172
 \dashBang 157
 \dashDash 157
 \dashDot 157
 dashed phrasing slur 174
 dashed slur 170
 dashed tie 64
 \dashHat 157
 \dashLarger 157
 \dashPlus 157

\dashUnderscore 157
 dead note, percussion 494
 \deadNote 44, 946
 \deadNotesOff 44
 \deadNotesOn 44
 debug-beam-scoring 680, 964
 debug-slur-scoring 680, 965
 debug-tie-scoring 680, 965
 debugging, vertical spacing 727
 decorating text 331
 \decr 159
 \decresc 161
 decrescendo 159
 decrescendoSpanner 167
 decrescendoText 167
 dedication 600
 default 33
 \default 141, 611
 ‘default’ accidental style 31, 33
 default bar line 131
 default bar line, changing 129
 default context property, changing 744
 default note duration 53
 default note name 8
 default pitch 53
 default vertical direction (-) 772
 default, offsetting 764
 default-staff-staff-spacing 695
 \defaultchild 736, 754
 \defaultTimeSignature 80
 \defineBarLine 125, 946
 defining bar line 125
 defining predefined fretboard 472
 delayed ‘turn’ ornament 158
 \deminutum 557, 562
 \denies 749, 751, 753
 \descends 557, 562
 desk parts 261
 Devnull 736, 737
 diagram, chord for fretted instruments 455
 diagram, fret 455
 diagram, fret, customized 463
 diagram, fret, transposing 468
 diamond note head 43
 diamond-shaped note head 428
 dichromatism, suitable colors 904
 dim 508
 \dim 161
 dimension 774
 dimension units 773
 dimension, of bounding box 883
 dimension-variables 965
 \dimHairpin 161
 diminuendo 159
 \dimTextDecr 161
 \dimTextDecresc 161
 \dimTextDim 161
 \dir-column 822
 direction 791
 direction, automatic, of stem, on center line 297
 direction, default (-) 772
 direction, default, of stem, on center line 296
 direction, down (v) 772
 direction, up (^) 772
 \discant 867

- discant symbol, accordion 424
 display vertical layout 727
`\displayLilyMusic` 664, 946
`\displayMusic` 946
`\displayScheme` 946
 distance, absolute 773
 distance, between staves 695
 distance, scaled 773
 divided lyrics 374
 divided voices 391
 divisi staves 259
 divisio 555
`\divisioMaior` 556
`\divisioMaxima` 556
`\divisioMinima` 556
 divisiones 555
 dodecaphonic 36
 ‘dodecaphonic’ accidental style 36
 dodecaphonic-first 37
 ‘dodecaphonic-first’ accidental style 37
 dodecaphonic-no-repeat 37
 ‘dodecaphonic-no-repeat’ accidental style 37
 doit 176
 Dorian 24
`\dorian` 24
`\dotsDown` 54
`\dotsNeutral` 54
`\dotsUp` 54
 dotted bar line 130
 dotted note 53
 dotted note, changing number of dots 54
 dotted note, moving horizontally 230
 dotted phrasing slur 174
 dotted slur 170
 dotted tie 64
 double bar line 120, 130, 131, 146
 double flat 8
 double sharp 8
 double slur, for legato chords 172
 double-dotted note 53
 double-time signature 93
`\doubleflat` 853
`\doublesharp` 853
`\doubleSlurs` 172
 down direction (↓) 772
 ‘down pralltriller’ ornament 155, 927
 ‘down-bow’ bowing indication 155, 428, 928
 DOWN 791, 794
`\downbow` 155, 428, 928
`\downmordent` 155, 927
`\downprall` 155, 927
`\draw-circle` 332, 839
`\draw-dashed-line` 840
`\draw-dotted-line` 840
`\draw-hline` 840
`\draw-line` 332, 841
`\draw-squiggle-line` 841
 drawing beam, within text 838
 drawing box, with rounded corners 842
 drawing box, with rounded corners, around text 847
 drawing circle, within text 839
 drawing dashed line, within text 840
 drawing dotted line, within text 840
 drawing ellipse, around text 842
 drawing graphic object 331
 drawing line, across a page 840
 drawing line, within text 841
 drawing oval, around text 843
 drawing path 844
 drawing polygon 845
 drawing solid box, within text 842
 drawing squiggled line, within text 841
 drawing triangle, within text 848
`\dropNote` 512, 946
 drum 487, 489
 drum staff 241
 drum, various 930
`\drummode` 241, 487, 587
`\drumPitchNames` 492
`\drumPitchTable` 492
`\drums` 487, 587
`\DrumStaff` 241, 735
`\drumStyleTable` 491
`\DrumVoice` 737
 duration line 534
 duration, default 53
 duration, isolated 53
 duration, of note 52
 duration, scaling 61
`\dwn` 576
`\dynamic` 168, 808
 dynamic mark, multiple on one note 160
 dynamic mark, new 167
 dynamic-event 267
`\dynamicDown` 162
`\DynamicLineSpanner` 162, 165
`\dynamicNeutral` 162
 dynamics 159
 Dynamics 737
 dynamics, absolute 159
 dynamics, breaking vertical alignment 166
 dynamics, centered in keyboard music 414
 dynamics, editorial 168
 dynamics, extender line, hiding 166
 dynamics, in MIDI 653
 dynamics, in MIDI, custom 653
 dynamics, parenthesis 168
 dynamics, text spanner, customize 312
 dynamics, text, style 167
 dynamics, vertical alignment 165
 dynamics, vertical positioning 162
`\dynamicUp` 162
- ## E
- easy notation 45
 easy notation, using numbers 45
 easy play note head 45
`\easyHeadsOff` 45
`\easyHeadsOn` 45
 editorial dynamics 168
 effects, in MIDI 661
 electric snare 930
`\ellipse` 842
 embedded graphics 333
 embedding files, in PDF 649
 embedding graphic object 331
 Emmentaler font 905
 Emoji fonts 337

- empty chord 150, 161, 414
- empty staff 256
- \EnableGregorianDivisiones 962
- \enablePerStaffTiming 947
- encapsulated postscript output 648
- enclosing text, in box 807
- enclosing text, in box with rounded corners 847
- encoding, of text 644
- end repeat 204
- \endcr 159
- \enddecr 159
- \endSpanners 782, 947
- \englishChords 516
- engraver, including in context 749
- Engraver_group 750
- ensemble music 393
- entering lyrics 346
- entering multiple tuplets 57
- ‘episem finis’ Gregorian articulation 556
- ‘episem initium’ Gregorian articulation 556
- \episemFinis 556
- \episemInitium 556
- EPS image 843
- EPS output 648
- \epsfile 333, 842
- equalization, instrument, replacing MIDI default 655
- \espressivo 155, 161, 927
- ‘espressivo’ articulation 155, 161, 927
- \etc 322, 640
- evenFooterMarkup 965
- evenHeaderMarkup 966
- \eventChords 947
- exact positioning of staves 702
- exception, chord names 518
- \expandEmptyMeasures 273
- expanding music 62
- explicitClefVisibility 786
- explicitKeySignatureVisibility 786
- expression markup 319
- expression, in MIDI 661
- extended chord 509
- extender 357
- extender line, dynamics, hiding 166
- extent, of actual inking 883
- extent, of bounding box 883
- extent, of grobs 789
- extra natural sign, preventing 9
- extra voice, for handling breaks 690
- extra-offset 695
- extra-spacing-height 718
- extra-spacing-width 718
- extreme pitch 10
- \eyeglasses 874
- Ez_numbers_engraver 45
- F**
- \f 159
- F clef 19, 921
- fall 176
- false (#f) 972
- false note, percussion 494
- \featherDurations 118, 947
- feathered beam 118
- feature, OpenType font 339, 813
- fermata 155, 928
- \fermata 77, 155, 853, 928
- fermata, Henze 155, 928
- fermata, long 155, 928
- fermata, on bar line 77
- fermata, on multi-measure rest 72
- fermata, short 155, 928
- Ferneyhough hairpin 165
- Feta font 905
- \ff 159
- \fff 159
- \ffff 159
- \ffffff 159
- figured bass 525
- figured bass, alignment 532
- figured bass, alteration, glyphs 529
- figured bass, alteration, position 529
- figured bass, extender lines 529
- figured bass, vertical distance of elements 531
- \figured-bass 808
- FiguredBass 737
- figuredBassAlterationDirection 529
- figuredBassPlusDirection 529
- figuredBassPlusStrokedAlist 529
- \figuremode 526, 587
- \figures 526, 587
- files, embedding in PDF 649
- \fill-line 330, 823
- \fill-with-pattern 624, 824
- \filled-box 332, 842
- final bar line 120, 131, 146
- final bar line, in Gregorian chant 555
- final bar line, in Kievan chant 565
- finalis 555
- \finalis 556
- fine 195
- \fine 131, 146, 194, 195, 565
- \finger 281, 809, 947
- finger change 281
- fingering 281
- fingering chart 496
- fingering number, vs. string 432
- fingering, adding to fret diagram 478
- fingering, and multi-measure rest 75
- fingering, glide 284
- fingering, inside of staff 283
- fingering, line between 284
- fingering, orientation 282
- fingering, right-hand, for fretted instruments 479
- fingering, right-hand, placement 480
- fingering, stem support 283
- fingering, symbols, for wind instruments 496
- fingering, thumb 155, 282, 928
- fingeringOrientations 282
- first-page-number 678, 966
- \first-visible 874
- \fixed 4, 947
- flag, beam-like 117
- flag, mensural 544
- flag, modern straight 117
- flag, old straight 117
- flag, stacked 117
- \flageolet 155, 928
- ‘flageolet’ harmonics 155, 928

- flags, flat 116
 - \flagStyleDefault 117
 - \flagStyleStacked 117
 - flared hairpin 165
 - flat 8
 - \flat 853
 - flat flags 116
 - flat, double 8
 - flex program 940
 - \flexa 557, 562
 - flexa, in mensural ligatures 548
 - floor tom tom 930
 - follow voice 418
 - followVoice 418
 - font 939
 - font family 325
 - font family, setting 340
 - font feature, OpenType 339, 813
 - font format, bitmap 337
 - font format, CFF2 336
 - font format, Font Variations (VF) 337
 - font format, OTC 337
 - font size (markup) 323
 - font size (notation) 277
 - font size (notation), scaling 277
 - font size (notation), standard 281
 - font size, setting 683
 - font, changing for entire document 340
 - font, Emmentaler 905
 - font, external files 337
 - font, Feta 905
 - font, finding 337
 - font, Parmesan 905
 - font, switching 323
 - font-interface 279
 - \font-select 809
 - font-size 278, 281
 - \fontCaps 809
 - FontConfig 336
 - fonts 340
 - fonts, color 337
 - fonts, for Emojis 337
 - fontSize 279
 - \fontsize 323, 809
 - foot mark 155, 928
 - footer 597
 - footer, page 604
 - footnote 610
 - \footnote 610, 874, 947
 - footnote, event-based 611
 - footnote, in music expressions 610
 - footnote, in stand-alone text 616
 - footnote, time-based 613
 - footnote-footer-padding 966
 - footnote-number-raise 966
 - footnote-numbering-function 966
 - footnote-padding 966
 - footnote-separator-markup 680, 966
 - Forbid_line_break_engraver 60
 - forced vertical direction of grobs 772
 - forget 37
 - ‘forget’ accidental style 37
 - formatting, cue notes 268
 - formatting, in lyrics 346
 - formatting, rehearsal mark 142
 - formatting, text spanner 311
 - four-bar music 689
 - four-string-banjo 485
 - \fp 159
 - \fraction 875
 - fragment 268
 - fragment, music 647
 - fragment, quoting 265
 - framing text 331
 - \freeBass 868
 - French clef 19, 921
 - \frenchChords 516
 - Frenched score 256
 - Frenched staff 253, 256
 - fret 434
 - fret diagram 455, 466
 - fret diagram, adding custom 469
 - fret diagram, adding fingering 478
 - fret diagram, automatic 477
 - fret diagram, changing orientation 464
 - fret diagram, custom 455
 - fret diagram, customized 463, 464
 - fret diagram, left-handed 459
 - fret diagram, mandolin 466
 - fret diagram, markup 457
 - fret diagram, transposing 468
 - fret diagram, ukulele 466
 - fret diagram, with chord names 467
 - \fret-diagram 457, 862
 - fret-diagram-interface 463
 - \fret-diagram-terse 459, 863
 - \fret-diagram-terse markup 459
 - \fret-diagram-verbose 461, 864
 - \fret-diagram-verbose markup 461
 - fretboard fret diagram, customized 471
 - fretboard, alternate table 475
 - fretboard, define predefined 472
 - FretBoards 466, 736
 - fretted instrument, chord shape 470
 - fretted instrument, dampened note 482
 - fretted instrument, harmonics 482
 - fretted instrument, indicating position and
barring 481
 - fretted instrument, predefined string tunings 452
 - fretted instrument, right-hand fingering 479
 - \fromproperty 875
 - full score 392, 393
 - full-measure rest 71
 - funk shape note head 46
 - \funkHeads 46
 - \funkHeadsMinor 47
- ## G
- G clef 19
 - \general-align 327, 824
 - \germanChords 516
 - ghost note 295
 - ghost note, percussion 494
 - \glide 284
 - gliding fingering 284
 - glissando 176
 - \glissando 176
 - glissando, across repeats 180
 - glissando, and repeats 204

glissando, breakable 179
 glissando, chords in tablatures 449
 glissando, contemporary 178
 glissando, timing marks 178
 \glissandoMap 177
 Global 734
 global replacement, automatic, of strings 646
 global variable 940
 glyph 939
 glyph set, accidental 920
 glyph, alternate accidentals 39
 glyph, bounding box 883
 glyph, for figured bass alteration 529
 \grace 147, 947
 grace note 147, 498
 grace note, and lyrics 383
 grace note, and strict spacing 150
 grace note, changing layout settings 149
 grace note, following 148
 grace note, synchronization 151
 grace note, tweaking 149
 grammar, for LilyPond 940
 grand staff 243
 GrandStaff 735
 graphic notation 332
 graphic object, drawing 331
 graphic object, embedding 331
 graphical object 939
 graphical object interface 940
 graphics, embedding 331, 333
 Gregorian accidental 555
 Gregorian articulation 556
 Gregorian articulation, accentus 556, 929
 Gregorian articulation, circulus 556, 929
 Gregorian articulation, episem finis 556
 Gregorian articulation, episem initium 556
 Gregorian articulation, ictus 556, 929
 Gregorian articulation, semicirculus 556, 929
 Gregorian key signature 555
 Gregorian music, modern transcription 405
 Gregorian square neumes ligature 557
 Gregorian transcription staff 242
 GregorianTranscriptionLyrics 736
 GregorianTranscriptionStaff 242, 736
 GregorianTranscriptionVoice 736
 grid line 301
 grid lines, changing appearance 301
 Grid_line_span_engraver 301
 Grid_point_engraver 301
 gridInterval 301
 grob 755, 939
 grob, aligning 789
 grob, and whiteout 65, 783
 grob, overwriting 65, 783
 grob, property 760
 grob, vertical position 772
 grob, visibility 782
 grob-interface 940
 \grobdescriptions 947
 grouping beats 110
 grow-direction 118
 guiro 930
 guitar note head 43
 guitar tablature 431
 guitar, chord chart 99

guitar, strumming rhythm, showing 99, 100
 gutter 676

H

hairpin 159
 hairpin, al niente 164
 hairpin, aligning ends to NoteColumn directions .. 164
 hairpin, angled 789
 hairpin, constante 165
 hairpin, Ferneyhough 165
 hairpin, flared 165
 hairpin, minimum length 163
 hairpin, moving ends 164
 hairpin, stopping at bar lines 163
 ‘half-open’ articulation 155, 928
 half-open high hat 155, 491, 930
 \halfopen 155, 491, 928
 \halign 326, 825
 hammer on 450
 hand clap 930
 Harmonia Sacra note head 46
 \harmonic 44, 429, 438
 harmonic indication, in tablature 438
 harmonic note head 43
 \harmonicByFret 438, 948
 \harmonicByRatio 438, 948
 \harmonicNote 948
 harmonics, artificial 429
 harmonics, flageolet 155, 928
 harmonics, in tablatures 445
 harmonics, natural 428
 harmonics, on fretted instrument 482
 \harmonicsOff 428
 \harmonicsOn 428, 948
 harp 425
 harp, pedal 425
 harp, pedal diagram 425
 \harp-pedal 426, 865
 ‘Haydn turn’ ornament 155, 927
 \haydnturn 155, 927
 \hbracket 331, 843
 \hcenter-in 826
 header 597
 \header 594
 header, page 604
 \heel 155, 423, 928
 ‘heel’ pedal mark 155, 423, 928
 \heelcircle 155, 423, 928
 Hel-arabic note name 575
 help, balloon 299
 Henze fermata 155, 928
 \henzelongfermata 155, 928
 \henzeshortfermata 155, 928
 hidden note 288
 \hide 783, 948
 \hideKeySignature 498
 \hideNotes 288
 \hideSplitTiedTabNotes 437
 \hideStaffSwitch 418
 hiding accidentals, on tied notes at start of system . 9
 hiding ancient staves 256
 hiding dynamics extender line 166
 hiding rhythmic staves 256

hiding staves 256
 hiding Vaticana staves 256
 high bongo 930
 high conga 930
 high hat 930
 high hat, half-open 155, 491, 930
 high hat, open 155, 930
 high hat, pedal 155, 491, 930
 high hat, pedal splash 491
 high timbale 930
 high tom tom 930
 highest pitch 10
 highlight, staff 291
 horizontal alignment, lyrics 364
 horizontal alignment, melisma 365
 horizontal beams 444
 horizontal bracket 303
 horizontal extent, of grobs 789
 horizontal movement, in markup 327
 horizontal ornament 156
 horizontal shift of notes 230
 horizontal spacing 711
 horizontal spacing, between columns 718
 horizontal spacing, between non-musical items ... 716
 horizontal text alignment 326
 horizontal-shift 676, 966
 Horizontal_bracket_engraver 303
 HorizontalBracketText 304
 horizontally centering text 821
 \hspace 327, 826
 Hufnagel 537, 538
 \huge 280, 326, 810
 hymn 400, 405
 hymn, and partial measures 410
 hyperlink, as QR code 879
 hyphen 357

I

\ictus 556, 929
 ‘ictus’ Gregorian articulation 556, 929
 \if 608, 862
 \iij 558
 \IIJ 558
 \ij 558
 \IJ 558
 image 843
 \image 843
 image, embedding 333
 immutable object 940
 immutable property 940
 implicit context 754
 importing stencil, into text 881
 improvisation 50
 improvisation, Arabic 579
 \improvisationOff 50, 99
 \improvisationOn 50, 99
 \in 773, 966
 in-note 619
 in-note-direction 619
 in-note-padding 619, 966
 in-note-system-padding 619, 966
 inch (in) 773
 \incipit 566, 948

incipit, adding 566
 incipit-width 966
 \inclinaturn 557, 562
 \include 596, 625
 include settings 638
 including files 625
 indent 262, 676, 720, 966
 indicating ‘No Chord’, in ChordNames 513
 indicating position and barring for fretted
 instrument 481
 individual parts 261
 \inherit-acceptability 750, 948
 \initialContextFrom 948
 inner-margin 676, 966
 input-language 940, 949
 inserting music, into text 858
 inserting PostScript directly, into text 846
 inserting URL link, into text 849
 \inStaffSegno 130, 131, 206, 948
 instrument 600
 instrument equalization, in MIDI, replacing
 default 655
 instrument name 261, 657
 instrument name, adding to other contexts 263
 instrument name, centering 262
 instrument name, changing 263
 instrument name, complex 262
 instrument name, short 261
 instrument, transposing 14
 \instrumentSwitch 948
 interface 940
 interface, layout 755
 interleaved music 237
 Internals Reference 733
 inversion 16
 \inversion 16, 949
 inversion, modal 18
 \invertChords 512, 949
 invisible note 288
 invisible rest 69
 invisible stem 296
 Ionian 24
 \ionian 24
 irregular measure 90
 is-last-bookpart 967
 isolated duration 53
 isolated percent repeat 210
 isolated pitch 53
 \italianChords 516
 \italic 323, 810
 item, musical 715
 item, non-musical 715

J

jazz chord 515
 \jump 207, 949
 \justified-lines 321, 884
 \justify 330, 827
 \justify-field 827
 \justify-line 828
 \justify-string 829
 justifying lines of text 884
 justifying text 330, 827

K

<code>\keep-with-tag</code>	636, 876
<code>keepAliveInterfaces</code>	257
keeping tagged music.....	628
<code>\keepWithTag</code>	628, 949
<code>\key</code>	24, 47, 949
key cancellation, before bar line.....	717
key signature.....	8, 24
key signature, Gregorian.....	555
key signature, mensural.....	545
key signature, non-traditional.....	26
key signature, preventing natural signs.....	25
key signature, visibility following explicit change.....	786
keyboard instrument staff.....	414
keyboard music, centering dynamics.....	414
keyed instrument staff.....	414
Kievan accidental.....	564
Kievan clef.....	542, 923
Kievan ligature.....	565
<code>Kievan_ligature_engraver</code>	565
<code>\kievanOff</code>	564
<code>\kievanOn</code>	564
<code>KievanStaff</code>	563, 736
<code>KievanVoice</code>	563, 736
<code>\killCues</code>	272, 949
<code>Kirchenpause</code>	275
knee gap, with beams, changing.....	103
<code>koron</code>	582

L

<code>\label</code>	622, 949
<code>label-alist-table</code>	967
<code>label-page-table</code>	967
<code>laissez vibrer</code>	64
<code>\laissezVibrer</code>	64
landscape.....	967
<code>\language</code>	949
language, note names in other.....	10
language, pitch names in other.....	10
<code>\languageRestore</code>	949
<code>\languageSaveAndChange</code>	949
<code>\large</code>	280, 326, 810
<code>\larger</code>	323, 326, 810
last-bottom-spacing.....	674, 707, 967
layer.....	783
<code>\layout</code>	594, 681, 734, 744
layout object.....	939
<code>\layout</code> , and <code>\book</code>	593
<code>\layout</code> , and <code>\bookpart</code>	593
<code>\layout</code> , and paper variables.....	681
layout, file.....	683
layout, interface.....	755
layout, major 7 chord.....	519
layout, vertical, debugging.....	727
<code>layout-set-staff-size</code>	683
lead sheet.....	514
ledger line.....	249
ledger line, internal.....	249
ledger line, modifying.....	249
<code>\left-align</code>	326, 829
left-aligning text.....	829
<code>\left-brace</code>	876
<code>\left-column</code>	830

left-handed fret diagram.....	459
left-margin.....	675, 967
<code>LEFT</code>	791, 792
length of multi-measure rest.....	73
length of note.....	52
lexer, for <code>LilyPond</code>	940
<code>\heel</code>	423
<code>\heeltoe</code>	423
ligature.....	539
<code>\ligature</code>	949
ligature, in text.....	822
ligature, Kievan.....	565
ligature, mensural.....	548
ligature, square neumes.....	557
<code>Ligature_bracket_engraver</code>	548, 565
<code>LilyPond grammar</code>	940
<code>LilyPond lexer</code>	940
<code>\line</code>	320, 321, 830
line break.....	120
line break, beams.....	102
line break, cadenzas.....	93
line break, managing with extra voice.....	690
line break, unmeasured music.....	93
line comment.....	590, 596
line, barré.....	481
line, between fingerings.....	284
line, cross-staff.....	418
line, grid.....	301
line, indicating duration.....	534
line, staff-change.....	418
line, staff-change follower.....	418
line, vertical, between staves.....	301
line-break-system-details.....	702
line-thickness.....	967
line-width.....	330, 674, 720, 967
<code>\linea</code>	557, 562
<code>\lineprall</code>	155, 927
list of colors.....	900
list of keys, in woodwind diagrams.....	506
list of markups.....	320
list of woodwind diagrams.....	503
<code>Locrian</code>	24
<code>\locrian</code>	24
long fermata.....	155, 928
<code>\longa</code>	52, 67
longa rest.....	67
<code>\longfermata</code>	155, 928
<code>\lookup</code>	876
low bongo.....	930
low conga.....	930
low timbale.....	930
low tom tom.....	930
<code>\lower</code>	327, 830
‘lower mordent’ ornament.....	155, 927
lowering text.....	830
lowest pitch.....	10
<code>\ltoe</code>	423
<code>\ltoeheel</code>	423
lute tablature.....	485
lute tuning.....	486
<code>ly:minimal-breaking</code>	692
<code>ly:one-line-auto-height-breaking</code>	693
<code>ly:one-line-breaking</code>	693
<code>ly:one-page-breaking</code>	692
<code>ly:optimal-breaking</code>	692

ly:page-turn-breaking 693
 Lydian 24
 \lydian 24
 \lyricmode 346, 347, 587
 \lyrics 587
 Lyrics 736
 lyrics, aligning to a melody 347
 lyrics, aligning with sporadic melody 741
 lyrics, and markup 347
 lyrics, and melodies 349
 lyrics, and tied notes 372
 lyrics, assigned to one voice 221
 lyrics, avoid bar lines 366
 lyrics, divided 374
 lyrics, entering 346
 lyrics, formatting 346
 lyrics, horizontal alignment 364
 lyrics, increasing space between 363
 lyrics, keeping inside margin 310, 366
 lyrics, on grace notes 383
 lyrics, positioning 255, 360
 lyrics, punctuation 346
 lyrics, repeating 366
 lyrics, repeats with alternative endings 370
 lyrics, separate, on single line 362
 lyrics, shared among voices 376
 lyrics, skip 70
 lyrics, skipping notes 371
 lyrics, using variables 358
 lyrics, with beam 104
 \lyricsto 347, 349

M

m (in chord) 508
 magnification->font-size 279, 683
 \magnify 323, 811
 magnifying text 811
 \magnifyMusic 277, 949
 \magnifyStaff 683, 950
 magstep 279, 683, 774
 maj 508
 major 24
 \major 24
 major 7 chord, layout 519
 major seven symbol 518
 majorSevenSymbol 516, 519
 makam 574, 580
 makam, example 581
 makamlar 574, 580
 make-dynamic-script 168
 make-footer 967
 make-header 967
 make-relative 643
 \makeClusters 220, 950
 \makeDefaultStringTuning 950
 manual bar line 120
 manual beam 101, 114
 manual beam, direction shorthand for 114
 manual beam, grace notes 114
 manual engraving, of ties 66
 manual line break 687
 manual measure line 120
 manual rehearsal mark 142
 manual repeat mark 204
 manual staff change 414
 maqam 574
 maracas 930
 \marcato 155, 927
 ‘marcato’ articulation 155, 927
 margin, text running over 310
 \mark 141, 313, 950
 mark, on every staff 143
 mark, phrasing 173
 mark, rehearsal 141
 mark, rehearsal, below staff 89
 mark, rehearsal, format 142
 mark, rehearsal, manual 142
 mark, rehearsal, style 142
 mark, text 313
 Mark_engraver 143
 \markalphabet 876
 \markLengthOff 88, 314
 \markLengthOn 88, 314
 \markletter 877
 markup 319
 \markup 307, 313, 317, 318, 319, 588
 markup list 320
 markup mode, quoted text 319
 markup mode, special characters 319
 markup object 307
 markup text, aligning 326
 markup text, alignment commands 331
 markup text, decorating 331
 markup text, framing 331
 markup text, justified 330
 markup text, line width 330
 markup text, multi-page 321
 markup text, padding 332
 markup text, size 323
 markup text, word-wrapped 330
 markup, aligning 326
 markup, centering on page 330
 markup, conditional 608
 markup, expression 319
 markup, horizontal movement 327
 markup, image 843
 markup, in lyrics 347
 markup, multi-line 329
 markup, multi-measure rest 75
 markup, multi-page 321
 markup, music notation inside 334
 markup, on multi-measure rest 72
 markup, rhythm 857
 markup, score inside 335
 markup, syntax 319
 markup, text 319
 markup, text, inside slurs 172
 markup, two-column 318
 markup, vertical movement 327, 328
 markup-markup-spacing 674, 968
 markup-system-spacing 673, 968
 \markuplist 318, 321
 \markupMap 950
 matter, optional 294
 matter, prefatory 715, 716
 max-systems-per-page 677, 968
 \maxima 52, 67
 maxima rest 67

- maximum pitch 10
- measure 78
- \measure 950
- measure counter 143
- measure line 120, 131
- measure line, invisible 120
- measure line, manual 120
- measure number 78, 132
- measure number, and repeats 204
- measure number, check 140
- measure number, style 135
- measure position 78, 91
- measure repeat 208
- measure, check 140
- measure, grouping 110
- measure, irregular 90
- measure, partial 90
- measure, partial, in hymns 410
- measure, pickup 90
- measure, subgrouping 110
- Measure_grouping_engraver 110
- measureBarType 129
- measureLength 78, 104
- measurePosition 78
- \measureRemainder 950
- measuring units 773
- Medicaea, Editio 537, 538
- medium interval 574
- melisma 354, 357
- \melisma 354
- melisma, horizontal alignment 365
- melisma, with beams 102
- \melismaEnd 354
- melismata 354
- melody rhythm, showing 98
- mensural 537, 538
- mensural clef 542, 923
- mensural flag 544
- mensural ligature 548
- mensural ligature, flexa 548
- mensural music, transcription 246
- mensural notation, signum congruentiae 929
- Mensural_ligature_engraver 548
- MensuralStaff 242, 541, 735
- MensuralVoice 541, 736
- mensuration sign 543
- Mensurstriche 567
- Mensurstriche, layout 246
- \mergeDifferentlyDottedOff 226
- \mergeDifferentlyDottedOn 226
- \mergeDifferentlyHeadedOff 226
- \mergeDifferentlyHeadedOn 226
- merging notes 226
- merging rests 231
- merging text 822, 831
- meter 79
- meter 600
- meter, additive 80
- meter, alternating 80
- meter, complex 80
- meter, polymetric 93
- meter, strictly alternating 130
- meter, style 80
- metronome mark 86
- metronome mark, below staff 89
- metronome mark, custom markup 90
- mezzo-soprano clef 19, 921
- \mf 159
- microtone 11
- microtone, in tablature 454
- mid tom tom 930
- \midi 594, 734
- MIDI 30, 651
- MIDI, balance 661
- MIDI, block 652
- MIDI, channels 658
- MIDI, chorus level 661
- MIDI, context definitions 656
- MIDI, custom dynamics 653
- MIDI, dynamics 653
- MIDI, effects 661
- MIDI, equalization 654
- MIDI, expression 661
- MIDI, instrument 657
- MIDI, metadata 609
- MIDI, one channel per voice 660
- MIDI, pan position 661
- MIDI, replacing default instrument equalization .. 655
- MIDI, reverb 661
- MIDI, stereo balance 661
- MIDI, supported notation 651
- MIDI, tracks 658
- MIDI, transposition 30
- MIDI, unsupported notation 652
- MIDI, using repeats 658
- MIDI, volume 654
- midiBalance 661
- midiChannelMapping 658
- midiChorusLevel 661
- midiDrumPitches 492
- midiExpression 661
- midiInstrument 657
- midiPanPosition 661
- midiReverbLevel 661
- millimeter (mm) 773
- min-systems-per-page 677, 968
- minimum length, hairpin 163
- minimum pitch 10
- minimum-Y-extent 695
- minimumFret 434, 478
- minor 24
- \minor 24
- minorChordModifier 518
- mirroring markup 848
- Mixolydian 24
- \mixolydian 24
- \mm 773, 968
- modal inversion 18
- modal transformation 17
- modal transposition 17
- \modalInversion 18, 950
- \modalTranspose 17, 951
- mode 24
- modern 34
- modern accidental 34
- ‘modern’ accidental style 33, 34
- modern transcription of Gregorian music 405
- modern-cautionary 34
- ‘modern-cautionary’ accidental style 33, 34
- modern-voice 34

modern-voice-cautionary 34
 ‘modern-voice-cautionary’ accidental style 34
 moderntab clef 454
 modifier, in chord 508
 modifying contexts 758
 modifying properties 758
 \mordent 155, 927
 ‘mordent’ ornament 155, 927
 ‘mordent, lower’ ornament 155, 927
 ‘mordent, upper’ ornament 155, 927
 movement in markup, horizontal 327
 movement in markup, vertical 327, 328
 movement, multiple 591
 \mp 159
 multi-line comment 590, 596
 multi-line markup 329
 multi-line text 329
 multi-measure rest 71
 multi-measure rest, and fingerings 75
 multi-measure rest, attaching fermata 72
 multi-measure rest, attaching text 72
 multi-measure rest, contracting multiple 273, 274
 multi-measure rest, expanding multiple 273, 274
 multi-measure rest, length 73
 multi-measure rest, markup 75
 multi-measure rest, numbering 275
 multi-measure rest, positioning 74
 multi-measure rest, script 72
 multi-measure rest, style 275
 multi-measure rest, with markup 72
 multi-measure rest, within text, by duration 856
 multi-measure rest, within text, by number of
 measures 854
 \multi-measure-rest-by-number 854
 multi-note acciaccatura 151
 multi-page markup 321
 multi-voice accidental 34
 MultiMeasureRestScript 73
 MultiMeasureRestText 73
 multiple dynamic marks, on one note 160
 multiple phrasing slurs 174
 multiple slurs 170
 multiple voices 226
 music expression, copying 641
 music expression, sharing 641
 music fragment 647
 music, beginners’ 45
 music, inside markup 334
 music, unmetred 78
 musica ficta 546
 musical cue 395
 musical item 715
 musical theater 392
 \musicglyph 854
 \musicLength 951
 \musicMap 951
 musicological analysis 303
 musicQuotes 940
 mutable object 940
 mutable property 940
 mute bongo 930
 mute conga 930
 mute timbale 930
 muted note, percussion 494

N

\n 159
 N.C. symbol 513
 N.C. symbol, customizing 515
 \name 749, 750
 name, character 393
 name, of singer 382
 \natural 854
 natural harmonics 428
 natural pitch 8
 natural sign 8
 natural sign, extra, preventing 9
 natural sign, preventing in key signatures 25
 neo-modern 35
 ‘neo-modern’ accidental style 35
 neo-modern-cautionary 36
 ‘neo-modern-cautionary’ accidental style 36
 neo-modern-voice 36
 ‘neo-modern-voice’ accidental style 36
 neo-modern-voice-cautionary 36
 ‘neo-modern-voice-cautionary’ accidental style 36
 neomensural 538
 nesting repeat 204
 nesting, staff bracket 247
 nesting, staves 247
 \new 737
 new context 737
 new dynamic mark 167
 new spacing section 712
 new staff 241
 \newSpacingSection 712
 niente, al, hairpin 164
 ‘No Chord’ symbol 513
 ‘No Chord’ symbol, customizing 515
 no-reset 37
 ‘no-reset’ accidental style 37
 \noBeam 114
 \noBeamBreak 114
 \noBreak 689
 noChordSymbol 515
 non-arpeggiato 183
 non-ASCII character 644
 non-default tuplet numbers 57
 non-empty text 309
 non-musical item 715
 non-musical item, horizontal spacing 716
 non-musical symbol 332
 \nonArpeggiato 183, 391, 420
 NonMusicalPaperColumn 702, 715
 nonstaff-nonstaff-spacing 695
 nonstaff-relatedstaff-spacing 695
 nonstaff-unrelatedstaff-spacing 695
 \noPageBreak 691, 951
 \noPageTurn 694, 951
 \normal-size-sub 811
 \normal-size-super 324, 811
 \normal-text 811
 \normal-weight 812
 \normalsize 278, 280, 326, 812
 \noStanza 378, 951
 notation, explaining 299
 notation, font size 277
 notation, graphic 332
 notation, inside markup 334

`\note` 855
 note cluster 220
 note collision 226
 note continuation 534
 note duration 52
 note duration, default 53
 note grouping bracket 303
 note head 277
 note head, Aiken 46
 note head, Aiken, thin variant 48
 note head, ancient 543, 564
 note head, Christian Harmony 46
 note head, cross 43
 note head, diamond 43
 note head, diamond-shaped 428
 note head, easy notation 45
 note head, easy play 45
 note head, funk 46
 note head, guitar 43
 note head, Harmonia Sacra 46
 note head, harmonic 43
 note head, improvisation 50
 note head, parlato 43
 note head, practice 45
 note head, Sacred Harp 46
 note head, shape 46
 note head, shape, merging 49
 note head, slashed 50
 note head, Southern Harmony 46
 note head, special 43
 note head, style 43, 920
 note head, Walker 46
 note length 52
 note name, Arabic 575
 note name, default 8
 note name, Dutch 8
 note name, Hel-arabic 575
 note name, other languages 10
 note name, printing 297
 note pitch, default 53
 note, colored 288
 note, colored, in chords 290
 note, cross-staff 414, 420
 note, dotted 53
 note, dotted, moving horizontally 230
 note, double-dotted 53
 note, ghost 295
 note, hidden 288
 note, horizontal shift 230
 note, invisible 288
 note, parenthesized 295
 note, smaller 268
 note, spacing horizontally 712
 note, splitting 97
 note, transparent 288
 note, transposition 13
 note, within text, by duration 855
 note, within text, by log and dot-count 855
`\note-by-number` 855
 note-event 267
`Note_heads_engraver` 97
`Note_name_engraver` 297
`NoteColumn` 715
`\notemode` 588
`noteNameFunction` 297

`NoteNames` 297, 737
`noteNameSeparator` 297
`\null` 877
`NullVoice` 376, 737
`\number` 812
 number, bar 132
 number, in easy notation 45
 number, measure 132
`number-footnote-table` 968
`\numericTimeSignature` 80

O

object, colored 288, 783
 object, markup 307
 object, overwriting 783
 object, rotating 789
 object, visibility 782
 objects, aligning 789
 octavation 26
 octave changing mark 3
 octave check 12
 octave correction 12
 octave entry, absolute 3
 octave entry, relative 4
 octave specification, absolute 3
 octave specification, relative 4
 octave transposition 20
 octave transposition, optional 20
`\octaveCheck` 12, 951
`oddFooterMarkup` 968
`oddHeaderMarkup` 968
`\offset` 764, 951
 offsetting 764
`\omit` 783, 951
`\on-the-fly` 877
`\once` 761, 766, 775, 951
`OneStaff` 244, 735
`\oneVoice` 221
`\open` 155, 428, 491, 496, 928
 ‘open’ articulation 155, 496, 928
 open bongo 930
 open conga 930
 open high hat 155, 930
 open string indication 428
 open timbale 930
 OpenType collections (.otc) 337
 OpenType font (.otf) 336
 OpenType, font feature 339, 813
 opera 392
 operation, inversion 16
 operation, modal 17
 operation, modal inversion 18
 operation, retrograde 17
 operation, transposition 17
 optional material 294
 optional octave transposition 20
 optional passage 294
 opus 600
 oratorio 389
 orchestra, notation for 393
 orchestral music 393
 orchestral strings 427
 ordering, vertical, of scripts 157

organ 423
organ pedal mark 155, 423, 928
orientation, of fingerings 282
orientation, of fret diagram, changing 464
orientation, of string numbers 282
orientation, of stroke finger 282
\oriscus 557, 562
ornament 147
ornament, down pralltriller 155, 927
ornament, Haydn turn 155, 927
ornament, horizontally 156
ornament, lower mordent 155, 927
ornament, mordent 155, 927
ornament, mordent, lower 155, 927
ornament, mordent, upper 155, 927
ornament, pralltriller 155, 927
ornament, pralltriller, down 155, 927
ornament, pralltriller, long 155, 927
ornament, pralltriller, up 155, 927
ornament, reverse turn 155, 927
ornament, signum congruentiae 155
ornament, slash turn 155, 927
ornament, trill 155, 927
ornament, turn 155, 927
ornament, turn, delayed 158
ornament, up pralltriller 155, 927
ornament, upper mordent 155, 927
orphan-penalty 968
ossia 253, 260
ossia, positioning 255
ottava 26
\ottava 26, 951
ottava spanner, modifying slope 29
ottava text 28
ottava, for single voice 28
ottavation 28
ottavation-numbers 27
ottavation-ordinals 27
ottavation-simple-ordinals 27
ottavationMarkups 27
Ottoman music 580
Ottoman, classical music 574
outer-margin 676, 968
output definition 734
output-count 940
output-def 940
output-filename 593, 968
output-scale 968
output-suffix 593, 940, 968
outside-staff-horizontal-padding 709
outside-staff-padding 709
outside-staff-priority 708, 936
\oval 843
\overlay 831
overlying contexts 244
\override 760, 762, 877
override, reverting 760
\override-lines 885
\overrideProperty 762, 951
\overrideTimeSignatureSettings 82, 952
overriding property, within text markup 877
\overtie 814
overwriting grob 65
overwriting object 783

P

\p 159
\pad-around 332, 831
\pad-markup 332, 831
\pad-to-box 332, 832
\pad-x 332, 832
\pad-x-left 332, 832
\pad-x-right 332, 833
padding 757
padding around text 332
padding text 831
padding text horizontally 832, 833
page break 720
page break, cadenzas 93
page break, managing with extra voice 690
page break, manual 691
page break, unmeasured music 93
page break, within markup 321
page footer 604
page header 604
page layout 720
page number, auto-numbering 678
page number, in roman numerals 678
page number, independent for introduction 679
page number, per book part 679
page number, referencing 620
page number, specify first 678
page number, suppress 678
page size 670
page, orientation 671
page-breaking 677, 968
page-breaking-system-system-spacing 677, 969
page-count 677, 969
\page-link 877
page-number-type 678, 969
page-post-process 969
\page-ref 622, 878
page-spacing-weight 677, 969
\pageBreak 691, 952
\pageTurn 694, 952
pageTurnMinimumRepeatLength 694
pageTurnMinimumRestLength 693
\palmMute 952
\palmMuteOn 952
pan position, in MIDI 661
Pango 336
\paper 594, 670
paper column 715
paper size 670
paper size, landscape 671
paper size, orientation 671
paper variable, predefined 670
paper variables, in \layout block 681
paper-height 672, 969
paper-width 674, 969
papersizename 969
parallel music 237
\parallelMusic 237, 952
parent-alignment-X 793
parent-alignment-Y 794
parenthesis 295
\parenthesize 295, 844, 952
parenthesized accidental 8
parlato 399

- parlato note head..... 43
- Parmesan font..... 905
- parser..... 940
- parser variable..... 940
- part combiner..... 232
- part combiner, changing text..... 236
- part song..... 389
- part, desk..... 261
- part, individual..... 261
- part, section..... 261
- \partCombine..... 232, 376, 952
- \partCombine, and lyrics..... 235, 376
- \partCombineApart..... 234
- \partCombineAutomatic..... 234
- \partCombineChords..... 234
- \partCombineDown..... 953
- \partCombineForce..... 953
- partCombineListener..... 940
- \partCombineSoloI..... 234
- \partCombineSoloII..... 234
- \partCombineUnisono..... 234
- \partCombineUp..... 953
- \partial..... 78, 90, 190, 953
- partial measure..... 90
- partial measure, in hymns..... 410
- \path..... 844
- path, drawing..... 844
- \pattern..... 878
- pause mark..... 76, 175
- PDF, embedding files..... 649
- PDF, metadata..... 609
- pedal diagram, harp..... 425
- pedal high hat..... 155, 491, 930
- pedal indication, bracket..... 422
- pedal indication, mixed..... 422
- pedal indication, style..... 422
- pedal indication, text..... 422
- pedal mark, heel..... 155, 423, 928
- pedal mark, organ..... 155, 423, 928
- pedal mark, toe..... 155, 423, 928
- pedal splash high hat..... 491
- pedal sustain, style..... 422
- pedal, harp..... 425
- pedal, piano..... 421
- pedal, sostenuto..... 421
- pedal, sustain..... 421
- pedalSustainStyle..... 422
- percent repeat..... 208
- percent repeat, count visibility..... 209
- percent repeat, counter..... 209
- percent repeat, isolated..... 210
- percussion..... 487, 489
- percussion clef..... 487, 922
- percussion staff..... 241
- percussion, custom..... 491
- percussion, dead note..... 494
- percussion, false note..... 494
- percussion, ghost note..... 494
- percussion, muted note..... 494
- percussion, silenced note..... 494
- Performer_group..... 751
- Persian accidentals (sori, koron)..... 582
- Persian classical music..... 582
- Persian makam..... 574
- \pes..... 557, 562
- Petrucchi..... 537, 538
- Petrucchi clef..... 542, 923
- PetrucchiStaff..... 548, 736
- PetrucchiVoice..... 548, 736
- phrase bar line..... 130, 131
- phrase bar line, in Gregorian chant..... 555
- phrase bar line, in hymns..... 409
- phrase bar line, in Kievan chant..... 565
- phrasing bracket..... 303
- phrasing mark..... 173
- phrasing slur..... 170, 173
- phrasing slur, dashed..... 174
- phrasing slur, defining dash patterns..... 174
- phrasing slur, dotted..... 174
- phrasing slur, half solid and half dashed..... 174
- phrasing slur, multiple..... 174
- phrasing slur, simultaneous..... 174
- phrasing, in lyrics..... 354
- \phrasingSlurDashed..... 174
- \phrasingSlurDashPattern..... 174, 953
- \phrasingSlurDotted..... 174
- \phrasingSlurDown..... 173
- \phrasingSlurHalfDashed..... 174
- \phrasingSlurHalfSolid..... 174
- \phrasingSlurNeutral..... 173
- \phrasingSlurSolid..... 174
- \phrasingSlurUp..... 173
- Phrygian..... 24
- \phrygian..... 24
- piano..... 35
- ‘piano’ accidental style..... 35
- piano music, centering dynamics..... 414
- piano pedal..... 421
- piano staff..... 244, 414
- piano-cautionary..... 35
- ‘piano-cautionary’ accidental style..... 35
- PianoStaff..... 414, 416, 735
- pickup measure..... 90
- pickup, in a repeat..... 190
- piece..... 600
- pitch..... 3
- pitch name..... 3
- pitch name, other languages..... 10
- pitch range..... 40
- pitch, approximate..... 10
- pitch, default..... 53
- pitch, extreme..... 10
- pitch, isolated..... 53
- pitch, transposition..... 13
- pitch, unspecified..... 10
- Pitch_squash_engraver..... 99
- pitched trill..... 186
- pitched trill, with accidental..... 186
- \pitchedTrill..... 186, 953
- pitch, ‘smart’ transposition..... 15
- pitchnames..... 940, 949
- pizzicato, Bartók..... 429
- pizzicato, snap..... 429
- place-fret..... 864
- placeholder event..... 216
- placement, lyrics..... 360
- placement, right-hand fingering..... 480
- placing horizontal brackets, around text..... 843
- placing parentheses, around text..... 844
- placing vertical brackets, around text..... 838

PNG image 843
 poet 600
 point (pt) 773
 point, big (bp) 773
 point, of alignment 790
 point, of reference 789
 \pointAndClickOff 953
 \pointAndClickOn 953
 \pointAndClickTypes 954
 \polygon 845
 \polymetric 93, 954
 polymetric meter, with beams 94
 polymetric signatures 93
 polyphonic music 226
 polyphony, additional voices 229
 polyphony, in tablatures 444
 polyphony, shared lyrics 376
 polyphony, single-staff 221
 \popContextProperty 759, 954
 \portato 155, 927
 ‘portato’ articulation 155, 927
 position, figured bass alteration 529
 position, in measure 78, 91
 position, lyrics 255
 position, multi-measure rest 74
 position, ossia 255
 position, vertical, of grobs 772
 positioning, exact, of staves 702
 post-event 927
 postscript 333
 \postscript 333, 846
 power chord 483
 \pp 159
 \ppp 159
 \pppp 159
 \ppppp 159
 practice note head 45
 \prall 155, 927
 \pralldown 155, 927
 \prallmordent 155, 927
 \prallprall 155, 927
 ‘pralltriller’ ornament 155, 927
 ‘pralltriller, down’ ornament 155, 927
 ‘pralltriller, long’ ornament 155, 927
 ‘pralltriller, up’ ornament 155, 927
 \prallup 155, 927
 \preBend 440, 954
 \preBendHold 440, 954
 predefined paper variables 670
 predefined string tuning, for fretted instruments 452
 predefinedDiagramTable 475
 \predefinedFretboardsOff 477
 \predefinedFretboardsOn 477
 prefatory matter 715, 716
 \premeasure 954
 prima volta 190
 print-all-headers 679, 969
 print-first-page-number 678, 969
 print-page-number 678, 969
 printAccidentalNames 297
 printing chord name 512
 printing order 783
 printing reserved character 319
 printing special character 319
 printNotesLanguage 297

printOctaveNames 297
 prob 941
 properties 764
 property object 941
 property, grob 760
 property, modifying 758
 property-defaults 969
 \property-recursive 878
 \propertyOverride 954
 \propertyRevert 954
 \propertySet 955
 \propertyTweak 955
 \propertyUnset 955
 psalm 400, 405
 \pt 773, 970
 pull off 450
 punctuation, in lyrics 346
 \push-to-tag 636, 878
 \pushContextProperty 759, 955
 \pushToTag 634, 955
 \pushToTagMarkup 636, 955
 \put-adjacent 833
 putting space around text 831

Q

q (chord repetition) 217, 435
 \qr-code 879
 QR code 879
 quarter tone 8
 quarter tone accidental 10
 quarter tone, in tablature 454
 \quilisma 557, 562
 quote, in lyrics 346, 353
 quote, voices 265
 quoted text 309
 quoted text, in markup mode 319
 quotedCueEventTypes 267
 quotedEventTypes 267
 \quoteDuring 265, 268, 955
 \quoteDuring, and tags 629

R

r (rest) 67
 R (full-measure rest) 71
 ragged-bottom 672, 970
 ragged-last 675, 720, 970
 ragged-last-bottom 672, 970
 ragged-right 675, 720, 970
 \raise 327, 833
 \raiseNote 512, 955
 raising text 833
 range of pitches 40
 Ratisbona, Editio 538
 \reduceChords 99, 955
 reference point 789
 referencing context 737
 referencing page label, in text 883
 referencing page number, in text 877, 878
 register symbol, accordion 424
 regular line break 689
 rehearsal mark 141
 rehearsal mark, below staff 89

- rehearsal mark, format 142
- rehearsal mark, manual 142
- rehearsal mark, style 142
- relative 4
- \relative 4, 6, 16, 417, 643, 956
- relative music, and \autoChange 417
- relative octave entry 4
- relative octave entry, and chords 7
- relative octave entry, and transposition 6
- relative octave specification 4
- relative pitch, chords 216
- religious music 400
- reminder accidental 8
- removal, in chord 510
- \remove 743
- remove-empty 257
- remove-first 257
- remove-grace-property 149
- remove-layer 259
- \remove-with-tag 636, 879
- \RemoveAllEmptyStaves 257, 963
- \RemoveEmptyStaves 257, 963
- \removeFromTagGroup 633, 956
- \removeWithTag 628, 956
- removing bar numbers 138
- removing cue notes 272
- removing tagged music 628
- Renaissance music 246
- repeat 123
- \repeat 188, 189, 190
- repeat bar 120
- repeat bar line 131
- repeat bar line, underlying 130
- repeat number, changing 204
- \repeat percent 208
- \repeat segno 130, 131, 195
- \repeat tremolo 211
- \repeat unfold 188
- \repeat volta 130, 131, 189, 190
- repeat volta, changing 204
- repeat, al fine 195
- repeat, alla coda 196
- repeat, alternative bar numbers 202
- repeat, ambiguous 204
- repeat, and glissandi 180, 204
- repeat, and lyrics 366
- repeat, and measure number 204
- repeat, and slur 204
- repeat, bar line at start of piece 189
- repeat, bar numbers with letters 202
- repeat, beat 208
- repeat, D.C. 196
- repeat, D.C., manual 207
- repeat, D.S. 197
- repeat, D.S., forced at start 198
- repeat, D.S., manual 207
- repeat, da capo 196
- repeat, da capo, manual 207
- repeat, dal segno 197
- repeat, dal segno, forced at start 198
- repeat, dal segno, manual 207
- repeat, double, style for volta 132
- repeat, e poi la coda 196
- repeat, end 204
- repeat, manual 204
- repeat, measure 208
- repeat, nested 204
- repeat, percent 208
- repeat, percent, count visibility 209
- repeat, percent, counter 209
- repeat, percent, isolated 210
- repeat, short 208
- repeat, simple 189
- repeat, slash 208
- repeat, start 204
- repeat, timing information 204
- repeat, tremolo 211
- repeat, unfolded 188
- repeat, with alternative endings 190
- repeat, with anacrusis 190
- repeat, with bar checks 190
- repeat, with pickup 190
- repeat, with segno 198
- repeat, with ties 64
- repeat, with upbeat 190
- repeat, written-out 188
- repeatCommands 204
- repeatCountVisibility 209
- repeated chords, suppressing 474, 514
- repeating lyrics, with alternative endings 370
- repeating tie 64
- repeats, in MIDI 658
- \repeatTie 64, 372
- repetition, using q 217, 435
- \replace 815
- \replace-with-tag 636, 880
- \replaceWithTag 635, 956
- \replaceWithTagMarkup 636, 956
- replacing strings, automatically 646
- reserved character, printing 319
- reset-footnotes-on-new-page 679, 970
- \resetRelativeOctave 7, 956
- \resetTagGroup 633, 956
- \resetTagGroups 632, 956
- resizing of staves 253
- \responsum 558, 956
- rest 67
- \rest 68, 856
- rest, ancient 545
- rest, church 275
- rest, collisions 75
- rest, condensing ordinary 75
- rest, entering durations 67
- rest, full-measure 71
- rest, invisible 69
- rest, merging 231
- rest, multi-measure 68, 71
- rest, specifying vertical position 68
- rest, splitting 97
- rest, style 68
- rest, whole, for a full measure 71
- rest, whole-measure 68
- rest, within text, by duration 856
- rest, within text, by log and dot-count 857
- \rest-by-number 857
- rest-event 267
- restNumberThreshold 275
- restoring default properties for time signatures 83
- restrainOpenStrings 434
- \retrograde 17, 956

retrograde transformation 17
 reverb, in MIDI 661
 ‘reverse turn’ ornament 155, 927
 \reverseturn 155, 927
 \revert 760
 reverting override 760
 \revertTimeSignatureSettings 83, 956
 \rfz 159
 rgb-color 290
 RGB color 290
 \rheel 423
 \rheeltoe 423
 \rhythm 735, 736, 737, 857
 rhythm, in text 857
 rhythm, showing melody 98
 rhythmic staff 242
 RhythmicStaff 242, 735
 ride bell 930
 ride cymbal 930
 \right-align 326, 833
 right-aligning text 833
 \right-brace 880
 \right-column 834
 right-hand fingering, for fretted instruments 479
 right-hand fingering, placement 480
 right-margin 675, 970
 RIGHT 791, 792
 \rightHandFinger 479, 956
 rolled chord 183
 \romanStringNumbers 428, 432
 root of chord 508
 \rotate 834
 rotating object 789
 rotating text 834
 \rounded-box 331, 847
 \rtoe 423
 \rtoeheel 423

S

s (invisible rest) 69
 Sacred Harp note head 46
 \sacredHarpHeads 46
 \sacredHarpHeadsMinor 47
 \sans 815
 SATB 389
 scalable vector graphics output 648
 \scale 848
 \scaleDurations 62, 93, 956
 scaling duration 61
 scaling markup 848
 scaling text 835
 Scheme object 941
 Scheme variable 940
 \score 590, 594, 858
 Score 734
 Score context, replacing 752
 score, inside markup 335
 score, vocal, adding cues 397
 \score-lines 885
 score-markup-spacing 674, 970
 score-system-spacing 674, 970
 score-title 970
 score-title-properties 970
 Score_engraver 753

Score_performer 753
 scoreTitleMarkup 605, 970
 Scottish highland bagpipe 498
 script 927
 script, on multi-measure rest 72
 script, vertical ordering 157
 script-priority 157, 937
 seconda volta 190
 \section 131, 146, 565
 section bar line 131, 146
 section bar line, in Gregorian chant 555
 section bar line, in Kievan chant 565
 section label 312
 section parts 261
 \sectionLabel 196, 312, 956
 segno 197
 \segno 155, 859, 929
 segno bar line 122, 131, 198
 ‘segno’ sign 155, 929
 ‘segno’ sign, bar line 122, 198
 ‘segno’ sign, manual 206
 ‘segno’ sign, with repeats 195, 198
 segno, forced at start 198, 206
 \segnoMark 130, 131, 198, 206, 956
 self-alignment-interface 792
 self-alignment-X 695, 792
 self-alignment-Y 794
 semai form 578
 semi-flat 8, 11
 semi-flat symbol, appearance 576
 semi-flat symbol, Persian (koron) 582
 semi-sharp 8, 11
 semi-sharp symbol, Persian (sori) 582
 semi-transparent colors 289
 \semicirculus 556, 929
 ‘semicirculus’ Gregorian articulation 556, 929
 \semiflat 859
 \semiGermanChords 516
 \semisharp 859
 \senzaMisura 957
 separate text 317
 separator mark, system 248
 \serif 815
 sesqui-flat 11
 sesqui-sharp 11
 \sesquiflat 859
 \sesquisharp 859
 \set 104, 758, 762
 set-global-staff-size 683
 \setDefaultMeasureLength 957
 \setMeasureLengthFromHere 957
 setting extent of text object 883
 setting horizontal text alignment 825
 setting subscript, in standard font size 811
 setting superscript, in standard font size 811
 seventh chord 508
 \sf 159
 \sff 159
 \sfz 159
 \shape 799, 957
 shape note 46
 shape note, merging 49
 shaping slurs and ties 799
 shared property 940
 sharp 8

- \sharp..... 859
- sharp, double..... 8
- shift note..... 226
- shift rest, automatic..... 226
- shift symbol, accordion..... 424
- shift, fingering..... 284
- \shiftDurations..... 957
- shifting voice..... 226
- \shiftOff..... 226
- \shiftOn..... 226
- \shiftOnn..... 226
- \shiftOnnn..... 226
- short bar line..... 121
- short bar line, in Gregorian chant..... 555
- short fermata..... 155, 928
- short-indent..... 262, 676, 970
- shortened volta brackets..... 201
- \shortfermata..... 155, 928
- show vertical layout..... 727
- showFirstLength..... 647, 940
- \showKeySignature..... 498
- showLastLength..... 647, 940
- \showStaffSwitch..... 418
- side-axis..... 791
- side-position-interface..... 791
- sidestick..... 930
- sign, coda..... 155, 929
- sign, coda, manual..... 206
- sign, coda, variant..... 155, 200, 929
- sign, coda, with repeats..... 195
- sign, conducting..... 110
- sign, segno..... 155, 929
- sign, segno, bar line..... 122, 198
- sign, segno, manual..... 206
- sign, segno, with repeats..... 195, 198
- sign, snappizzicato..... 155, 928
- sign, variant coda..... 155, 200, 929
- signature, polymetric..... 93
- ‘signum congruentiae’ mensural notation..... 929
- ‘signum congruentiae’ ornament..... 155
- \signumcongruentiae..... 155, 929
- silenced note, percussion..... 494
- \simple..... 816
- simple repeat..... 189
- simple text string, with tie characters..... 861
- simultaneous notes and accidentals..... 38
- simultaneous phrasing slurs..... 174
- simultaneous slurs..... 170
- singer name..... 382
- \single..... 614, 762, 764, 767, 957
- single bar line..... 131
- single staff, with bracket or brace..... 245
- single-line comment..... 590, 596
- single-staff polyphony..... 221
- skip..... 69
- \skip..... 69, 371, 957
- skip typesetting..... 647
- skipBars..... 275
- skipping notes, in lyrics..... 371
- skipTypesetting..... 647
- slash repeat..... 208
- ‘slash turn’ ornament..... 155, 927
- slashChordSeparator..... 517
- slashed beam..... 119
- slashed digit..... 880
- slashed note head..... 50
- slashed stem..... 149
- \slashed-digit..... 880
- \slashedGrace..... 147, 957
- \slashSeparator..... 679
- \slashturn..... 155, 927
- slide, in tablature..... 448
- slope, ottava spanner, modifying..... 29
- slur..... 170
- slur, above notes..... 170
- slur, adjusting start and end..... 171
- slur, and repeats..... 204
- slur, below notes..... 170
- slur, dashed..... 170
- slur, dashed phrasing..... 174
- slur, defining dash patterns..... 171, 172
- slur, defining dash patterns for phrasing..... 174
- slur, dotted..... 170
- slur, dotted phrasing..... 174
- slur, double, for legato chords..... 172
- slur, for tuplets..... 56
- slur, half dashed and half solid..... 170
- slur, half solid and half dashed phrasing..... 174
- slur, manual placement..... 170
- slur, modifying..... 799
- slur, multiple..... 170
- slur, multiple phrasing..... 174
- slur, phrasing..... 170, 173
- slur, phrasing, defining dash patterns..... 174
- slur, simultaneous..... 170
- slur, simultaneous phrasing..... 174
- slur, solid..... 170
- slur, style..... 170
- slur, text markup inside..... 172
- slur, vertical..... 183
- slur-event..... 267
- \slurDashed..... 170
- \slurDashPattern..... 171, 957
- \slurDotted..... 170
- \slurDown..... 170
- \slurHalfDashed..... 170
- \slurHalfSolid..... 170
- \slurNeutral..... 170
- \slurSolid..... 170
- \slurUp..... 171
- \small..... 280, 326, 816
- \smallCaps..... 816
- \smaller..... 323, 326, 816
- smaller note..... 268
- smob..... 941
- snap pizzicato..... 429
- \snappizzicato..... 155, 928
- ‘snappizzicato’ sign..... 155, 928
- snare..... 930
- Solesmes..... 538
- solid slur..... 170
- solo part..... 232
- soprano clef..... 19, 921
- sori..... 582
- sos..... 421
- sostenuto pedal..... 421
- \sostenutoOff..... 421
- \sostenutoOn..... 421
- sound..... 651
- \sourcefileline..... 596

- \sourcefilename..... 596
- Southern Harmony note head..... 46
- \southernHarmonyHeads..... 46
- \southernHarmonyHeadsMinor..... 47
- \sp..... 159
- space, between staves..... 695
- space, in lyrics..... 346, 353
- space, inside systems..... 695
- space-alist..... 716
- spacer note..... 69
- spacer rest..... 69
- spacing..... 711
- spacing section, new..... 712
- spacing, display of layout..... 727
- spacing, horizontal..... 711
- spacing, lyrics..... 363
- spacing, vertical..... 695
- span bar..... 125
- Span_stem_engraver..... 420
- spanner..... 774, 941
- spanner, modifying..... 774
- special arpeggio symbol..... 182
- special character..... 644
- special character, in markup mode..... 319
- special note head..... 43
- splash cymbal..... 930
- splicing, into tagged music..... 634
- splitting notes..... 97
- splitting rests..... 97
- \spp..... 159
- Sprechgesang..... 399
- square bracket, at start of staff group..... 245
- square neumes ligature..... 557
- \staccatissimo..... 155, 927
- 'staccatissimo' articulation..... 155, 927
- \staccato..... 155, 927
- 'staccato' articulation..... 155, 927
- stacked flags..... 117
- stacking text, in a column..... 821
- Staff..... 735
- staff brace, in markup..... 876
- staff change, automatic..... 416
- staff change, manual..... 414
- staff group..... 243
- staff group, with square bracket at start..... 245
- staff line, modifying..... 249
- staff line, stopping and starting..... 249
- staff symbol..... 249
- staff, choir..... 243
- staff, distance..... 695
- staff, drum..... 241
- staff, empty..... 256
- staff, exact positioning..... 702
- staff, Frenched..... 253
- staff, grand..... 243
- staff, hiding..... 256
- staff, highlight..... 291
- staff, initiation..... 241
- staff, instantiation..... 241
- staff, keyboard instruments..... 414
- staff, keyed instruments..... 414
- staff, metronome mark below..... 89
- staff, multiple..... 243
- staff, nested..... 247
- staff, new..... 241
- staff, percussion..... 241
- staff, piano..... 244, 414
- staff, resizing..... 253
- staff, single..... 241
- staff, single, with bracket or brace..... 245
- staff, size..... 683
- staff, switching..... 418
- staff-affinity..... 695
- staff-change line..... 418
- staff-height..... 971
- staff-padding..... 283
- \staff-space..... 773, 971
- staff-staff-spacing..... 695
- Staff_collecting_engraver..... 143, 316
- Staff_symbol_engraver..... 256
- StaffGroup..... 735
- staffgroup-staff-spacing..... 695
- StaffGroupier..... 695
- \staffHighlight..... 291, 957
- stand-alone text..... 317
- StandaloneRhythmScore..... 735
- StandaloneRhythmStaff..... 736
- StandaloneRhythmVoice..... 737
- standard font size (notation)..... 281
- \stanza..... 377, 958
- stanza number..... 377
- stanza reminder..... 378
- stanzaReminders..... 378
- stanzaReminderText..... 378
- start of system..... 243
- start repeat..... 204
- start-repeat..... 204
- startAcciacaturaMusic..... 150
- startAppoggiaturaMusic..... 150
- startGraceMusic..... 150
- \startGradualTempoChange..... 958
- \startGroup..... 303
- \startOptionalMaterial..... 294
- \startStaff..... 249, 253, 735
- \startTextSpan..... 311, 781, 782
- \startTrillSpan..... 185
- staves, divisi..... 259
- \stdBass..... 868
- \stdBassIV..... 869
- \stdBassV..... 870
- \stdBassVI..... 871
- stem..... 296
- stem, automatic direction on center line..... 297
- stem, cross-staff..... 420
- stem, default direction on center line..... 296
- stem, direction..... 296
- stem, down..... 296
- stem, in tablature..... 444
- stem, invisible..... 296
- stem, neutral..... 296
- stem, up..... 296
- stem, with slash..... 149
- stem-spacing-correction..... 711
- \stemDown..... 296
- stemLeftBeamCount..... 115, 116
- \stemNeutral..... 296
- stemRightBeamCount..... 115, 116
- \stemUp..... 296
- stencil..... 941
- \stencil..... 881

stencil, removing 783
 stereo balance, in MIDI 661
 stopAcciaccaturaMusic 150
 stopAppoggiaturaMusic 150
 stopGraceMusic 150
 \stopGradualTempoChange 958
 \stopGroup 303
 \stopOptionalMaterial 294
 \stopped 155, 491, 496, 928
 ‘stopped’ articulation 155, 496, 928
 \stopStaff 249, 253, 256, 735
 \stopStaffHighlight 291
 \stopTextSpan 311, 781, 782
 \stopTrillSpan 185
 \storePredefinedDiagram 470, 475, 958
 straight flags, modern 117
 straight flags, old 117
 strict spacing, and grace notes 150
 strict-beat beaming 110
 strictBeatBeaming 110
 strictly alternating meter 130
 string bending, in tablature 440
 string number 428, 432
 string number, orientation 282
 string number, vs. fingering 432
 string, automatic replacement 646
 string, indicating open 428
 \string-lines 885
 stringNumberOrientations 282
 strings, orchestral 427
 strings, writing for 427
 \stringTuning 452, 958
 stringTunings 452, 466
 stroke finger, orientation 282
 strokeFingerOrientations 282, 480
 \strophia 557, 562
 strumming rhythm, showing 99, 100
 \strut 881
 style, bar number 135
 style, double repeat for volta 132
 style, measure number 135
 style, multi-measure rests 275
 style, note heads 43
 style, rehearsal mark 142
 style, rests 68
 style, slur 170
 style, text dynamics 167
 style, voice 226
 \styledNoteHeads 958
 \sub 324, 816
 subbass clef 19, 921
 subdivideBeams 109
 subdividing beams 109
 submeasure bar line 130
 \submeasureBarsOn 130
 submeasureStructure 81, 130
 subscript 324
 subscript text 816
 substitution function, and relative octave entry .. 643
 subsubtitle 600
 subtitle 600
 suggestAccidentals 158, 546
 \super 324, 817
 superscript 324
 superscript text 817

suppressing repeated chords 474, 514
 sus 511
 sustain pedal 421
 sustain pedal, style 422
 \sustainOff 421
 \sustainOn 421
 SVG output 648
 swing 857
 swing.ly script 662
 switching font 323
 syllable duration, automatic 349
 symbol, break-align 716
 symbol, breath mark, changing 175
 symbol, major seven 518
 symbol, non-musical 332
 syntax, markup 319
 system 243
 system separator mark 248
 system start delimiter 243
 system start delimiter, nested 247
 system-count 677, 971
 system-separator-markup 679, 971
 system-system-spacing 674, 971
 systems-per-page 677, 971

T

tab clef 454, 922
 \tabChordRepeats 435, 958
 \tabChordRepetition 958
 \tabFullNotation 434
 tablature 242, 431
 tablature, and beams 444
 tablature, and harmonic indications 438
 tablature, and harmonics 445
 tablature, and polyphony 444
 tablature, and slides 448
 tablature, and stems 444
 tablature, and string bending 440
 tablature, banjo 431, 452, 484
 tablature, basic 433
 tablature, bass 452
 tablature, bass guitar 452
 tablature, cello 452
 tablature, chord glissando 449
 tablature, custom 452
 tablature, custom string tunings 452
 tablature, default 433
 tablature, double bass 452
 tablature, guitar 431, 452
 tablature, hammer on 450
 tablature, lute 485
 tablature, mandolin 452
 tablature, microtones 454
 tablature, predefined string tunings 452
 tablature, pull off 450
 tablature, quarter tones 454
 tablature, ukulele 452
 tablature, viola 452
 tablature, violin 452
 \table 885
 table of contents 622
 table of contents, customized functions 623
 \table-of-contents 624, 886

- TabStaff..... 242, 433, 735
- TabVoice..... 433, 737
- tag..... 628
- \tag..... 628, 881, 958
- tag groups..... 631
- \tag, and quoting music..... 629
- \tag-list..... 637, 886
- \tagGroup..... 631, 958
- \tagGroupRef..... 632, 959
- tagline..... 600, 971
- tam tam..... 930
- tambourine..... 930
- \taor..... 498
- taqasim..... 578
- teaching..... 37
- ‘teaching’ accidental style..... 37
- \teeny..... 280, 326, 817
- template, Arabic music..... 579
- tempo..... 86
- \tempo..... 86
- tempo, change, without metronome mark..... 89
- tempo, with rhythm..... 857
- tempoCountPrecision..... 86
- \temporary..... 766, 775, 959
- tenor clef..... 19, 921
- tenor clef, choral..... 20
- tenor G clef..... 921
- tenor varC clef..... 921
- \tenuto..... 155, 927
- ‘tenuto’ articulation..... 155, 927
- text alignment, commands..... 331
- text column, left-aligned..... 830
- text column, right-aligned..... 834
- text dynamics, style..... 167
- text encoding..... 644
- text item, non-empty..... 309
- text mark..... 313
- text mark, alignment..... 315
- text mark, below staff..... 315
- text mark, on every staff..... 316
- text mark, vertical stacking..... 315
- text markup..... 319
- text markup, inside slurs..... 172
- text object..... 307
- text script..... 309
- text script, breaking vertical alignment..... 166
- text script, vertical alignment..... 165
- text size..... 323
- text spanner..... 311
- text spanner, dynamics, customize..... 312
- text spanner, formatting..... 311
- text, aligning..... 326
- text, at beginning of line..... 313
- text, at end of score..... 313
- text, between notes..... 313
- text, centering on page..... 330
- text, decorating..... 331
- text, framing..... 331
- text, horizontal alignment..... 326
- text, in columns..... 318, 329
- text, in volta bracket..... 206
- text, justified..... 330
- text, keeping inside margin..... 310
- text, line width..... 330
- text, multi-line..... 329
- text, on bar line..... 312, 313
- text, on multi-measure rest..... 72
- text, other languages..... 307
- text, ottavation..... 28
- text, outside margin..... 310
- text, padding..... 332
- text, separate..... 317
- text, spread over multiple pages..... 321
- text, stand-alone..... 317
- text, top-level..... 317
- text, vertical alignment..... 327
- text, with a tie above..... 814, 817
- text, with a tie below..... 817, 818
- text, word-wrapped..... 330
- \text-accidental..... 860
- \text-common-time..... 860
- \text-cut-time..... 860
- \text-doubleflat..... 860
- \text-doublesharp..... 860
- \text-flat..... 861
- text-font-size..... 323, 971
- \text-natural..... 861
- \text-sharp..... 861
- Text_mark_engraver..... 316
- \textEndMark..... 313, 959
- \textLengthOff..... 73, 75, 310
- \textLengthOn..... 73, 75, 165, 310
- \textMark..... 313, 959
- \textSpannerDown..... 311
- \textSpannerNeutral..... 311
- \textSpannerUp..... 311
- thorough bass..... 525
- \thumb..... 155, 282
- ‘thumb’ fingering..... 155, 282, 928
- tick bar line..... 121
- tick bar line, in Gregorian chant..... 555
- tick mark..... 175
- tie..... 63
- \tie..... 817
- tie, above text..... 814, 817
- tie, alternative endings..... 64
- tie, and volta bracket..... 64
- tie, appearance..... 64
- tie, below text..... 817, 818
- tie, dashed..... 64
- tie, dotted..... 64
- tie, from nothing..... 64
- tie, in chord..... 63
- tie, in lyrics..... 353
- tie, in repeats..... 64
- tie, laissez vibrer..... 64
- tie, manual engraving..... 66
- tie, modifying..... 799
- tie, placement..... 64
- tie, repeating..... 64
- tie, to nothing..... 64
- tie, with arpeggios..... 65
- TieColumn..... 66
- tied note, accidental..... 8
- \tied-lyric..... 861
- \tieDashed..... 64
- \tieDashPattern..... 64, 959
- \tieDotted..... 64
- \tieDown..... 64
- \tieHalfDashed..... 64

- `\tieHalfSolid`..... 64
- `\tieNeutral`..... 64
- `\tieSolid`..... 64
- `\tieUp`..... 64
- `tieWaitForNote`..... 65
- `timbale`..... 930
- `\time`..... 79, 104, 959
- time administration 78
- time signature 79
- time signature, additive 80
- time signature, alternating 80
- time signature, and volta repeats 85
- time signature, complex 80
- time signature, default settings 81
- time signature, double 93
- time signature, mensural 543
- time signature, mid-measure 90
- time signature, polymetric 93
- time signature, printing only numerator 84
- time signature, properties, restoring default values 83
- time signature, style 80, 543
- time signature, visibility 79
- time, common 80
- time, cut 80
- `\timeAbbrev`..... 959
- `\times`..... 959
- `timeSignature`..... 93
- Timing 78, 734
- timing 78
- timing information, and repeats 204
- timing mark, for glissando 178
- timing, within score 78
- `\tiny`..... 280, 326, 817
- title 597
- title 600
- toc 622
- `tocFormatMarkup`..... 624, 971
- `tocIndentMarkup`..... 624, 971
- `\tocItem`..... 624, 960
- `tocItemMarkup`..... 624, 971
- `\tocItemWithDotsMarkup`..... 623
- `tocTitleMarkup`..... 624, 971
- `\toe`..... 155, 423, 928
- ‘toe’ pedal mark 155, 423, 928
- `toeHeelStyle`..... 423
- tom tom 930
- top-level text 317
- top-margin 672, 971
- top-markup-spacing 674, 971
- top-system-spacing 674, 972
- toplevel-bookparts 940
- toplevel-scores 940
- transcription, mensural to modern 571
- transcription, modern of Gregorian music 405
- transcription, of mensural music 246
- transformation, modal 17
- transformation, retrograde 17
- `\translate`..... 327, 834
- `\translate-scaled`..... 327, 835
- translating text 834, 835
- transparency, semi 289
- `\transparent` 881
- transparent note 288
- transparent objects 783
- `\transpose`..... 6, 13, 16, 960
- transposed clef, visibility 788
- `\transposedCueDuring`..... 271, 960
- transposing 13
- transposing clef 20
- transposing fret diagram 468
- transposing instrument 14, 30
- transposition 13
- `\transposition`..... 30, 265, 960
- transposition, and relative octave entry 6
- transposition, instrument 30
- transposition, MIDI 30
- transposition, modal 17
- transposition, of notes 13
- transposition, of pitches 13
- transposition, pitches, ‘smart’ 15
- tre corde 421
- treble clef 19, 921
- `\treCorde`..... 421
- tremolo 211
- tremolo beam 211
- tremolo mark 212
- tremolo, cross-staff 212
- triad 508
- triangle 930
- `\triangle`..... 332, 848
- trill 185
- `\trill`..... 155, 185, 927
- ‘trill’ ornament 155, 927
- trill, pitched 186
- trill, with accidental 186
- triplet 55
- triplet, formatting 57
- `\tripletFeel`..... 663
- true (#t) 972
- tuning, banjo 485
- tuning, lute 486
- tuning, non-Western 574
- tuplet 55
- `\tuplet` 55, 93, 960
- tuplet bracket, note head side 59
- tuplet bracket, placement 55
- tuplet bracket, visibility 56, 58
- tuplet number, changing 57
- tuplet number, non-default 57
- tuplet number, visibility 56
- tuplet slur 56
- tuplet, beamed, line break within 60
- tuplet, entering multiple 57
- tuplet, formatting 57
- tuplet, grouping 55
- tuplet slur 56
- `\tupletDown`..... 55
- `\tupletNeutral`..... 55
- `TupletNumber`..... 57
- `\tupletSpan`..... 57, 960
- `tupletSpannerDuration`..... 57
- `\tupletUp`..... 55
- Turkish makam 574
- Turkish makam, example 581
- Turkish music 580
- Turkish note name 580
- Turkish, classical music 574
- `\turn` 155, 927
- ‘turn’ ornament 155, 927
- ‘turn’ ornament, delayed 158

`\tweak` 762, 960
`\tweak`, relation to `\override` 762
 tweaking 762
 tweaking control point 764
 tweaking grace note 149
 two-column text 318
 two-sided 676, 972
`\type` 749, 750
 typeface 939
 typesetting text 319
 typesetting, skip 647
`\typewriter` 818

U

U.C. 421
 ukulele 457
 ultima volta 190
 una corda 421
`\unaCorda` 421
`\underline` 323, 818
 underlining text 818
 underlying repeat bar line 130
`\undertie` 818
`\undo` 767, 960
`\unfolded` 192, 961
 unfolding repeat 188
`\unfoldRepeats` 192, 658, 961
`\unHideNotes` 288
 Unicode 645
 units, of measuring 773
 universal-color 290, 904
`\unless` 608, 862
 unmetred music 78, 91
 unmetred music, accidentals 91
 unmetred music, bar lines 91
 unmetred music, bar numbers 91
 unmetred music, beams 91
 unmetred music, line breaks 93
 unmetred music, page breaks 93
`\unset` 758
 unspecified pitch 10
 up direction (°) 772
 ‘up pralltriller’ ornament 155, 927
 ‘up-bow’ bowing indication 155, 428, 928
 UP 791, 794
 upbeat 90
 upbeat, in a repeat 190
`\upbow` 155, 428, 928
`\upmordent` 155, 927
 ‘upper mordent’ ornament 155, 927
`\upprall` 155, 927
`\upright` 819
 URL link, as QR code 879
 UTF-8 644

V

varbaritone clef 19
 varC clef 921
`\varcoda` 155, 861, 929
`\varheel` 155, 423, 928
 variable 595
 variable, and `\book` 592
 variable, and `\bookpart` 592
 variable, using 626
 variant ‘coda’ sign 155, 200, 929
 Variation Font format (VF) 337
`\vartoe` 155, 423, 928
 Vaticana, Editio 537, 538
 VaticanaLyrics 554, 736
 VaticanaScore 554, 735
 VaticanaStaff 242, 554, 735
 VaticanaVoice 554, 736
`\vcenter` 835
`\verbatim-file` 882
`\verboseBarNumbers` 961
`\version` 596
`\versus` 558, 961
 vertical alignment, dynamics 165
 vertical alignment, dynamics, breaking 166
 vertical alignment, text 327
 vertical alignment, text scripts 165
 vertical direction, default, of grobs 772
 vertical direction, forced, of grobs 772
 vertical distance, figured bass elements 531
 vertical extent, of grobs 789
 vertical line, between staves 301
 vertical movement, in markup 327, 328
 vertical ordering, of scripts 157
 vertical positioning, of dynamics 162
 vertical slur 183
 vertical spacing 695, 720
 vertical spacing, debugging 727
 VerticalAxisGroup 695
 vertically centering text 835
`\verylongfermata` 155, 928
`\veryshortfermata` 155, 928
 vibraslap 930
 violin clef 19, 921
`\virga` 557, 562
`\virgula` 556
 visibility of object 782
 visibility of transposed clef 788
 visibility of tuplet brackets 58
 visibility of tuplets 56
 vocal score 392
 vocal score, adding cues 397
 voice 221
 Voice 221, 736
 voice 33
 ‘voice’ accidental style 33
 voice style 226
 voice, additional, in polyphonic music 229
 voice, ambitus 41
 voice, divided 391
 voice, extra, for handling breaks 690
 voice, following 418
 voice, multiple 226
 voice, `\partCombine` with `\autoBeamOff` 103
 voice, quoting 265, 268

voice, shifting 226
 voice, with ottavation 28
`\voiceFour` 221
`\voiceFourStyle` 226
`\voiceNeutralStyle` 226
`\voiceOne` 221
`\voiceOneStyle` 226
`\voices` 224, 961
`\voiceThree` 221
`\voiceThreeStyle` 226
`\voiceTwo` 221
`\voiceTwoStyle` 226
`\void` 664, 961
 volta 189, 190
`\volta` 190, 192, 961
 volta bracket 204
 volta bracket, and tie 64
 volta bracket, in additional staves 201
 volta bracket, shortened 201
 volta bracket, with text 206
 volta repeat, and time signatures 85
 volta repeat, bar line at start of piece 189
 volta repeat, below chords 519
 volta, double repeat style 132
 volta, prima 190
 volta, seconda 190
 volta, ultima 190
`\volta-number` 819
`\Volta_engraver` 201
 vowel transition 357
`\vowelTransition` 357
`\vshape` 800, 961
`\vspace` 328, 835

W

Walker shape note head 46
`\walkerHeads` 46
`\walkerHeadsMinor` 47
 whistle 930
 white mensural ligature 548
 whiteout 65, 783
`\whiteout` 882
 whitespace 596
`\whiteTriangleMarkup` 516

whole rest, for a full measure 71
 wind instrument 495
 wind instrument, fingering symbols 496
`\with` 743, 747
`\with-color` 288, 883
`\with-dimension` 883
`\with-dimension-from` 883
`\with-dimensions` 883
`\with-dimensions-from` 883
`\with-link` 883
`\with-outline` 883
`\with-string-transformer` 819
`\with-true-dimension` 883
`\with-true-dimensions` 884
`\with-url` 849
`\withMusicProperty` 961
`\withRelativeDir` 961
 woodblock 930
 woodwind diagram, key lists 506
 woodwind diagram, list 503
 woodwind diagram, modifying 504
`\woodwind-diagram` 866
 word-wrapping text 330
`\wordwrap` 330, 836
`\wordwrap-field` 836
`\wordwrap-lines` 321, 887
`\wordwrap-string` 837
 writing music in parallel 237
 written-out repeat 188

X

`x11-color` 289, 290, 901
 X 791
 X-offset 695, 791
 X11 color 289, 290
`\xNote` 44, 962
`\xNotesOff` 44
`\xNotesOn` 44

Y

Y 791
 Y-offset 791